
City of New Albany ADA Transition Plan 2025 Update



Updated: September 2025

This document serves as an update and supplement to the City of New Albany's ADA Transition Plan originally adopted in 2017. It provides a current status of compliance efforts, updates on practices and projects, and documentation of progress in accordance with INDOT's Local Public Agency (LPA) requirements. This supplement should be reviewed alongside the original ADA Transition Plan for full context.

ADA Coordinator Update

Scott Wood continues to serve as the City's ADA Coordinator. He is expected to retire in the coming years, at which time the responsibility is likely to transition to the City Engineer.

ADA Complaint Log

Since the adoption of the original ADA Transition Plan, no formal ADA-related complaints have been submitted to the City's ADA email address or received via other means. The City reviews the complaint log annually as part of its ADA compliance monitoring.

Systematic ADA Improvements with Annual Paving Program

The City of New Albany follows a consistent policy of upgrading non-compliant curb ramps and, where feasible, adjacent sidewalk panels in conjunction with annual street resurfacing projects. All resurfacing projects are evaluated for ADA impacts, and improvements are made accordingly to ensure systematic barrier removal.

This policy ensures ongoing progress toward full ADA compliance using recurring capital funds.

CDBG ADA Sidewalk Projects (2017–2025)

The following projects have been completed using Community Development Block Grant (CDBG) funding to address sidewalk and ramp needs in disadvantaged neighborhoods:

- Thomas St (Beeler St to Market St)
- Oak St (North side from Vincennes St to Silver St)
- Elm St (Vincennes St to Silver St.)
- Union St (State St to Bono Rd)
- Green St (State St to Bono Rd)
- Olive Ave (State St to Bono Rd)
- Beechwood Ave (Lopp St to the CSX railroad tracks)

- Lopp St (Beechwood Ave to Roosevelt Ave)

Sidewalk and Ramp Inventory Update

The City engaged Clark Dietz in 2023 to perform a citywide inventory of curb ramps and sidewalks. This inventory is currently being updated in 2025. Findings are used to prioritize future improvements and guide systematic compliance efforts citywide.

This inventory is included in Appendix O.

Appendices

- Appendix N – ADA Barrier Removal & Program Updates (2017-2025)
- Appendix O – Sidewalk and Ramp Inventory (Clark Dietz 2023)

This 2025 update ensures that the City of New Albany remains aligned with INDOT's ADA Transition Plan requirements for Local Public Agencies. Questions about this plan may be directed to the City Engineer or ADA Coordinator.



TRANSITION PLAN

March 2018



VS ENGINEERING, INC.

4275 North High School Road
vsei@vsengineering.com
Phone: (317) 293-3542

Indianapolis, Indiana 46254
www.vsengineering.com
Fax: (317) 293-4737



TABLE OF CONTENTS

Executive Summary	III - IV
ADA Public Notice	1-2
Responsible Official	3
ADA Accommodation and Grievance	4-5
Design Standards	6
Assessment Methodology	7-9
Prioritization of Improvements	10-13
Schedule and Funding	14-15
Ongoing Quality Control	16-17
Public Involvement	18
References	19
Appendix A - Adopted ADA Resolutions	A1-A2
Appendix B – ADA Forms	B1-B3
Appendix C – Self-Evaluations & Inventory – Curb Ramps	C1-C26
Appendix D – Self-Evaluations & Inventory – City Facilities	D1-D2
Appendix E – Self-Evaluations & Inventory – Traffic Signals	E1-E4
Appendix F – Self-Evaluations & Inventory – Programs & Events	F1
Appendix G – Design Standards (Pedestrian Facilities)	1-112
Appendix H – Design Standards (Building Facilities)	1-275
Appendix I – Design Standards (Website Content)	1-41
Appendix J – ADA Requests for Accommodation	TBD
Appendix K – ADA Grievances	TBD
Appendix L – ADA Barrier Removal Summary	TBD
Appendix M – Annual Program Monitoring Reports	TBD

LIST OF FIGURES

Pedestrian Traffic Generator Map	13



Introduction

The Americans with Disabilities Act (ADA) of 1990 is a Federal Civil Rights Legislation, which mandates non-discrimination to persons with disabilities. The U.S. Congress signed the ADA in 1990, and it went into effect in 1992. The ADA is a civil rights law that prohibits discrimination against individuals with disabilities in access to jobs, public accommodations, and governmental services and programs, public transportation, and telecommunications. Section 504 of the Rehabilitation Act of 1973:

“No otherwise qualified [disabled] individual in the United States shall, solely by reason of [disability], be excluded from the participation in, be denied the benefits of, or be subjected to discrimination under any program or activity receiving federal financial assistance.”

The City of New Albany recognizes that it is important for its facilities, programs, and services to be available to all of its citizens and the general public. The City of New Albany further understands that some of its existing facilities, programs and services may have met accessibility requirements previously, but may not now, or may not in the future, as standards are revised or new standards developed. Therefore, in order to fulfill its commitment to endeavor to provide equal access to all of its public programs, services, facilities for citizens with disabilities, and in compliance with the ADA, the City of New Albany has developed an Americans with Disabilities Act Transition Plan (ADA Transition Plan). To develop this plan, the City of New Albany completed a self-evaluation of its facilities, programs, services and public right-of-way to determine what types of access barriers exist for individuals with disabilities. This information was used to develop the City of New Albany ADA Transition Plan. This plan will be used to guide future planning and implementation of accessibility improvements.

The City of New Albany ADA Transition Plan is intended to help determine whether issues of accessibility could be addressed through changes in the way such programs and services are provided. The City will attempt to remove physical barriers or provide alternative solutions to accessibility when program changes cannot ensure access to services, programs, and activities in existing facilities.

Realizing that structural changes generally require time and expense, the Department of Justice Regulations, Federal Register 28 CFR Part 35 state that "in the event that structural changes to facilities will be undertaken to achieve program accessibility, a public entity that employs 50 or more persons shall develop a Transition Plan setting forth the steps necessary to complete such changes". Additionally, "if a public entity has responsibility or authority over streets, roads, or walkways, its Transition Plan shall include a schedule for providing curb ramps or other sloped areas where pedestrian



EXECUTIVE SUMMARY

walks cross curbs, giving priority to walkways serving entities covered by the Act". The schedule for compliance the City of New Albany has adopted is "As soon as possible, administratively, physically, and financially."

The City of New Albany's Transition Plan includes provisions to require specifications on upcoming design projects and programs, to comply with ADA requirements. The City of New Albany plans to progressively remove physical barriers to accessibility when facilities, programs, services, and activities do not provide access to persons with special needs. Work toward reducing accessibility barriers within City owned or operated facilities, City infrastructure, and City programming, is to be guided by public and/or employee requests, and/or initial or revised prioritization of the Transition Plan items; giving priority to the highest utilized programs or facilities. Additionally, The City will strive to include annual budgetary allotments to remove accessibility barriers that will eventually make the various facilities and programs as accessible as is reasonably possible. Where access cannot be provided, alternate means to provide the same opportunities to persons with disabilities will be attempted.



ADA Public Notice

28 CFR PART 35, Section 35.106 of the Title II Americans with Disabilities Act (ADA) requires a public entity to disseminate sufficient information to applicants, participants, beneficiaries, and other interested persons to inform them of the rights and protections afforded by the ADA and this regulation. Methods of providing this information include, for example, the publication of information in handbooks, manuals, and pamphlets that are distributed to the public to describe a public entity's programs and activities; the display of informative posters in service centers and other public places; or the broadcast of information by television or radio. In providing the notice, a public entity must comply with the requirements for effective communication in §35.160. The preamble to that section gives guidance on how to effectively communicate with individuals with disabilities. The current version of the City of New Albany ADA Transition Plan is posted on the City's website and is also available at the City's Planning and Zoning Office and Public Library.

The public will continue to be able to view and make comments about the ADA Transition Plan on a perpetual basis, as this plan is considered to be part of a continuous improvement process. The City will update the plan and its associated improvement project lists annually to reflect completed improvement projects, barrier removals, or additions and/or changes suggested by the public, as appropriate. The City of New Albany provided an opportunity for the public to view and comment on this ADA Transition Plan. Public comments were received between February 20, 2018 and March 20, 2018 at the City Hall, during the regularly scheduled City Council meetings, which were fully accessible. The City of New Albany's formal ADA Public Notice is on the following page.





NOTICE UNDER THE AMERICANS WITH DISABILITIES ACT

In accordance with the requirements of Title II of the Americans with Disabilities Act of 1990 ("ADA"), the City of New Albany will not discriminate against qualified individuals with disabilities on the basis of disability in its services, programs, or activities.

Employment: The City of New Albany does not discriminate on the basis of disability in its hiring or employment practices and complies with all regulations promulgated by the U.S. Equal Employment Opportunity Commission under title I of the ADA.

Effective Communication: The City of New Albany will generally, upon request, provide appropriate aids and services leading to effective communication for qualified persons with disabilities so they can participate equally in the City of New Albany's programs, services, and activities, including qualified sign language interpreters, documents in Braille, and other ways of making information and communications accessible to people who have speech, hearing, or vision impairments.

Modifications to Policies and Procedures: The City of New Albany will make all reasonable modifications to policies and programs to ensure that people with disabilities have an equal opportunity to enjoy all of its programs, services, and activities. For example, individuals with service animals are welcomed in the City of New Albany offices, even where pets are generally prohibited.

Anyone who requires an auxiliary aid or service for effective communication, or a modification of policies or procedures to participate in a program, service, or activity of the City of New Albany, should contact the office of Scott Wood, ADA Coordinator, 311 Hauss Square, Room 329 , as soon as possible but no later than 48 hours before the scheduled event.

The ADA does not require the City of New Albany to take any action that would fundamentally alter the nature of its programs or services, or impose an undue financial or administrative burden.

Complaints that a program, service, or activity of The City of New Albany is not accessible to persons with disabilities should be directed to Scott Wood, ADA Coordinator, 311 Hauss Square Room 329.

The City of New Albany will not place a surcharge on a particular individual with a disability or any group of individuals with disabilities to cover the cost of providing auxiliary aids/services or reasonable modifications of policy, such as retrieving items from locations that are open to the public but are not accessible to persons who use wheelchairs.



Designation of an ADA Coordinator

Public entities with 50 or more employees are required to designate at least one responsible employee to coordinate ADA compliance. The ADA Coordinator's role for the City of New Albany includes:

- ✓ Monitoring compliance with the ADA and investigating complaints of violations,
- ✓ Serving as a resource to the public to assist with questions and concerns about disability discrimination, and
- ✓ Serving as a resource to other internal City staff so any questions from the public can be answered quickly and consistently.

The City's ADA Coordinator has been designated the ADA Coordinator and is in charge of overall compliance with the ADA when feasible. The contact info for the City of New Albany's ADA Coordinator is below:

- Scott Wood, ADA Coordinator
City of New Albany, Indiana
311 Hauss Square Room 329
New Albany, IN 47150
Phone: (812) 948-5333
Email: swood@cityofnewalbany.com



General Procedure

The City of New Albany has implemented a process for the public to file requests for reasonable accommodation and grievances as pertaining to ADA accessibility. The process is intended to promote effective communication regarding any ADA issues brought before the City. The City of New Albany is committed to appropriately addressing any public concerns or requests regarding ADA compliance of its facilities to ensure that filing of a formal grievance is not required.

Request for Reasonable Accommodation

The Request for Reasonable Accommodation Form should be completed by anyone who has an ADA concern or need in regards to one of the City's programs, services or facilities. The contact information of the person making the request should be included as well as a description of why the accommodation is needed.

The completed Request for Reasonable Accommodation Form should be submitted to:

- Scott Wood, ADA Coordinator
City of New Albany, Indiana
311 Hauss Square Room 329
New Albany, IN 47150
Phone: (812) 948-5333
Email: swood@cityofnewalbany.com

The ADA Coordinator will respond to the individual requesting the accommodation within fifteen (15) calendar days of receiving the written request. If the ADA Coordinator's response does not satisfactorily resolve the issue, the individual may file a formal grievance. The City of New Albany shall keep records of all requests for accommodation received by the ADA Coordinator for a period of three years. The Request for Reasonable Accommodation Form can be found in Appendix B.

Filing an ADA Grievance

The City of New Albany established a formal Grievance Procedure to meet the requirements of the ADA. The procedure may be utilized by anyone filing a complaint that alleges discrimination on the basis of a disability relating to a City program, service or facility. The City's formal ADA Grievance Procedure is outlined on the following page and a copy of the ADA Grievance Form is located in Appendix B.





CITY OF NEW ALBANY GRIEVANCE PROCEDURE UNDER THE AMERICANS WITH DISABILITIES ACT

This Grievance Procedure is established to meet the requirements of the Americans with Disabilities Act of 1990 ("ADA"). It may be used by anyone who wishes to file a complaint alleging discrimination on the basis of disability in the provision of services, activities, programs, or benefits by the City of New Albany. The City's Personnel Policy governs employment-related complaints of disability discrimination.

The complaint should be in writing and contain information about the alleged discrimination such as name, address, phone number of complainant and location, date, and description of the problem. Alternative means of filing complaints, such as personal interviews or a tape recording of the complaint will be made available for persons with disabilities upon request.

The complaint should be submitted by the grievant and/or his/her designee as soon as possible but no later than 60 calendar days after the alleged violation to:

Scott Wood, ADA Coordinator
City Hall
Planning & Zoning
311 Hauss Square Room 329, New Albany, IN 47150

Within 15 calendar days after receipt of the complaint, **Scott Wood, ADA Coordinator**, or his designee will meet with the complainant to discuss the complaint and the possible resolutions. Within 15 calendar days of the meeting, **Scott Wood, ADA Coordinator**, or his designee will respond in writing, and where appropriate, in a format accessible to the complainant, such as large print, Braille, or audio tape. The response will explain the position of the City of New Albany and offer options for substantive resolution of the complaint.

If the response by **Scott Wood, ADA Coordinator**, or his designee does not satisfactorily resolve the issue, the complainant and/or his/her designee may appeal the decision within 15 calendar days after receipt of the response to the Mayor or his designee.

Within 15 calendar days after receipt of the appeal, the Mayor or his designee will meet with the complainant to discuss the complaint and possible resolutions. Within 15 calendar days after the meeting, the Mayor or his designee will respond in writing, and, where appropriate, in a format accessible to the complainant, with a final resolution of the complaint.

All written complaints received by **Scott Wood, ADA Coordinator**, or his designee, appeals to the Mayor or his designee, and responses from these two offices will be retained by the City of New Albany for at least three years.



Pedestrian Facilities

The City of New Albany has adopted Accessibility Guidelines for Pedestrian Facilities in the Public Right-of-Way (PROWAG) as standards for assessment of ADA compliance and design for public streets. The PROWAG document has not been adopted or approved, but it is recognized as a best practice and has been recommended for use by the Federal Highway Administration (FHWA).

All pedestrian facilities constructed or replaced by the City of New Albany or as part of any planned developments shall be built in accordance with the PROWAG. A copy of the standards for pedestrian facilities can be found online at www.access-board.gov or in Appendix G.

Building Facilities and Programs

The City of New Albany will make all reasonable modifications to ensure that people with disabilities have equal opportunity to enjoy all of its facilities, programs, services, and activities. The 2010 ADA Standards for Accessible Design have been adopted as design standards pertaining to ADA compliance of City facilities and programs. The design standards can be found online at www.access-board.gov or in Appendix H.

Website

The City of New Albany will continue to improve its website design in order to make web content more accessible. As such, the City follows recommendations as outlined in the Web Content Accessibility Guidelines (WCAG) 2.0 to ensure web site information is accessible to broad range of people with disabilities, including blindness and low vision, deafness and hearing loss, learning disabilities, cognitive limitations, limited movement, speech disabilities, photosensitivity and combinations of these. The guidelines for website accessibility can be found online at www.w3.org/tr/wcag or in Appendix I.



Self-Evaluation of Programs, Services and Activities

The purpose of the self-evaluation for the City of New Albany was to identify all the physical barriers that exist currently in The City in order to create a schedule and priority list for removing the barriers. The second purpose was to create a record of areas that were compliant. Therefore, if the ADA rules were to change the City can determine which items or areas may be affected and re-evaluate those items or areas to determine if they would become non-compliant based on new laws.

The City compiled a list of all of its public programs, services, activities, facilities, sidewalk and existing curb ramp locations to ensure that people with disabilities have equal access to said public programs, services, activities, facilities, sidewalk and curb ramp locations.

➤ Public Streets

This assessment of ADA compliance for public streets in New Albany is based on the 2011 Proposed Accessibility Guidelines for Pedestrian Facilities in the Public Right-of-Way (PROWAG), published by the United States Access Board. The PROWAG document has not been adopted or approved, but it is recognized as a best practice and has been recommended for use by the Federal Highway Administration (FHWA). Compliance or non-compliance as noted herein is in reference to PROWAG, assuming it is the standard by which we should be measured. The City of New Albany does not endorse or dispute the validity of PROWAG.

The City of New Albany has over 160 miles of public streets, and over 2,400 public street curb ramp locations, including intersections under the Indiana Department of Transportation's (INDOT) jurisdiction. There are 63 signalized intersections in the City, 16 of which are currently maintained by INDOT. Improvements to any associated pedestrian signals, ramps and crosswalks will be evaluated on a case by case basis as any adjacent or planned improvements are considered, or as recommendations or complaints are received.

It has been and continues to be a priority for the City to improve accessibility for pedestrians through the expansion of an accessible sidewalk network. The City has replaced sidewalk and curb ramps in an attempt to make the City more traversable for all of its citizens and visitors. Additionally, the City requires that all new developments and site expansions or improvements include accessible facilities in the public rights-of-way; reviews all transportation capital projects for pedestrian access and compliance with the current ADA design standards and guidelines; considers constructing new and/or replacing non-compliant existing curb ramps



adjacent to road reconstruction, overlay or improvement projects; and replaces deteriorated and non-compliant sidewalks as budget allows.

➤ **Sidewalk and Curb Ramps**

The City recently had an inventory of curb ramps for all streets in the City limits completed. This data was used to create a map of all the existing curb ramps to sort out which ramps were non-compliant and see if there were any particular areas where the curb ramps needed to be addressed. The inventory of sidewalks throughout the City is currently underway. Upon completion of the sidewalk inventory the data will be added to the maps and analyzed in this document.

The curb ramps inventory process included using GPS survey equipment to locate the ramps as well as either a visual inspection or a more detailed measured inspection. The visual inspection was to serve as a screening of pedestrian facilities that can easily be identified as not meeting standards due to items such as gaps in sidewalks, curb ramps not being present, no detectable warnings on curb ramps, etc. Any ramps that appeared to be ADA compliant were noted. In some instances, curb ramps had a higher level analysis to confirm they are ADA compliant. This analysis was only performed when it was feasible to do so.

The ramps were assigned four different designations:

- None – Any location that has no ramp but should
- Non-ADA – Any ramp that is clearly not ADA compliant
- ADA – Any ramp that appears to be ADA compliant but was not verified
- ADA-Confirmed – Any ramp that was confirmed to be ADA compliant

The curb ramp inventory identified 2,472 curb ramps in the City with approximately 52% of the ramps meeting current design standards based on the visual inspection and 13% of the ramps confirmed to meet the design standards based on the higher level analysis. The repair/improvement estimate for non-compliant curb ramps is approximately \$1.73 million based on an estimated replacement cost of \$2,000 per ramp. A map of the curb ramp inventory and assessed designations can be found in Appendix C.

The review of the City's sidewalk network is currently ongoing. The information gathered during this review will be added into this document upon its completion. The sidewalk inventory and assessment will also be added to the Inventory Maps found in Appendix C.



A set of Curb Ramp and Sidewalk Inventory Maps were developed to depict the locations of all existing curb ramps within the City. Curb ramps were located using GPS and plotted on the maps with a color-coded legend to identify which ramps are compliant. The curb ramp inventory was completed in a manner that will allow for inclusion in City's current GIS and allow for ongoing updates to the data as the City continues to make ADA improvements. The sidewalk inventory is being completed in a similar manner. A copy of the Curb Ramp and Sidewalk Inventory Maps is located in Appendix C.

➤ **City Facilities**

The City of New Albany is directly responsible for ADA compliance as owner or operator of numerous facilities. As required, City staff has conducted a self-evaluation of all buildings, parks, etc. that are owned or operated by the City of New Albany. The self-evaluation includes site and architectural barriers consistent with the requirements outlined in the 2010 ADA Standards for Accessible Design. The on-site evaluation at each location included assessment of the parking area(s), accessible routes from the parking area(s) to the building entrance(s) and all publicly accessible areas within each facility. A complete list of the facilities assessed with any noted barriers is located in Appendix D.

➤ **City Programs, Classes and Events**

The City of New Albany is committed to allowing persons with disabilities to participate in municipally sponsored programs, classes and events. This includes recreation opportunities sponsored by the City's Parks and Recreation Department and other events hosted or sponsored by the City. The City has conducted self-evaluations of the accessibility of all New Albany sponsored programs, classes and events, which are summarized in Appendix E.

The assessment method used in development of the ADA Transition Plan was intended to be efficient, yet comprehensive. The City of New Albany understands that the self-evaluation process is critical to the overall success in implementing and maintaining a quality ADA Transition Plan. The intent is to continually build upon the initial assessment completed as part of this plan as budget allows.



General Overview

City of New Albany staff is responsible for making recommendations regarding barrier removal projects on an annual basis. The ADA Coordinator will review all recommendations provided by staff and collaborate with the Mayor for authorization of the selected projects.

It should be noted that sometimes it is not feasible to meet the technical requirements for ADA compliance when improving accessibility of existing facilities. The PROWAG states that “where existing physical constraints make it impracticable for altered elements, spaces or facilities to fully comply with the requirements for new construction, compliance is required to the extent practicable within the scope of the project.” Constraints may include items such as right-of-way availability, adjacent developed facilities, drainage and the presence of a notable natural or historic feature.

Additionally, under Program Accessibility of Title II of the ADA, public entities are not necessarily required to make each of their existing facilities accessible, as long as its programs, activities and services are readily accessible as a whole. Numerous options are available for achieving program accessibility, which include but are not limited to the following:

1. Structural methods such as alteration of existing facilities and acquisition or construction of additional facilities.
2. Nonstructural methods such as assignment of aides to beneficiaries or provisions to provide services at alternate accessible sites.

Prioritization of Barrier Removal Projects

Recognizing that the City has annual budgets for infrastructure projects and will not be able to make all building and pedestrian facilities fully accessible immediately, New Albany must prioritize the ADA improvements to be completed.

The Pedestrian Traffic Generator Map on page 13 was developed to identify community facilities, parks, major shopping areas, schools, etc. that may experience higher volumes of pedestrian traffic. Additionally, the map depicts important arterials, collector roads, and local streets within the City that may also be serviced by pedestrian facilities. A distance of a ½ mile was estimated to be a reasonable distance at which pedestrians would be more likely to walk to the various destinations shown on the map. Therefore a shaded circle representing a ½ mile effective walk radius was placed at the center of each pedestrian traffic generator. Based on the proximity of the generators to one



PRIORITIZATION OF IMPROVEMENTS

another, the effective walk areas overlap indicating darker shaded areas where the density of pedestrian traffic would be anticipated to be greater.

The City of New Albany considers these areas to be higher priority areas for ADA improvements. As expected, the map depicts these regions to include the downtown business district, as well as along the corridors of major roads in the City, including Main Street, Spring Street, State Street, Vincennes Street, Silver Street, and to a lesser degree, Charlestown Road.

➤ **Curb Ramps**

The following criteria are used by the City of New Albany to help prioritize the addition, removal, or replacement of curb ramps:

1. Locations where sidewalk improvements are taking place
2. Locations requested by the public
3. Locations of higher density pedestrian traffic (as delineated on the City Pedestrian Traffic Generator Map on page 13)
4. Proximity to government facilities, medical facilities, parks, and schools.
5. All public street intersections in the City
6. Locations where crosswalks exist without curb ramps
7. Locations without current ramps and no crosswalks
8. Locations with ramps that do not appear to meet current standards

➤ **Sidewalks**

The following criteria are used by the City of New Albany to help prioritize the addition, removal or replacement of sidewalk:

1. Locations where curb ramp improvements are taking place
2. Locations requested by the public
3. Locations of higher density pedestrian traffic (as delineated on the City Pedestrian Traffic Generator Map on page 13)
4. Proximity to government facilities, medical facilities, parks, and schools
5. Locations that do not meet current standards

➤ **Traffic Signals**

The City of New Albany intends to improve traffic signals to meet ADA requirements as funds allow. The City will also advocate for improvements at signalized intersections within New Albany that are controlled by INDOT. A summary of traffic signals within the City can be found in Appendix F.




PRIORITIZATION OF IMPROVEMENTS

The priorities listed are a guide only, as any specific location requested to be improved, whether currently on the list or not, may move that specific location up in priority. Also, any location where adjacent work is to be completed may include improving a lower priority item. As maintenance and/or repair work is done to existing sidewalks, curb ramps, traffic signals etc., all replacement work will attempt to meet current ADA standards. If such work involves ADA ramps on one corner of an intersection, the receiving corner will be considered for inclusion in such work if it is not in compliance. Barrier removal is based on the field inventory conducted. As needs may arise, through either complaints from the public or by the City's own review, select specific locations may be addressed.



PRIORITIZATION OF IMPROVEMENTS



SCHEDULE OF ADA IMPROVEMENTS

The City of New Albany continues to make ADA accessibility improvements to pedestrian facilities within the public right-of-way. ADA upgrades are scheduled and completed as part of the City's annual maintenance projects, such as roadway resurfacing. Utilities will replace sidewalks and curb ramps to ADA standards in disturbed areas. Additionally, all planned transportation improvement projects include ADA improvements as part of the scope of work. As a result, whenever an intersection improvement project or new construction project takes place, any affected curb ramps, sidewalks and crosswalks shall be reconstructed for ADA compliance. The City is also planning to implement a sidewalk replacement program to improve its pedestrian facilities annually according to the prioritization previously noted. The schedule of ADA improvements is intended to be perpetual, meaning that it is continually ongoing and updated on an annual basis.

FUNDING AVAILABILITY AND UNDUE BURDEN

Multiple funding sources exist to assist the City in upgrading its infrastructure that is not currently ADA compliant. The ADA Transition Plan serves as a key component for the City to remain eligible for state and federal funding programs for making such improvements. The City of New Albany will continue to apply for funding to improve the accessibility of its infrastructure. Several of the funding sources are listed below.

- Congestion Mitigation and Air Quality Program
- Highway Safety Improvement Program
- Recreational Trails Program
- Safe Routes to School Program
- Surface Transportation Program
- Transportation Enhancement Activities Program
- Community Crossing Grants

The ADA does not require The City to take any action that it can demonstrate would result in a fundamental alteration in the nature of a program or activity, would create a hazardous condition for other people, or would represent an undue financial or administrative burden. This determination can only be made by the ADA Coordinator, department head, or designee and must be accompanied by a statement citing the reasons for reaching that conclusion. The determination that an undue financial or administrative burden would result will be based on an evaluation of all resources available for use in a program. For example, if a barrier removal action is judged unduly burdensome, The City must consider other options for providing access that would attempt to provide individuals with disabilities the benefits and services of the program



SCHEDULE AND FUNDING

and activity. Dependent upon funding availability, The City of New Albany will continue to implement a barrier removal program within the right-of-way and its facilities. Accessibility improvements that can be made through general maintenance of City facilities (signage, clear pathways, relocation of restroom fixtures, etc.), or as part of the regular administrative duties of department staff (providing documents in alternate forms, training, website improvements, etc.) will typically be completed first; with larger capital improvements projects being completed when necessary funding is available. Standards currently implemented by The City of New Albany, when undergoing new or improvement road projects, adhere to those ADA laws.



PREPARATION OF ANNUAL MONITORING REPORT

At the end of each fiscal year, the City provides an annual report to the City Council describing the work completed under implementation of the ADA Transition Plan during the previous twelve months period. The ADA Transition Plan Annual Report will be completed within one hundred and twenty (120) days from the end of the fiscal year and will include:

1. A summary or listing of all written complaints or requests for removal of particular barriers received since the prior report, including information specifying whether the City has taken action to remove the barrier.
2. Summaries of work done to improve access and/or remove physical barriers in conjunction with locally and federally funded projects.
3. Information on the City's efforts to leverage additional funding opportunities to support ADA improvements as identified in the Transition Plan.
4. A prospective outlook on the planned projects for the upcoming year based on the priority recommendations of the ADA Transition Plan and City staff. This will also account for planned roadway projects that will include ADA improvements as a component of the work to be completed.

A summary of all ADA Requests for Accommodation and Grievances can be found in Appendices J and K respectively. Appendix L contains a summary of the barriers removed on an annual basis and each year's program monitoring reports are located in Appendix M.

ADDITIONAL ADA PLAN COMMITMENTS

The City, through its ADA Coordinator, will provide all employees with annual reminders about the ADA requirements with links to instructional/training information, and any pertinent information regarding any changes to the ADA law since the initial plan or the previous year.



Additionally, the City is committed to providing the following:

1. Telephone

The City of New Albany proposes to have at least one TTY text telephone. To date, the City of New Albany has not received any complaints regarding communication with the City of New Albany.

2. Walk-In Service

At City of New Albany buildings where the public is assisted, there are pathways clear of temporary or permanent barriers. Improvements will be considered continuously as comments, requests for accommodation and/or grievances are received.

3. Public Meetings, Hearings, & Events

The City provides public meetings, hearings, or other events that are open and accessible to all citizens, regardless of disability. All departments that host public meetings, hearings, or other public events, provide accommodations for people with disabilities.

4. Printed Materials

The City provides a variety of informational and promotional materials for public use, including forms, brochures, fact sheets, reports, plans, proposals, agendas, ordinances, and resolutions. The City will provide printed materials in alternate formats, as requested.

5. Contracting and Purchasing

The City's current processes do not discriminate based on disability when selecting contractors, consultants or vendors for City projects, or services.

6. Employment

The City of New Albany does not discriminate on the basis of disability in its hiring or employment practices and always attempts to comply with all regulations promulgated by the U.S. Equal Employment Opportunity Commission under Title I of the ADA.



PUBLIC INPUT

The City of New Albany considers input from the community a very important component of the ADA Transition Plan. The City provided the following opportunities for individuals to comment on the plan:

- New Albany Board of Public Works and Safety meetings on February 20, 2018 and March 20, 2018.
- A copy of the plan was made available for review at the City's Planning and Zoning offices at 311 Hauss Square, Room 329.
- A copy of the plan was made available for review at the City of New Albany-Floyd County Public Library located at 180 W. Spring Street.
- The plan was available to the public on the City of New Albany's website at <http://www.cityofnewalbany.com>.

The City published notices regarding the ADA Transition Plan in the (New Albany) *News and Tribune* and on the City's website, Facebook and Twitter pages. The notices announced that the ADA Transition Plan document was available for review on the City's website, at the City's Planning and Zoning Department office and at the City of New Albany-Floyd County Public Library. Additionally, the notices stated that the City would hear any public comments at the regularly scheduled New Albany Board of Public Works and Safety meeting between February 20, 2018 and March 20, 2018.

These notices indicated the time period for which comments on the draft would be accepted and where comments should be submitted. Public comments were accepted for a period of no less than 30 days. A copy of the public comment form is provided in Appendix B.



REFERENCES

1. ***Americans with Disabilities Act of 1990***, Pub. L. No. 101-336, 104 Stat. 328 (1990).
2. ***Proposed Accessibility Guidelines for Pedestrian Facilities in the Public Right-of-Way***, United States Access Board, Washington, D.C., 2011.
3. ***2010 ADA Standards for Accessible Design***, Department of Justice, September 15, 2010.
4. ***Web Content Accessibility Guidelines (WCAG) 2.0***, World Wide Web Consortium (W3C), 2008.





TRANSITION PLAN

APPENDIX A

ADOPTED ADA RESOLUTIONS









TRANSITION PLAN

APPENDIX B

*ADA FORMS FOR
ACCOMMODATION, GRIEVANCE AND PUBLIC INPUT*





CITY OF NEW ALBANY, INDIANA ADA TITLE II REQUEST FOR REASONABLE ACCOMMODATION FORM

Instructions: Please fill out this form completely. The form may be mailed to or submitted at the address at the bottom of the page.

Date:	☐ Citizen	☐ Representative of Citizen
Reporting Individual Contact information		
Name:		
Address:		
Telephone Number:		
E-Mail Address:		
Preferred Method of Contact: ☐ E-Mail ☐ Telephone ☐ Mail		
Service, Program or Facility Requiring Accommodation		
Name of Program, Service or Facility:		
Date of Incident or Discovery:		
Describe the accommodation you are requesting (please use additional attachments as necessary):		
Response or Action Taken (for City of New Albany use only):		Date of Response or Action:
Signature of Reporting Individual:		

Please mail or submit to: Scott Wood, City of New Albany, 311 Hauss Square Room329, New Albany, IN 47150

For Office Use: Date Received: _____ Received By: _____



ADA
TRANSITION PLAN



ADA GRIEVANCE FORM

Today's Date: _____

Complainant: _____

Address: _____

City, State, Zip: _____

Telephone and E-mail: _____

Individual Discriminated Against: _____

Address: _____

City, State, Zip: _____

Telephone and E-mail: _____

Alleged Violation: _____ Date(s) of Occurrence: _____

Description of Violation and Town Department Involved: _____

Requested Action by Town to Correct Violation: _____

Has Complaint been Filed with State or Federal Agency: ☐ Yes ☐ No

Name of Agency: _____

Date Filed: _____

Contact Person: _____

Complainant Signature: _____





CITY OF NEW ALBANY ADA TRANSITION PLAN PUBLIC COMMENT FORM

Date of Comment:	
Contact Information of Individual Submitting Comment	
Name:	
Address:	
Telephone Number:	
E-Mail Address:	
Preferred Method of Contact: ☐ E-Mail ☐ Telephone ☐ Mail	
Please provide any comments that you have on the City of New Albany's ADA Transition Plan (please use additional attachments as necessary):	
Response (for City of New Albany use only):	Date of Response:

Please mail or submit to: Scott Wood, City of New Albany, 311 Hauss Square Room329, New Albany, IN 47150

For Office Use: Date Received: _____ Received By: _____





TRANSITION PLAN

APPENDIX C

SELF-EVALUATION & INVENTORY OF CURB RAMPS





SELF-EVALUATION & INVENTORY CURB RAMPS



	A	B	C	D	E	F	
1							1
2							2
3							3
4							4
5							5
6							6
7							7
	A	B	C	D	E	F	



SELF-EVALUATION & INVENTORY CURB RAMPS



TRANSITION PLAN





SELF-EVALUATION & INVENTORY CURB RAMPS



TRANSITION PLAN





SELF-EVALUATION & INVENTORY CURB RAMPS



TRANSITION PLAN






SELF-EVALUATION & INVENTORY CURB RAMPS



TRANSITION PLAN






SELF-EVALUATION & INVENTORY CURB RAMPS



TRANSITION PLAN






SELF-EVALUATION & INVENTORY CURB RAMPS



TRANSITION PLAN





SELF-EVALUATION & INVENTORY CURB RAMPS



TRANSITION PLAN




1 in = 750 ft



SELF-EVALUATION & INVENTORY CURB RAMPS



TRANSITION PLAN



SHEET C-2

- ADA (Visual Inspection)
- ADA (Measured)
- Not ADA Compliant
- No Ramp

1 in = 750 ft



SELF-EVALUATION & INVENTORY CURB RAMPS



TRANSITION PLAN






SELF-EVALUATION & INVENTORY CURB RAMPS



TRANSITION PLAN





SELF-EVALUATION & INVENTORY CURB RAMPS



TRANSITION PLAN






SELF-EVALUATION & INVENTORY CURB RAMPS



TRANSITION PLAN





SELF-EVALUATION & INVENTORY CURB RAMPS



TRANSITION PLAN





SELF-EVALUATION & INVENTORY CURB RAMPS



TRANSITION PLAN

SHEET D-2

- ADA (Visual Inspection)
- ADA (Measured)
- Not ADA Compliant
- No Ramp




1 in = 750 ft



SELF-EVALUATION & INVENTORY CURB RAMPS



TRANSITION PLAN



SHEET D-3

- ADA (Visual Inspection)
- ADA (Measured)
- Not ADA Compliant
- No Ramp

1 in = 750 ft



SELF-EVALUATION & INVENTORY CURB RAMPS



TRANSITION PLAN






SELF-EVALUATION & INVENTORY CURB RAMPS



TRANSITION PLAN





SELF-EVALUATION & INVENTORY CURB RAMPS



TRANSITION PLAN



1 in = 750 ft

SHEET D-6

- ADA (Visual Inspection)
- ADA (Measured)
- Not ADA Compliant
- No Ramp



SELF-EVALUATION & INVENTORY CURB RAMPS



TRANSITION PLAN





SELF-EVALUATION & INVENTORY CURB RAMPS



TRANSITION PLAN




1 in = 750 ft



SELF-EVALUATION & INVENTORY CURB RAMPS



TRANSITION PLAN





SELF-EVALUATION & INVENTORY CURB RAMPS



TRANSITION PLAN



SHEET E-4

- ADA (Visual Inspection)
- ADA (Measured)
- Not ADA Compliant
- No Ramp

1 in = 750 ft




SELF-EVALUATION & INVENTORY CURB RAMPS



TRANSITION PLAN

SHEET E-5

- ADA (Visual Inspection)
- ADA (Measured)
- Not ADA Compliant
- No Ramp




1 in = 750 ft



SELF-EVALUATION & INVENTORY CURB RAMPS



TRANSITION PLAN



1 in = 750 ft



SELF-EVALUATION & INVENTORY CURB RAMPS



TRANSITION PLAN



1 in = 750 ft



TRANSITION PLAN

APPENDIX D

SELF-EVALUATION & INVENTORY OF CITY FACILITIES





SELF-EVALUATION & INVENTORY

CITY OF NEW ALBANY OWNED OR OPERATED FACILITIES



AREAS REVIEWED IN ACCORDANCE WITH 2010 ADA STANDARDS FOR ACCESSIBLE DESIGN

Facility	Location/ Parcel #	Area of Facility	Date of Review	Date of Compliance	Entrance & Doors	Parking	Path of Travel	Elevators, Stairs & Railings	Common Areas	Public Restrooms & Drinking Fountains	Special Rooms/Built- in Elements	General Notes	Estimated Improvement Cost
Valley View Golf Course	3748 Lawrence Banet Road	Outside Staircase	5/2017		No Barriers Observed	Make accessible spaces 8 feet wide. Make van accessible spaces plus adjacent access aisle equal to at least 16 feet. Give all the accessible spaces a striped access aisle.	No Barriers Observed	No Barriers Observed	No Barriers Observed	No accessibility signage near restroom.	No Barriers Observed	Paved parking lot.	Restriping Parking Lot = \$500. Bathroom Signage = \$25 per bathroom
Joe Kraft Park	500 West 7th Street	Ramp / Park	5/2017			There is no parking lot.	No existing clear, accessible path of travel from parking to the facility entrance. No handrails on two ramps.	No Barriers Observed.				Path of travel redone and added to park playground.	Sidewalks = \$15 per linear foot
Binford Park	1701 Graybrook Lane	Bathrooms	5/2017		Inaccessible Interior door(s).	No Barriers Observed	No Barriers Observed	No Barriers Observed	No Barriers Observed		No Barriers Observed	Restrooms are locked.	TBD
Silver Street Park	2043 Silver Street	Bleachers	5/2017		Adjacent doors have less than 48 inches between them.		No Barriers Observed	All levels are not accessible by ramp or elevator.	No toe / knee clearance for bleachers or tables.	Does not have at least one accessible restroom per floor. Paper Towel dispenser is too high (50+ inches).			Accessible Elevator = \$28,000
Fire Station #1	1219 E. Market Street	Building	5/2017									Evaluation is underway.	TBD
Anderson Park	711 Hildreth Street	Park	5/2017		No Barriers Observed	Only has 1 accessible space, but 112 parking spots total.	No Barriers Observed	No Barriers Observed	No Barriers Observed	No accessibility signage near restroom. Paper towel dispenser is too high (55 inches).	No Barriers Observed		Restriping Parking Lot = \$500. Bathroom Signage = \$25 per bathroom
Fire Station #2	3037 Grant Line Road	Building	5/2017		No Barriers Observed	Accessible space is not 8 feet wide and does not have a striped access aisle.	No Barriers Observed	All levels open to the public are not accessible by ramp or elevator.	No Barriers Observed	No accessibility signage near restroom. Does not have at least one accessible restroom per floor.			Restriping Parking Lot = \$350. Bathroom Signage = \$25 per bathroom
Fire Station #4	210 W. Daisy Lane	Building	5/2017		No Barriers Observed	No Barriers Observed	One ramp is steeper than 1:20. Ramps over 6 feet long do not have handrails.		Some areas in the clear/open space are not 36 inches wide.	Does not have at least one accessible restroom per floor.	No Barriers Observed		TBD
Fire Station #5	2571 Charlestown Road	Building	5/2017		Interior doors are inaccessible.	No van accessible spaces. Accessible spaces are not 8 feet wide and do not have a striped access aisle. Parking lot lines are faded.	No Barriers Observed	No Barriers Observed.	There are protrusions that stick out 4 inches into the aisle between the heights of 27" to 80".	No accessibility signage near restroom. Does not have at least one accessible bathroom per floor. Restroom/stall is not at least 5' x 5'. No grip bars at the back and side of the toilet. Paper towel dispenser, soap dispenser, and mirror are too high (78", 76", and 66" respectively). Drinking fountain is higher than 36 inches and the flow of water from it is not at least 4 inches high.	No Barriers Observed	Has screen doors adjacent to each other.	Restriping Parking Lot = \$350. Bathroom Signage = \$25 per bathroom. Remodeling Bathroom to be handicapped = \$5,300 per bathroom.
Police Station	311 Hauss Square	Building	5/2017		It is not clear which of the main public entrances is the accessible entrance. Adjacent doors has less than 48 inches between them.	No Barriers Observed	Curb ramp slope (1:30) is steeper than 1:12.	There are stairs with handrails, but no mention of a ramp or elevator.	There are protrusions between the heights of 27" and 80" that stick out 4 inches into the aisle.	Does not have at least one accessible bathroom per floor.		One accessible parking spot. The rest of the parking lot is reserved.	Accessible Elevator = \$28,000. Remodel to make bathroom handicapped = \$5,300 per bathroom. Curb Ramp = \$1,200.
Municipal Utilities Office	303 Scribner Drive. STE 101	Suite inside of a building	5/2017		No Barriers Observed		There are uneven areas along the path of travel (more than a 1/2 inch)	There are stairs with handrails, but no mention of a ramp or elevator.	Service counter has no barriers observed, but nothing was mentioned about the general clear/open space.				TBD
Billy Herman Park	600 Scribner Drive	Park	5/2017		No Barriers Observed	No Barriers Observed	No Barriers Observed			There is no accessibility signage near the restroom. The restroom stall is not at least 5' x 5'. There are no grab bars at the back and side of the toilet.		There are handrails down the road to concession. A key is needed to use the bathroom.	Bathroom Signage = \$25 per bathroom. Remodeling Bathroom to be handicapped = \$5,300 per bathroom.



SELF-EVALUATION & INVENTORY
CITY OF NEW ALBANY OWNED OR OPERATED FACILITIES



AREAS REVIEWED IN ACCORDANCE WITH 2010 ADA STANDARDS FOR ACCESSIBLE DESIGN

Facility	Location/ Parcel #	Area of Facility	Date of Review	Date of Compliance	Entrance & Doors	Parking	Path of Travel	Elevators, Stairs & Railings	Common Areas	Public Restrooms & Drinking Fountains	Special Rooms/Built- in Elements	General Notes	Estimated Improvement Cost
Fire Station #3 / Headquarters	316 E. Spring Street	Building	5/2017		No Barriers Observed	No Barriers Observed	Path of travel is not clear of protruding objects between 27" and 80" from the ground.	No Barriers Observed		There is not one accessible restroom per floor. The toilet paper dispenser is not between 15" and 48" from the ground and no farther than 9" in front of the toilet. The paper towel dispenser is too high (51 inches).	No Barriers Observed	Front Entrance Ramp is covered by AC unit.	TBD
Fairmont Park	1725 Abbie Dell (Abbeydell Avenue)	Park	5/2017		No Barriers Observed	No Barriers Observed	No Barriers Observed	No Barriers Observed	No Barriers Observed	No Barriers Observed		There is no dedicated parking lot for the facility. They use the school parking lot. There is no public restroom there.	TBD
Street/Stormwater Headquarters	2113 Grant Line Road	Building	5/2017		Door Threshold is too high (at 1/2"). There is nothing mentioned about the interior doors.	No van accessible spaces. Their accessible space is not 8 feet wide. It does have an access aisle, but the access aisle needs to be striped. Need to add one more handicap spot.	No Barriers Observed	All levels open to the public are not accessible by ramp or elevator.	No Barriers Observed	There is no restroom / drinking fountain. No Barriers Observed.	No Barriers Observed		Accessible Elevator = \$28,000. Restripe Parking Lot = \$350
West Haven Cemetery	1145 West Street	Cemetery	5/2017		Exterior doors are nonaccessible. There is nothing mentioned about interior doors.	There is no parking lot.	No Barriers Observed	No Barriers Observed	No Barriers Observed	There is no restroom / drinking fountain. No Barriers Observed.	No Barriers Observed		TBD
Sertoma Park	1315 Mills Lane	Park	5/2017		There are no doors / entrances. No Barriers Observed.	Needs 1 accessible parking spot.	There is no path to the basketball court.	There is no need for stairs, elevators, or ramps. No Barriers Observed.	Need handicap accessible picnic table.	There is a porta potty. The drinking fountain needs to have the flow of water within 5 inches from the front of the unit.	No Barriers Observed	There are picnic tables under a shelterhouse. There is a porta potty as well as a new fountain. The drinking fountain is old. There is no path to the Basketball court.	Handicapped picnic table = \$900 per table. Sidewalks = \$15 per linear foot. Handicap porta potty = \$2,200
River Run	224 W. Daisy Lane	Park	5/2017		It is not clear which of the main public entrances is the accessible entrance.	No Barriers Observed	No Barriers Observed	No Barriers Observed	No Barriers Observed	No Barriers Observed	No Barriers Observed	There is a family restroom as well as the typical men/women bathrooms. There is a water park.	TBD
Millerwood Park	1759 Millerwood Drive	Park	5/2017		No Barriers Observed	There is no parking lot.	No solid surface path to Basketball court or playground. A ramp is needed.	No Barriers Observed	Need handicap accessible picnic table.	There are no restrooms / drinking fountains. No Barriers Observed	A ramp is needed on the playground.	There are picnic tables.	Accessible Ramp = \$2,000. Handicap picnic table = \$900 per table. Sidewalks = \$15 per linear foot.
Division Street Park	1728 Division Street	Park	5/2017		There are no doors / entrances. No Barriers Observed.	Accessible spaces are not 8 feet wide and do not have a 5 wide striped access aisle.	A path is needed to connect the parking lot to the park.	There is no need for stairs, elevators, or ramps. No Barriers Observed.	No Barriers Observed	There are no restrooms / drinking fountains. No Barriers Observed	No Barriers Observed	There is an open Basketball court with a paved lot.	Sidewalks = \$15 per linear foot
Cannon Acres Park	1935 Budd Road	Park	5/2017		There are no doors / entrances. However, there is a gate. No Barriers Observed.	Needs 4 accessible spaces. Install handicap signs. The parking lot lines are faded. The parking lot is made of gravel / dirt. Needs to have the accessible spaces paved.	No Barriers Observed	There is no need for stairs, elevators, or ramps. No Barriers Observed.	No Barriers Observed	There is a porta potty. No Barriers Observed.	No Barriers Observed	The parking lot is made of gravel / dirt. This is a dog park.	Pave enough of the parking lot for 4 handicapped spaces = \$14,000. Handicap porta potty = \$2,200.
Fairview Cemetery	800 E. 6th Street	Cemetery	5/2017		There are no doors. No Barriers Observed.	There is no parking lot.	No Barriers Observed	All levels open to the public are not accessible by ramp or elevator.	No Barriers Observed	There are no restrooms / drinking fountains. No Barriers Observed	No Barriers Observed		TBD
Ritter Park	1218 Culbertson Avenue	Park	5/2017		There are no doors / entrances. No Barriers Observed.	There is no parking lot.	No Barriers Observed	No Barriers Observed	No Barriers Observed	There are no restrooms / drinking fountains. No Barriers Observed	No Barriers Observed	There is no dedicated parking lot for the facility. They use the school parking lot. There is no public restroom there.	TBD



TRANSITION PLAN

APPENDIX E

SELF-EVALUATION & INVENTORY OF TRAFFIC SIGNALS





SELF-EVALUATION & INVENTORY TRAFFIC SIGNALS



INTERSECTION	PEDESTRIAN SIGNAL HEADS	PEDESTRIAN PUSHBUTTONS	ACCESSIBLE PEDESTRIAN SIGNALS	REVIEW DATE	COMPLIANCE DATE	ESTIMATED IMPROVEMENT COST	COMMENTS
Spring & Silver	8	0	8	6/5/2017	6/5/2017		
15th & Spring	8	8	0	6/5/2017		\$40,000	
E. 7th & Spring	8	8	0	6/5/2017		\$20,000	
Bank & Spring	8	8	0	6/5/2017		\$20,000	
Pearl & Spring	8	8	0	6/5/2017		\$20,000	
E. Elm & Pearl	8	8	0	6/5/2017		\$20,000	
Scribner & Market	8	0	0	6/5/2017		\$40,000	
Pearl & Market	8	8	0	6/5/2017		\$20,000	
Bank & Market	8	8	0	6/5/2017		\$20,000	
E. 7th & Market	8	8	0	6/5/2017		\$20,000	
Vincennes & Market	0	0	0	6/5/2017		\$15,000	
State & Oak	8	0	0	6/5/2017		\$40,000	
State & Cherry	8	0	0	6/5/2017		\$40,000	
State & Cottom	6	6	0	6/5/2017		\$15,000	
State & Green Valley (West St.)	6	0	0	6/5/2017			Signal Modernization in 2017
State & Captain Frank (Knable Ln.)	6	0	0	6/5/2017			Signal Modernization in 2017
State & Target Store (Kroger)	8	8	0	6/5/2017			Signal Modernization in 2017
State & Wesley Commons (Home Depot)	0	0	0	6/5/2017			Signal Modernization in 2017
State & Daisy	0	0	0	6/5/2017			Signal Modernization in 2017
Daisy & Green Valley	8	8	0	6/5/2017		\$20,000	



SELF-EVALUATION & INVENTORY TRAFFIC SIGNALS



INTERSECTION	PEDESTRIAN SIGNAL HEADS	PEDESTRIAN PUSHBUTTONS	ACCESSIBLE PEDESTRIAN SIGNALS	REVIEW DATE	COMPLIANCE DATE	ESTIMATED IMPROVEMENT COST	COMMENTS
Daisy & Graybrook	6	6	0	6/5/2017		\$20,000	
Daisy & Grant Line	6	6	0	6/5/2017		\$15,000	
Green Valley & Mt. Tabor	6	6	0	6/5/2017		\$15,000	
Charlestown & Vincennes	7	7	0	6/5/2017		\$20,000	
Charlestown & Beechwood	8	0	8	6/5/2017	6/5/2017		
Charlestown & Silver	0	0	0	6/5/2017		\$30,000	
Charlestown & Hardee's	0	0	0	6/5/2017		\$40,000	
Charlestown & McDonald	8	0	8	6/5/2017	6/5/2017		
Charlestown & Slate Run Road	4	4	0	6/5/2017		\$10,000	
Charlestown & Klermer (Old Ford)	6	6	0	6/5/2017		\$15,000	
Charlestown & Lafayette	6	6	0	6/5/2017		\$15,000	
Charlestown & Mt. Tabor	8	8	0	6/5/2017		\$20,000	
Charlestown & Blackiston Mill	8	8	0	6/5/2017		\$20,000	
Charlestown & Charlestown Crossing	8	8	0	6/5/2017		\$20,000	
Mt. Tabor & Bells	4	4	0	6/5/2017		\$10,000	
Grant Line & Barrack Obama Way (Security Pkwy)	2	2	0	6/5/2017		\$7,500	
Grant Line & Klermer (US)	0	0	0	6/5/2017	6/5/2017		No sidewalks, curb ramps or marked crosswalks present.
Grant Line & University Woods	8	8	0	6/5/2017		\$20,000	
Grant Line & Rolling Creek	8	8	0	6/5/2017		\$20,000	
Grant Line & McDonald	8	8	0	6/5/2017		\$20,000	



SELF-EVALUATION & INVENTORY TRAFFIC SIGNALS



INTERSECTION	PEDESTRIAN SIGNAL HEADS	PEDESTRIAN PUSHBUTTONS	ACCESSIBLE PEDESTRIAN SIGNALS	REVIEW DATE	COMPLIANCE DATE	ESTIMATED IMPROVEMENT COST	COMMENTS
Grant Line & Sleepy Lane	0	0	0	6/5/2017		\$40,000	
Grant Line & Beechwood	0	0	0	6/5/2017		\$7,500	One curb ramp with no receiving ramp present.
Vincennes & Ekin	8	8	0	6/5/2017		\$20,000	
Vincennes & Elm	8	8	0	6/5/2017		\$20,000	
Vincennes & Spring	8	8	0	6/5/2017		\$20,000	
Main & Pearl	8	8	0	6/5/2017		\$40,000	
Charlestown & Sunset	4	4	0	6/5/2017		\$20,000	
State & Elm	8	8	0	6/5/2017		\$20,000	
State & Spring	8	8	0	6/5/2017		\$20,000	
State & Market	8	8	0	6/5/2017		\$20,000	
State & Main	8	8	0	6/5/2017		\$20,000	
Spring & Scribner	8	8	0	6/5/2017		\$20,000	
Main & W. 5th	8	8	0	6/5/2017		\$20,000	
State & I-265 E	0	0	0	6/5/2017	6/5/2017		No sidewalks, curb ramps or marked crosswalks present.
State & I-265 W	0	0	0	6/5/2017	6/5/2017		No sidewalks, curb ramps or marked crosswalks present.
Grant Line & Mt. Tabor	2	2	0	6/5/2017		\$7,500	
Grant Line & I-265 E	0	0	0	6/5/2017	6/5/2017		No sidewalks, curb ramps or marked crosswalks present.
Grant Line & I-265 W	0	0	0	6/5/2017	6/5/2017		No sidewalks, curb ramps or marked crosswalks present.
Grant Line & Hausfeldt	0	0	0	6/5/2017		\$7,500	One curb ramp with no receiving ramp present.
Charlestown & St. Joe/Innovation	2	2	0	6/5/2017		\$7,500	



SELF-EVALUATION & INVENTORY TRAFFIC SIGNALS



INTERSECTION	PEDESTRIAN SIGNAL HEADS	PEDESTRIAN PUSHBUTTONS	ACCESSIBLE PEDESTRIAN SIGNALS	REVIEW DATE	COMPLIANCE DATE	ESTIMATED IMPROVEMENT COST	COMMENTS
Charlestown & I-265 E	0	0	0	6/5/2017	6/5/2017		No sidewalks, curb ramps or marked crosswalks present.
Charlestown & I-265 W	0	0	0	6/5/2017	6/5/2017		No sidewalks, curb ramps or marked crosswalks present.
Charlestown & Kamer Miller	0	0	0	6/5/2017	6/5/2017		No curb ramps or marked crosswalks present.



TRANSITION PLAN

APPENDIX F

SELF-EVALUATION & INVENTORY OF CITY PROGRAMS & EVENTS





SELF-EVALUATION & INVENTORY

PROGRAMS, CLASSES, AND EVENTS



FACILITY	CITY SPONSORED PROGRAM, CLASS OR EVENT	BARRIER	REVIEW DATE	COMPLIANCE DATE	ESTIMATED IMPROVEMENT COST	COMMENTS
Anderson Park	tournaments and leagues	None	6/1/2017	6/1/2017		
Bicentennial Park	Concerts (May, June, July, and August), Holiday Fest Tree Lighting	None	6/1/2017	6/1/2017		
Bicknell Park	fall bonfire and soccer	None	6/1/2017	6/1/2017		
Billy Herman Park	tournaments and leagues	None	6/1/2017	6/1/2017		
Binford Park	soccer	None	6/1/2017	6/1/2017		
Bud Flynn Center	staff training, art and senior programs	None	6/1/2017	6/1/2017		
Cannon Acres	soccer and special events	None	6/1/2017	6/1/2017		
Griffin Center	art, fitness, senior, youth, afterschool, and sports programs and special events indoors and outdoors	None	6/1/2017	6/1/2017		
Movie Night	Rotates all summer around the parks	None	6/1/2017	6/1/2017		
New Albany Dog Park	members only and special events such as Easter Egg Hunt and Trainings outdoors	None	6/1/2017	6/1/2017		
River Run Waterpark	swim lessons, open to general public in summer, and special events such as Police and Fire Day outdoors	None	6/1/2017	6/1/2017		
Riverfront Amphitheater	Independence Day Celebration, Trunk or Treat	None	6/1/2017	6/1/2017		
Silver Street Park	fitness, sports, leagues, afterschool programs and special events such as Easter Egg Hunt, Star Wars, etc indoors and outdoors	None	6/1/2017	6/1/2017		



TRANSITION PLAN

APPENDIX G

DESIGN STANDARDS FOR PEDESTRIAN FACILITIES





Proposed Accessibility Guidelines for Pedestrian Facilities in the Public Right-of-Way

July 26, 2011

UNITED STATES ACCESS BOARD
A FEDERAL AGENCY COMMITTED TO ACCESSIBLE DESIGN



UNITED STATES ACCESS BOARD
A FEDERAL AGENCY COMMITTED TO ACCESSIBLE DESIGN

1331 F Street, N.W. Suite 1000 • Washington, D.C. 20004-1111
(800) 872-2253 (voice) • (800) 993-2822 (TTY) • Fax: (202) 272-0081
Website: www.access-board.gov • E-mail: ta@access-board.gov

ARCHITECTURAL AND TRANSPORTATION BARRIERS COMPLIANCE BOARD	3
Preamble	3
Accessibility Guidelines for Pedestrian Facilities in the Public Right-of-Way	3
Supplementary Information	4
Availability of Proposed Guidelines with Figures	4
Statutory and Regulatory Background	4
Rulemaking History	9
Major Issues	10
Overview of Proposed Guidelines	12
Use of Mandatory Language in Proposed Guidelines	13
Impacts on State and Local Governments	13
Section-by-Section Analysis	17
Other Issues	45
Regulatory Process Matters	46
CHAPTER R1: APPLICATION AND ADMINISTRATION	57
R101 Purpose	57
R102 Equivalent Facilitation	57
R103 Conventions	57
R104 Referenced Standards	59
R105 Definitions	59
CHAPTER R2: SCOPING REQUIREMENTS	63
R201 Application	63
R202 Alterations and Elements Added to Existing Facilities	63
R203 Machinery Spaces	65
R204 Pedestrian Access Routes	65
R205 Alternate Pedestrian Access Routes	66
R206 Pedestrian Street Crossings	66
R207 Curb Ramps and Blended Transitions	66
R208 Detectable Warning Surfaces	67
R209 Accessible Pedestrian Signals and Pedestrian Pushbuttons	68
R210 Protruding Objects	68
R211 Signs	69
R212 Street Furniture	70
R213 Transit Stops and Transit Shelters	70
R214 On-Street Parking Spaces	71
R215 Passenger Loading Zones	71
R216 Stairways and Escalators	71
R217 Handrails	71
R218 Doors, Doorways, and Gates	71
CHAPTER R3: TECHNICAL REQUIREMENTS	73
R301 General	73
R302 Pedestrian Access Routes	73
R303 Alternate Pedestrian Access Routes	78
R304 Curb Ramps and Blended Transitions	78
R305 Detectable Warning Surfaces	83

TABLE OF CONTENTS

R306 Pedestrian Street Crossings	89
R307 Accessible Pedestrian Signals and Pedestrian Pushbuttons	91
R308 Transit Stops and Transit Shelters	91
R309 On-Street Parking Spaces	94
R310 Passenger Loading Zones	98
CHAPTER R4: SUPPLEMENTARY TECHNICAL REQUIREMENTS	99
R401 General	99
R402 Protruding Objects	99
R403 Operable Parts	100
R404 Clear Spaces	101
R405 Knee and Toe Clearance	101
R406 Reach Ranges	103
R407 Ramps	104
R408 Stairways	106
R409 Handrails	106
R410 Visual Characters on Signs	110
R411 International Symbol of Accessibility	111

ARCHITECTURAL AND TRANSPORTATION BARRIERS COMPLIANCE BOARD

36 CFR Part 1190

[Docket No. ATBCB 2011-04]

RIN 3014-AA26

Accessibility Guidelines for Pedestrian Facilities in the Public Right-of-Way

AGENCY: Architectural and Transportation Barriers Compliance Board.

ACTION: Notice of Proposed Rulemaking.

SUMMARY: The Architectural and Transportation Barriers Compliance Board is proposing accessibility guidelines for the design, construction, and alteration of pedestrian facilities in the public right-of-way. The guidelines ensure that sidewalks, pedestrian street crossings, pedestrian signals, and other facilities for pedestrian circulation and use constructed or altered in the public right-of-way by state and local governments are readily accessible to and usable by pedestrians with disabilities. When the guidelines are adopted, with or without additions and modifications, as accessibility standards in regulations issued by other federal agencies implementing the Americans with Disabilities Act, Section 504 of the Rehabilitation Act, and the Architectural Barriers Act, compliance with the accessibility standards is mandatory.

DATES: Submit comments by November 23, 2011. Hearings will be held on the proposed guidelines on September 12, 2011 from 9:30 to 11:30 a.m. in Dallas, TX; and on November 9, 2011 from 9:30 to 11:30 a.m. in Washington, DC.

ADDRESSES: Submit comments by any of the following methods:

- Federal eRulemaking Portal: <http://www.regulations.gov>. Follow the instructions for submitting comments. Regulations.gov ID for this docket is ATBCB-2011-0004.
- E-mail: row@access-board.gov. Include docket number ATBCB 2011-04 in the subject line of the message.
- Fax: 202-272-0081.
- Mail or Hand Delivery/Courier: Office of Technical and Informational Services, Access Board, 1331 F Street, NW, Suite 1000, Washington, DC 20004-1111.

All comments will be posted without change to <http://www.regulations.gov>, including any personal information provided.

The hearing locations are the Sheraton Dallas (San Antonio A Ballroom), 400 North Olive Street, Dallas, TX 75201; and the Access Board Conference Room, 1331 F Street, NW, Suite 800, Washington, DC 20004.

FOR FURTHER INFORMATION CONTACT: Scott Windley, Office of Technical and Information Services, Architectural and Transportation Barriers Compliance Board, 1331 F Street NW, Suite 1000,

Washington, DC 20004-1111. Telephone (202) 272-0025 (voice) or (202) 272-0028 (TTY). E-mail address row@access-board.gov.

SUPPLEMENTARY INFORMATION:

Availability of Proposed Guidelines with Figures

The proposed guidelines will be codified as an appendix to 36 CFR part 1190. In the past, the Architectural and Transportation Barriers Compliance Board (Access Board) submitted “camera ready” copy (i.e., images) of its guidelines to the Federal Register for the appendices since the guidelines included figures that illustrate the requirements in the guidelines. The appendices were not word searchable when viewed online because they are images. After discussions with the Office of the Federal Register, the Access Board has decided to submit the proposed guidelines as a Word document with only one image, the International Symbol of Accessibility (Figure R411), so the appendix will be word searchable when viewed on-line. A copy of the proposed guidelines with figures is available on the Access Board website at: <http://www.access-board.gov/prowac/nprm.htm>. Except for the International Symbol of Accessibility (Figure R411), the figures are for illustration purposes only and do not establish requirements. The copy of the proposed guidelines on the Access Board website also sets out advisory sections in shaded boxes, and indents subsections under the main sections.

Introduction

The Access Board is an independent federal agency established by section 502 of the Rehabilitation Act (29 U.S.C. 792).¹ The Access Board is responsible for developing accessibility guidelines for the design, construction, and alteration of facilities to ensure that they are readily accessible to and usable by individuals with disabilities. The Access Board’s guidelines play an important part in the implementation of three laws that require newly constructed and altered facilities to be accessible to individuals with disabilities: the Americans with Disabilities Act, Section 504 of the Rehabilitation Act, and the Architectural Barriers Act. As further discussed under the Statutory and Regulatory Background, these laws require other federal agencies to issue regulations which include accessibility standards for the design, construction, and alteration of facilities. The regulations issued by the other federal agencies to implement these laws adopt, with or without additions and modifications, the Access Board’s guidelines as accessibility standards. When the Access Board’s guidelines are adopted, with or without additions and modifications, as accessibility standards in regulations issued by other federal agencies implementing these laws, compliance with the accessibility standards is mandatory.

Statutory and Regulatory Background

Americans with Disabilities Act

1. The Access Board consists of 13 members appointed by the President from the public, a majority of which are individuals with disabilities, and the heads of 12 federal agencies or their designees whose positions are Executive Level IV or above. The federal agencies are: The Departments of Commerce, Defense, Education, Health and Human Services, Housing and Urban Development, Interior, Justice, Labor, Transportation, and Veterans Affairs; General Services Administration; and United States Postal Service.

The Americans with Disabilities Act (42 U.S.C. 12101 et seq.) is a federal civil rights law that prohibits discrimination against individuals with disabilities. Title II of the Americans with Disabilities Act covers state and local governments.² The Department of Justice is responsible for issuing regulations to implement Title II of the Americans with Disabilities Act, except for the public transportation parts.³ The regulations issued by the Department of Justice include accessibility standards for the design, construction, and alteration of facilities (other than facilities used in the provision of public transportation covered by regulations issued by the Department of Transportation).⁴ The Department of Justice's accessibility standards adopt, with additions and modifications, the Access Board's current guidelines, which are discussed below under the Need for Rulemaking.⁵ See 28 CFR 35.104 and 35.151.

The Department of Transportation is responsible for issuing regulations to implement the public transportation parts of Title II of the Americans with Disabilities Act.⁶ The regulations issued by the Department of Transportation include accessibility standards for the design, construction, and alteration of facilities used in the provision of public transportation covered by the public transportation parts of Title II of the Americans with Disabilities Act. The Department of Transportation's accessibility standards adopt, with additions and modifications, the Access Board's current guidelines, which are discussed below under the Need for Rulemaking. See 49 CFR 37.9 and Appendix A to 49 CFR part 37.

The Department of Justice is responsible for overall enforcement of Title II of the Americans with Disabilities Act. The Department of Justice has designated the Department of Transportation as the federal agency responsible for investigating complaints and conducting compliance reviews "relating to programs, services, and regulatory activities relating to transportation, including highways." See 28 CFR 35.190 (b) (8).

Section 504 of the Rehabilitation Act

2. Other titles of the Americans with Disabilities Act cover employers (Title I), private entities that own, lease, or operate places of public accommodation and commercial facilities (Title III), and telecommunications (Title IV). This preamble focuses on Title II because pedestrian facilities in the public right-of-way are constructed and altered by state and local governments.
3. Title II of the Americans with Disabilities Act contains two subtitles. Subtitle A applies to all state and local government programs, services, and activities. Subtitle B contains two parts. Subtitle B, Part I applies to designated public transportation provided by state and local governments by bus, rail, or other conveyance (other than aircraft or intercity or commuter rail) as a general or special service (including charter service) to the general public on a regular and continuing basis. Subpart B, Part II applies to public transportation provided by the National Railroad Passenger Corporation and commuter authorities by intercity and commuter rail. The Department of Justice is responsible for issuing regulations to implement Subtitle A of Title II, except for matters within the scope of authority of the Department of Transportation under Parts I and II of Subtitle B of Title II. See 42 U.S.C. 12134. The Department of Transportation is responsible for issuing regulations to implement Parts I and II of Subtitle B of Title II. See 42 U.S.C. 12149 and 12164.
4. Subtitle A of Title II of the Americans with Disabilities Act requires that the regulations issued by the Department of Justice include accessibility standards that are "consistent with the minimum guidelines and requirements issued by the Architectural and Transportation Barriers Compliance Board." 42 U.S.C. 12134(c). The accessibility standards issued by the Department of Justice can include additional or modified requirements provided they are consistent with the Access Board's guidelines.

Section 504 of the Rehabilitation Act (29 U.S.C. 794) (hereinafter referred to as “Section 504”) prohibits discrimination against individuals with disabilities under any program or activity receiving federal financial assistance. The term “program or activity” includes all the operations of a state or local government entity that receives federal financial assistance directly or indirectly from the federal government. See 29 U.S.C. 794 (b). Each federal agency that provides federal financial assistance is responsible for issuing regulations to implement Section 504 that are consistent with requirements established by the Department of Justice. See Executive Order 12250 in Appendix A to 28 CFR part 41. The Department of Justice requires facilities designed, constructed, or altered by recipients of federal financial assistance to be accessible to individuals with disabilities. See 28 CFR 41.58.

The Department of Transportation provides federal financial assistance to state and local governments for the development of transportation networks, including pedestrian facilities in the public right-of-way.⁷ The regulations issued by the Department of Transportation to implement Section 504 require facilities designed, constructed, or altered by recipients of federal financial assistance from the Department to comply with accessibility standards included in the Department’s regulations implementing the public transportation parts of Title II of the Americans with Disabilities Act, or the Uniform Federal Accessibility Standards. See 49 CFR §27.3. As discussed above, the accessibility standards included in the Department of Transportation regulations implementing the public transportation parts of Title II of the Americans with Disabilities Act adopt, with additions and modifications, the Access Board’s current guidelines, which are discussed below under the Need for Rulemaking. See 49 CFR 37.9 and Appendix A to 49 CFR part 37.

The Department of Transportation is responsible for investigating complaints and conducting compliance reviews under Section 504 relating to recipients of federal financial assistance from the Department. See 49 CFR 27.121 and 27.123.

Architectural Barriers Act

-
5. In September 2010, the Department of Justice issued regulations with revised accessibility standards for Titles II and III of the Americans with Disabilities Act (DOJ 2010 Standards). See 75 FR 56164 (September 15, 2010). Compliance with the DOJ 2010 Standards is required on or after March 15, 2012. State and local governments are permitted to comply with earlier standards (DOJ 1991 Standards without the elevator exception or UFAS) or the DOJ 2010 Standards between September 15, 2010 and March 14, 2012. Additional information on the applicable standards and their effective dates is available on the Department of Justice website at: http://www.ada.gov/revised_effective_dates-2010.htm. The DOJ 2010 Standards are available on the Department of Justice website at: http://www.ada.gov/2010ADASTandards_index.htm.
 6. Parts I and II of Subtitle B of Title II of the Americans with Disabilities Act require that the regulations issued by the Department of Transportation include accessibility standards that are “consistent with the minimum guidelines and requirements issued by the Architectural and Transportation Barriers Compliance Board.” 42 U.S.C. 12149 (b) and 12163. The accessibility standards issued by the Department of Transportation can include additional or modified requirements provided they are consistent with the Access Board’s guidelines.
 7. See Department of Transportation “Policy Statement on Bicycle and Pedestrian Accommodation Regulations and Recommendations” at: <http://www.dot.gov/affairs/2010/bicycle-ped.html>.
-

The Architectural Barriers Act (42 U.S.C. 4151 et seq.) requires certain facilities financed with federal funds to be accessible to individuals with disabilities. The Architectural Barriers Act covers facilities financed in whole or part by a federal grant or loan where the federal agency that provides the grant or loan is authorized to issue standards for the design, construction, or alteration of the facilities.⁸ See 42 U.S.C. 4151 (3). The General Services Administration is required to issue accessibility standards for facilities covered by the Architectural Barriers Act.⁹ See 42 U.S.C. 4156. The accessibility standards issued by the General Services Administration adopt, without any additions or modifications, the Access Board's current guidelines, which are discussed below under the Need for Rulemaking. See 41 CFR 102-76.65.

The Access Board is responsible for enforcing the Architectural Barriers Act. See 29 U.S.C. 792 (b) (1) and (e).

Need for Rulemaking

This section discusses the Congressional findings in the Americans with Disabilities Act that establish the need for accessibility guidelines, the Access Board's current accessibility guidelines, and why the Access Board is proposing to issue accessibility guidelines for pedestrian facilities in the public right-of-way.

Congressional Findings of Discrimination

The Americans with Disabilities Act was enacted in 1990 by overwhelming bipartisan majorities in the House of Representatives (377 – 28) and in the Senate (91 – 6).¹⁰ Congress compiled an extensive record of the discrimination experienced by individuals with disabilities in critical areas such as employment, public accommodations, state and local government services, and transportation. Congress found that “despite some improvements such forms of discrimination against individuals with disabilities continue to be a serious and pervasive social problem.” 42 U.S.C. 12101 (a) (2). Among the forms of discrimination that Congress found to be a continuing problem are “the discriminatory effects of architectural, transportation, and communication barriers.” 42 U.S.C. 12101 (a) (5). Congress found that “the continuing existence of unfair and unnecessary discrimination and prejudice denies people with disabilities the opportunity to compete on an equal basis and to pursue those opportunities for which our free society is justifiably famous, and costs the United States billions of dollars in unnecessary expenses resulting from dependency and nonproductivity.” 42 U.S.C. 12101 (a) (9). Congress declared that “the Nation's proper goals regarding individuals with disabilities are to ensure equality of opportunity, full

8. The Architectural Barriers Act also covers facilities constructed, altered, or leased by federal agencies; and facilities constructed or altered by the Washington Metropolitan Area Transit Authority. See 42 U.S.C. 4151 (1), (2), and (4).

9. The accessibility standards issued by the General Services Administration apply to all facilities covered by the Architectural Barriers Act, except for postal, military, and residential facilities. The United States Postal Service is responsible for issuing accessibility standards for postal facilities; the Department of Defense is responsible for issuing accessibility standards for military facilities; and the Department of Housing and Urban Development is responsible for issuing accessibility standards for residential facilities. See 42 U.S.C. 4153, 4154, and 4154a.

10. 101 Cong. Rec. H4629 and 4630 (July 12, 1990); 101 Cong. Rec. S9695 (July 13, 1990).

participation, independent living, and economic self-sufficiency for such individuals.” 42 U.S.C. 12101 (a) (8).

The purpose of the Americans with Disabilities Act is “to provide a clear and comprehensive national mandate for the elimination of discrimination against individuals with disabilities” and “to provide clear, strong, and consistent, enforceable standards addressing discrimination against individuals with disabilities.” 42 U.S.C. 12101 (b) (1) and (2). Congress directed the Access Board to supplement the accessibility guidelines developed earlier for the Architectural Barriers Act to include “additional requirements, consistent with this Act, to ensure that buildings, facilities, rail passenger cars, and vehicles are accessible in terms of architecture and design, transportation, and communication, to individuals with disabilities.” 42 U.S.C. 12204 (b).

Current Guidelines Developed Primarily for Buildings and Facilities on Sites

The Access Board’s current accessibility guidelines were issued in 2004 and are known as the Americans with Disabilities Act and Architectural Barriers Act Accessibility Guidelines (hereinafter referred to as “2004 ADA and ABA Accessibility Guidelines”).¹¹ 69 FR 44083 (July 23, 2004). The 2004 ADA and ABA Accessibility Guidelines revised and updated the Americans with Disabilities Act Accessibility Guidelines, which were issued by the Access Board in 1991 (hereinafter referred to as “1991 ADAAG”). 56 FR 35408 (July 26, 1991). The requirements in the 1991 ADAAG and 2004 ADA and ABA Accessibility Guidelines were developed primarily for buildings and facilities on sites.¹² Some of the requirements can be readily applied to pedestrian facilities in the public right-of-way. However, other requirements need to be adapted for pedestrian facilities in the public right-of-way.

11. The 2004 ADA and ABA Accessibility Guidelines are codified in 36 CFR part 1191 and consist of six appendices:

- Appendix A is the Table of Contents to the guidelines;
- Appendix B contains ADA Chapters 1 and 2, which include application and scoping requirements for the design, construction, and alteration of facilities covered by the Americans with Disabilities Act;
- Appendix C contains ABA Chapters 1 and 2, which include application and scoping requirements for the design, construction, and alteration of facilities covered by the Architectural Barriers Act;
- Appendix D contains Chapters 3 through 10, which include common technical requirements for the design, construction, and alteration of facilities covered by the Americans with Disabilities Act or the Architectural Barriers Act;
- Appendix E contains the index of terms and list of figures included in the guidelines; and
- Appendix F contains additions and modifications to the guidelines issued by the Department of Transportation.

The DOJ 2010 Standards and the Department of Transportation standards for transportation facilities used in the provision of transportation services covered by the transportation parts of Title II of the ADA and facilities covered by Section 504 adopt Appendices B and D, with additions and modifications. The General Services Administration standards for facilities covered by the Architectural Barriers Act adopt Appendices C and D, without additions and modifications.

12. The term “site” is defined in the 1991 ADAAG (see 3.5) and 2004 ADA and ABA Accessibility Guidelines (see 106.5 and F106.5) as a “parcel of land bounded by a property line or a designated portion of a public right-of-way.”

Proposed Guidelines Developed Specifically for Pedestrian Facilities in the Public Right-of-Way

The proposed guidelines are developed specifically for pedestrian facilities in the public right-of-way and address conditions and constraints that exist in the public right-of-way. As discussed below under the Major Issues, the requirements in the proposed guidelines make allowances for typical roadway geometry and permit flexibility in alterations to existing facilities where existing physical constraints make it impractical to fully comply with new construction requirements. The proposed guidelines also include requirements for elements and facilities that exist only in the public right-of-way such as pedestrian signals and roundabouts.

Rulemaking History

The Access Board began developing accessibility guidelines for pedestrian facilities in the public right-of-way shortly after the Americans with Disabilities Act was enacted in 1990. Proposed guidelines for state and local government facilities, including pedestrian facilities in the public right-of-way, were initially issued in 1992. 57 FR 60612 (December 21, 1992). Interim guidelines were issued in 1994. 59 FR 31676 (June 20, 1994). Final guidelines were issued in 1998, but did not include requirements for pedestrian facilities in the public right-of-way because comments submitted on the proposed and interim guidelines demonstrated a need for additional research, as well as education and outreach. 63 FR 2000 (January 13, 1998).

The Access Board subsequently sponsored research on accessible pedestrian signals and pedestrian pushbuttons, detectable warning surfaces, and pedestrian facilities at roundabouts.¹³ The Access Board also produced a series of videos, a design guide, and an accessibility checklist for pedestrian facilities in the public right-of-way, and conducted training programs around the country. The Access Board coordinated its work with organizations representing state and local government transportation officials and other transportation industry professionals, including the American Association of State Highway and Transportation Officials, Institute of Transportation Engineers, National Committee on Uniform Traffic Control Devices, and Transportation Research Board.

The Access Board established a federal advisory committee in 1999 to recommend accessibility guidelines for pedestrian facilities in the public right-of-way. The advisory committee included representatives of state and local governments, the transportation industry, disability organizations, and other interested groups.¹⁴ The advisory committee provided significant sources of expertise and produced consensus recommendations for accessibility guidelines for pedestrian facilities in the public right-of-way. The advisory committee presented its recommendations, “Building a True Community: Final Report of the Public Rights-of-Way Access Advisory Committee”, to the Access Board in 2001.¹⁵

The Access Board developed draft accessibility guidelines for pedestrian facilities in the public right-of-way based on the advisory committee’s recommendations, and made the draft guidelines available for public review and comment in 2002.¹⁶ 67 FR 41206 (June 17, 2002). The Access Board revised the

13. The reports on the research sponsored by the Access Board and technical assistance materials on accessible design of pedestrian facilities in the public right-of-way are available on the Access Board website at: <http://www.access-board.gov/prowac/index.htm>.

draft guidelines in 2005 and made the revised draft guidelines available for public review to facilitate the gathering of data for a regulatory assessment of the potential costs and benefits of the guidelines. 70 FR 70734 (November 23, 2005). The Access Board entered into an interagency agreement with the Volpe National Transportation Systems Center (Volpe Center) to gather data and prepare cost estimates for the regulatory assessment.¹⁷

Major Issues

Transportation officials who commented on the 2002 draft guidelines raised some major issues that are addressed below.

Alterations to Existing Facilities

The draft guidelines required alterations to existing facilities to comply with the requirements for new construction to the maximum extent feasible. Most of the improvements in the public right-of-way involve alterations to existing facilities. Transportation officials noted that the meaning of the term “to the maximum extent feasible” was not clear and wanted additional guidance on how to apply the guidelines when existing facilities are altered.

The proposed guidelines clarify that where elements, spaces, or facilities are altered, each altered element, space, or facility within the scope of the project must comply with the applicable requirements for new construction (see R202.3). The phrase “within the scope of the project” is intended to focus on whether the alteration project presents an opportunity to design the altered element, space, or facility in an accessible manner. It is not intended for additional work to be done outside the scope of the project. For example, if an alteration project involves only installing pedestrian signals at existing intersections and there are no detectable warning surfaces on the curb ramps at the intersections, the proposed

-
14. The following organizations were members of the advisory committee: AARP, America Walks, American Association of State Highway and Transportation Officials, American Council of the Blind, American Institute of Architects, American Public Transit Association, American Public Works Association, Association for Education and Rehabilitation of the Blind and Visually Impaired, Bicycle Federation of America, Californians for Disability Rights, Canadian Standards Association (Technical Committee on Barrier-Free Design), City of Birmingham (Department of Planning, Engineering and Permits), Council of Citizens with Low Vision International, Disability and Business Technical Assistance Centers, Disability Rights Education and Defense Fund, Federal Highway Administration, Hawaii Commission on Persons with Disabilities, Hawaii Department of Transportation, Institute of Traffic Engineers, Los Angeles Department of Public Works (Bureau of Street Services), Massachusetts Architectural Access Board, Municipality of Anchorage, National Center for Bicycling and Walking, National Council on Independent Living, National Federation of the Blind, New York State Department of Transportation, Paralyzed Veterans of America, Portland Office of Transportation, San Francisco Mayor’s Office on Disability, State of Alaska, TASH, Texas Department of Transportation, and The Seeing Eye.
 15. The advisory committee report is available on the Access Board website at: <http://www.access-board.gov/prowac/commrept/index.htm>.
 16. The 2002 and 2005 draft guidelines and comments submitted on the 2002 draft guidelines are available on the Access Board website at: <http://www.access-board.gov/prowac/index.htm>.
 17. Volpe Center, “Cost Analysis of Public Rights-of-Way Accessibility Guidelines” (November 29, 2010). The document is available in the rulemaking docket (ATBCB-2011-0004) at: <http://www.regulations.gov>.

guidelines would require accessible pedestrian signals and pedestrian pushbuttons to be provided at the intersections because they are within the scope of the project, but would not require detectable warning surfaces to be provided on the curb ramps because they are not within the scope of the project. The proposed guidelines also clarify that where elements are altered or added to existing facilities but the pedestrian circulation path to the altered or added elements is not altered, the pedestrian circulation path is not required to comply with the proposed requirements for pedestrian access routes (see R202.1). For example, if a new bench is installed on a sidewalk that has a cross slope exceeding 2 percent, the sidewalk is not required to be altered to reduce the cross slope because the bench is installed on the sidewalk.

In addition, the proposed guidelines recognize that it is not always possible for altered elements, spaces, or facilities to fully comply with new construction requirements because of existing physical constraints. Where existing physical constraints make it impracticable for altered elements, spaces, or facilities to fully comply with the requirements for new construction, compliance is required to the extent practicable within the scope of the project (see R202.3.1). Existing physical constraints include, but are not limited to, underlying terrain, right-of-way availability, underground structures, adjacent developed facilities, drainage, or the presence of a notable natural or historic feature. The proposed guidelines permit flexibility in alterations to existing facilities where needed.

Existing Facilities That Are Not Altered

Transportation officials expressed concern about application of the draft guidelines to existing facilities that are not altered. The proposed guidelines clarify that the guidelines do not address existing facilities unless they are included within the scope of an alteration undertaken at the discretion of a covered entity (see R101.2).

The Department of Justice regulations implementing Title II of the Americans with Disabilities Act contain requirements for state and local governments regarding program accessibility and existing facilities. See 28 CFR 35.150. The Department of Transportation regulations implementing Section 504 also contain requirements for recipients of federal financial assistance from the Department regarding compliance planning. See 49 CFR 27.11 (c). The Access Board acknowledges that transportation officials are concerned about their obligations under the Title II of the Americans with Disabilities Act and Section 504 for existing facilities that are not altered, but the Access Board does not have the authority to address the application of the proposed guidelines to existing facilities that are not altered. When the Department of Justice and Department of Transportation conduct rulemaking to include accessibility standards for pedestrian facilities in the public right-of-way in regulations implementing Title II of the Americans with Disabilities Act and Section 504, they will address the application of the accessibility standards to existing facilities that are not altered. Comments concerning existing facilities that are not altered should be directed to the Department of Justice and Department of Transportation when they conduct rulemaking to include accessibility standards for pedestrian facilities in the public right-of-way in regulations implementing Title II of the Americans with Disabilities Act and Section 504.

Allowances for Typical Roadway Geometry

The 1991 ADAAG and 2004 ADA and ABA Accessibility Guidelines specify a maximum running slope of 5 percent and maximum cross slope of 2 percent for walking surfaces on accessible routes. The draft

guidelines adapted these requirements for pedestrian access routes in the public right-of-way and made an allowance for typical roadway geometry by permitting the grade of pedestrian access routes within sidewalks to equal the general grade established for the adjacent street or highway. The draft guidelines also permitted the cross slope of pedestrian access routes within midblock pedestrian street crossings and of curb ramps at midblock pedestrian street crossings to equal the street or highway grade.

Transportation officials recommended that additional allowances be made for typical roadway geometry. The proposed guidelines include the following allowances for typical roadway geometry:

- The grade of pedestrian access routes within sidewalks is permitted to equal the general grade established for the adjacent street or highway (see R302.5).
- A maximum cross slope of 5 percent is permitted for pedestrian access routes within pedestrian street crossings without yield or stop control where vehicles can proceed through the intersection without slowing or stopping (see R302.6.1).
- The cross slope of pedestrian access routes within midblock pedestrian street crossings is permitted to equal the street or highway grade (see R302.6.2).
- The cross slope of curb ramps, blended transitions, and turning spaces at pedestrian street crossings without yield or stop control where vehicles can proceed through the intersection without slowing or stopping, and at midblock pedestrian street crossings are permitted to equal the street or highway grade (see R304.5.3).
- Clear spaces required at accessible pedestrian signals and pedestrian pushbuttons and at other accessible elements are permitted to have a running slope consistent with the grade of the adjacent pedestrian access route (see R404.2).

A maximum grade of 5 percent and maximum cross slope of 2 percent are required otherwise for pedestrian access routes within sidewalks and pedestrian street crossings (see R302.5 and R302.6).

Overview of Proposed Guidelines

The proposed guidelines apply to pedestrian facilities in the public right-of-way. The proposed guidelines define the public right-of-way to mean “public land or property, usually in interconnected corridors, that is acquired for or dedicated to transportation purposes” (see R105.5). The proposed guidelines ensure that the following facilities for pedestrian circulation and use located in the public right-of-way are readily accessible to and usable by pedestrians with disabilities:

- Sidewalks, pedestrian overpasses and underpasses, and other pedestrian circulation paths, including requirements for pedestrian access routes, alternate pedestrian access routes when pedestrian circulation paths are temporarily closed, and protruding objects along or overhanging pedestrian circulation paths;
- Pedestrian street crossings, medians, and pedestrian refuge islands, including requirements for curb ramps or blended transitions, and detectable warning surfaces;
- Pedestrian street crossings at roundabouts, including requirements for detectable edge treatments where pedestrian crossing is not intended, and pedestrian activated signals at multi-lane pedestrian street crossings;
- Pedestrian street crossings at multi-lane channelized turn lanes at roundabouts and at other signalized intersections, including requirements for pedestrian activated signals;

- Pedestrian signals, including requirements for accessible pedestrian signals and pedestrian pushbuttons;
- Transit stops and transit shelters for buses and light rail vehicles, including requirements for boarding and alighting areas at sidewalk or street level, boarding platforms, and route signs;
- Pedestrian at-grade rail crossings, including requirements for flangeway gaps;
- On-street parking that is marked or metered, and passenger loading zones;
- Pedestrian signs, including requirements for visible characters on signs and alternative requirements for audible sign systems and other technologies;
- Street furniture for pedestrian use, including drinking fountains, public toilet facilities, tables, counters, and benches; and
- Ramps, stairways, escalators, handrails, doors, doorways, and gates.

Use of Mandatory Language in Proposed Guidelines

The proposed guidelines use the mandatory language “shall” and “requirement” because the guidelines are intended to be adopted, with or without additions and modifications, as accessibility standards in regulations issued by other federal agencies implementing Title II of the Americans with Disabilities Act, Section 504, and the Architectural Barriers Act. In this regard, the proposed guidelines are analogous to model codes. Model codes use mandatory language but compliance with model codes is not mandatory until they are adopted by a state or local government. When the Access Board’s guidelines are adopted, with or without additions and modifications, as accessibility standards in regulations issued by other federal agencies implementing Title II of the Americans with Disabilities Act, Section 504, and the Architectural Barriers Act, compliance with the accessibility standards is mandatory. The other federal agencies will conduct separate rulemakings to include accessibility standards for pedestrian facilities in the public right-of-way in regulations implementing Title II of the Americans with Disabilities Act, Section 504, and the Architectural Barriers Act. The other federal agencies will establish the effective dates for compliance with the accessibility standards when they complete their rulemakings. The other federal agencies may permit use of the proposed guidelines as best practices pending the completion of their rulemakings. However, the proposed guidelines are not legally enforceable until adopted, with or without additions and modifications, as accessibility standards by other federal agencies in regulations implementing Title II of the Americans with Disabilities Act, Section 504, and the Architectural Barriers Act.

Impacts on State and Local Governments

When the proposed guidelines are adopted, with or without additions and modifications, as accessibility standards by other federal agencies in the regulations implementing Title II of the Americans with Disabilities Act, Section 504, and the Architectural Barriers Act, the accessibility standards will apply to units of state and local government that construct streets and highways.¹⁸ For ease of reference, these

18. Private entities that design, construct, or alter places of public accommodation or commercial facilities on sites are required to comply with accessibility standards included in regulations issued by the Department of Justice to implement Title III of the Americans with Disabilities Act. See 28 CFR 36.401 through 36.406. State or local laws may require sites with frontage on the public right-of-way or frontage that will revert to the public right-of-way to make frontage improvements in accordance with state or local standards which contain accessibility requirements that are similar to the proposed guidelines.

state and local governmental units are referred to as “state and local transportation departments” in this preamble but may go by different names (e.g., public works departments, or highway or streets departments) in their respective jurisdictions. State and local transportation departments may be required to comply with three accessibility standards. For example, a state or local transportation department that finances the design, construction, or alteration of a pedestrian facility in the public right-of-way with a federal grant or loan from the Department of Transportation would be required to comply with the accessibility standards issued by the Department of Justice in regulations implementing Title II of the Americans with Disabilities Act, the accessibility standards issued by the Department of Transportation in regulations implementing Section 504, and the accessibility standards issued by the General Services Administration in regulations implementing the Architectural Barriers Act. All three accessibility standards would be basically uniform because they adopt the proposed guidelines, but may vary to the extent that Department of Justice, Department of Transportation, and General Services Administration include additions or modifications to the proposed guidelines in their accessibility standards.

The Access Board prepared a regulatory assessment of the potential costs and benefits of the proposed guidelines. The regulatory assessment is available in the regulatory docket at <http://www.regulations.gov> and on the Access Board website at: <http://www.access-board.gov/prowac/index.htm>. The proposed guidelines are compared to a baseline to assess their potential costs and benefits. The baseline is how state and local transportation departments would design and construct pedestrian facilities in the public right-of-way in the absence of the proposed guidelines. All state transportation departments maintain design manuals and standard drawings for improvements in the public right-of-way.¹⁹ Most local transportation department also maintain design manuals and standard drawings for improvements in the public right-of-way that are consistent with the design manuals and standard drawings maintained by their state transportation departments. State and local transportation departments use publications issued by the American Association of State and Highway Transportation Officials (AASHTO) in their design manuals and standard drawings, including the “Policy on Geometric Design of Highways and Streets” (2004) (commonly referred to as the “AASHTO Green Book”) and the “Guide for the Planning, Design, and Operation of Pedestrian Facilities” (2004) which incorporate accessibility in the design of sidewalks and other pedestrian facilities.²⁰ The Federal Highway Administration as part of its stewardship and oversight responsibilities has also worked with state transportation departments to incorporate accessibility in their design manuals and standards drawings. The Federal Highway Administration has issued guidance that the accessibility standards in the Department of Justice regulations implementing Title II of the Americans with Disabilities Act and the Department of Transportation regulations implementing Section 504 “are to be used to the extent feasible” for the design of pedestrian facilities in the public right-of-way until new accessibility standards

19. Links to the design manuals and standard drawings maintained by state transportation departments are available on the Federal Highway Administration website at: <http://www.fhwa.dot.gov/programadmin/statemanuals.cfm> and <http://www.fhwa.dot.gov/programadmin/statestandards.cfm>.

20. The AASHTO “Policy on Geometric Design of Highways and Streets” and “Guide for the Planning, Design, and Operation of Pedestrian Facilities” incorporate accessibility in the design of sidewalks, including minimum clear width, passing spaces, grade, cross slope, protruding objects, and surface treatments; curb ramps, including detectable warning surfaces; pedestrian overpasses and underpasses; and transit stops and transit shelters.

are adopted for these facilities.²¹ The Federal Highway Administration has also issued guidance that the 2005 draft of the proposed guidelines for pedestrian facilities in the public right-of-way “are the currently recommended best practices, and can be considered the state of the practice that could be followed for areas not fully addressed” in the existing accessibility standards.²²

In the absence of the proposed guidelines, the regulatory assessment assumes that state and local transportation departments will use the revised accessibility standards in the Department of Justice regulations implementing Title II of the Americans with Disabilities Act (hereinafter referred to as “DOJ 2010 Standards”) to the extent feasible when designing, constructing, or altering pedestrian facilities in the public right-of-way, consistent with the guidance issued by the Federal Highway Administration, as well as other applicable standards and industry practices.²³ An analysis of the proposed guidelines compared to the DOJ 2010 Standards, other applicable standards, and industry practices is included in the appendix to the regulatory assessment. The analysis consists of three tables.

Table 1. Proposed Guidelines Contain Same Requirements as in DOJ 2010 Standards

Table 1 analyzes requirements in the proposed guidelines that are the same as requirements in the DOJ 2010 Standards.²⁴ The requirements in the proposed guidelines in Table 1 will have no impacts on state and local transportation departments compared to the requirements in the DOJ 2010 Standards because the requirements are the same.

Table 2. Proposed Guidelines Adapt Requirements in DOJ 2010 Standards

Table 2 analyzes requirements in the proposed guidelines that adapt requirements in the DOJ 2010 Standards to allow for conditions and constraints in the public right-of-way.²⁵ The requirements in the proposed guidelines in Table 2 do not establish greater requirements for accessibility in the public right-

21. See Federal Highway Administration, Office of Program Administration, “Pedestrians and Accessible Design” at: <http://www.fhwa.dot.gov/programadmin/pedestrians.cfm>. When the guidance was issued, the applicable accessibility standards in the Department of Justice regulations implementing Title II of the Americans with Disabilities Act and the Department of Transportation regulations implementing Section 504 adopted the 1991 ADAAG and permitted the Uniform Federal Accessibility Standards to be used.

22. See Federal Highway Administration, “Public Rights-of-Way Access Advisory” (January 23, 2006) at: <http://www.fhwa.dot.gov/environment/bikeped/prwaa.htm>.

23. See footnote 5 regarding the DOJ 2010 standards and effective dates.

24. The requirements analyzed in Table 1 include: drinking fountains, public toilet facilities, tables, counters, passenger loading zones, ramps, stairways, handrails, doors, doorways, gates, operable parts, clear spaces, knee and toe clearance, and reach ranges.

25. The requirements analyzed in Table 2 include: sidewalks and other pedestrian circulation paths, pedestrian street crossings, pedestrian overpasses and underpasses, pedestrian at-grade rail crossings, curb ramps and blended transitions, protruding objects, transit stops and transit shelters used by buses and light rail vehicles, on-street parking, and escalators. The requirements for transit stops and transit shelters used by buses and light vehicles are compared to the accessibility standards in the Department of Transportation regulations implementing the public transportation parts of Title II of the Americans with Disabilities Act.

of-way than the requirements in the DOJ 2010 Standards and industry practices. Some of the requirements in the proposed guidelines in Table 2 establish lesser requirements for accessibility in the public right-of-way than the requirements in the DOJ 2010 Standards. For example, where the pedestrian access route in a sidewalk is contained within the street or highway right-of-way, the grade of the pedestrian access route is permitted to equal the general grade established for the adjacent street or highway to allow for typical roadway geometry instead of the running slope requirements for accessible routes on sites. The requirements in the proposed guidelines in Table 2 will have no impacts on state and local transportation departments compared to the requirements in the DOJ 2010 Standards and industry practices, except for the 2 percent maximum cross slope requirement for pedestrian access routes contained within pedestrian street crossings with stop or yield control where vehicles slow or stop before proceeding through the intersection (see R204.3 and R302.6). This requirement will have more than minimal impacts on the design and construction of new tabled intersections in hilly urban areas that contain pedestrian street crossings with stop or yield control. The impacts are analyzed in the regulatory assessment and discussed below under Cross Slope (R302.6) in the Section-by-Section Analysis.

Table 3. Proposed Guidelines Contain Requirements Not in DOJ 2010 Standards

Table 3 analyzes requirements in the proposed guidelines for which there are no corresponding requirements in the DOJ 2010 Standards.²⁶ The requirements in the proposed guidelines in Table 3 are compared to other applicable accessibility standards and the 2009 edition of Manual on Uniform Traffic Control Devices for Streets and Highways (MUTCD). Where the requirements in the proposed guidelines in Table 3 are the same as the requirements in other applicable accessibility standards or the MUTCD, the requirements will have no impacts on state and local transportation departments. Where a requirement in the proposed guidelines in Table 3 differs from a corresponding requirement in other applicable accessibility standards or there is no corresponding requirement in other applicable accessibility standards, the analysis used the following factors to identify whether the requirement will have more than minimal impacts on state and local transportation departments:

- Whether the requirement can be easily incorporated into the design of the element or facility?
- Whether the requirement adds features to the element or facility?
- Whether the requirement reduces space needed for other purposes?
- What are the additional costs due to the requirement compared to the total design and construction costs for the element or facility?

A requirement that can be easily incorporated into the design of an element or facility, and does not add features to the element or facility or reduce space needed for other purposes will have minimal impacts on state and local transportation departments. A requirement that cannot be easily incorporated into the design of an element or facility, adds features to the element or facility, or reduces space needed for other purposes and that results in additional costs compared to the total design and construction costs of

26. The requirements analyzed in Table 3 include: alternate pedestrian access routes, pedestrian signal phase timing, accessible pedestrian signals and pedestrian pushbuttons, pedestrian street crossings at roundabouts, detectable warning surfaces on curb ramps and blended transitions at pedestrian street crossings, detectable warning surfaces on pedestrian at-grade rail crossings not located within a street or highway, pedestrian signs, and benches.

the element or facility which are not negligible (i.e., are worth considering) will have more than minimal impacts on state and local transportation departments.

The analysis identified three requirements in the proposed guidelines in Table 3 that will have more than minimal impacts on state and local transportation departments:

- Detectable warning surfaces on curb ramps and blended transitions at pedestrian street crossings (see R208.1 and R305);
- Accessible pedestrian signals and pedestrian pushbuttons (see R209); and
- Pedestrian activated signals at roundabout intersections with multi-lane pedestrian street crossings (see R206 and R306.3.2).

The impacts of these requirements are analyzed in the regulatory assessment and are discussed below under the relevant requirements in the Section-by-Section Analysis.

Question 1. Comments are requested on whether other requirements in the proposed guidelines will have more than minimal impacts on state and local transportation departments, in addition to the requirements identified in Tables 2 and 3. Comments should:

- Identify the requirement by section number or other information that identifies the specific requirement;
- Explain why the requirement will have more than minimal impacts using the factors described above or other appropriate factors; and
- Provide estimates of the additional costs due to the requirement compared to the total design and construction costs for the element or facility.

Question 2. Comments are requested on whether the requirements in the proposed guidelines have any unintended positive or negative consequences.

Question 3. Comments are requested on alternative regulatory approaches for achieving the objectives of the Americans with Disabilities Act, Section 504, and Architectural Barriers Act to eliminate the discriminatory effects of architectural, transportation, and communication barriers in the design and construction of pedestrian facilities in the public right-of-way.

Section-by-Section Analysis

The proposed guidelines consist of four chapters. Chapter R1 addresses the application and administration of the proposed guidelines. Chapter R2 contains scoping requirements. Chapter R3 contains technical requirements. Chapter R4 contains supplementary technical requirements, which are the same as in the 2004 ADA and ABA Accessibility Guidelines with a few exceptions. The sections in each chapter are discussed below. Sections marked as “advisory” contain advisory information related to the preceding section. Advisory sections do not establish mandatory requirements. Some advisory sections reference related mandatory requirements to alert readers about those requirements.

The Access Board is committed to writing guidelines that are clear, concise, and easy to understand so that persons who use the guidelines know what is required. If any of the proposed guidelines are

ambiguous or not clear, point out the problematic language in your comments so it can be improved in the final guidelines.

Chapter R1: Application and Administration

R101 Purpose

The proposed guidelines contain scoping and technical requirements to ensure that facilities for pedestrian circulation and use located in the public right-of-way are readily accessible to and usable by pedestrians with disabilities. When the guidelines are adopted, with or without additions and modifications, as accessibility standards in regulations issued by other federal agencies implementing Title II of the Americans with Disabilities Act, Section 504, and the Architectural Barriers Act, compliance with the accessibility standards is mandatory.

The proposed guidelines do not address existing facilities unless they are included within the scope of an alteration to an existing facility undertaken at the discretion of a covered entity. The Department of Justice regulations implementing Title II of the Americans with Disabilities Act contain requirements for state and local governments regarding program accessibility and existing facilities. See 28 CFR 35.150. The Department of Transportation regulations implementing Section 504 also contain requirements for recipients of federal financial assistance from the Department regarding compliance planning. See 49 CFR 27.11 (c). As discussed above under the Major Issues, transportation officials who commented on the 2002 draft guidelines expressed concern about existing facilities that are not altered. When the Department of Justice and Department of Transportation conduct rulemaking to include accessibility standards for pedestrian facilities in the public right-of-way in regulations implementing Title II of the Americans with Disabilities Act and Section 504, they will address the application of the accessibility standards to existing facilities that are not altered. Comments concerning existing facilities that are not altered should be directed to the Department of Justice and Department of Transportation when they conduct rulemaking to include accessibility standards for pedestrian facilities in the public right-of-way in regulations implementing Title II of the Americans with Disabilities Act and Section 504.

R102 Equivalent Facilitation

The use of alternative designs, products, or technologies that result in substantially equivalent or greater accessibility and usability than the proposed guidelines is permitted.

R103 Conventions

Conventional industry tolerances apply where dimensions are not stated as a range. Where the required number of accessible facilities or elements is based on ratios or percentages and remainders or fractions result, the next greater whole number is required. Where the required size or dimension of a facility or element is based on ratios or percentages, rounding down for values less than one half is permitted. Measurements are stated in metric and U.S. customary units, and each system of measurement is to be used independently of the other.

R104 Referenced Standards

The proposed guidelines incorporate by reference certain standards in the 2009 edition of the Manual on Uniform Traffic Control Devices for Streets and Highways (MUTCD). The referenced MUTCD standards are discussed below under the relevant requirements regarding the provision of alternate pedestrian access routes when a pedestrian circulation path is temporarily closed, the provision of accessible pedestrian signals and pedestrian pushbuttons, and pedestrian signal phase timing. The MUTCD is available on the Federal Highway Administration website at: <http://mutcd.fhwa.dot.gov>.

R105 Definitions

The proposed guidelines incorporate the MUTCD definitions for the following terms: highway, intersection, island, median, pedestrian, roundabout, sidewalk, splitter island, and street. The proposed guidelines define the following terms: accessible, alteration, blended transition, cross slope, curb line, curb ramp, element, facility, grade break, operable part, pedestrian access route, pedestrian circulation path, public right-of-way, qualified historic facility, running slope, and vertical surface discontinuities. These definitions are discussed in the sections where the terms are used. Collegiate dictionaries are used to determine the meaning of terms that are not defined in the proposed guidelines, referenced MUTCD standards, or regulations issued by federal agencies that adopt the proposed guidelines as accessibility standards. Singular and plural words, terms, and phrases are used interchangeably.

Chapter R2: Scoping Requirements

Scoping requirements specify what pedestrian facilities must comply with the proposed guidelines. Some of the scoping requirements are triggered where certain pedestrian facilities are provided such as pedestrian signals (see R209), street furniture (see R212), transit stops and transit shelters (see R213), on-street parking (see R214), and passenger loading zones (see R215). The scoping requirements reference the technical requirements that each pedestrian facility must comply with in order to be considered accessible. The technical requirements are discussed in Chapters R3 and R4.

R201 Application

The proposed guidelines apply to newly constructed facilities, altered portions of existing facilities, and elements added to existing facilities for pedestrian circulation and use located in the public right-of-way. The proposed guidelines apply to both permanent and temporary facilities in the public right-of-way. An advisory section provides examples of temporary facilities in the public right-of-way that are covered by the scoping requirements (e.g., temporary pedestrian circulation routes around work zones and portable public toilets).

Buildings and structures in the public right-of-way that are not covered by the proposed guidelines must comply with the applicable requirements in the 2004 ADA and ABA Accessibility Guidelines. An advisory section provides examples of buildings and structures in the public right-of-way that are not covered by the proposed guidelines and must comply with the applicable requirements in the 2004 ADA and ABA Accessibility Guidelines (e.g., towers and temporary performance stages and reviewing stands).

R202 Alterations and Elements Added to Existing Facilities

The proposed guidelines apply to alterations and elements added to existing facilities. Alterations are changes to an existing facility that affect or could affect pedestrian access, circulation, or use (see R105.5). Alterations include, but are not limited to, resurfacing, rehabilitation, reconstruction, historic restoration, or changes or rearrangement of structural parts or elements of a facility. The Department of Justice and Department of Transportation may provide guidance on the meaning of the word “resurfacing” when they conduct rulemaking to include accessibility standards for pedestrian facilities in the public right-of-way in regulations implementing Title II of the Americans with Disabilities Act and Section 504. Comments requesting guidance on the meaning of the term “resurfacing” should be directed to the Department of Justice and Department of Transportation when they conduct rulemaking to include accessibility standards for pedestrian facilities in the public right-of-way in regulations implementing Title II of the Americans with Disabilities Act and Section 504.

Where elements are altered or added to existing facilities but the pedestrian circulation path to the altered or added elements is not altered, the pedestrian circulation path is not required to comply with the proposed requirements for pedestrian access routes. For example, if a new bench is installed on an existing sidewalk that has a cross slope exceeding 2 percent, the sidewalk is not required to be altered to reduce the cross slope because the bench is installed on the sidewalk. Advisory information recommends that, where possible, added elements should be located on an existing pedestrian access route. This provision is based on similar provisions in the 2004 ADA and ABA Accessibility Guidelines which do not require the circulation path to altered elements or spaces to comply with the requirements for accessible routes where the circulation path to the altered elements or spaces is not altered (see 202.3, Exception 1; and F202.3, Exception 1).

Where existing physical constraints make it impractical for altered elements, spaces, or facilities to fully comply with new construction requirements, compliance is required to the extent practicable within the scope of the project. Existing physical constraints include, but are not limited to, underlying terrain, right-of-way availability, underground structures, adjacent developed facilities, drainage, or the presence of a notable natural or historic feature.

The 2004 ADA and ABA Accessibility Guidelines (see 202.4 and F202.4) and the Department of Justice regulations implementing Title II of the Americans with Disabilities Act (see 28 CFR 35.151 (b)) include an additional requirement for facilities on sites whereby an alteration that affects or could affect the usability of or access to an area containing a “primary function” must be made so as to ensure that, to the maximum extent feasible, the “path of travel” to the altered area is accessible, unless the additional cost and scope of the alterations to provide an accessible “path of travel” are disproportionate to the cost of the alteration to the “primary function” area. The Department of Justice regulations define the terms “primary function” and “path of travel.” See 28 CFR 35.151 (b) (4) (i) and (ii). According to the Department of Justice regulations, a “primary function” is a major activity for which the facility is intended. “Primary function” areas include the dining area of a cafeteria, the meeting rooms in a conference center, as well as offices and other work areas in which the activities of the public entity using the facility are carried out. Mechanical rooms, boiler rooms, supply storage rooms, employee lounges or locker rooms, janitorial closets, entrances, and corridors are not “primary function” areas. Restrooms are not “primary function” areas unless the provision of restrooms is a primary purpose of the area (e.g., restrooms in highway rest stops). Alterations to windows, hardware, controls, electrical outlets, and signage are not alterations that affect the usability of or access to a “primary function” area.

The Department of Justice regulations further state that a “path of travel” includes a continuous, unobstructed way of pedestrian passage by means of which the altered area may be approached, entered, and exited, and which connects the altered area with an exterior approach (including sidewalks, streets, and parking areas), an entrance to the facility, and other parts of the facility. An accessible “path of travel” may consist of walks and sidewalks; curb ramps and other interior or exterior pedestrian ramps; clear floor paths through lobbies, corridors, rooms, and other improved areas; parking access aisles; elevators and lifts; or a combination of these elements; and also includes the restrooms, telephones, and drinking fountains serving the altered area.

The Department of Justice regulations deem the additional cost of alterations to provide an accessible “path of travel” to the altered area disproportionate when it exceeds 20 percent of the cost of the alteration to the “primary function” area. See 28 CFR 35.151 (b) (4) (iii). When the additional cost of alterations to provide an accessible “path of travel” to the altered area is disproportionate, the Department of Justice regulations require the “path of travel” to be made accessible to the extent that it can be made accessible without incurring disproportionate costs (i.e., an amount equal to 20 percent of the cost of the alteration to the “primary function” area must be expended to provide an accessible “path of travel” to the altered area). See 28 CFR 35.151 (b) (4) (iv). A similar requirement is not included in the proposed guidelines because of the uncertainty how the terms “primary function” and “path of travel” as defined in the Department of Justice regulations for facilities on sites would apply to pedestrian facilities in the public right-of-way. Revising the definitions of “primary function” and “path of travel” to apply to pedestrian facilities in the public right-of-way will not necessarily result in additional accessibility. For example, if an area that contains a “primary function” is defined to include sidewalks, an accessible “path of travel” would be required to the altered sidewalks, which in effect would require the cost and scope of planned sidewalk alteration projects to be increased by 20 percent. Sidewalk alteration projects can be planned to take into account the additional 20 percent scope and cost of work. For example, if a 5 block sidewalk alteration project would be planned in the absence of a requirement for an accessible “path of travel” to the altered sidewalks, imposing a requirement for an accessible “path of travel” to the altered sidewalks could result in a 4 block sidewalk alteration project being planned and the additional 20 percent scope and cost of work would result in a 5 block sidewalk alteration project.

Transitional segments of pedestrian access routes must connect to unaltered segments of existing pedestrian circulation paths and comply with the technical requirements for pedestrian access routes to the extent practicable. Alterations must not decrease or have the effect of decreasing the accessibility of a facility or an accessible connection to an adjacent building or site below the requirements for new construction in effect at the time of the alteration.

Where the State Historic Preservation Officer or Advisory Council on Historic Preservation determines that compliance with a requirement would threaten or destroy historically significant features of a qualified historic facility, compliance is required to the extent that it does not threaten or destroy historically significant features of the facility. A qualified historic facility is a facility that is listed in or is eligible for listing in the National Register of Historic Places, or is designated as historic under state or local law (see R105.5)

R203 Machinery Spaces

Vaults, tunnels, and other spaces used by service personnel only are not required to comply with the proposed guidelines.

R204 Pedestrian Access Routes

A pedestrian access route is a continuous and unobstructed path of travel provided for pedestrians with disabilities within or coinciding with a pedestrian circulation path in the public right-of-way (see R105.5). Pedestrian access routes in the public right-of-way ensure that the transportation network used by pedestrians is accessible to pedestrians with disabilities. Pedestrian access routes in the public right-of-way are analogous to accessible routes on sites in that they connect to accessible elements, spaces, and facilities in the public right-of-way, including accessible pedestrian signals and pedestrian pushbuttons, accessible street furniture, accessible transit stops and transit shelters, accessible on-street parking spaces and parking meters and parking pay stations serving those parking spaces, and accessible passenger loading zones. Pedestrian access routes in the public right-of-way also connect to accessible routes at building and facility site arrival points.²⁷

Pedestrian access routes must be provided within:

- Sidewalks and other pedestrian circulation paths located in the public right-of-way;
- Pedestrian street crossings and at-grade rail crossings, including medians and pedestrian refuge islands; and
- Overpasses, underpasses, bridges, and similar structures that contain pedestrian circulation paths.

Where an overpass, underpass, bridge, or similar structure is designed for pedestrian use only and the approach slope to the structure exceeds 5 percent, a ramp, elevator, limited use/limited application elevator, or platform lift must be provided. Elevators and platform lifts must be unlocked during the operating hours of the facility served.

An advisory section notes that the Federal Highway Administration has issued guidance on the obligations of state and local governments to keep pedestrian access routes open and usable throughout the year, including snow and debris removal.

R205 Alternate Pedestrian Access Routes

Alternate pedestrian access routes must be provided when a pedestrian circulation path is temporarily closed by construction, alterations, maintenance operations, or other conditions. The alternate pedestrian access route must comply with the referenced MUTCD standards. The MUTCD standards require alternate pedestrian routes to be accessible and detectable, including warning pedestrians who are blind or have low vision about sidewalk closures. Proximity-actuated audible signs are a preferred means to warn pedestrians who are blind or have low vision about sidewalk closures.

R206 Pedestrian Street Crossings

27. The ADA and ABA Accessibility Guidelines require accessible routes on sites to connect to site arrival points, including public streets and sidewalks (see 206.2.1 and F206.2.1).

Pedestrian street crossings must comply with technical requirements in Chapter R3 that reference MUTCD standards for pedestrian signal phase timing. The technical requirements in Chapter R3 also include requirements for roundabouts and multi-lane channelized turn lanes.

R207 Curb Ramps and Blended Transitions

Curb ramps, blended transitions, or a combination of curb ramps and blended transitions must connect the pedestrian access routes at each pedestrian street crossing. Curb ramps and blended transitions must be wholly contained within the pedestrian street crossings served. Typically, two curb ramps must be provided at each street corner. In alterations where existing physical constraints prevent two curb ramps from being installed at a street corner, a single diagonal curb ramp is permitted at the corner.

R208 Detectable Warning Surfaces

Detectable warning surfaces consist of small truncated domes built in or applied to a walking surface that are detectable underfoot. On pedestrian access routes, detectable warning surfaces indicate the boundary between a pedestrian route and a vehicular route where there is a flush rather than a curbed connection for pedestrians who are blind or have low vision. Detectable warning surfaces are not intended to provide wayfinding for pedestrians who are blind or have low vision. An advisory section provides information on streetscape designs that can make wayfinding easier. Detectable warning surfaces must be provided at the following locations on pedestrian access routes and at transit stops:

- Curb ramps and blended transitions at pedestrian street crossings;
- Pedestrian refuge islands;
- Pedestrian at-grade rail crossings not located within a street or highway;
- Boarding platforms at transit stops for buses and rail vehicles where the edges of the boarding platform are not protected by screens or guards; and
- Boarding and alighting areas at sidewalk or street level transit stops for rail vehicles where the side of the boarding and alighting areas facing the rail vehicles is not protected by screens or guards.

Detectable warning surfaces are not required at pedestrian refuge islands that are cut-through at street level and are less than 1.8 meters (6 feet) in length in the direction of pedestrian travel because detectable warning surfaces must extend 610 millimeters (2 feet) minimum on each side of the island and be separated by a 610 millimeters (2 feet) minimum length of island without detectable warning surfaces (see R305.1.4 and R305.2.4). Installing detectable warning surfaces at cut-through pedestrian islands that are less than 1.8 meters (6 feet) in length would compromise the effectiveness of detectable warning surfaces. An advisory section recommends that where a cut-through pedestrian island is less than 1.8 meters (6 feet) in length and the pedestrian street crossing is signalized, the signal should be timed for a complete crossing of the street.

Comments from Individuals Who Are Blind or Have Low Vision

The National Federation of the Blind was a member of the advisory committee that recommended the proposed guidelines, but filed a minority report recommending detectable warning surfaces should be required only on curb ramps with slopes of 6.6 percent or less, and at medians and pedestrian refuge

islands. Comments on the 2002 draft guidelines from individuals who identified themselves as blind or having low vision supported requiring detectable warning surfaces on all curb ramps by a margin of 2:1.

Detectable Warning Surfaces on Curb Ramps

When the Access Board issued the 1991 ADAAG, the guidelines contained a requirement for detectable warning surfaces on curb ramps. The requirement was temporarily suspended between 1994 and 2001 pending additional research and review of issues relating to requirement. The Access Board deferred addressing detectable warning surfaces on curb ramps in the 2004 ADA and ABA Accessibility Guidelines pending completion of the guidelines for pedestrian facilities in the public right-of-way. As a result of these actions, there are different requirements for detectable warning surfaces on curb ramps in the accessibility standards included the regulations issued by the Department of Justice implementing Title II of the Americans with Disabilities Act and by the Department of Transportation implementing Section 504.

When the Department of Justice initially issued regulations in 1991 implementing Title II of the Americans with Disabilities Act, the regulations required state and local governments to use accessibility standards (hereinafter referred to as the “DOJ 1991 Standards”) that included the 1991 ADAAG which contained a requirement for detectable warning surfaces on curb ramps, or the Uniform Federal Accessibility Standards (UFAS) which did not contain a requirement for detectable warning surfaces on curb ramps.²⁸ When the Department of Justice adopted the DOJ 2010 Standards, those standards included the 2004 ADA and ABA Accessibility Guidelines which do not contain a requirement for detectable warning surfaces on curb ramps.

The Department of Transportation regulations implementing Section 504 require state and local governments that receive federal financial assistance directly or indirectly from the Department to use accessibility standards that include the 2004 ADA and ABA Accessibility Guidelines, as modified by the Department, or UFAS. See 49 CFR 27.3 (b). The Department of Transportation modified the 2004 ADA and ABA Accessibility Guidelines by retaining certain requirements from the 1991 ADAAG, including the requirement for detectable warning surfaces on curb ramps. See 406.8 in Appendix A to 49 CFR part 37.

State and local transportation departments will be affected differently by the requirement in the proposed guidelines for detectable warning surfaces on curb ramps depending on the accessibility standards that they use for curb ramps in the public right-of-way. The Access Board reviewed the standard drawings for the design of curb ramps on state transportation department websites and found that the transportation departments in all 50 states and the District of Columbia specify detectable warning surfaces on curb ramps in the standard drawings.²⁹ Most local transportation departments use standard drawings for the design of curb ramps that are consistent with the standard drawings maintained by their

28. UFAS was issued in 1984 by the General Services Administration and other federal agencies responsible for issuing accessibility standards for facilities covered by the Architectural Barriers Act. See 49 FR 31528 (August 7, 1984).

29. Links to each state transportation department’s standard drawings that specify detectable warning surfaces on curb ramps are available on the Access Board website at: <http://www.access-board.gov/prowac/index.htm>.

state transportation departments. These state and local transportation departments use either the DOJ 1991 Standards, which include the 1991 ADAAG requirement for detectable warning surfaces on curb ramps, or the Department of Transportation accessibility standards, which include the 2004 ADA and ABA Accessibility Guidelines as modified by the Department to include the requirement from the 1991 ADAAG for detectable warning surfaces on curb ramps.³⁰

Governmental Units Affected

State and local transportation departments are divided into four groups for the purpose of evaluating the impacts of the requirement in the proposed guidelines for detectable warning surfaces on curb ramps:

- Group 1 consists of state and local transportation departments that use UFAS for curb ramps as currently permitted by the Department of Justice and Department of Transportation regulations implementing Title II of the Americans with Disabilities Act and Section 504. UFAS did not contain a requirement for detectable warning surfaces on curb ramps. The Access Board is not aware of any state or local transportation departments that use UFAS. The Department of Justice regulations do not permit the use of UFAS on or after March 15, 2012. See 28 CFR 35.151 (c) (3). Thus, Group 1 will cease to exist as of March 15, 2012, and any state and local transportation departments currently in Group 1 will fall into one of the other groups.

Question 4. The Access Board seeks information on whether any state and local transportation departments currently use UFAS for curb ramps in the public right-of-way.

- Group 2 consists of state and local transportation departments that receive federal financial assistance directly or indirectly from the Department of Transportation. State and local transportation departments in Group 2 are required to comply with the accessibility standards in the Department of Justice regulations implementing Title II of the Americans with Disabilities Act and the Department of Transportation regulations implementing Section 504. Where the requirements in the accessibility standards in the Department of Justice and Department of Transportation regulations differ, the more stringent requirement must be used. Excluding any state and local transportation departments in Group 1, state and local transportation departments in Group 2 must comply with the requirement for detectable warning surfaces on curb ramps in the Department of Transportation regulations because it is the more stringent requirement. All state transportation departments and most local transportation departments are in Group 2 and specify detectable warning surfaces on curb ramps in their standard drawings. The requirement in the proposed guidelines for detectable warning

30. The DOJ 1991 Standards require detectable warning surfaces to extend the full width and depth of the curb ramp (see 4.7.7, Appendix E to 28 CFR part 36). The Department of Transportation standards require detectable warning surfaces to extend the full width of the curb ramp (exclusive of flared sides) and either the full depth of the curb ramp or 24 inches deep minimum measured from the back of the curb on the ramp surface (see 406.8, Appendix A to 49 CFR part 37). Guidance issued by the Department of Justice permits the use of the Department of Transportation standards for detectable warning surfaces on curb ramps. See Department of Justice, "ADA Best Practices Tool Kit for State and Local Governments, Curb Ramps and Pedestrian Crossings" (May 7, 2006) at: <http://www.ada.gov/pcatoolkit/toolkitmain.htm>.

surfaces on curb ramps will not have any impacts on state and local transportation departments in Group 2.

- Group 3 consists of local transportation departments that do not receive federal financial assistance directly or indirectly from the Department of Transportation. Local transportation departments in Group 3 are required to comply only with the accessibility standards in the Department of Justice regulations implementing Title II of the Americans with Disabilities Act. Excluding any local transportation departments in Group 1, local transportation departments in Group 3:
 - a) Used the DOJ 1991 Standards, which include the 1991 ADAAG and contain a requirement for detectable warning surfaces on curb ramps, before September 15, 2010. See 28 CFR 35.151 (c) (1).
 - b) Are permitted to use the DOJ 1991 Standards, which include the 1991 ADAAG and contain a requirement for detectable warning surfaces on curb ramps, or the DOJ 2010 Standards, which include the 2004 ADA and ABA Accessibility Guidelines and do not contain a requirement for detectable warnings on curb ramps, between September 15, 2010 and March 14, 2012. See 28 CFR 35.151 (c) (2).
 - c) Must use the DOJ 2010 Standards, which include the 2004 ADA and ABA Accessibility Guidelines and do not contain a requirement for detectable warnings on curb ramps, on or after March 15, 2012. See 28 CFR 35.151 (c) (3).

Thus, local transportation departments in Group 3 were required to provide detectable warning surfaces on curb ramps before September 15, 2010; may or may not be required to provide detectable warning surfaces on curb ramps between September 15, 2010 and March 14, 2012 depending on the accessibility standard they use (DOJ 1991 Standards or DOJ 2010 Standards); and are not required to provide detectable warning surfaces on curb ramps on or after March 15, 2012 pending the future adoption of accessibility standards for pedestrian facilities in the public right-of-way by the Department of Justice.

Question 5. The Access Board seeks information on whether local transportation departments in Group 3 will continue or discontinue providing detectable warning surfaces on curb ramps in the public right-of-way pending the future adoption of accessibility standards for pedestrian facilities in the public right-of-way by the Department of Justice.

- Group 4 consists of state and local transportation departments that do not comply with accessibility standards for curb ramps in the public right-of-way. The Department of Justice and Federal Highway Administration have provided guidance on accessibility standards that apply to curb ramps in the public right-of-way, including the requirement for detectable warning surfaces.³¹ Despite the guidance provided by the Department of Justice and the Federal Highway Administration on the accessibility standards that apply to curb ramps in the public right-of-way, there may be state and local transportation departments that do not comply with the standards.

31. See Department of Justice, "ADA Best Practices Tool Kit for State and Local Governments, Curb Ramps and Pedestrian Crossings" (May 7, 2006) at: <http://www.ada.gov/pccatoolkit/toolkitmain.htm>; and Federal Highway Administration, "Information on Detectable Warnings" (May 6, 2002) at: <http://www.fhwa.dot.gov/environment/bikeped/dwm.htm>.

Question 6. Comments are requested on whether the future adoption of accessibility standards for pedestrian facilities in the public right of way by the Department of Justice and Department of Transportation in regulations implementing Title II of the Americans with Disabilities Act and Section 504 will have a positive or negative effect, or no effect on the compliance rates of state and local transportation departments, particularly with respect to providing detectable warning surfaces on curb ramps.

Question 7. The Access Board seeks information on the number of curb ramps that are constructed or altered on an annual basis in the public right-of-way by state and local transportation departments.

Costs to Provide Detectable Warning Surfaces on Curb Ramps

Detectable warning surfaces are available in a variety of materials. The Volpe Center gathered data from local transportation departments and vendors on various detectable warning materials and estimated the costs of 8 square feet of the materials for a typical curb ramp as shown in the table below. The estimates do not include installation costs.

Detectable Warning Surfaces	Materials Costs for Typical Curb Ramp
Concrete pavers	\$48 to \$80
Brick pavers	\$128
Polymer and composite materials	\$120 to \$200
Stainless steel or cast iron products	\$240

Question 8. The Access Board seeks additional information on the costs for detectable warning materials (8 square feet) and installation of the materials on a typical curb ramp.

Detectable Warning Surfaces on Boarding Platforms Used by Buses and Rail Vehicles, and Boarding and Alighting Areas Used by Rail Vehicles

The 1991 ADAAG and 2004 ADA and ABA Accessibility Guidelines contain a requirement for detectable warning surfaces on rail platforms.³² The proposed guidelines adapt this requirement to transit stops in the public right-of-way, and require detectable warning surfaces on boarding platforms at transit stops for buses and rail vehicles (i.e., raised platforms used for level boarding by bus rapid transit systems and light rail systems) and at boarding and alighting areas at sidewalk or street level transit stops for rail vehicles. Detectable warning surfaces are not required where the edges of the boarding platform or the boarding and alighting areas facing the rail vehicles are protected by screens or guards.

Durability and Maintenance of Detectable Warning Surfaces

Transportation officials who commented on the 2002 draft guidelines expressed concern about the durability and maintenance of detectable warning surfaces. The National Cooperative Highway

32. See 1991 ADAAG, 10.3.1 (8); and 2004 ADA and ABA Accessibility Guidelines, 810.5.2.

Research Program (NCHRP) has conducted two studies on the durability and maintenance of detectable warning surfaces. The first study was completed in 2005 and reviewed performance information submitted by state and local transportation departments.³³ The performance information was limited in terms of the products reviewed and time period of review (about 2 years). The study noted that there were new promising detectable warning products on the market, and recommended that test methods be developed for evaluating the long-term performance and durability of the products. The second study was completed in 2010 and recommended procedures for testing and evaluating detectable warning products.³⁴ The test methods can be used by state and local transportation departments to select detectable warning products that will provide long-term performance and durability under different environmental conditions. Many state and local transportation departments have evaluated and approved detectable warning products that are suited to their environments.

R209 Accessible Pedestrian Signals and Pedestrian Pushbuttons

An accessible pedestrian signal and pedestrian pushbutton is an integrated device that communicates information about the WALK and DON'T WALK intervals at signalized intersections in non-visual formats (i.e., audible tones and vibrotactile surfaces) to pedestrians who are blind or have low vision. The pedestrian pushbutton has a locator tone for detecting the device and a tactile arrow to indicate which pedestrian street crossing is served by the device. The MUTCD contains standards for accessible pedestrian signals and pedestrian pushbuttons, but does not require that they be provided. The proposed guidelines require accessible pedestrian signals and pedestrian pushbuttons to be provided when new pedestrian signals are installed. For existing pedestrian signals, the proposed guidelines require accessible pedestrian signals and pedestrian pushbuttons to be provided when the signal controller and software are altered, or the signal head is replaced. Accessible pedestrian signals and pedestrian pushbuttons must comply with the referenced standards in the MUTCD and the technical requirements for operable parts in Chapter R4. Technical assistance and training on the installation of accessible pedestrian signals and pedestrian pushbuttons is available from the Access Board and transportation industry professional associations.³⁵

Comments from Individuals Who Are Blind or Have Low Vision

The National Federation of the Blind was a member of the advisory committee that recommended the proposed guidelines, but filed a minority report recommending that state and local governments consult with the local blind community to determine whether to provide accessible pedestrian signals and

33. "Synthesis of Maintenance and Durability Information for Detectable Warnings on Sidewalks" March 2005 at: <http://maintenance.transportation.org/Documents/DetectableWarning20-7%28177%29.pdf>.

34. "Procedures for Testing and Evaluating Detectable Warning Systems" March 2010 at: http://online-pubs.trb.org/onlinepubs/nchrp/nchrp_rpt_670.pdf.

35. Technical assistance and training on the installation of accessible pedestrian signals are available on the following websites:

Access Board at: <http://www.access-board.gov/research/pedestrian-signals/bulletin.htm>;

Accessible Design for the Blind: http://www.accessforblind.org/aps_abt.html;

Institute of Transportation Engineers at: <http://www.ite.org/education/olg.asp>;

National Highway Cooperative Research Program at: <http://www.apsguide.org/>; and

Transportation Research Board at: <http://www.trb.org/Main/Public/Blurbs/159938.aspx>.

pushbuttons on an intersection-by-intersection basis. Comments on the 2002 draft guidelines from individuals who identified themselves as blind or having low vision supported providing accessible pedestrian signals and pushbuttons at each signalized intersection where pedestrian signals are newly installed or replaced by a margin of 2:1.

Governmental Units Affected

The Transportation Equity Act for the 21st Century (TEA-21) directed that audible traffic signals be included in transportation plans and projects where appropriate. See 23 U.S.C. 217 (g). Some state and local transportation departments currently provide accessible pedestrian signals and pedestrian pushbuttons when pedestrian signals are newly installed or replaced at signalized intersections. The requirement in the proposed guidelines for accessible pedestrian signals and pedestrian pushbuttons will have impacts on state and local transportation departments that do not currently provide accessible pedestrian signals and pedestrian pushbuttons when pedestrian signals are newly installed or replaced at signalized intersections.

Question 9. The Access Board seeks information on how many state and local transportation departments currently provide accessible pedestrian signals and pedestrian pushbuttons when pedestrian signals are newly installed or replaced at signalized intersections.

Costs to Provide Accessible Pedestrian Signals and Pedestrian Pushbuttons

The Volpe Center estimated the additional cost for an accessible pedestrian pushbutton compared to conventional pushbutton is \$350 per unit. For a typical intersection with four crosswalks, two accessible pedestrian pushbuttons would be required at each corner for a total of eight units per intersection and a total additional cost of \$2,800 for the eight units. The cost of the units is expected to decrease as a result of the proposed guidelines due to greater standardization of customer requirements and increased orders. The total additional cost to provide accessible pedestrian signals and pedestrian pushbuttons, including labor and other equipment such as stub poles and conduit, will vary by location. The Volpe Center estimated that the total additional costs are \$3,600 per intersection based on a published cost study and interviews with local transportation departments.

Question 10. The Access Board seeks information from state and local transportation departments that currently provide accessible pedestrian signals and pedestrian pushbuttons on the additional costs to provide the accessible pedestrian signals and pedestrian pushbuttons.

The Volpe Center estimated that pedestrian signals are newly installed or replaced at 13,095 signalized intersections on an annual basis based on the following assumptions:

- There are over 300,000 existing signalized intersections in the United States using a rule-of-thumb of one signalized intersection per 1,000 population.³⁶
- There are 2,550 new signalized intersections in the United States each year based on the US Census Bureau forecast of future population growth (0.85 percent).

36. See MUTCD "Frequently Asked Questions – Part 4 – Highway Traffic Signals" at: http://mutcd.fhwa.dot.gov/knowledge/faqs/faq_part4.htm.

- Ninety (90) percent of new and existing signalized intersections in the United States provide pedestrian signals.
- The life cycle or replacement rate for existing pedestrian signals is 25 years.

The Volpe Center estimated that the total annual costs are \$47 million for requiring accessible pedestrian signals and pedestrian pushbuttons when pedestrian signals are newly installed or replaced at signalized intersections.

Question 11. Comments are requested on the assumptions used to estimate the total annual costs for requiring accessible pedestrian signals and pushbuttons when pedestrian signals are newly installed or replaced at signalized intersections.

R210 Protruding Objects

Objects that protrude into pedestrian circulation paths can be hazardous for pedestrians, especially pedestrians who are blind or have low vision. Objects along or overhanging any portion of a pedestrian circulation path must comply with the technical requirements for protruding objects in Chapter R4. Objects also must not reduce the clear width required for pedestrian access routes. An advisory section provides examples of street furniture and other objects that must comply with these requirements, and notes that the AASHTO “Guide for the Planning, Design, and Operation of Pedestrian Facilities” recommends that local governments regulate the use of sidewalks by private entities for activities such as outdoor dining, vending carts and stands, and street fairs under an encroachment permit process that addresses accessibility, including protruding objects and maintaining the clear width of pedestrian access routes.

R211 Signs

Signs that provide directions, warnings, or other information for pedestrians only and signs that identify routes served by transit stops must comply with the technical requirements for visual characters in Chapter R4. An advisory section provides examples of signs that are required and are not required to comply with the technical requirements for visual characters in Chapter R4. Signs displaying the International Symbol of Accessibility must be provided at accessible parking spaces and accessible passenger loading zones.

The 2004 ADA and ABA Accessibility Guidelines contain similar requirements for transit signs (see 810.4 and 810.6). In the 2004 ADA and ABA Accessibility Guidelines, characters on bus route signs must comply with the technical requirements for character height “to the maximum extent practicable.”³⁷ The phrase “to the maximum extent practicable” was intended to provide flexibility where there are restrictions on the size of signs. A similar provision is not included in the proposed guidelines because it is almost always practicable to comply with the technical requirements for character height.

37. The 2004 ADA and ABA Accessibility Guidelines also do not require bus route signs to comply with the technical requirements for minimum height above the ground and line spacing (see 703.5.6, 703.5.9, and 810.4).

Audible sign systems and other technologies are widely used today to transmit information and are more usable by pedestrians who are blind or have low vision.³⁸ Where audible sign systems and other technologies are used to transmit information equivalent to the information contained on signs, the signs are not required to comply with the technical requirements for visual characters in Chapter R4.

Question 12. The Access Board seeks information on technologies that are currently used or are under development to transmit information that is equivalent to the information contained on pedestrian signs and transit signs provided in the public right-of-way.

R212 Street Furniture

Drinking fountains, public toilet facilities, tables, and counters must comply with applicable requirements in the 2004 ADA and ABA Accessibility Guidelines. Where multiple single-user public toilet facilities are clustered at a single location, at least 5 percent, but no less than one, of the toilet facilities in each cluster must be accessible and identified by the International Symbol of Accessibility. At least 50 percent, but no less than one, of benches at each location must provide a clear space for a wheelchair adjacent to the bench. Benches at tables are not required to comply.

R213 Transit Stops and Transit Shelters

Transit stops and transit shelters must comply with the technical requirements for transit stops and transit shelters in Chapter R3. Transit stops in the public right-of-way typically serve fixed route bus systems, including bus rapid transit systems, and light rail transit systems. An advisory section notes that the Federal Highway Administration has issued guidance on the obligation of state and local transportation departments, metropolitan planning organizations, and transit agencies to coordinate the planning and funding of accessibility improvements to transit systems and facilities.

R214 On-Street Parking Spaces

Where on-street parking is provided on the block perimeter and the parking is marked or metered, a minimum number of parking spaces must be accessible and comply with the technical requirements for parking spaces in Chapter R3. For every 25 parking spaces on the block perimeter up to 100 spaces, one parking space must be accessible. For every additional 50 parking spaces on the block perimeter between 101 and 200 spaces, an additional parking space must be accessible. Where more than 200 parking spaces are provided on the block perimeter, 4 percent of the parking spaces must be accessible. Metered parking includes parking metered by parking pay stations. Where parking is metered by parking pay stations and the parking is not marked, each 6.1 meters (20 feet) of the block perimeter where parking is permitted is counted as one parking space for determining the minimum number of accessible parking spaces.

R215 Passenger Loading Zones

38.The ANSI approved standard “ICC A117.1-2009: Accessible and Usable Buildings and Facilities” includes technical requirements for remote infrared audible sign systems (see 703.8).

Where passenger loading zones are provided, at least one passenger loading zone for each 30 meters (100 feet) of continuous loading zone space or fraction thereof must be accessible and comply with the technical requirements for passenger loading zones in Chapter R3.

R216 Stairways and Escalators

Stairways on pedestrian circulation paths must comply with technical requirements for stairways in Chapter R4. Escalators on pedestrian circulation paths must comply with the applicable technical requirements in the 2004 ADA and ABA Accessibility Guidelines. Stairways and escalators cannot be part of a pedestrian access route.

R217 Handrails

Handrails are not required on pedestrian circulation paths. However, if handrails are provided on pedestrian circulation paths, the handrails must comply with the technical requirements for handrails in Chapter R4.

R218 Doors, Doorways, and Gates

Doors, doorways, and gates to pedestrian facilities such as transit shelters must comply with applicable technical requirements in the 2004 ADA and ABA Accessibility Guidelines.

Chapter R3: Technical Requirements

Technical requirements specify what design criteria elements, spaces, and facilities must comply with in order to be considered accessible.

R301 General

The technical requirements in Chapter R3 apply where required by the scoping requirements in Chapter R2, or where referenced by another technical requirement in Chapters R3 or R4.

R302 Pedestrian Access Routes

General (R302.1)

The technical requirements for pedestrian access routes are contained in R302, and adapt the technical requirements for accessible routes in the 2004 ADA and ABA Accessibility Guidelines to the public right-of-way. In alterations where existing physical constraints make it impractical to fully comply with the technical requirements, compliance is required to the extent practicable within the scope of the project (see R202.3.1).

Components (R302.2)

The components of pedestrian access routes and the technical requirements for each component are listed in R302.2. Sidewalks and other pedestrian circulation paths, pedestrian street crossings, and pedestrian overpasses and underpasses and similar structures must comply with all the technical

requirements in R302.3 through R302.7. Curb ramps and blended transitions must comply with the technical requirements in R302.7 and R304. Ramps must comply with the technical requirements in R407. Elevators, limited use/limited application elevators, platform lifts, and doors, doorways, and gates must comply with applicable technical requirements in the 2004 ADA and ABA Accessibility Guidelines.

Continuous Width (R302.3)

The continuous clear width of pedestrian access routes (exclusive of the width of the curb) must be 1.2 meters (4 feet) minimum, except for medians and pedestrian refuge islands where the clear width must be 1.5 meters (5 feet) minimum in order to allow for passing space. The AASHTO “Guide for the Planning, Design, and Operation of Pedestrian Facilities” recommends that sidewalks be wider than 1.2 meters (4 feet), particularly in urban areas. Where sidewalks are wider than 1.2 meters (4 feet), only a portion of the sidewalk is required to comply with the technical requirements in R302.3 through R302.7.

The advisory committee recommended a minimum width of 1.5 meters (5 feet) for pedestrian access routes. The proposed guidelines specify a minimum width of 1.2 meters (4 feet) in order to allow for street furniture and other objects that may be located on sidewalks. R210 prohibits street furniture and other objects from reducing the clear width required for pedestrian access routes. A minimum width of 1.2 meters (4 feet) will accommodate turns at intersections and building entrances. Advisory information recommends additional maneuvering clearance at turns or changes in direction, recesses and alcoves, building entrances, and along curved or angled routes, particularly where the grade exceeds 5 percent.

Passing Spaces (R302.4)

Where the clear width of pedestrian access routes is less than 1.5 meters (5 feet), passing spaces must be provided at intervals of 61 meters (200 feet) maximum. Passing spaces must be 1.5 meters (5 feet) minimum by 1.5 meters (5 feet) minimum. Passing spaces are permitted to overlap pedestrian access routes.

Grade (R302.5)

Grade is the slope parallel to the direction of pedestrian travel. Grade is calculated by dividing the vertical change in elevation by the horizontal distance covered, and is expressed as a percent. Where pedestrian access routes are contained within a street or highway right-of-way, the grade of the pedestrian access route is permitted to equal the general grade established for the adjacent street or highway, except that where pedestrian access routes are contained within pedestrian street crossings a maximum grade of 5 percent is required. This is consistent with the AASHTO “Policy on Geometric Design of Highways and Streets” which recommends that the sidewalk grade follow the grade of adjacent roadways, and also recommends maximum cross slopes for roadways. Where pedestrian access routes are not contained within a street or highway right-of-way, a maximum grade of 5 percent is required.

Cross Slope (R302.6)

Cross slope is the slope perpendicular to the direction of pedestrian travel (see R105.5). On a sidewalk, cross slope is measured perpendicular to the curb line or edge of the street or highway. Cross slope

impedes travel by pedestrians who use wheeled mobility devices since energy must be expended to counteract the perpendicular force of the cross slope. Cross slope makes it more difficult for pedestrians who use wheelchairs to travel on uphill slopes and to maintain balance and control on downhill slopes. Cross slope also negatively affects pedestrians who use braces, lower limb prostheses, crutches, or walkers, as well as pedestrians who have gait, balance, or stamina impairments. The maximum cross slope permitted on accessible routes in the 2004 ADA and ABA Accessibility Guidelines is 2 percent. In exterior environments, a maximum cross slope of 2 percent is generally accepted as adequate to allow water to drain off paved walking surfaces.

A maximum cross slope of 2 percent is specified for pedestrian access routes, except for pedestrian access routes contained within certain pedestrian street crossings in order to allow for typical roadway geometry. A 5 percent maximum cross slope is specified for pedestrian access routes contained within pedestrian street crossings without yield or stop control to avoid any unintended negative impacts on the control and safety of vehicles, their occupants, and pedestrians in the vicinity of the intersection. Pedestrian street crossings without yield or stop control are crossings where there is no yield or stop sign, or where there is a traffic signal that is designed for the green phase. At pedestrian street crossings without yield or stop control vehicles can proceed through the intersection without slowing or stopping. The cross slope of pedestrian access routes contained within midblock pedestrian street crossings is permitted to equal the street or highway grade.

Question 13. Comments are requested on whether the description of pedestrian street crossings without yield or stop control is clear, or whether there is a better way to describe such crossings?

In new construction, where pedestrian access routes within sidewalks intersect at corners, the 2 percent maximum cross slope requirement will result in level corners (i.e., the slope at the corners will not exceed 2 percent in each direction of pedestrian travel). The level corners will provide a platform for providing level spaces for curb ramps and blended transitions, pedestrian street crossings, and accessible pedestrian signals and pedestrian pushbuttons.

Newly Constructed Tabled Intersections That Contain Pedestrian Street Crossings With Yield or Stop Control

The 2 percent maximum cross slope requirement applies to pedestrian access routes within pedestrian street crossings with yield or stop control where vehicles slow or stop before proceeding through the intersection. The cross slope of the pedestrian access route within the pedestrian street crossing is the longitudinal grade of the street being crossed, and the 2 percent maximum cross slope requirement will impact the vertical alignment of streets in the vicinity of the intersection. In new construction, street intersections in hilly urban areas are typically cut-and-filled to produce relative flat or tabled intersections. Where pedestrian street crossings with yield or stop control are provided at newly constructed tabled intersections, the tabling would be extended to the pedestrian street crossings to comply with the 2 percent maximum cross slope for pedestrian access routes within the pedestrian street crossings.

Question 14. The Access Board seeks information on the current design policies and practices of state and local transportation departments with respect to tabling newly constructed intersections in hilly urban areas, and particularly whether the tabling is extended to pedestrian street crossings with yield or stop control.

In new construction, extending the tabling of intersections to pedestrian street crossings with yield or stop control involves additional costs for site preparation, grading, and earthwork. The Volpe Center roughly estimated the additional costs to extend the tabling to pedestrian street crossings with yield or stop control to be \$60,000 per intersection based on information provided by a transportation official to the Access Board. The costs will vary by site.

Question 15. The Access Board seeks information on the additional costs to extend the tabling of newly constructed intersections in hilly urban areas to pedestrian street crossings with yield or stop control.

Question 16. The Access Board seeks information on number of tabled intersections which contain pedestrian street crossings with yield or stop control that are newly constructed in hilly urban areas on an annual basis by state and local transportation departments.

Surfaces (R302.7)

The proposed technical requirements for surfaces apply to pedestrian access routes, including curb ramps and blended transitions, and accessible elements and spaces that connect to pedestrian access routes. An advisory section lists the accessible elements and spaces that connect to pedestrian access routes and are required to comply with the technical requirements for surfaces.

The surfaces of pedestrian access routes and the surfaces at accessible elements and spaces that connect to pedestrian access routes must be firm, stable, and slip resistant. Vertical alignment of surfaces within pedestrian access routes (including curb ramp runs, blended transitions, turning spaces, and gutter areas within pedestrian access routes) and within the surfaces at accessible elements and spaces that connect to pedestrian access routes must be generally planar. Grade breaks (i.e., the line where two surface planes with different grades meet, see R105.5) must be flush. Where pedestrian access routes cross rails at grade, the pedestrian access route must be level and flush with the top of the rail at the outer edges of the rails, and the surfaces between the rails must be aligned with the top of the rail.

Vertical surface discontinuities (i.e., vertical difference in level between two adjacent surfaces, see R105.5) must be 13 millimeters (0.5 inch) maximum. Vertical surface discontinuities between 6.4 millimeters (0.25 inch) and 13 millimeters (0.5 inch) must be beveled with a slope not steeper than 50 percent, and the bevel must be applied across the entire vertical surface discontinuity. Horizontal openings in gratings and joints must not permit the passage of a sphere more than 13 millimeters (0.5 inch) in diameter. Elongated openings in gratings must be placed so that the long dimension is perpendicular to the dominant direction of travel.

Flangeway gaps at pedestrian at-grade rail crossings must be 64 millimeters (2.5 inches) maximum on non-freight rail track, and 75 millimeters (3 inches) maximum on freight rail track. These are the typical gaps required to allow passage of train wheel flanges. The flangeway gaps are wider than the maximum gap allowed for horizontal openings in other surfaces. These wider flangeway gaps pose a potential safety hazard to pedestrians who use wheelchairs because the gap can entrap the wheelchair casters.³⁹ The Federal Railroad Administration is sponsoring research to develop materials or devices that will fill the flangeway gap under light loads of a wheelchair but will compress or retract when a train wheel

flange passes over it.⁴⁰ The materials or devices will be tested under heavy and light train loads for safety, effectiveness, durability, and cost.

Question 17. The Access Board seeks information on materials and devices that fill the flangeway gap, and any related research and sources of expertise.

R303 Alternate Pedestrian Access Routes (See R205)

In the 2005 draft of the proposed guidelines, the technical requirements for alternate pedestrian access routes were contained in Chapter R3. The proposed guidelines reference MUTCD standards for alternate pedestrian access routes in the scoping requirements at R205. This section heading is included in Chapter R3 of the proposed guidelines to notify readers who were familiar with the 2005 draft of the proposed guidelines where to find the requirements for alternate pedestrian access routes. This section heading will not be included in the final guidelines.

R304 Curb Ramps and Blended Transitions

General (R304.1)

Curb ramps are ramps that are cut through or built up to the curb (see R105.5). Curb ramps can be perpendicular or parallel, or a combination of parallel and perpendicular ramps. Blended transitions are raised pedestrian street crossings, depressed corners, or similar connections between the pedestrian access route at the level of the sidewalk and the level of the pedestrian street crossing that have a grade of 5 percent or less (see R105.5).

The technical requirements for curb ramps and blended transitions are contained in R304 and adapt the technical requirements for curb ramps in the 2004 ADA and ABA Accessibility Guidelines to the public right-of-way. In alterations where existing physical constraints make it impractical to fully comply with the technical requirements, compliance is required to the extent practicable within the scope of the project (see R202.3.1).

Perpendicular Curb Ramps (R304.2)

39. For additional information on the potential safety hazard of flangeway gaps, see "Wheelchair Safety at Rail Level Crossings, International Review Working Paper" (2003) at [http://www.transport.vic.gov.au/DOI/DOIElect.nsf/\\$UNIDS+for+Web+Display/43D9BDF138FFE9F9CA256D630011A607/\\$FILE/Rail_Crossing_Disability_Access-International_Review.pdf](http://www.transport.vic.gov.au/DOI/DOIElect.nsf/$UNIDS+for+Web+Display/43D9BDF138FFE9F9CA256D630011A607/$FILE/Rail_Crossing_Disability_Access-International_Review.pdf); and "Rail Crossing Disability Access Kit" (2003) available at: [http://www.transport.vic.gov.au/DOI/DOIElect.nsf/\\$UNIDS+for+Web+Display/E995EA3FEB44F07CCA256D630011AD71/\\$FILE/Rail_Crossing_Disability_Access-Toolkit.pdf](http://www.transport.vic.gov.au/DOI/DOIElect.nsf/$UNIDS+for+Web+Display/E995EA3FEB44F07CCA256D630011AD71/$FILE/Rail_Crossing_Disability_Access-Toolkit.pdf).

40. For announcement of award of research contact in 2010, see <http://www.volpe.dot.gov/sbir/ph1rec10.html> and <http://www.integran.com/news/IT%20USA%20DOT%20Flangeway%20Gap%20SBIR%20-%20100323.pdf>. The Transportation Research Board has also developed research need statements for reducing flangeway gaps at railroad crossings. See "Wheelchairs Crossing Flangeway Gaps at Railroad Crossings" (2007); and "Reducing Flangeway Gaps at Railroad Crossings to Better Accommodate Pedestrians" (2008). The research need statements are available at: <http://rns.trb.org/dproject.asp?n=13462> and <http://rns.trb.org/dproject.asp?n=17644>.

Perpendicular curb ramps have a running slope that cuts through or is built up to the curb at right angles or meets the gutter grade break at right angles where the curb is curved. On corners with a large curb radius, it will be necessary to indent the gutter grade break on one side of the curb ramp in order for the curb ramp to meet the gutter grade break at right angles.

A turning space must be provided at the top of perpendicular curb ramps. The turning space must be 1.2 meters (4 feet) minimum by 1.2 meters (4 feet) minimum, and is permitted to overlap other turning spaces and clear spaces. Where the turning space is constrained at the back of the sidewalk, the turning space must be 1.2 meters (4 feet) minimum by 1.5 meters (5 feet) minimum, with the 1.5 meters (5 feet) dimension provided in the direction of the ramp run.

A minimum running slope of 5 percent and a maximum running slope of 8.3 percent are specified for perpendicular curb ramps, and the ramp length is limited to 4.5 meters (15 feet). A maximum running slope of 2 percent is specified for the turning space at the top of the curb ramp. The running slope is measured parallel to the direction of pedestrian travel.

A maximum slope of 10 percent is specified for the flared sides of perpendicular curb ramps where a pedestrian circulation path crosses the curb ramp. The flared sides are part of the pedestrian circulation path, but are not part of the pedestrian access route. The slope of the flared sides is measured parallel to the curb line. The 10 percent maximum slope for the flared sides is the same as in the 2004 ADA and ABA Accessibility Guidelines (see 403.6). Transportation officials have reported that the 10 percent maximum slope for the flared sides can make it difficult to provide two perpendicular curb ramps at some street corners due to the width of the flared sides at the base of the curb ramp. The Access Board is considering increasing the maximum slope for the flared sides to 12.5 percent or 16.7 percent to address this issue.

Question 18. Comments are requested on whether the maximum slope for the flared sides of perpendicular curb ramps should be increased from 10 percent to 12.5 percent or 16.7 percent, and what impact such a change would have on providing two perpendicular curb ramps at street corners. Comments are also requested on any public safety issues that may arise from increasing the maximum slope for the flared sides from 10 percent to 12.5 percent or 16.7 percent.

Parallel Curb Ramps (R304.3)

Parallel curb ramps have a running slope that is in-line with the direction of sidewalk travel and lower the sidewalk to a level turning space where a turn is made to enter the pedestrian street crossing.

A turning space must be provided at the bottom of parallel curb ramps. The turning space must be 1.2 meters (4 feet) minimum by 1.2 meters (4 feet) minimum, and is permitted to overlap other turning spaces and clear spaces. Where the turning space is constrained on two or more sides, the turning space must be 1.2 meters (4 feet) minimum by 1.5 meters (5 feet) minimum, with the 1.5 meters (5 feet) dimension provided in the direction of the pedestrian street crossing.

A minimum running slope of 5 percent and a maximum running slope of 8.3 percent are specified for parallel curb ramps, and the ramp length is limited to 4.5 meters (15 feet). A maximum running slope of

2 percent is specified for the turning space at the bottom of the curb ramp. The running slope is measured parallel to the direction of pedestrian travel.

Blended Transitions (R304.4)

A maximum running slope of 5 percent is specified for blended transitions. The running slope is measured parallel to the direction of pedestrian travel.

Common Requirements (R304.5)

The clear width of curb ramp runs (excluding flared sides), blended transitions, and turning spaces must be 1.2 meters (4 feet) minimum. Grade breaks at the top and bottom of curb ramp runs must be perpendicular to the direction of the ramp run. Grade breaks are not permitted on the surface of ramp runs and turning spaces. Surface slopes that meet at grade breaks must be flush. A maximum cross slope of 2 percent is specified for curb ramps, blended transitions, and turning spaces. At pedestrian street crossings without yield or stop control and at midblock pedestrian street crossings, the cross slope is permitted to equal the street or highway grade. The cross slope is measured perpendicular to the direction of pedestrian travel. A maximum counter slope of 5 percent is specified for the gutter or street at the foot of curb ramp runs, blended transitions, and turning spaces. A clear space must be provided beyond the bottom of the grade break that is within the width of the pedestrian street crossing and wholly outside the parallel vehicle traffic lane. The clear space must be 1.2 meters (4 feet) minimum by 1.2 meters (4 feet) minimum.

R305 Detectable Warning Surfaces

Detectable warning surfaces consist of truncated domes aligned in a square or radial grid pattern. The dimensions for dome size and dome spacing are the same as in the 2004 ADA and ABA Accessibility Guidelines. The detectable warning surfaces must contrast visually with adjacent gutter, street or highway, or pedestrian access route surface, either light-on-dark or dark-on-light. The detectable warning surfaces must extend 610 millimeters (2 feet) minimum in the direction of pedestrian travel. At curb ramps and blended transitions, detectable warning surfaces must extend the full width of the ramp run (excluding flared sides), blended transition, or turning space. At pedestrian at-grade rail crossings not located within a street or highway, detectable warning surfaces must extend the full width of the crossing. At boarding platforms for buses and rail vehicles, detectable warning surfaces must extend the full length of the public use areas of the platform. At boarding and alighting areas at sidewalk or street level transit stops for rail vehicles, detectable warning surfaces must extend the full length of the transit stop. The proposed technical requirements specify where detectable warning surfaces must be placed on perpendicular curb ramps, parallel curb ramps, blended transitions, pedestrian refuge islands, pedestrian at-grade rail crossings, boarding platforms for buses and rail vehicles, and boarding and alighting areas at sidewalk or street level transit stops for rail vehicles.

R306 Pedestrian Street Crossings

The technical requirements in R306 address pedestrian signal phase timing and pedestrian street crossings at roundabouts and multi-lane channelized turn lanes.

Pedestrian Signal Phase Timing

Pedestrian signal phase timing must comply with referenced MUTCD standards and use a pedestrian clearance time that is calculated based on pedestrian walking speed of 1.1 meters/second (3.5 feet/second) or less.

Roundabouts

A roundabout is a circular intersection with yield control at entry, which permits a vehicle on the circulatory roadway to proceed, and with deflection of the approaching vehicle counter-clockwise around a central island (MUTCD section 1A.13). Pedestrian street crossings at roundabouts can be difficult for pedestrians who are blind or have low vision to identify because the crossings are located off to the side of the pedestrian circulation path around the street or highway. Where sidewalks are flush against the curb at roundabouts and pedestrian street crossing is not intended, a continuous and detectable edge treatment must be provided along the street side of the sidewalk at roundabouts. Detectable warning surfaces must not be used for edge treatment. Where chains, fencing, or railings are used for edge protection, the bottom edge of the treatment must be 380 millimeters (15 inches) maximum above the sidewalk to be detectable by cane.

The continuous traffic flow at roundabouts removes many of the audible cues that pedestrians who are blind use to navigate pedestrian street crossings. At roundabouts with multi-lane pedestrian street crossings, a pedestrian activated signal must be provided for each multilane segment of each crossing, including the splitter island (i.e., median island used to separate opposing directions of traffic entering and exiting a roundabout, MUTCD section 1A.13). Transportation officials who commented on the 2002 draft guidelines expressed concern that signalization of roundabouts would interfere with the flow of traffic at roundabout intersections. Pedestrian Hybrid Beacons can be used at roundabouts. See MUTCD sections 4F.01 through 4F.03. Pedestrian Hybrid Beacons are traffic signals that consist of a yellow signal centered below two horizontally aligned red signals. The signals are normally dark (i.e., not illuminated). The signals are initiated only upon pedestrian activation and can be timed to minimize the interruption of traffic. The signals cease operation after the pedestrian clears the crosswalk. When activated by a pedestrian, the following signals are displayed to drivers: a flashing yellow signal, then a steady yellow signal, then two steady red signals during the pedestrian walk interval, and then alternating flashing red signals during the pedestrian clearance interval. The following signals are displayed to pedestrians: a steady upraised hand (symbolizing DON'T WALK) when the flashing or steady yellow signal is operating, then a walking person (symbolizing WALK) when the steady red signals are operating, and then a flashing upraised hand (symbolizing DON'T WALK) when the alternating flashing red signals are operating. Transportation officials may request permission from the Federal Highway Administration to experiment with alternative signals at roundabouts (see MUTCD section 1A.10).⁴¹

41. The Federal Highway Administration has granted interim approval to Rectangular Flashing Rapid Beacons, which can be used at roundabouts. However, Rectangular Flashing Rapid Beacons do not provide positive indication to drivers to stop and positive indication to pedestrians that the walk interval has been actuated. Rectangular Flashing Rapid Beacons do not meet MUTCD standards for accessible pedestrian signals and pedestrian pushbuttons.

Multi-Lane Channelized Turn Lanes

Pedestrian activated signals must be provided at pedestrian street crossings at multi-lane channelized turn lanes at roundabouts and other signalized intersections. The pedestrian activated signals must comply with MUTCD standards for accessible pedestrian signals and pedestrian pushbuttons.

Governmental Units Affected

The requirement for pedestrian activated signals at roundabouts with multi-lane pedestrian street crossings will affect state and local transportation departments that construct new roundabouts with multi-lane pedestrian street crossings. The Volpe Center estimated that state and local transportation departments construct 27 new roundabouts with multi-lane pedestrian street crossings on an annual basis.⁴²

Costs to Provide Pedestrian Activated Signals at Roundabouts with Multi-Lane Pedestrian Street Crossings

The Volpe Center estimated the cost to provide pedestrian activated signals at new roundabouts with multi-lane pedestrian street crossings to range from \$90,000 to \$230,000 per roundabout, and the total annual costs for requiring pedestrian activated signals at new roundabouts with multi-lane pedestrian street crossings to range from \$2.4 million to \$6.2 million.

Question 19. The Access Board seeks additional information on the number of roundabouts with multi-lane pedestrian street crossings that are newly constructed on an annual basis by state and local transportation departments, and the costs to provide pedestrian activated signals at newly constructed roundabouts with multi-lane pedestrian street crossings.

R307 Accessible Pedestrian Signals and Pedestrian Pushbuttons (See R209)

In the 2005 draft of the proposed guidelines, the technical requirements for accessible pedestrian signals and pedestrian pushbuttons were contained in Chapter R3. The proposed guidelines reference MUTCD standards for accessible pedestrian signals and pedestrian pushbuttons in the scoping requirements at R209. This section heading is included in Chapter R3 of the proposed guidelines to notify readers who were familiar with the 2005 draft of the proposed guidelines where to find the requirements for accessible pedestrian signals and pedestrian pushbuttons. This section heading will not be included in the final guidelines.

R308 Transit Stops and Transit Shelters

42. The Volpe Center used the roundabout database at: <http://roundabout.kittelson.com/> to estimate the number of new roundabouts with multi-lane pedestrian street crossings that are constructed on an annual basis. During the five year period between 2005 and 2009, 435 new roundabouts were constructed, of which 117 were multi-lane. The data was adjusted for a small number of roundabouts that are listed in the database as having an “unknown” number of lanes and for roundabouts that do have any pedestrian facilities (i.e., sidewalks and pedestrian street crossings).

The technical requirements for transit stops and transit shelters are contained in R308 and adapt the technical requirements for transit facilities in the 2004 ADA and ABA Accessibility Guidelines to the public right-of-way.

Transit Stops (R308.1)

Boarding and alighting areas at sidewalk or street level transit stops must be 2.4 meters (8 feet) minimum measured perpendicular to the street or highway, and 1.5 meters (5 feet) minimum measured parallel to the street or highway. The grade of the boarding and alighting area parallel to the street or highway must be equal to street or highway grade to the extent practicable. The grade of the boarding and alighting area perpendicular to the street or highway must not exceed 2 percent. Where transit stops serve vehicles with more than one car, boarding and alighting areas serving each car must comply with these requirements.

Boarding platforms at transit stops must be positioned to coordinate with vehicles to minimize the vertical and horizontal gaps. The slope of boarding platforms must not exceed 2 percent in any direction. Where boarding platforms serve vehicles operating on existing track or existing street or highway, the slope of the platform parallel to the track or street or highway is permitted to equal the grade of the track or street or highway.

The surfaces of boarding and alighting areas and boarding platforms must comply with the technical requirements for surfaces (see R302.7). Boarding and alighting areas and boarding platforms must be connected to streets, sidewalks, or pedestrian circulation paths by a pedestrian access route.

Transit Shelters (R308.2)

Transit shelters must be connected by a pedestrian access route to boarding and alighting areas or boarding platforms. A clear space (see R404) must be provided entirely within the transit shelter. Where seating is provided within transit shelters, the clear space must be located either at the end of a seat, or not overlap the area within 460 millimeters (1.5 feet) from the front edge of the seat in order to not interfere with others using the seating. Environmental controls within transit shelters must be proximity actuated. Protruding objects within transit shelters must comply with the technical requirements for protruding objects (see R402).

The Access Board is considering whether to require a turning space in transit shelters. Transit shelter designs vary. Some transit shelters are enclosed on three or four sides, with an opening for ingress and egress. The turning space would be based on the 2004 ADA and ABA Accessibility Guidelines (see 304.3).⁴³ The turning space would be permitted to overlap the clear space within the transit shelter and

43. The 2004 ADA and ABA Accessibility Guidelines require a turning space to be either a circular space 1.5 meters (5 feet) minimum in diameter, or a T-shaped space within a square with sides 1.5 meters (5 feet) minimum where the arms and base of the T-shaped space are 915 millimeters (3 feet) minimum. Each arm of the T-shaped space must be clear of obstructions 305 millimeters (1 foot) minimum in each direction, and the base must be clear of obstructions 610 millimeters (2 feet) minimum. A circular space is permitted to include knee and toe clearance. A T-shaped space is permitted to include knee and toe clearance only at the end of either the base or one arm.

the pedestrian access route, but would not be permitted to overlap the area within 460 millimeters (1.5 feet) from the front edge of seats in the transit shelter in order to not interfere with others using the seating. The portion of the turning space that does not overlap the clear space would be permitted to be outside the transit shelter.

Question 20. Comments are requested on whether a turning space should be required in transit shelters and what impact such a requirement would have on the design and placement of transit shelters?

R309 On-Street Parking Spaces

General (R309.1)

The technical requirements for accessible on-street parking spaces are contained in R309 and adapt the technical requirements for accessible parking spaces in the 2004 ADA and ABA Accessibility Guidelines to the public right-of-way.

Parallel Parking Spaces (R309.2)

Where the adjacent sidewalk or available right-of-way is more than 4.3 meters (14 feet) wide, an access aisle must be provided at street level for the entire length of each accessible parallel parking space. The access aisle must be 1.5 meters (5 feet) wide minimum and connect to a pedestrian access route. The access aisle must not encroach on the vehicular travel lane and comply with the technical requirements for surfaces (see R302.7). In alterations where the street or sidewalk adjacent to the parking spaces is not altered, an access aisle is not required provided the parking spaces are located at the end of the block face.

Where the adjacent sidewalk or available right-of-way is less than or equal to 4.3 meters (14 feet) wide, an access aisle is not required, but accessible parallel parking spaces must be located at the end of the block face.

Perpendicular and Angled Parking Spaces (R309.3)

An access aisle must be provided at street level for the entire length of each accessible perpendicular or angled parking space. The access aisle must be 2.4 meters (8 feet) wide minimum to accommodate vans with lifts, and connect to a pedestrian access route. Two accessible parking spaces are permitted to share a common access aisle. The access aisle must be marked to discourage parking in the aisle and comply with the technical requirements for surfaces (see R302.7).

Curb Ramps and Blended Transitions (R309.4)

Curb ramps or blended transitions must connect the access aisle serving each accessible on-street parking space to the pedestrian access route. Curb ramps are not permitted within the access aisle. Parking spaces at the end of block face can be served by curb ramps or blended transitions at the pedestrian street crossing. Detectable warning surfaces are not required on curb ramps and blended transitions that connect the access aisle to the sidewalk, including where the sidewalk is at the same

level as the parking spaces, unless the curb ramps and blended transitions also serve pedestrian street crossings.

Parking Meters and Parking Pay Stations (R309.5)

Operable parts of parking meters and parking pay stations that serve accessible on-street parking spaces must comply with technical requirements for operable parts in Chapter R4. Displays and information must be visible from a point located 1 meter (3.3 feet) maximum above the center of the clear space in front of the parking meter or parking pay station. At accessible parallel parking spaces, parking meters must be located at the head or foot of the space.

R310 Passenger Loading Zones

The technical requirements for accessible passenger loading zones are the same as in the 2004 ADA and ABA Accessibility Guidelines. A vehicular pull-up space 2.4 meters (8 feet) wide minimum and 6.1 meters (20 feet) long minimum must be provided at accessible passenger loading zones. An access aisle must be provided at the same level as the vehicle pull-up space. The access aisle must be 1.5 meters (5 feet) wide minimum, extend the entire length of the vehicle pull-up space, and connect to the pedestrian access route. The access aisle must be marked to discourage parking in the aisle and comply with the technical requirements for surfaces (see R302.7).

Chapter R4: Supplementary Technical Requirements

Chapter R4 contains supplementary technical requirements that are the same as in the 2004 ADA and ABA Accessibility Guidelines unless otherwise noted below.

R401 General

The supplementary technical requirements in Chapter R4 apply where required by scoping requirements in Chapter R2, or where referenced by another technical requirement in Chapters R3 or R4.

R402 Protruding Objects

Objects with leading edges between 685 millimeters (2.25 feet) and 2 meters (6.7 feet) above the finish surface must not protrude into pedestrian circulation paths more than 100 millimeters (4 inches). Post-mounted objects such as signs that are between 685 millimeters (2.25 feet) and 2 meters (6.7 feet) above the finish surface must not overhang pedestrian circulation paths more than 100 millimeters (4 inches) measured horizontally from the base of the post. The post base must be 64 millimeters (2.5 inches) thick minimum. Where objects are mounted between posts and the clear distance between the posts is more than 305 millimeters (1 foot), the lowest edge of the object must be 685 millimeters (2.25 feet) minimum or 2 meters (6.7 feet) maximum above the finish surface. The requirement for post-mounted objects differs from the 2004 ADA and ABA Accessibility Guidelines but is consistent with the MUTCD which requires the bottom of signs installed on the sidewalk to be 7 feet minimum above the sidewalk, and the bottom of secondary signs (i.e., signs mounted below another sign) that are lower than 7 feet above the sidewalk to project not more than 4 inches into the sidewalk (see MUTCD section 2A.18).

Guardrails or other barriers to pedestrian travel must be provided where the vertical clearance on pedestrian circulation paths is less than 2 meters (6.7 feet) high. The leading edge of the guardrail or barrier must be 685 millimeters (2.25 feet) maximum above the finish surface.

R403 Operable Parts

An operable part is a component of an element used to insert or withdraw objects, or to activate, deactivate, or adjust the element (see R105.5). The technical requirements for operable parts apply to operable parts on accessible pedestrian signals and pedestrian pushbuttons (see R209) and parking meters and parking pay stations that serve accessible parking spaces (see R309.5). A clear space must be provided at operable parts (see R404). Operable parts must be located within the reach ranges (see R406). Operable parts must be operable with one hand and not require tight grasping, pinching, or twisting of the wrist. The force required to activate operable parts must be no more than 22 newtons (5 pounds).

R404 Clear Spaces

Clear spaces are required at operable parts (see R403.2), including accessible pedestrian signals and pedestrian pushbuttons (see R209) and parking meters and parking pay stations that serve accessible parking spaces (see R309.5). Clear spaces are also required at benches (see R212.6) and within transit shelters (see R308.2). Clear spaces must be 760 millimeters (2.5 feet) minimum by 1220 millimeters (4 feet) minimum. Additional maneuvering space must be provided where an element is confined on all or part of three sides. Clear spaces are permitted to include knee and toe clearance and to be positioned for either forward or parallel approach to an element, unless another requirement specifies otherwise. The running slope of clear spaces is permitted to be consistent with the grade of the adjacent pedestrian access route. This requirement differs from the 2004 ADA and ABA Accessibility Guidelines which does not permit slopes steeper than 2 percent at clear spaces. A 2 percent maximum cross slope is specified for clear spaces. Clear spaces must comply with the technical requirements for surfaces (see R302.7).

R405 Knee and Toe Clearance

The technical requirements for knee and toe clearance apply where space beneath an element is included as part of the clear space.

R406 Reach Ranges

Forward and side reach ranges must be between 380 millimeters (1.25 feet) and 1220 millimeters (4 feet) above the finish surface. The requirements for reach ranges differ from the 2004 ADA and ABA Accessibility Guidelines in that forward reach over an obstruction is not permitted, and side reach over an obstruction is permitted where the depth of the obstruction between the clear space and the element is 225 millimeters (10 inches) maximum.

R407 Ramps

R408 Stairways

R409 Handrails

R410 Visual Characters on Signs

R411 International Symbol of Accessibility

The technical requirements ramps, stairways, handrails, visual characters on signs, and the International Symbol of Accessibility are the same as in the 2004 ADA and ABA Accessibility Guidelines.

Other Issues

Rollability and Smoothness of Walking Surfaces

Rollability refers to the ease and comfort with which pedestrians using wheelchairs and other wheeled mobility devices can travel on walking surfaces. Rough or jointed walking surfaces can cause pedestrians using wheelchairs and other wheeled mobility devices to expend extra energy or pushing effort that makes it more difficult for them to use the walking surface, and the resulting surface vibration can cause discomfort or pain that may prevent them from using the walking surface all together. There are smoothness measures for road surfaces but no similar measures for walking surfaces. The Access Board is sponsoring preliminary research that will produce a plan for a test protocol and instrumentation to measure the rollability and smoothness of walking surfaces and to establish an index of surface vibration.

Question 21. The Access Board seeks information on related research and sources of expertise on measuring the rollability and smoothness of walking surfaces, including information from the medical community on the effects of surface vibration on individuals with disabilities.

Shared Streets

A shared street is a common space designed for use by pedestrians, bicyclists, and vehicles.⁴⁴ Shared streets typically do not have curbs and delineated sidewalks. Vehicles typically travel at low speeds on shared streets. Trees, planters, parking areas, and other obstacles may be placed on shared streets to slow vehicles. Shared streets can be in a commercial area or residential area. Shared streets are difficult for pedestrians who are blind or have low vision to navigate because of the absence of curbs and clearly delineated sidewalks.⁴⁵ The Pedestrian Accessibility and Movement Environment Laboratory at

44. The Pedestrian and Bicycle Information Center provides information on shared streets on its website at: <http://www.walkinginfo.org/engineering/calming-street.cfm>.

45. Focus groups and surveys of pedestrians who are blind or have low vision commissioned by the Guide Dogs for the Blind Association in the United Kingdom and Netherlands document the difficulties that these pedestrians have using shared streets. See "The Impact of Shared Surface Streets and Shared Use Pedestrian/Cycle Paths on the Mobility and Independence of Blind and Partially Sighted People" (2010) available at: http://gdbass.net/efficiency.co.uk/fileadmin/sharedsurfaces/user/documents/TNS_Report_Text_version_Impact_of_shared_surface_streets_and_shared_use_paths_GD_2010.doc ; "Shared Surface Street Design Research Project, The Issues: Report of Focus Groups" (2006) at http://community.stroud.gov.uk/documents/23_Shared_Surface_Street_Design_Research_Project.pdf ; and "Shared Surface Street Design: Report of Focus Groups Held in Holland" (2006) at http://www.alan-hunt.co/pdf/Report_of_Holland_Focus_Groups.pdf.

University College London has conducted limited research on the use of tactile surfaces to delineate the space on shared streets that is to be used exclusively by pedestrians, and not vehicles.⁴⁶ The tactile surfaces tested included raised truncated domes that, in the United States, are used as detectable warning surfaces on curb ramps and blended transitions to indicate the boundary between the pedestrian route and the vehicular route at pedestrian street crossings. Using detectable warning surfaces to facilitate wayfinding along shared streets would be expanding the use of such surfaces.

Question 22. The Access Board seeks information on the design of shared streets in the United States, and whether tactile surfaces or other design features are used to facilitate wayfinding along shared streets. The Access Board also seeks information about other research that is planned or underway on the use of tactile surfaces or other design features to facilitate wayfinding along shared streets.

Regulatory Process Matters

Executive Orders 12866 and 13563

The Office of Management and Budget has reviewed this proposed rule pursuant to Executive Orders 12866 and 13563.⁴⁷ The Access Board prepared a regulatory assessment of the potential costs and benefits of the proposed rule. The regulatory assessment is available on the Access Board website at: <http://www.access-board.gov/prowac/index.htm>, and is also available in the regulatory docket at <http://www.regulations.gov>. The information in the regulatory assessment is discussed in the preamble under Impacts on State and Local Governments and under the relevant requirements in the Section-by-Section Analysis. The information in the regulatory assessment is also summarized in the tables below. As indicated in the tables below, the regulatory assessment does not include estimates of the total annual costs for two of the requirements in the proposed guidelines that will have more than minimal impacts because information is not available to estimate the costs. Questions are included in the preamble seeking additional information to assist the Board to estimate the total annual costs of these two

46. "Shared Space Delineators, Are They Detectable?" (2010) available at: http://www.tap.iht.org/objects_store/201004/TfL%20Report%2020100415.pdf. See also "Testing Proposed Delineators to Demarcate Pedestrian Paths in a Shared Space Environment, Report of Design Trials Conducted at University College London" (2008) available at: <http://www.homezones.org.uk/public/downloads/news/Exec%20Summary%20&%20Full%20Report%20of%20design%20trials%20at%20UCL%20PAMELA%200108.pdf>.

47. Executive Orders 12866 and 13563 establish and reaffirm principles of regulation that direct federal agencies among other things to: "(1) propose or adopt a regulation only upon a reasoned determination that its benefits justify its costs (recognizing that some benefits and costs are difficult to quantify); (2) tailor its regulations to impose the least burden on society, consistent with obtaining regulatory objectives, taking into account, among other things, and to the extent practicable, the costs of cumulative regulations; (3) select, in choosing among alternative regulatory approaches, those approaches that maximize net benefits (including potential economic, environmental, public health and safety, and other advantages; distributive impacts; and equity); (4) to the extent feasible, specify performance objectives, rather than specifying the behavior or manner of compliance that regulated entities must adopt; and (5) identify and assess available alternatives to direct regulation, including providing economic incentives to encourage the desired behavior, such as user fees or marketable permits, or providing information upon which choices can be made by the public." Executive Order 13563, section 1 (b).

requirements and to refine the cost estimates for the other requirements in the proposed guidelines. Consequently, the Access Board has not determined whether the proposed guidelines are an economically significant regulatory action.⁴⁸ The Access Board will analyze the information received in response to the questions in the preamble. When the final guidelines are issued, the Access Board will revise the regulatory assessment and determine whether the guidelines are an economically significant regulatory action.

Baseline

All state transportation departments and most local transportation departments maintain design manuals and standard drawings for improvements in the public right-of-way. The local transportation department design manuals and standard drawings are generally consistent with their state transportation department design manuals and standard drawings. State and local transportation departments use publications issued by the American Association of State and Highway Transportation Officials (AASHTO) in their design manuals and standard drawings, including the “Policy on Geometric Design of Highways and Streets” (2004) (commonly referred to as the “AASHTO Green Book”) and the “Guide for the Planning, Design, and Operation of Pedestrian Facilities” (2004) which incorporate accessibility in the design of sidewalks and other pedestrian facilities.⁴⁹ The Federal Highway Administration as part of its stewardship and oversight responsibilities has also worked with state transportation departments to incorporate accessibility in their design manuals and standards drawings. The Federal Highway Administration has issued guidance that the accessibility standards in the Department of Justice regulations implementing Title II of the Americans with Disabilities Act and the Department of Transportation regulations implementing Section 504 are to be used to the extent feasible for the design of pedestrian facilities in the public right-of-way until new accessibility standards are adopted for these facilities.

In the absence of the proposed guidelines, the regulatory assessment assumes that state and local transportation departments will use the DOJ 2010 Standards in the Department of Justice regulations implementing Title II of the Americans with Disabilities Act to the extent feasible when designing, constructing, or altering pedestrian facilities in the public right-of-way, consistent with the guidance issued by the Federal Highway Administration, as well as other applicable standards and industry practices. An analysis of the proposed guidelines compared to the DOJ 2010 Standards, other applicable standards, and industry practices is included in the appendix to the regulatory assessment. The analysis identified four requirements in the proposed guidelines that will have more than minimal impacts on state and local transportation departments. The factors used to identify whether the requirements in the proposed guidelines will have more than minimal impacts are discussed in the regulatory assessment and in the preamble under Impacts on State and Local Governments. The four requirements in the proposed guidelines that will have more than minimal impacts on state and local transportation departments are summarized in the table below, along with a description of the

48. A regulatory action is economically significant if it is anticipated to “[h]ave an annual effect on the economy of \$100 million or more” or to “adversely affect in a material way the economy, a sector of the economy, productivity, competition, jobs, the environment, public health or safety, or State, local, or tribal government communities.” Executive Order 12866, section 2 (f) (1).

49. See footnote 20 for additional information on the AASHTO publications and accessibility.

governmental units affected by proposed requirements and questions in the preamble to the proposed guidelines that seek additional information on the governmental units affected.

Requirements in Proposed Guidelines That Will Have More Than Minimal Impacts on State and Local Transportation Departments

Requirement	Governmental Units Affected
Detectable warning surfaces required on newly constructed and altered curb ramps and blended transitions at pedestrian street crossings (R208.1 and R305)	Will affect state and local transportation departments that do not currently provide detectable warning surfaces on curb ramps All state transportation departments currently specify detectable warning surfaces on curb ramps in their standard drawings; most local transportation departments maintain standard drawings that are consistent with standard drawings maintained by their state transportation departments Questions 4, 5, and 6 in preamble seek information on state and local transportation departments that do not currently provide detectable warning surfaces on curb ramps
Accessible pedestrian signals and pushbuttons required when pedestrian signals newly installed or replaced at signalized intersections (R209)	Will affect state and local transportation departments that do not currently provide accessible pedestrian signals and pedestrian pushbuttons when pedestrian signals are newly installed or replaced at signalized intersections Some state and local transportation departments currently provide accessible pedestrian signals and pedestrian pushbuttons when pedestrian signals are newly installed or replaced at signalized intersections; TEA-21 (23 U.S.C. 217 (g)) directed that audible traffic signals be included in transportation plans and projects where appropriate Question 9 in preamble seeks information on state and local transportation departments that currently provide accessible pedestrian signals and pedestrian pushbuttons when pedestrian signals are newly installed or replaced at signalized intersections

Requirements in Proposed Guidelines That Will Have More Than Minimal Impacts on State and Local Transportation Departments

Requirement	Governmental Units Affected
Maximum cross slope of 2 percent required on pedestrian access routes, including within pedestrian street crossings with yield or stop control (R204.3 and R302.6)	Will affect state and local transportation departments that construct new tabled intersections in hilly urban areas which contain pedestrian street crossings with yield or stop control Question 14 in preamble seeks information on the current design policies and practices of state and local transportation departments with respect to tabling newly constructed intersections in hilly urban areas, particularly with respect to extending the tabling to pedestrian street crossings with yield or stop control
Pedestrian activated signals required at roundabouts with multi-lane pedestrian crossings (R206 and R306.3.2)	Will affect state and local transportation departments that construct new roundabouts with multi-lane pedestrian street crossings

The Access Board entered into an interagency agreement with the Volpe National Transportation Systems Center (Volpe Center) to gather data and prepare cost estimates for the regulatory assessment. The cost estimates prepared by the Volpe Center are summarized in the table below, along with questions in the preamble to the proposed guidelines that seek additional information to refine the cost estimates.

Estimated Total Annual Costs for Requirements That Will Have More Than Minimal Impacts on State and Local Transportation Departments

Requirement	Additional Costs Per Element or Facility Due to Requirement	Number of Elements or Facilities Constructed or Altered on Annual Basis	Total Annual Costs for Requirement
Detectable warning surfaces required on newly constructed and altered curb ramps and blended transitions at pedestrian street crossings (R208.1 and R305)	\$48 to \$240 for detectable warning materials for typical curb ramp Question 8 in preamble seeks additional information on costs for detectable warning materials and installation of the materials on typical curb ramp	No information available Question 7 in preamble seeks information on number of curb ramps that are constructed or altered on an annual basis in the public right-of-way	No estimate provided Total annual costs will depend on number of state and local transportation departments that do not currently provide detectable warning surfaces on curb ramps, and number of curb ramps that they construct or alter on an annual basis
Accessible pedestrian signals and pushbuttons required when pedestrian signals newly installed or replaced at signalized intersections (R209)	\$3,600 per signalized intersection Question 10 in preamble seeks additional information on costs for providing accessible pedestrian signals and pedestrian pushbuttons at signalized intersections	Pedestrian signals newly installed or replaced at 13,095 signalized intersections on an annual basis	\$47 million

Estimated Total Annual Costs for Requirements That Will Have More Than Minimal Impacts on State and Local Transportation Departments

Requirement	Additional Costs Per Element or Facility Due to Requirement	Number of Elements or Facilities Constructed or Altered on Annual Basis	Total Annual Costs for Requirement
Maximum cross slope of 2 percent required on pedestrian access routes, including within pedestrian street crossings with yield or stop control (R204.3 and R302.6)	\$60,000 per tabled intersection Question 15 in preamble seeks additional information on costs to extend tabling of newly constructed intersections in hilly urban areas to pedestrian street crossings with yield or stop control	No information available Question 16 in preamble seeks information on number of tabled intersections which contain pedestrian street crossings with yield or stop control that are newly constructed in hilly urban areas on an annual basis	No estimate provided Total annual costs will depend on number of tabled intersections which contain pedestrian street crossings with yield or stop control that are newly constructed in hilly urban areas on an annual basis
Pedestrian activated signals required at roundabouts with multi-lane pedestrian crossings (R206 and R306.3.2)	\$90,000 to \$230,000 per roundabout Question 19 in preamble seeks additional information on costs to provide pedestrian activated signals at roundabouts with multi-lane pedestrian crossings	27 new roundabouts with multi-lane pedestrian street crossings constructed on an annual basis	\$2.4 million to \$6.2 million

Benefits

The proposed guidelines will benefit pedestrians with disabilities. The U.S. Census Bureau reports that 54.4 million Americans, about one in five U.S. residents, reported some level of disability in 2005.⁵⁰ The number of individuals with disabilities is almost equal to the combined total population of California and Florida. The U.S. Census Bureau provides this breakdown of the population of people aged 15 and older:

- 27.4 million (11.9 percent) had difficulty with ambulatory activities of the lower body;

50. "Americans with Disabilities: 2005" (2008) available on the web at: <http://www.census.gov/prod/2008pubs/p70-117.pdf>.

- 22.6 million people (9.8 percent) had difficulty walking a quarter of a mile;
- 21.8 million (9.4 percent) had difficulty climbing a flight of stairs;
- 10.2 million (4.4 percent) used a cane, crutches, or walker to assist with mobility;
- 3.3 million (1.4 percent) used a wheelchair or other wheeled mobility device; and
- 7.8 million (3 percent) had difficulty seeing words or letters in ordinary newspaper print, including 1.8 million who are completely unable to see.

Executive Order 13563 states that to the extent permitted by law federal agencies must “propose or adopt a regulation only upon a reasoned determination that its benefits justify its costs (recognizing that some benefits and costs are difficult to quantify)” and that “where appropriate and permitted by law, each agency may consider and (discuss qualitatively) values that are difficult or impossible to quantify, including equity, human dignity, fairness, and distributive impacts.” The proposed guidelines promote important societal values that are difficult or impossible to quantify. As discussed above under the Need for Rulemaking, when enacting the Americans with Disabilities Act, Congress found “the discriminatory effects of architectural, transportation, and communication barriers” to be a continuing problem that “denies people with disabilities the opportunity to compete on an equal basis and to pursue those opportunities for which our free society is justifiably famous, and costs the United States billions of dollars in unnecessary expenses resulting from dependency and nonproductivity.” 42 U.S.C. 12101 (a) (5) and (9). Congress declared that “the Nation’s proper goals regarding individuals with disabilities are to assure equality of opportunity, full participation, independent living, and economic self-sufficiency.” 42 U.S.C. 12101 (a) (8). The proposed guidelines promote the goals declared by Congress by eliminating the discriminatory effects of architectural, transportation, and communication barriers in the design and construction of pedestrian facilities in the public right-of-way. The proposed guidelines are also important to achieving the benefits of the other parts of the Americans with Disabilities Act. As the House Report for the Americans with Disabilities Act stated, “[t]he employment, transportation, and public accommodation sections . . . would be meaningless if people who use wheelchairs were not afforded the opportunity to travel on and between the streets.” H.R. 485, 101st Cong., 2d Sess. 84 (1990).

Question 23. Comments are requested on whether the proposed guidelines have other quantitative or qualitative benefits in addition to those discussed above.

Regulatory Flexibility Act: Initial Regulatory Flexibility Analysis

The impacts of the proposed guidelines on small governmental jurisdictions with a population of less than 50,000 are discussed below. This information is required by the Regulatory Flexibility Act (5 U.S.C. §603).

Reasons for issuing proposed accessibility guidelines

The Access Board’s current accessibility guidelines, the 2004 ADA and ABA Accessibility Guidelines, were developed primarily for buildings and facilities on sites. Some of the requirements in the 2004 ADA and ABA Accessibility Guidelines can be readily applied to pedestrian facilities in the public right-of-way, but other requirements need to be adapted for pedestrian facilities in the public right-of-way. The proposed guidelines are developed specifically for pedestrian facilities in the public right-of-way and address conditions and constraints that exist in the public right-of-way.

Objectives of, and legal basis for, proposed accessibility guidelines

The Access Board is required to issue accessibility guidelines by the Americans with Disabilities Act (42 U.S.C. §12204) and Section 502 of the Rehabilitation Act (29 U.S.C. §792) to ensure that newly constructed and altered facilities are readily accessible to and usable by pedestrians with disabilities.

Small governmental jurisdictions affected by proposed accessibility guidelines

The number of small governmental jurisdictions with a population less than 50,000 affected by the proposed guidelines is shown in the table below.

Governmental Jurisdictions	Population Less Than 50,000
County	2,178
Municipal	18,824
Town or Township	16,371
Total	37,375

Source: US Census Bureau 2002 Census of Governments available at: <http://www.census.gov/prod/2003pubs/gc021x1.pdf>.

Almost 70 percent of municipal governments (13,038) and more than 75 percent of towns and townships (12,331) have a population of less than 2,500. Many of these small governmental jurisdictions are located in rural areas, which generally do not construct pedestrian transportation networks (e.g., sidewalks, pedestrian street crossings, and pedestrian signals).

Compliance requirements

The proposed accessibility guidelines address the design, construction, and alteration of pedestrian facilities in the public right-of-way, including sidewalks, pedestrian street crossings, pedestrian overpasses and underpasses, curb ramps and blended transitions at pedestrian street crossings, pedestrian signals, street furniture (i.e., drinking fountains, public toilet facilities, tables, counters, and benches), pedestrian signs, transit stops and transit shelters for buses and light rail vehicles, on-street parking that is marked or metered, and passenger loading zones. The Section-by-Section Analysis of the preamble describes the proposed accessibility guidelines. Compliance with the proposed accessibility guidelines is not mandatory until they are adopted, without or without additions and modifications, as accessibility standards by other federal agencies. There are no reporting or recordkeeping requirements.

Other federal rules

The Department of Justice, Department of Transportation, and General Services Administration are responsible for issuing accessibility standards that are consistent with the accessibility guidelines issued by the Access Board and are expected to conduct rulemaking to adopt the proposed guidelines, with or

without additions and modifications, as accessibility standards in regulations implementing Title II of the Americans with Disabilities Act (28 CFR part 36 and 49 CFR part 37), Section 504 of the Rehabilitation Act (49 CFR part 27), and the Architectural Barriers Act (41 CFR part 102). Additional information on these laws and regulations is provided under the Statutory and Regulatory Background in the preamble to the proposed guidelines.

Significant alternatives which minimize any significant economic impacts on small entities

The regulatory assessment analyzes the following four requirements in the proposed guidelines that will have more than minimal impacts on state and local transportation departments:

- Detectable warning surfaces required on newly constructed and altered curb ramps and blended transitions at pedestrian street crossings (see R208.1 and R305). Detectable warning surfaces consist of small truncated domes that are detectable underfoot. Where curb ramps or blended transitions are provided at pedestrian street crossings, detectable warning surfaces indicate the boundary between a pedestrian route and a vehicular route for pedestrians who are blind or have low vision in place of the missing curb.
- Accessible pedestrian signals and pedestrian pushbuttons required when pedestrian signals newly installed or replaced at signalized intersections (see R209). Accessible pedestrian signals and pedestrian pushbuttons communicate the information about the WALK and DON'T WALK intervals at signalized intersections in non-visual formats (i.e., audible tones and vibrotactile surfaces) to pedestrians who are blind or have low vision.
- Maximum cross slope of 2 percent required on pedestrian access routes, including within pedestrian street crossings with yield or stop control. Cross slope is the slope perpendicular to the direction of pedestrian travel. Cross slope impedes travel by pedestrians who use wheeled mobility devices since energy must be expended to counteract the perpendicular force of the cross slope. The 2 percent maximum cross slope required on pedestrian access routes has more than minimal impacts on the construction of new tabled intersections in hilly urban areas that contain pedestrian street crossings with yield or stop control where vehicles slow or stop before proceeding through the intersection.
- Pedestrian activated signals at roundabouts with multi-lane pedestrian street crossings. A roundabout is a circular intersection with yield control at entry, which permits a vehicle on the circulatory roadway to proceed, and with deflection of the approaching vehicle counter-clockwise around a central island. Pedestrian activated signals are required at roundabouts with multi-lane pedestrian street crossings to facilitate crossing by pedestrians who are blind or have low vision. Small governmental jurisdictions with a population less than 50,000 are not likely to construct roundabouts with multi-lane pedestrian street crossings and will not be affected by this requirement.

There are no significant alternatives that will minimize any significant impacts of these requirements on small governmental jurisdictions and achieve the objectives of the Americans with Disabilities Act, Section 504 of the Rehabilitation Act, and the Architectural Barriers Act to eliminate the discriminatory effects of architectural, transportation, and communication barriers in the design and construction of pedestrian facilities in the public right-of-way.

Executive Order 13132: Federalism

The proposed rule adheres to the fundamental federalism principles and policy making criteria in Executive Order 13132. The proposed rule is issued under the authority of the Americans with Disabilities Act, civil rights legislation that was enacted by Congress pursuant to its authority to enforce the Fourteenth Amendment to the U.S. Constitution and to regulate commerce. The Americans with Disabilities Act was enacted “to provide a clear and comprehensive national mandate for the elimination of discrimination against individuals with disabilities.” 42 U.S.C. §12101 (b) (1). The Americans with Disabilities Act recognizes the authority of State and local governments to enact and enforce laws that “provide for greater or equal protection for the rights of individuals with disabilities than are afforded by this chapter.” 42 U.S.C. §12201 (b). The proposed rule is based on the recommendations of a federal advisory committee which included representatives of state and local governments. The Access Board made drafts of the proposed rule available for public review and comment. State and local governments provided comments on the drafts of the proposed rule.

Unfunded Mandates Reform Act

The Unfunded Mandates Reform Act does not apply to proposed or final rules that enforce constitutional rights of individuals or enforce statutory rights that prohibit discrimination on the basis of race, color, sex, national origin, age, handicap, or disability. Since the proposed rule is issued under the Americans with Disabilities Act, which prohibits discrimination on the basis of disability, an assessment of the rule’s effect on State, local, and tribal governments, and the private sector is not required by the Unfunded Mandates Reform Act.

List of Subjects in 36 CFR Part 1190

Buildings and facilities, Civil rights, Individuals with disabilities, Transportation.

Nancy Starnes,

Chair.

For the reasons stated in the preamble, the Access Board proposes to add part 1190 to title 36 of the Code of Federal Regulations to read as follows:

PART 1190 –ACCESSIBILITY GUIDELINES FOR PEDESTRIAN FACILITIES IN THE PUBLIC RIGHT-OF-WAY

Sec.

1190.1 Accessibility guidelines.

Appendix to part 1190 – Accessibility Guidelines for Pedestrian Facilities in the Public Right-of-Way

Authority: 29 U.S.C. 792 and 42 U.S.C. 12204.

§ 1190.1 Accessibility Guidelines.

The accessibility guidelines for pedestrian facilities in the public right-of-way are set forth in the appendix to this part. When the guidelines are adopted, with or without additions and modifications, as accessibility standards in regulations issued by other federal agencies implementing the Americans with Disabilities Act, Section 504 of the Rehabilitation Act, and the Architectural Barriers Act, compliance with the accessibility standards is mandatory. A copy of the guidelines with figures is available on the Access Board website at: <http://www.access-board.gov/prowac/nprm.htm>. Except for the International Symbol of Accessibility in Figure R411, which is included in the appendix to this part, the figures are for illustration purposes only and do not establish requirements.

CHAPTER R1: APPLICATION AND ADMINISTRATION

R101 Purpose

R101.1 General. This document contains scoping and technical requirements to ensure that facilities for pedestrian circulation and use located in the public right-of-way are readily accessible to and usable by pedestrians with disabilities. Compliance with this document is mandatory when required by regulations issued by federal agencies that include accessibility standards for the design, construction, and alteration of pedestrian facilities in the public right-of-way.

Advisory R101.1 General. Sections marked as “advisory” contain advisory information related to the preceding section. Advisory sections do not establish mandatory requirements. Some advisory sections reference related mandatory requirements to alert readers about those requirements.

R101.2 Effect on Existing Facilities. This document does not address existing facilities unless the facilities are included within the scope of an alteration undertaken at the discretion of a covered entity.

Advisory R101.2 Effect on Existing Facilities. The Department of Justice regulations implementing Title II of the Americans with Disabilities Act contain requirements for state and local governments regarding program accessibility and existing facilities. See 28 CFR 35.150. The Department of Transportation regulations implementing Section 504 of the Rehabilitation Act also contain requirements for recipients of federal financial assistance from the Department regarding compliance planning. See 49 CFR 27.11 (c).

R102 Equivalent Facilitation. The use of alternative designs, products, or technologies that result in substantially equivalent or greater accessibility and usability than the requirements in this document is permitted.

R103 Conventions

R103.1 Conventional Industry Tolerances. Dimensions are subject to conventional industry tolerances except where dimensions are stated as a range.

Advisory R103.1 Conventional Industry Tolerances. Conventional industry tolerances include tolerances for field conditions and tolerances that may be a necessary consequence of a particular manufacturing process. Conventional industry tolerances do not apply to design work.

R103.2 Calculation of Percentages. Where the required number of elements or facilities to be provided is determined by calculations of ratios or percentages and remainders or fractions result, the next greater whole number of such elements or facilities shall be provided. Where the determination of the required size or dimension of an element or facility involves ratios or percentages, rounding down for values less than one half is permitted.







Convention	Description
	dimension showing International System of Units (in millimeters unless otherwise specified) above the line and US customary units (in inches unless otherwise specified) below
	dimension for small measurements
	dimension showing a range with minimum - maximum
min	minimum
max	maximum
>	greater than
≥	greater than or equal to
<	less than
≤	less than or equal to
	boundary of clear floor space or maneuvering clearance
	centerline
	a permitted element or its extension
	direction of travel or approach
	a highlighted element in elevation or plan
	location zone of element, control or feature

Figure R103
Graphic Convention for Figures

R103.3 Units of Measurement. Measurements are stated in metric and U.S. customary units. The values stated in each system (metric and U.S. customary units) may not be exact equivalents, and each system shall be used independently of the other.

Advisory R103.3 Units of Measurement. Users should work entirely within one system of measurement, either metric or U.S. customary units. Combining values from the two systems may result in non-compliance.

R104 Referenced Standards

R104.1 Incorporation by Reference. The specific editions of the standards listed in R104.2 are incorporated by reference in this document and are part of the requirements to the prescribed extent of each such reference. The Director of the Federal Register has approved the standards for incorporation by reference in accordance with 5 U.S.C. 552(a) and 1 CFR part 51. Copies of the referenced standards may be inspected at the Access Board, 1331 F Street, NW, Suite 1000, Washington, DC 20004; or at the National Archives and Records Administration (NARA). For information on the availability of the referenced standards at NARA, call (202) 741-6030, or go to: http://www.archives.gov/federal_register/code_of_federal_regulations/ibr_locations.html.

R104.2 MUTCD. The portions of the Manual on Uniform Traffic Control Devices for Streets and Highways (MUTCD), 2009 Edition, that are incorporated by reference in this document consist of definitions (see R105.2) and standard statements, as defined in section 1A.13 of the MUTCD (see R205, R209, and R306.3). Guidance, option, and support statements, as defined in section 1A.13 of the MUTCD, shall be used to assist in the interpretation of the standard statements. Where there are differences between this document and the referenced standards, this document applies. The MUTCD is available on the Federal Highway Administration website at <http://mutcd.fhwa.dot.gov>. Printed copies may be purchased from the American Association of State Highway and Transportation Officials, 444 N Capitol Street, NW, Washington, DC 20001 (<http://www.transportation.org/>).

Advisory R104.2 MUTCD. MUTCD definitions and standard statements are referenced in the following sections of this document:

- R105.2 references definitions in section 1A.13 of the MUTCD;
- R205 references standard statements in sections 6D.01, 6D.02, 6G.05, 6F.63, 6F.68, and 6F.71 of the MUTCD for providing alternate pedestrian access routes when a pedestrian circulation path is temporarily closed;
- R209 references standard statements in sections 4E.08 through 4E.13 of the MUTCD for accessible pedestrian signals and pedestrian pushbuttons; and
- R306.2 references standard statements in section 4E.06 of the MUTCD for pedestrian signal phase timing.

R105 Definitions

R105.1 General. For the purpose of this document, the terms defined in R105.5 have the indicated meaning.

R105.2 Terms Defined in Referenced Standards. Terms used in specific sections of the MUTCD that are incorporated by reference in this document shall have the meaning specified in section 1A.13 of the MUTCD (incorporated by reference, see R104.2). In addition, the following terms shall have the meaning specified in section 1A.13 of the MUTCD (incorporated by reference, see R104.2): highway, intersection, island, median, pedestrian, roundabout, sidewalk, splitter island, and street.

R105.3 Undefined Terms. The meaning of terms not specifically defined in R105.5, the referenced standards, or regulations issued by Federal agencies that adopt this document as accessibility standards shall be as defined by collegiate dictionaries in the sense that the context implies.

R105.4 Interchangeability. Words, terms, and phrases used in the singular include the plural and those used in the plural include the singular.

R105.5 Defined Terms.

Accessible. Describes a facility in the public right-of-way that complies with this document.

Alteration. A change to a facility in the public right-of-way that affects or could affect pedestrian access, circulation, or use. Alterations include, but are not limited to, resurfacing, rehabilitation, reconstruction, historic restoration, or changes or rearrangement of structural parts or elements of a facility.

Blended Transition. A raised pedestrian street crossing, depressed corner, or similar connection between the pedestrian access route at the level of the sidewalk and the level of the pedestrian street crossing that has a grade of 5 percent or less.

Cross Slope. The grade that is perpendicular to the direction of pedestrian travel.

Curb Line. A line at the face of the curb that marks the transition between the curb and the gutter, street, or highway.

Curb Ramp. A ramp that cuts through or is built up to the curb. Curb ramps can be perpendicular or parallel, or a combination of parallel and perpendicular ramps.

Element. An architectural or mechanical component of a building, facility, space, site, or public right-of-way.

Facility. All or any portion of buildings, structures, improvements, elements, and pedestrian or vehicular routes located in the public right-of-way.

Grade Break. The line where two surface planes with different grades meet.

Operable Part. A component of an element used to insert or withdraw objects, or to activate, deactivate, or adjust the element.

Pedestrian Access Route. A continuous and unobstructed path of travel provided for pedestrians with disabilities within or coinciding with a pedestrian circulation path.

Pedestrian Circulation Path. A prepared exterior or interior surface provided for pedestrian travel in the public right-of-way.

Public Right-of-Way. Public land or property, usually in interconnected corridors, that is acquired for or dedicated to transportation purposes.

Qualified Historic Facility. A facility that is listed in or eligible for listing in the National Register of Historic Places, or designated as historic under an appropriate state or local law.

Running Slope. The grade that is parallel to the direction of pedestrian travel.

Vertical Surface Discontinuities. Vertical differences in level between two adjacent surfaces.

CHAPTER R2: SCOPING REQUIREMENTS

R201 Application

R201.1 Scope. All newly constructed facilities, altered portions of existing facilities, and elements added to existing facilities for pedestrian circulation and use located in the public right-of-way shall comply with the requirements in this document.

Advisory R201.1 Scope. The requirements in this document are to be applied to all areas of a facility within the scope of the project. Where multiple features of the same type are provided, such as on-street parking spaces, and a percentage of the features are required to be accessible, only the required number of features must comply with the technical requirements in this document and be connected to a pedestrian access route. Where elements are provided on a site that is a designated portion of a public right-of-way, the elements are required to comply with the applicable requirements in this document instead of the requirements in the Americans with Disabilities Act Accessibility Guidelines for Buildings and Facilities and the Architectural Barriers Act Accessibility Guidelines (36 CFR part 1191).

R201.2 Temporary and Permanent Facilities. The requirements in this document shall apply to temporary and permanent facilities in the public right-of-way.

Advisory R201.2 Temporary and Permanent Facilities. Temporary pedestrian circulation paths around work zones and portable public toilets are examples of temporary facilities in the public right-of-way that are covered by the requirements in this document.

R201.3 Buildings and Structures. Buildings and structures in the public right-of-way that are not covered by the requirements in this document shall comply with the applicable requirements in 36 CFR part 1191.

Advisory R201.3 Buildings and Structures. Towers and temporary performance stages and reviewing stands are examples of structures that may be provided in the public right-of-way and are not covered by the requirements in this document. These structures are required to comply with the applicable requirements in the Americans with Disabilities Act Accessibility Guidelines for Buildings and Facilities and the Architectural Barriers Act Accessibility Guidelines (36 CFR part 1191).

R202 Alterations and Elements Added to Existing Facilities

R202.1 General. Alterations and elements added to existing facilities shall comply with R202. Where elements are altered or added and the pedestrian circulation path to the altered or added elements is not altered, the pedestrian circulation path is not required to comply with R204.

Advisory R202.1 General. Where possible, added elements should be located on an existing pedestrian access route.

R202.2 Added Elements. Where elements are added to existing facilities, the added elements shall comply with the applicable requirements for new construction.

R202.3 Alterations. Where existing elements, spaces, or facilities are altered, each altered element, space, or facility within the scope of the project shall comply with the applicable requirements for new construction.

Advisory R202.3 Alterations. The alteration of multiple elements or spaces within a facility may provide a cost-effective opportunity to make the entire facility or a significant portion of the facility accessible.

R202.3.1 Existing Physical Constraints. Where existing physical constraints make it impracticable for altered elements, spaces, or facilities to fully comply with the requirements for new construction, compliance is required to the extent practicable within the scope of the project. Existing physical constraints include, but are not limited to, underlying terrain, right-of-way availability, underground structures, adjacent developed facilities, drainage, or the presence of a notable natural or historic feature.

R202.3.2 Transitional Segments. Transitional segments of pedestrian access routes shall connect to existing unaltered segments of pedestrian circulation paths and shall comply with R302 to the extent practicable.

R202.3.3 Reduction in Access Prohibited. An alteration shall not decrease or have the effect of decreasing the accessibility of a facility or an accessible connection to an adjacent building or site below the requirements for new construction in effect at the time of the alteration.

Advisory R202.3.3 Reduction in Access Prohibited. Sidewalk improvements that correct existing excessive cross slope should be carefully planned to avoid creating excessive slope in curb ramps or adding a step at existing building entrances. Solutions may include:

- Split sidewalks that serve building entrances and street or highway at separate levels;
- Sidewalks with greater cross slope along the curb and pedestrian access routes with lesser cross slope along building fronts;
- Pedestrian access routes along the curb and ramped entrances to buildings.

R202.3.4 Alterations to Qualified Historic Facilities. Where the State Historic Preservation Officer or Advisory Council on Historic Preservation determines that compliance with a requirement would threaten or destroy historically significant features of a qualified historic facility, compliance shall be required to the extent that it does not threaten or destroy historically significant features of the facility.

Advisory R202.3.4 Alterations to Qualified Historic Facilities. Where there is a federal agency “undertaking”, as defined in 36 CFR 800.16 (y), the requirements in section 106 of the National Historic Preservation Act (16 U.S.C. 470f) and 36 CFR part 800 apply. Location of a facility within an historic district by itself does not excuse compliance with the requirements in this document. The State Historic Preservation Officer or Advisory Council on Historic Preservation must determine that compliance would threaten or destroy historically significant features of the facility. Reproductions or replications of historic facilities are not qualified historic facilities.

R203 Machinery Spaces. Vaults, tunnels, and other spaces used by service personnel only for maintenance, repair, or monitoring are not required to comply with this document.

R204 Pedestrian Access Routes

R204.1 General. Pedestrian access routes shall be provided in accordance with R204 and shall comply with R302.

Advisory R204.1 General. The Federal Highway Administration (FHWA) has issued guidance on the obligations of state and local governments to keep pedestrian access routes open and usable throughout the year, including snow and debris removal. The guidance is available at FHWA’s website:

http://www.fhwa.dot.gov/civilrights/programs/ada_sect504qa.htm.

R204.2 Sidewalks. A pedestrian access route shall be provided within sidewalks and other pedestrian circulation paths located in the public right-of-way. The pedestrian access route shall connect to accessible elements, spaces, and facilities required by this document and to accessible routes required by section 206.2.1 of appendix B to 36 CFR part 1191 or section F206.2.1 of appendix C to 36 CFR 1191 that connect building and facility entrances to public streets and sidewalks.

Advisory R204.2 Sidewalks. The accessible elements, spaces, and facilities located in the public right-of-way that pedestrian access routes must connect to include accessible pedestrian signals and pedestrian pushbuttons (see R209), street furniture (see R212), boarding and alighting areas and boarding platforms at transit stops (see R213 and R308.1.3.2), transit shelters (see R213 and R308.2), accessible on-street parking spaces (see R214 and R309), parking meters and parking pay stations serving accessible parking spaces (see R309.5), and accessible passenger loading zones (see R215 and R310).

R204.3 Pedestrian Street Crossings. A pedestrian access route shall be provided within pedestrian street crossings, including medians and pedestrian refuge islands, and pedestrian at-grade rail crossings. The pedestrian access route shall connect departure and arrival sidewalks.

R204.4 Pedestrian Overpasses and Underpasses. A pedestrian access route shall be provided within overpasses, underpasses, bridges, and similar structures that contain pedestrian circulation paths. Where an overpass, underpass, bridge, or similar structure is designed for pedestrian use only and the approach slope to the structure exceeds 5 percent, a ramp, elevator, limited use/limited application

elevator, or platform lift shall be provided. Elevators and platform lifts shall be unlocked during the operating hours of the facility served.

Advisory R204.4 Pedestrian Overpasses and Underpasses. Where an overpass, underpass, bridge, or similar structure is designed for both pedestrian and vehicle use and the pedestrian access route is contained within the street or highway right-of-way, the grade of the pedestrian access route must not exceed the general grade established for the adjacent street or highway (see R302.5). Where the pedestrian access route is not contained within the street or highway right-of-way, the grade of the pedestrian access route must be 5 percent maximum (see R302.5). Where pedestrian overpasses or underpasses provide an alternative pedestrian circulation path to street level crossings, both the pedestrian overpass or underpass and the street level crossing must contain a pedestrian access route. State and local governments can provide a ramp, elevator, or lift at overpasses and underpasses designed for pedestrian use only. Long ramps present difficulties for some pedestrians with disabilities and can require snow clearance. Elevators or lifts can require maintenance.

R205 Alternate Pedestrian Access Routes. When a pedestrian circulation path is temporarily closed by construction, alterations, maintenance operations, or other conditions, an alternate pedestrian access route complying with sections 6D.01, 6D.02, and 6G.05 of the MUTCD (incorporated by reference, see R104.2) shall be provided. Where provided, pedestrian barricades and channelizing devices shall comply with sections 6F.63, 6F.68, and 6F.71 of the MUTCD (incorporated by reference, see R104.2).

Advisory R205 Alternate Pedestrian Access Routes. Section 6G.05 of the MUTCD recommends that whenever possible work should be done in a manner that does not create a need to detour pedestrians from existing pedestrian routes. Extra distance and additional pedestrian street crossings add complexity to a trip and increase exposure of risk to accidents. Sections 6D.01 and 6G.05 of the MUTCD require alternate pedestrian routes to be accessible and detectable, including warning pedestrians who are blind or have low vision about sidewalk closures. Proximity-actuated audible signs are a preferred means to warn pedestrians who are blind or have low vision about sidewalk closures.

R206 Pedestrian Street Crossings. Pedestrian street crossings shall comply with R306.

Advisory R206 Pedestrian Street Crossings. All pedestrian street crossings must be accessible to pedestrians with disabilities. If pedestrian crossing is prohibited at certain locations, "No Pedestrian Crossing" signs should be provided along with detectable features, such as grass strips, landscaping, planters, chains, fencing, railings, or other barriers.

R207 Curb Ramps and Blended Transitions

R207.1 General. A curb ramp, blended transition, or a combination of curb ramps and blended transitions complying with R304 shall connect the pedestrian access routes at each pedestrian street

crossing. The curb ramp (excluding any flared sides) or blended transition shall be contained wholly within the width of the pedestrian street crossing served.

R207.2 Alterations. In alterations where existing physical constraints prevent compliance with R207.1, a single diagonal curb ramp shall be permitted to serve both pedestrian street crossings.

R208 Detectable Warning Surfaces

R208.1 Where Required. Detectable warning surfaces complying with R305 shall be provided at the following locations on pedestrian access routes and at transit stops:

1. Curb ramps and blended transitions at pedestrian street crossings;
2. Pedestrian refuge islands;
3. Pedestrian at-grade rail crossings not located within a street or highway;
4. Boarding platforms at transit stops for buses and rail vehicles where the edges of the boarding platform are not protected by screens or guards; and
5. Boarding and alighting areas at sidewalk or street level transit stops for rail vehicles where the side of the boarding and alighting areas facing the rail vehicles is not protected by screens or guards.

Advisory R208.1 Where Required. On pedestrian access routes, detectable warning surfaces indicate the boundary between pedestrian and vehicular routes where there is a flush rather than a curbed connection. Detectable warning surfaces should not be provided at crossings of residential driveways since the pedestrian right-of-way continues across residential driveway aprons. However, where commercial driveways are provided with yield or stop control, detectable warning surfaces should be provided at the junction between the pedestrian route and the vehicular route. Where pedestrian at-grade rail crossings are located within a street or highway, detectable warning surfaces at the curb ramps or blended transitions make a second set of detectable warning surfaces at the rail crossing unnecessary.

Detectable warning surfaces are not intended to provide wayfinding for pedestrians who are blind or have low vision. Wayfinding can be made easier by:

- Sidewalks that provide a clear path free of street furniture;
- Visual contrast between walking and non-walking areas (e.g., planted borders);
- Route edges that are clear and detectable by cane;
- Direct pedestrian street crossings and curb ramps that are in-line with direction of travel;
- Small corner radiuses that permit pedestrian street crossings to be as short and direct as possible;
- Orthogonal intersections that facilitate navigation using parallel and perpendicular vehicle sound cues;
- and barriers where pedestrian travel or crossing is not permitted.

R208.2 Where Not Required. Detectable warning surfaces are not required at pedestrian refuge islands that are cut-through at street level and are less than 1.8 meters (6.0 ft) in length in the direction of pedestrian travel.

Advisory R208.2 Where Not Required. Detectable warning surfaces are not required at cut-through pedestrian refuge islands that are less than 1.8 meters (6.0 ft) in length because detectable warning surfaces must extend 610 millimeters (2.0 ft) minimum on each side of the island and be separated by 610 millimeters (2.0 ft) minimum length of island without detectable warning surfaces (see R305.1.4 and R305.2.4). Installing detectable warning surfaces at cut-through pedestrian islands that are less than 1.8 meters (6.0 ft) in length would compromise the effectiveness of detectable warning surfaces. Where a cut-through pedestrian refuge island is less than 1.8 m (6.0 ft) in length and the pedestrian street crossing is signalized, the signal should be timed for a complete crossing of the street.

R209 Accessible Pedestrian Signals and Pedestrian Pushbuttons

R209.1 General. Where pedestrian signals are provided at pedestrian street crossings, they shall include accessible pedestrian signals and pedestrian pushbuttons complying with sections 4E.08 through 4E.13 of the MUTCD (incorporated by reference, see R104.2). Operable parts shall comply with R403.

Advisory R209 Accessible Pedestrian Signals and Pedestrian Pushbuttons. An accessible pedestrian signal and pedestrian pushbutton is an integrated device that communicates information about the WALK and DON'T WALK intervals at signalized intersections in non-visual formats (i.e., audible tones and vibrotactile surfaces) to pedestrians who are blind or have low vision.

R209.2 Alterations. Existing pedestrian signals shall comply with R209.1 when the signal controller and software are altered, or the signal head is replaced.

R210 Protruding Objects. Objects along or overhanging any portion of a pedestrian circulation path shall comply with R402 and shall not reduce the clear width required for pedestrian access routes.

Advisory R210 Protruding Objects. Protruding objects can be hazardous for pedestrians, especially pedestrians who are blind or have low vision. The requirements for protruding objects in R402 apply across the entire width of the pedestrian circulation path, not just the pedestrian access route. In addition, objects must not reduce the clear width required for pedestrian access routes. State and local governments must comply with the requirements for protruding objects and maintain the clear width of pedestrian access routes when installing or permitting the installation of street furniture on sidewalks, including street lights, utility poles and equipment cabinets, sign posts and signs, parking meters, trash receptacles, public telephones, mailboxes, newspaper vending machines, benches, transit shelters, kiosks, bicycle racks, planters and planted trees, and street sculptures. The American Association of State Highway and Transportation Officials (AASHTO) recommends that local governments use an encroachment permit process to regulate the use of sidewalks by private entities for activities such as outdoor dining, vending carts and stands, and street fairs in order to control protruding objects and maintain the clear width of pedestrian access routes. See AASHTO, Guide for the Planning, Design, and Operation of Pedestrian Facilities (2004), section 3.2.3.

R211 Signs

R211.1 General. Signs shall comply with R211. Where audible sign systems and other technologies are used to provide information equivalent to the information contained on pedestrian signs and transit signs, the signs are not required to comply with R211.2 and R211.3.

Advisory R211.1 General. Audible sign systems and other technologies that provide information equivalent to the information contained on signs are more usable by pedestrians who are blind or have low vision. Remote infrared audible signs that transmit information to portable devices that are carried by and audible only to the user are an example of audible sign systems and other technologies.

R211.2 Pedestrian Signs. Signs, other than transit signs, that provide directions, warnings, or other information for pedestrians only shall comply with R410.

Advisory R211.2 Pedestrian Signs. Pedestrian route signs along an historic trail, sidewalk closure and pedestrian detour signs, and tourist information signs are examples of signs that provide directions, warnings, or other information for pedestrians only. Signs provided for motorists and pedestrians such as highway and street name signs are not required to comply with R410.

R211.3 Transit Signs. Signs that identify the routes served by transit stops shall comply with R410.

Advisory R211.3 Transit Signs. Transit schedules, timetables, and maps are not required to comply with R410.

R211.4 Accessible Parking Space and Passenger Loading Zone Signs. Accessible parking spaces and accessible passenger loading zones shall be identified by signs displaying the International Symbol

of Accessibility complying with R411. At accessible parallel parking spaces and accessible passenger loading zones, the signs shall be located at the head or foot of the parking space or passenger loading zone.

R212 Street Furniture

R212.1 General. Where provided, street furniture shall comply with the applicable requirements in R212.

R212.2 Drinking Fountains. Drinking fountains shall comply with sections 602.1 through 602.6 of Appendix D to 36 CFR part 1191.

R212.3 Public Toilet Facilities. Public toilet facilities shall comply with sections 206.2.4 and 603 of Appendix D to 36 CFR part 1191. At least one fixture of each type provided shall comply with sections 604 through 610 of Appendix D to 36 CFR part 1191. Where multiple single-user public toilet facilities are clustered at a single location, at least 5 percent, but no less than one, of single-user toilets at each cluster shall comply with R212.3 and shall be identified by the International Symbol of Accessibility complying with R411.

R212.4 Tables. At least 5 percent, but no less than one, of tables at each location shall comply with section 902 of Appendix D to 36 CFR part 1191.

R212.5 Counters. Counters shall comply with section 904 of Appendix D to 36 CFR part 1191.

R212.6 Benches. At least 50 percent, but no less than one, of benches at each location shall provide clear space complying with R404 adjacent to the bench. The clear space shall be located either at one end of the bench or shall not overlap the area within 460 mm (1.5 ft) from the front edge of the bench. Benches at tables are not required to comply.

Advisory R212.6 Benches. Benches that provide full back support and armrests to assist in sitting and standing are more usable by pedestrians with disabilities.

R213 Transit Stops and Transit Shelters. Where provided, transit stops and transit shelters shall comply with R308.

Advisory R213 Transit Stops and Transit Shelters. Transit stops in the public right-of-way typically serve fixed route bus systems, including bus rapid transit systems, and light rail transit systems. Signs that identify the routes served by the transit stop must comply with the technical requirements for visual characters on signs unless audible sign systems or other technologies are used to provide the information (see R211 and R410). The Federal Highway Administration (FHWA) has issued guidance on the obligations of state transportation departments, metropolitan planning organizations, and transit agencies to coordinate the planning and funding of accessibility improvements to transit systems and facilities. The guidance is available at FHWA's website:
http://www.fhwa.dot.gov/civilrights/memos/ada_memo_clarificationa.htm.

R214 On-Street Parking Spaces. Where on-street parking is provided on the block perimeter and the parking is marked or metered, accessible parking spaces complying with R309 shall be provided in accordance with Table R214. Where parking pay stations are provided and the parking is not marked, each 6.1 m (20.0 ft) of block perimeter where parking is permitted shall be counted as one parking space.

Table R214 On-Street Parking Spaces

Total Number of Marked or Metered Parking Spaces on the Block Perimeter	Minimum Required Number of Accessible Parking Spaces
1 to 25	1
26 to 50	2
51 to 75	3
76 to 100	4
101 to 150	5
151 to 200	6
201 and over	4 percent of total

Advisory R214 On-Street Parking Spaces. The MUTCD contains provisions for marking on-street parking spaces (see section 3B.19). Metered parking includes parking metered by parking pay stations. Where parking on part of the block perimeter is altered, the minimum number of accessible parking spaces required is based on the total number of marked or metered parking spaces on the block perimeter.

R215 Passenger Loading Zones. Where passenger loading zones other than transit stops are provided, at least one accessible passenger loading zone complying with R310 shall be provided for each 30 m (100.0 ft) of continuous loading zone space or fraction thereof.

R216 Stairways and Escalators. Where provided on pedestrian circulation paths, stairways shall comply with R408 and escalators shall comply with section 810.9 of Appendix D to 36 CFR part 1191. Stairways and escalators shall not be part of a pedestrian access route.

R217 Handrails. Where provided on pedestrian circulation paths, handrails shall comply with R409.

R218 Doors, Doorways, and Gates. Where provided at pedestrian facilities, doors, doorways, and gates shall comply with section 404 of Appendix D to 36 CFR part 1191.

Advisory R218 Doors, Doorways, and Gates. Enclosed transit shelters are an example of pedestrian facilities where doors and doorways are provided.

CHAPTER R3: TECHNICAL REQUIREMENTS

R301 General

R301.1 Scope. The technical requirements in Chapter 3 shall apply where required by Chapter 2 or where referenced by a requirement in this document.

R302 Pedestrian Access Routes

R302.1 General. Pedestrian access routes shall comply with R302.

R302.2 Components. Pedestrian access routes shall consist of one or more of the following components:

1. Sidewalks and other pedestrian circulation paths, or a portion of sidewalks and other pedestrian circulation paths, complying with R302.3 through R302.7;
2. Pedestrian street crossings and at-grade rail crossings complying with R302.3 through R302.7, and R306;
3. Pedestrian overpasses and underpasses and similar structures complying with R302.3 through R302.7;
4. Curb ramps and blended transitions complying with R302.7 and R304;
5. Ramps complying with R407;
6. Elevators and limited use/limited application elevators complying with sections 407 or 408 of Appendix D to 36 CFR part 1191;
7. Platform lifts complying with section 410 of Appendix D to 36 CFR part 1191; and
8. Doors, doorways, and gates complying with section 404 of Appendix D to 36 CFR part 1191.

Advisory R302.2 Components. The technical requirement for elevators, limited use/limited application elevators, platform lifts, and doors, doorways, and gates are contained in the Americans with Disabilities Act Accessibility Guidelines for Buildings and Facilities and the Architectural Barriers Act Accessibility Guidelines (36 CFR part 1191).

R302.3 Continuous Width. Except as provided in R302.3.1, the continuous clear width of pedestrian access routes shall be 1.2 m (4.0 ft) minimum, exclusive of the width of the curb.

Advisory R302.3 Continuous Width. The continuous clear width requirements in R302.3 apply to sidewalks and other pedestrian circulation paths, pedestrian street crossings and at-grade rail crossings, and pedestrian overpasses and underpasses and similar structures (see R302.2). Clear width requirements are contained in R304.5.1 for curb ramps and blended transitions, and in R407.4 for ramps. Where sidewalks are wider than 1.2 m (4.0 ft), only a portion of the sidewalk is required to comply with the requirements in R302.3 through R302.7. Additional maneuvering space should be provided at turns or changes in direction, transit stops, recesses and alcoves, building entrances, and along curved or angled routes, particularly where the grade exceeds 5 percent. R210 prohibits street furniture and other objects from reducing the minimum clear width of pedestrian access routes.




Figure R302.3
Continuous Width

R302.3.1 Medians and Pedestrian Refuge Islands. The clear width of pedestrian access routes within medians and pedestrian refuge islands shall be 1.5 m (5.0 ft) minimum.

R302.4 Passing Spaces. Where the clear width of pedestrian access routes is less than 1.5 m (5.0 ft), passing spaces shall be provided at intervals of 61 m (200.0 ft) maximum. Passing spaces shall be 1.5 m (5.0 ft) minimum by 1.5 m (5.0 ft) minimum. Passing spaces are permitted to overlap pedestrian access routes.




Figure R302.4
Passing Spaces

R302.5 Grade. Except as provided in R302.5.1, where pedestrian access routes are contained within a street or highway right-of-way, the grade of pedestrian access routes shall not exceed the general grade established for the adjacent street or highway. Where pedestrian access routes are not contained within a street or highway right-of-way, the grade of pedestrian access routes shall be 5 percent maximum.

Advisory R302.5 Grade. The grade requirements in R302.5 apply to sidewalks and other pedestrian circulation paths, pedestrian street crossings and at-grade rail crossings, and pedestrian overpasses and underpasses and similar structures (see R302.2). The grade of the pedestrian access route is measured parallel to the direction of pedestrian travel. Running slope requirements are contained in R304.2.2 for perpendicular curb ramps, in R304.3.2 for parallel curb ramps, in R304.4.1 for blended transitions, and in R407.2 for ramps.

R302.5.1 Pedestrian Street Crossings. Where pedestrian access routes are contained within pedestrian street crossings, the grade of the pedestrian access route shall be 5 percent maximum.

R302.6 Cross Slope. Except as provided in R302.6.1 and R302.6.2, the cross slope of pedestrian access routes shall be 2 percent maximum.

Advisory R302.6 Cross Slope. The cross slope requirements in R302.6 apply to sidewalks and other pedestrian circulation paths, pedestrian street crossings and at-grade rail crossings, and pedestrian overpasses and underpasses and similar structures (see R302.2). The cross slope of the pedestrian access route is measured perpendicular to the direction of pedestrian travel. Cross slope requirements are contained in R304.5.3 for curb ramps and blended transitions, and in R407.3 for ramps.

R302.6.1 Pedestrian Street Crossings Without Yield or Stop Control. Where pedestrian access routes are contained within pedestrian street crossings without yield or stop control, the cross slope of the pedestrian access route shall be 5 percent maximum.

Advisory R302.6.1 Pedestrian Street Crossings Without Yield or Stop Control. Pedestrian street crossings without yield or stop control are crossings where there is no yield or stop sign, or where there is a traffic signal that is designed for the green phase. At pedestrian street crossings without yield or stop control, vehicles can proceed through the intersection without slowing or stopping. Where pedestrian access routes are contained within pedestrian street crossings with yield or stop control, the cross slope of the pedestrian access route must be 2 percent maximum (see R302.6). At pedestrian street crossings with yield or stop control, vehicles slow or stop before proceeding through the intersection.

R302.6.2 Midblock Pedestrian Street Crossings. Where pedestrian access routes are contained within midblock pedestrian street crossings, the cross slope of the pedestrian access route shall be permitted to equal the street or highway grade.

R302.7 Surfaces. The surfaces of pedestrian access routes and elements and spaces required to comply with R302.7 that connect to pedestrian access routes shall be firm, stable, and slip resistant and shall comply with R302.7.

Advisory R302.7 Surfaces. The surface requirements in R302.7 apply to sidewalks and other pedestrian circulation paths, pedestrian street crossings and at-grade rail crossings, pedestrian overpasses and underpasses and similar structures, and curb ramps and blended transitions (see R302.2). The surface requirements in R302.7 also apply to surfaces at the following accessible elements and spaces that connect to pedestrian access routes:

- Clear spaces (see R404.2), including clear spaces at operable parts (see R403.2) such as accessible pedestrian signals and pedestrian pushbuttons (see R209), clear spaces at street furniture such as benches (see R212.6), and clear spaces within transit shelters (see R308.2);
- Boarding and alighting areas and boarding platforms at transit stops (see R308.1.3.1);
- Access aisles at accessible parking spaces (see R309.2.1 and R309.3) and accessible passenger loading zones (see R310.3.4); and ramp runs and landings (see R407.7).

R302.7.1 Vertical Alignment. Vertical alignment shall be generally planar within pedestrian access routes (including curb ramp runs, blended transitions, turning spaces, and gutter areas within pedestrian access routes) and surfaces at other elements and spaces required to comply with R302.7 that connect to pedestrian access routes. Grade breaks shall be flush. Where pedestrian access routes cross rails at grade, the pedestrian access route surface shall be level and flush with the top of rail at the outer edges of the rails, and the surface between the rails shall be aligned with the top of rail.

Advisory R302.7.1 Vertical Alignment. Pedestrian access route surfaces must be generally planar and smooth. Surfaces should be chosen for easy rollability. Surfaces that are heavily textured, rough, or chamfered and paving systems consisting of individual units that cannot be laid in plane will greatly increase rolling resistance and subject pedestrians who use wheelchairs, scooters, and rolling walkers to the stressful and often painful effects of vibration. Such materials should be reserved for borders and decorative accents located outside of or only occasionally crossing the pedestrian access route. Surfaces should be designed, constructed, and maintained according to appropriate industry standards, specifications, and recommendations for best practice.

R302.7.2 Vertical Surface Discontinuities. Vertical surface discontinuities shall be 13 mm (0.5 in) maximum. Vertical surface discontinuities between 6.4 mm (0.25 in) and 13 mm (0.5 in) shall be beveled with a slope not steeper than 50 percent. The bevel shall be applied across the entire vertical surface discontinuity.

Advisory R302.7.2 Vertical Surface Discontinuities. The allowance for vertical surface discontinuities is for occasional expansion joints and objects such as utility covers, vault frames, and gratings that cannot be located in another portion of the sidewalk outside the pedestrian access route. However, objects such as utility covers, vault frames, and gratings should not be located on curb ramp runs, blended transitions, turning spaces, or gutter areas within the pedestrian access route. This may not always be possible in alterations, but should be avoided wherever possible. Vertical surface discontinuities between unit pavers should be minimized.




Figure R302.7.2
Vertical Surface Discontinuities

R302.7.3 Horizontal Openings. Horizontal openings in gratings and joints shall not permit passage of a sphere more than 13 mm (0.5 in) in diameter. Elongated openings in gratings shall be placed so that the long dimension is perpendicular to the dominant direction of travel.




Figure R302.7.3
Horizontal Openings

R302.7.4 Flangeway Gaps. Flangeway gaps at pedestrian at-grade rail crossings shall be 64 mm (2.5 in) maximum on non-freight rail track and 75 mm (3 in) maximum on freight rail track.

Advisory R302.7.4 Flangeway Gaps. Flangeway gaps are necessary to allow the passage of train wheel flanges. Flangeway gaps pose a potential hazard to pedestrians who use wheelchairs because the gaps can entrap the wheelchair casters.




Figure R302.7.4
Flangeway Gaps

R303 Alternate Pedestrian Access Routes (See R205)

R304 Curb Ramps and Blended Transitions

R304.1 General. Curb ramps and blended transitions shall comply with R304.

Advisory R304.1 General. There are two types of curb ramps:

- Perpendicular curb ramps have a running slope that cuts through or is built up to the curb at right angles or meets the gutter break at right angles where the curb is curved. On large corner radiuses, it will be necessary to indent the gutter break on one side of the curb ramp in order for the curb ramp to meet the gutter break at right angles.
- Parallel curb ramps have a running slope that is in-line with the direction of sidewalk travel and lower the sidewalk to a level turning space where a turn is made to enter the pedestrian street crossing.

Advisory R304.1 General (continued). Perpendicular curb ramps can be provided where the sidewalk is at least 3.7 m (12.0 ft) wide. Parallel curb ramps can be provided where the sidewalk is at least 1.2 m (4.0 ft) wide. Parallel and perpendicular curb ramps can be combined. A parallel curb ramp is used to lower the sidewalk to a mid-landing and a short perpendicular curb ramp connects the landing to the street. Combination curb ramps can be provided where the sidewalk is at least 1.8 m (6.0 ft) wide.

Blended transitions are raised pedestrian street crossings, depressed corners, or similar connections between pedestrian access routes at the level of the sidewalk and the level of the pedestrian street crossing that have a grade of 5 percent or less. Blended transitions are suitable for a range of sidewalk conditions.

R304.2 Perpendicular Curb Ramps. Perpendicular curb ramps shall comply with R304.2 and R304.5.

R304.2.1 Turning Space. A turning space 1.2 m (4.0 ft) minimum by 1.2 m (4.0 ft) minimum shall be provided at the top of the curb ramp and shall be permitted to overlap other turning spaces and clear spaces. Where the turning space is constrained at the back-of-sidewalk, the turning space shall be 1.2 m (4.0 ft) minimum by 1.5 m (5.0 ft) minimum. The 1.5 m (5.0 ft) dimension shall be provided in the direction of the ramp run.




Figure R304.2.1
Turning Space

R304.2.2 Running Slope. The running slope of the curb ramp shall cut through or shall be built up to the curb at right angles or shall meet the gutter grade break at right angles where the curb is curved. The running slope of the curb ramp shall be 5 percent minimum and 8.3 percent maximum but shall not require the ramp length to exceed 4.5 m (15.0 ft). The running slope of the turning space shall be 2 percent maximum.

R304.2.3 Flared Sides. Where a pedestrian circulation path crosses the curb ramp, flared sides shall be sloped 10 percent maximum, measured parallel to the curb line.

Advisory R304.2.3 Flared Sides. The flared sides are part of the pedestrian circulation path, but are not part of the pedestrian access route. Curb ramps whose sides have returned curbs provide useful directional cues where they are aligned with the pedestrian street crossing and are protected from cross travel by landscaping, street furniture, chains, fencing, or railings.




Figure R304.2.3
Flared Sides

R304.3 Parallel Curb Ramps. Parallel curb ramps shall comply with R304.3 and R304.5.

R304.3.1 Turning Space. A turning space 1.2 m (4.0 ft) minimum by 1.2 m (4.0 ft) minimum shall be provided at the bottom of the curb ramp and shall be permitted to overlap other turning spaces and clear spaces. If the turning space is constrained on 2 or more sides, the turning space shall be 1.2 m (4.0 ft) minimum by 1.5 m (5.0 ft). The 1.5 m (5.0 ft) dimension shall be provided in the direction of the pedestrian street crossing.




Figure R304.3.1
Turning Space

R304.3.2 Running Slope. The running slope of the curb ramp shall be in-line with the direction of sidewalk travel. The running slope of the curb ramp shall be 5 percent minimum and 8.3 percent maximum but shall not require the ramp length to exceed 4.5 m (15.0 ft) minimum. The running slope of the turning space shall be 2 percent maximum.

R304.4 Blended Transitions. Blended transitions shall comply with R304.4 and R304.5.

R304.4.1 Running Slope. The running slope of blended transitions shall be 5 percent maximum.




Figure R304.4.1
Running Slope

R304.5 Common Requirements. Curb ramps and blended transitions shall comply with R304.5.

R304.5.1 Width. The clear width of curb ramp runs (excluding any flared sides), blended transitions, and turning spaces shall be 1.2 m (4.0 ft) minimum.




Figure R304.5.1
Width

R304.5.2 Grade Breaks. Grade breaks at the top and bottom of curb ramp runs shall be perpendicular to the direction of the ramp run. Grade breaks shall not be permitted on the surface of ramp runs and turning spaces. Surface slopes that meet at grade breaks shall be flush.




Figure R304.5.2
Grade Breaks

R304.5.3 Cross Slope. The cross slope of curb ramps, blended transitions, and turning spaces shall be 2 percent maximum. At pedestrian street crossings without yield or stop control and at midblock pedestrian street crossings, the cross slope shall be permitted to equal the street or highway grade.

Advisory R304.5.3 Cross Slope. Pedestrian street crossings without yield or stop control are crossings where there is no yield or stop sign, or where there is a traffic signal that is designed for the green phase. At pedestrian street crossings without yield or stop control, vehicles can proceed through the intersection without slowing or stopping.

R304.5.4 Counter Slope. The counter slope of the gutter or street at the foot of curb ramp runs, blended transitions, and turning spaces shall be 5 percent maximum.

R304.5.5 Clear Space. Beyond the bottom grade break, a clear space 1.2 m (4.0 ft) minimum by 1.2 m (4.0 ft) minimum shall be provided within the width of the pedestrian street crossing and wholly outside the parallel vehicle travel lane.




Figure R304.5.5
Clear Space

R305 Detectable Warning Surfaces

R305.1 General. Detectable warning surfaces shall consist of truncated domes aligned in a square or radial grid pattern and shall comply with R305.

R305.1.1 Dome Size. The truncated domes shall have a base diameter of 23 mm (0.9 in) minimum and 36 mm (1.4 in) maximum, a top diameter of 50 percent of the base diameter minimum and 65 percent of the base diameter maximum, and a height of 5 mm (0.2 in).

Advisory R305.1.1 Dome Size. Where the truncated domes are arrayed radially, they may differ in diameter and center-to-center spacing within the ranges specified in R305.1.1 and R305.1.2.




Figure R305.1.1
Dome Size

R305.1.2 Dome Spacing. The truncated domes shall have a center-to-center spacing of 41 mm (1.6 in) minimum and 61 mm (2.4 in) maximum, and a base-to-base spacing of 17 mm (0.65 in) minimum, measured between the most adjacent domes.




Figure R305.1.2
Dome Spacing

R305.1.3 Contrast. Detectable warning surfaces shall contrast visually with adjacent gutter, street or highway, or pedestrian access route surface, either light-on-dark or dark-on-light.

Advisory R305.1.3 Contrast. Visual contrast may be provided on the full surface of the curb ramp but should not extend to flared sides. Visual contrast also helps pedestrians who use wheelchairs to locate the curb ramp from the other side of the street.

R305.1.4 Size. Detectable warning surfaces shall extend 610 mm (2.0 ft) minimum in the direction of pedestrian travel. At curb ramps and blended transitions, detectable warning surfaces shall extend the full width of the ramp run (excluding any flared sides), blended transition, or turning space. At pedestrian at-grade rail crossings not located within a street or highway, detectable warnings shall extend the full width of the crossing. At boarding platforms for buses and rail vehicles, detectable warning surfaces shall extend the full length of the public use areas of the platform. At boarding and alighting areas at sidewalk or street level transit stops for rail vehicles, detectable warning surfaces shall extend the full length of the transit stop.




Figure R305.1.4
Size

R305.2 Placement. The placement of detectable warning surfaces shall comply with R305.2.

Advisory R305.2 Placement. Some detectable warning products require a concrete border for proper installation. The concrete border should not exceed 51 mm (2 in). Where the back of curb edge is tooled to provide a radius, the border dimension should be measured from the end of the radius.

R305.2.1 Perpendicular Curb Ramps. On perpendicular curb ramps, detectable warning surfaces shall be placed as follows:

1. Where the ends of the bottom grade break are in front of the back of curb, detectable warning surfaces shall be placed at the back of curb.
2. Where the ends of the bottom grade break are behind the back of curb and the distance from either end of the bottom grade brake to the back of curb is 1.5 m (5.0 ft) or less, detectable warning surfaces shall be placed on the ramp run within one dome spacing of the bottom grade break.
3. Where the ends of the bottom grade break are behind the back of curb and the distance from either end of the bottom grade brake to the back of curb is more than 1.5 m (5.0 ft), detectable warning surfaces shall be placed on the lower landing at the back of curb.

Advisory R305.2.1 Perpendicular Curb Ramps. Detectable warning surfaces are intended to provide a tactile equivalent underfoot of the visible curb line. If detectable warning surfaces are placed too far from the curb line because of a large curb radius, the location may compromise effective crossing. Detectable warning surfaces should not be placed on paving or expansion joints. The rows of truncated domes in detectable warning surfaces should be aligned perpendicular to the grade break between the ramp run and the street so pedestrians who use wheelchairs can "track" between the domes. Where detectable warning surfaces are provided on a surface with a slope that is less than 5 percent, dome orientation is less critical.




Figure R305.2.1
Perpendicular Curb Ramps

R305.2.2 Parallel Curb Ramps. On parallel curb ramps, detectable warning surfaces shall be placed on the turning space at the flush transition between the street and sidewalk.




Figure R305.2.2
Parallel Curb Ramps

R305.2.3 Blended Transitions. On blended transitions, detectable warning surfaces shall be placed at the back of curb. Where raised pedestrian street crossings, depressed corners, or other level pedestrian street crossings are provided, detectable warning surfaces shall be placed at the flush transition between the street and the sidewalk.




Figure R305.2.3
Blended Transitions

R305.2.4 Pedestrian Refuge Islands. At cut-through pedestrian refuge islands, detectable warning surfaces shall be placed at the edges of the pedestrian island and shall be separated by a 610 mm (2.0 ft) minimum length of surface without detectable warnings.

Advisory R305.2.4 Pedestrian Refuge Islands. The edges of cut-through pedestrian refuge islands can provide useful cues to the direction of the crossing.




Figure R305.2.4
Pedestrian Refuge Islands

R305.2.5 Pedestrian At-Grade Rail Crossings. At pedestrian at-grade rail crossings not located within a street or highway, detectable warning surfaces shall be placed on each side of the rail crossing. The edge of the detectable warning surface nearest the rail crossing shall be 1.8 m (6.0 ft) minimum and 4.6 m (15.0 ft) maximum from the centerline of the nearest rail. Where pedestrian gates are provided, detectable warning surfaces shall be placed on the side of the gates opposite the rail.




Figure R305.2.5
Pedestrian At-Grade Rail Crossings

R305.2.6 Boarding Platforms. At boarding platforms for buses and rail vehicles, detectable warning surfaces shall be placed at the boarding edge of the platform.

R305.2.7 Boarding and Alighting Areas. At boarding and alighting areas at sidewalk or street level transit stops for rail vehicles, detectable warning surfaces shall be placed at the side of the boarding and alighting area facing the rail vehicles.

R306 Pedestrian Street Crossings

R306.1 General. Pedestrian street crossings shall comply with R306.

R306.2 Pedestrian Signal Phase Timing. All pedestrian signal phase timing shall comply with section 4E.06 of the MUTCD (incorporated by reference, see R104.2) and shall be based on a pedestrian clearance time that is calculated using a pedestrian walking speed of 1.1 m/s (3.5 ft/s) or less.

R306.3 Roundabouts. Where pedestrian facilities are provided at roundabouts, they shall comply with R306.3.

Advisory R306.3 Roundabouts. Pedestrian street crossings at roundabouts can be difficult for pedestrians who are blind or have low vision to identify because the crossings are located off to the side of the pedestrian circulation path around the street or highway. The continuous traffic flow at roundabouts removes many of the audible cues that pedestrians who are blind use to navigate pedestrian street crossings. Water fountains and other features that produce background noise should not be placed in the middle island of a roundabout because pedestrians who are blind use auditory cues to help detect gaps in traffic. Multi-lane pedestrian street crossings at roundabouts involve an increased risk of pedestrian exposure to accident.

R306.3.1 Separation. Where sidewalks are flush against the curb and pedestrian street crossing is not intended, a continuous and detectable edge treatment shall be provided along the street side of the sidewalk. Detectable warning surfaces shall not be used for edge treatment. Where chains, fencing, or railings are used for edge treatment, they shall have a bottom edge 380 mm (15 in) maximum above the sidewalk.

Advisory R306.3.1 Separation. Carefully delineated pedestrian street crossing approaches with plantings or other defined edges provide effective non-visual cues for identifying pedestrian street crossings at roundabouts. European and Australian roundabouts provide a 610 mm (24 inch) width of tactile surface treatment from the centerline of the curb ramp or blended transition across the full width of the sidewalk to provide an underfoot cue for identifying pedestrian street crossings. Detectable warning surfaces should not be used to guide pedestrians who are blind or have low vision to pedestrian street crossings because detectable warning surfaces indicate the flush transition between the sidewalk and the street or highway. Schemes that remove cyclists from the street or highway by means of a ramp that angles from the curb lane to the sidewalk and then provide re-entry by means of a similar ramp beyond pedestrian street crossings can provide false cues to pedestrians who are using the edge of the sidewalk for wayfinding about the location of pedestrian street crossings.

R306.3.2 Pedestrian Activated Signals. At roundabouts with multi-lane pedestrian street crossings, a pedestrian activated signal complying with R209 shall be provided for each multi-lane segment of each pedestrian street crossing, including the splitter island. Signals shall clearly identify which pedestrian street crossing segment the signal serves.

Advisory R306.3.2 Pedestrian Activated Signals. Roundabouts with single-lane approach and exit legs are not required to provide pedestrian activated signals. Pedestrian activated signals must comply with the requirements for accessible pedestrian signals and pedestrian pushbuttons (see R209). Pedestrian activated signals installed at splitter islands should be carefully located and separated so that signal spillover does not give conflicting information about which pedestrian street crossing has the WALK indication displayed. Pedestrian Hybrid Beacons can be used at roundabouts (see MUTCD sections 4F.01 through 4F.03). Pedestrian Hybrid Beacons are traffic signals that consist of a yellow signal centered below two horizontally aligned red signals. The signals are normally not illuminated. The signals are initiated only upon pedestrian activation and can be timed to minimize the interruption of traffic. The signals cease operation after the pedestrian clears the crosswalk. When activated by a pedestrian, the following signals are displayed to drivers: a flashing yellow signal, then a steady yellow signal, then two steady red signals during the pedestrian walk interval, and then alternating flashing red signals during the pedestrian clearance interval. The following signals are displayed to pedestrians: a steady upraised hand (symbolizing DON'T WALK) when the flashing or steady yellow signal is operating, then a walking person (symbolizing WALK) when the steady red signals are operating, and then a flashing upraised hand (symbolizing DON'T WALK) when the alternating flashing red signals are operating.

R306.4 Channelized Turn Lanes at Roundabouts. At roundabouts with pedestrian street crossings, pedestrian activated signals complying with R209 shall be provided at pedestrian street crossings at multi-lane channelized turn lanes.

R306.5 Channelized Turn Lanes at Other Signalized Intersections. At signalized intersections other than roundabouts with pedestrian street crossings, pedestrian activated signals complying with R209 shall be provided at pedestrian street crossings at multi-lane channelized turn lanes.

R307 Accessible Pedestrian Signals and Pedestrian Pushbuttons (See R209)

R308 Transit Stops and Transit Shelters

R308.1 Transit Stops. Transit stops shall comply with R308.1.

Advisory R308.1 Transit Stops. Transit stops should be located so that there is a level and stable surface for boarding vehicles. Locating transit stops at signalized intersections increases the usability for pedestrian with disabilities. Where security bollards are installed at transit stops, they must not obstruct the clear space at boarding and alighting areas or reduce the required clear width at pedestrian access routes (see R210).

R308.1.1 Boarding and Alighting Areas. Boarding and alighting areas at sidewalk or street level transit stops shall comply with R308.1.1 and R308.1.3. Where transit stops serve vehicles with more than one car, boarding and alighting areas serving each car shall comply with R308.1.1 and R308.1.3.

Advisory R308.1.1 Boarding and Alighting Areas. Where a transit shelter is provided, the boarding and alighting area can be located either within or outside of the shelter.

R308.1.1.1 Dimensions. Boarding and alighting areas shall provide a clear length of 2.4 m (8.0 ft) minimum, measured perpendicular to the curb or street or highway edge, and a clear width of 1.5 m (5.0 ft) minimum, measured parallel to the street or highway.




**Figure R308.1.1.1
Dimensions**

R308.1.1.2 Grade. Parallel to the street or highway, the grade of boarding and alighting areas shall be the same as the street or highway, to the extent practicable. Perpendicular to the street or highway, the grade of boarding and alighting areas shall not be steeper than 2 percent.

R308.1.2 Boarding Platforms. Boarding platforms at transit stops shall comply with R308.1.2 and R308.1.3.

R308.1.2.1 Platform and Vehicle Floor Coordination. Boarding platforms shall be positioned to coordinate with vehicles in accordance with the applicable requirements in 49 CFR parts 37 and 38.

Advisory R308.1.2.1 Platform and Vehicle Floor Coordination. The Department of Transportation regulations (49 CFR parts 37 and 38) require the height of the vehicle floor and the station platform to be coordinated so as to minimize the vertical and horizontal gaps.

R308.1.2.2 Slope. Boarding platforms shall not exceed a slope of 2 percent in any direction. Where boarding platforms serve vehicles operating on existing track or existing street or highway, the slope of the platform parallel to the track or the street or highway is permitted to be equal to the grade of the track or street or highway.

R308.1.3 Common Requirements. Boarding and alighting areas and boarding platforms shall comply with R308.1.3.

R308.1.3.1 Surfaces. The surfaces of boarding and alighting areas and boarding platforms shall comply with R302.7.

Advisory R308.1.3.1 Surfaces. Detectable warning surfaces are required at boarding and alighting areas for rail vehicles and at boarding platforms for buses and rail vehicles (see R208).

R308.1.3.2 Connection. Boarding and alighting areas and boarding platforms shall be connected to streets, sidewalks, or pedestrian circulation paths by pedestrian access routes complying with R302.




Figure R308.1.3.2
Connection

R308.2 Transit Shelters. Transit shelters shall be connected by pedestrian access routes complying with R302 to boarding and alighting areas or boarding platforms complying with R308.1. Transit shelters

shall provide a minimum clear space complying with R404 entirely within the shelter. Where seating is provided within transit shelters, the clear space shall be located either at one end of a seat or shall not overlap the area within 460 mm (1.5 ft) from the front edge of the seat. Environmental controls within transit shelters shall be proximity-actuated. Protruding objects within transit shelters shall comply with R402.

Advisory R308.2 Transit Shelters. The clear space must be located entirely within the transit shelter and not interfere with other persons using the seating.

R309 On-Street Parking Spaces

R309.1 General. On-street parking spaces shall comply with R309.

Advisory R309.1 General. R214 specifies how many accessible parking spaces must be provided on the block perimeter where on-street parking is marked or metered. Accessible parking spaces must be identified by signs displaying the International Symbol of Accessibility (see R211.3 and R411). Accessible parking spaces should be located where the street has the least crown and grade and close to key destinations.

R309.2 Parallel Parking Spaces. Parallel parking spaces shall comply with R309.2.

Advisory R309.2 Parallel Parking Spaces. The sidewalk adjacent to accessible parallel parking spaces should be free of signs, street furniture, and other obstructions to permit deployment of a van side-lift or ramp or the vehicle occupant to transfer to a wheelchair or scooter. Accessible parallel parking spaces located at the end of the block face are usable by vans that have rear lifts and cars that have scooter platforms.

R309.2.1 Wide Sidewalks. Where the width of the adjacent sidewalk or available right-of-way exceeds 4.3 m (14.0 ft), an access aisle 1.5 m (5.0 ft) wide minimum shall be provided at street level the full length of the parking space and shall connect to a pedestrian access route. The access aisle shall comply with R302.7 and shall not encroach on the vehicular travel lane.

Advisory R309.2.1 Wide Sidewalks. Vehicles may park at the curb or at the parking lane boundary and use the space required by R309.2.1 on either the driver or passenger side of the vehicle to serve as the access aisle.




Figure R309.2.1
Wide Sidewalks

R309.2.1.1 Alterations. In alterations where the street or sidewalk adjacent to the parking spaces is not altered, an access aisle shall not be required provided the parking spaces are located at the end of the block face.

R309.2.2 Narrow Sidewalks. An access aisle is not required where the width of the adjacent sidewalk or the available right-of-way is less than or equal to 4.3 m (14.0 ft). When an access aisle is not provided, the parking spaces shall be located at the end of the block face.

Advisory R309.2.2 Narrow Sidewalks. Vehicle lifts or ramps can be deployed on a 2.4 m (8.0 ft) sidewalk if there are no obstructions.




Figure R309.2.2
Narrow Sidewalks

R309.3 Perpendicular or Angled Parking Spaces. Where perpendicular or angled parking is provided, an access aisle 2.4 m (8.0 ft) wide minimum shall be provided at street level the full length of the parking space and shall connect to a pedestrian access route. The access aisle shall comply with R302.7 and shall be marked so as to discourage parking in the access aisle. Two parking spaces are permitted to share a common access aisle.

Advisory R309.3 Perpendicular or Angled Parking Spaces. Perpendicular and angled parking spaces permit the deployment of a van side-lift or ramp.




Figure R309.3
Perpendicular or Angled Parking Spaces

R309.4 Curb Ramps or Blended Transitions. Curb ramps or blended transitions complying with R304 shall connect the access aisle to the pedestrian access route. Curb ramps shall not be located within the access aisle.

Advisory R309.4 Curb Ramps or Blended Transitions. At parallel parking spaces, curb ramps and blended transitions should be located so that a van side-lift or ramp can be deployed to the sidewalk and the vehicle occupant can transfer to a wheelchair or scooter. Parking spaces at the end of the block face can be served by curb ramps or blended transitions at the pedestrian street crossing. Detectable warning surfaces are not required on curb ramps and blended transitions that connect the access aisle to the sidewalk, including where the sidewalk is at the same level as the parking spaces, unless the curb ramps and blended transitions also serve pedestrian street crossings (see R208).

R309.5 Parking Meters and Parking Pay Stations. Parking meters and parking pay stations that serve accessible parking spaces shall comply with R309.5. Operable parts shall comply with R403.

R309.5.1 Location. At accessible parallel parking spaces, parking meters shall be located at the head or foot of the parking space.

Advisory R309.5.1 Location. Locating parking meters at the head or foot of the parking space permits deployment of a van side-lift or ramp or the vehicle occupant to transfer to a wheelchair or scooter.

R309.5.2 Displays and Information. Displays and information shall be visible from a point located 1.0 m (3.3 ft) maximum above the center of the clear space in front of the parking meter or parking pay station.

R310 Passenger Loading Zones

R310.1 General. Passenger loading zones shall comply with R310.

Advisory R310.1 General. Accessible passenger loading zones must be identified by signs displaying the International Symbol of Accessibility (see R211.3 and R411).

R310.2 Vehicle Pull-Up Space. Passenger loading zones shall provide a vehicular pull-up space 2.4 m (8.0 ft) wide minimum and 6.1 m (20.0 ft) long minimum.

R310.3 Access Aisle. Passenger loading zones shall provide access aisles complying with R310.3 adjacent to the vehicle pull-up space. Access aisles shall be at the same level as the vehicle pull-up space they serve and shall not overlap the vehicular travel lane. Curb ramps or blended transitions complying with R304 shall connect the access aisle to the pedestrian access route. Curb ramps are not permitted within the access aisle.




**Figure R310.3
Access Aisle**

R310.3.1 Width. Access aisles serving vehicle pull-up spaces shall be 1.5 m (5.0 ft) wide minimum.

R310.3.2 Length. Access aisles shall extend the full length of the vehicle pull-up spaces they serve.

R310.3.3 Marking. Access aisles shall be marked so as to discourage parking in them.

R310.3.4 Surfaces. Access aisle surfaces shall comply with R302.7.

CHAPTER R4: SUPPLEMENTARY TECHNICAL REQUIREMENTS

R401 General

R401.1 Scope. The supplemental technical requirements in Chapter 4 shall apply where required by Chapter 2 or where referenced by a requirement in this document.

R402 Protruding Objects

R402.1 General. Protruding objects shall comply with R402.

R402.2 Protrusion Limits. Objects with leading edges more than 685 mm (2.25 ft) and not more than 2 m (6.7 ft) above the finish surface shall protrude 100 mm (4 in) maximum horizontally into pedestrian circulation paths.




Figure R402.2
Protrusion Limits

R402.3 Post-Mounted Objects. Where objects are mounted on free-standing posts or pylons and the objects are 685 mm (2.25 ft) minimum and 2030 mm (6.7 ft) maximum above the finish surface, the objects shall overhang pedestrian circulation paths 100 mm (4 in) maximum measured horizontally from the post or pylon base. The base dimension shall be 64 mm (2.5 in) thick minimum. Where objects are mounted between posts or pylons and the clear distance between the posts or pylons is greater than 305 mm (1.0 ft), the lowest edge of the object shall be 685 mm (2.25 ft) maximum or 2 m (6.7 ft) minimum above the finish surface.




Figure R402.3
Post-Mounted Objects

R402.4 Reduced Vertical Clearance. Guardrails or other barriers to pedestrian travel shall be provided where the vertical clearance is less than 2 m (6.7 ft) high. The leading edge of the guardrail or barrier shall be located 685 mm (2.25 ft) maximum above the finish surface.




Figure R402.4
Reduced Vertical Clearance

R403 Operable Parts

R403.1 General. Operable parts shall comply with R403.

Advisory R403.1 General. Operable parts on accessible pedestrian signals and pedestrian pushbuttons (see R209) and parking meters and parking pay stations that serve accessible parking spaces (see R309.5) must comply with R403.

R403.2 Clear Space. A clear space complying with R404 shall be provided at operable parts.

R403.3 Height. Operable parts shall be placed within one or more of the reach ranges specified in R406.

R403.4 Operation. Operable parts shall be operable with one hand and shall not require tight grasping, pinching, or twisting of the wrist. The force required to activate operable parts shall be 22 N (5 lbs) maximum.

R404 Clear Spaces

R404.1 General. Clear spaces shall comply with R404.

Advisory R404.1 General. Clear spaces are required at operable parts (see R403.2), including accessible pedestrian signals and pedestrian pushbuttons (see R209) and parking meters and parking pay stations that serve accessible parking spaces (see R309.5). Clear spaces are also required at benches (see R212.6) and within transit shelters (see R308.2).

R404.2 Surfaces. Surfaces of clear spaces shall comply with R302.7 and shall have a running slope consistent with the grade of the adjacent pedestrian access route and cross slope of 2 percent maximum.

R404.3 Size. Clear spaces shall be 760 mm (2.5 ft) minimum by 1220 mm (4.0 ft) minimum.

R404.4 Knee and Toe Clearance. Unless otherwise specified, clear spaces shall be permitted to include knee and toe clearance complying with R405.

R404.5 Position. Unless otherwise specified, clear spaces shall be positioned for either forward or parallel approach to an element.

R404.6 Approach. One full unobstructed side of a clear space shall adjoin a pedestrian access route or adjoin another clear space.

R404.7 Maneuvering Space. Where a clear space is confined on all or part of three sides, additional maneuvering space shall be provided in accordance with R404.7.1 and R404.7.2.

R404.7.1 Forward Approach. The clear space and additional maneuvering space shall be 915 mm (3.0 ft) wide minimum where the depth exceeds 610 mm (2.0 ft).

R404.7.2 Parallel Approach. The clear space and additional maneuvering space shall be 1525 mm (5.0 ft) wide minimum where the depth exceeds 380 mm (1.25 ft).

R405 Knee and Toe Clearance

R405.1 General. Where space beneath an element is included as part of a clear space, the space shall comply with R405. Additional space shall not be prohibited beneath an element but shall not be considered as part of the clear space.

Advisory R405.1 General. Clearances are measured in relation to the usable clear space, not necessarily to the vertical support for an element. When determining clearance under an object, care should be taken to ensure that the space is clear of any obstructions.

R405.2 Toe Clearance

R405.2.1 General. Space under an element between the finish surface and 230 mm (9 in) above the finish surface shall be considered toe clearance and shall comply with R405.2.

R405.2.2 Maximum Depth. Toe clearance shall extend 635 mm (2.1 ft) maximum under an element.

R405.2.3 Minimum Required Depth. Where toe clearance is required at an element as part of a clear space, the toe clearance shall extend 430 mm (1.4 ft) minimum under the element.

R405.2.4 Width. Toe clearance shall be 760 mm (2.5 ft) wide minimum.




**Figure R405.2
Toe Clearance**

R405.3 Knee Clearance

R405.3.1 General. Space under an element between 230 mm (9 in) and 685 mm (2.25 ft) above the finish surface shall be considered knee clearance and shall comply with R405.3.

R405.3.2 Maximum Depth. Knee clearance shall extend 635 mm (2.1 ft) maximum under an element at 230 mm (9 in) above the finish surface.

R405.3.3 Minimum Required Depth. Where knee clearance is required under an element as part of a clear space, the knee clearance shall be 280 mm (11 in) deep minimum at 230 mm (9 in) above the finish surface, and 205 mm (8 in) deep minimum at 685 mm (2.25 ft) above the finish surface.

R405.3.4 Clearance Reduction. Between 230 mm (9 in) and 685 mm (2.25 ft) above the finish surface, the knee clearance shall be permitted to reduce at a rate of 25 mm (1 in) in depth for each 150 mm (6 in) in height.

R405.3.5 Width. Knee clearance shall be 760 mm (2.5 ft) wide minimum.




Figure R405.3
Knee Clearance

R406 Reach Ranges

R406.1 General. Reach ranges shall comply with R406.

R406.2 Unobstructed Forward Reach. Where a forward reach is unobstructed, the high forward reach shall be 1220 mm (4.0 ft) maximum and the low forward reach shall be 380 mm (1.25 ft) minimum above the finish surface. Forward reach over an obstruction is not permitted.




Figure R406.2
Unobstructed Forward Reach

R406.3 Unobstructed Side Reach. Where a clear space allows a parallel approach to an element and the side reach is unobstructed, the high side reach shall be 1220 mm (4.0 ft) maximum and the low side reach shall be 380 mm (1.25 ft) minimum above the finish surface. An obstruction shall be permitted between the clear space and the element where the depth of the obstruction is 255 mm (10 in) maximum.




Figure R406.3
Unobstructed Side Reach

R407 Ramps

R407.1 General. Ramps shall comply with R407.

R407.2 Running Slope. Ramp runs shall have a running slope between 5 percent minimum and 8.3 percent maximum.

Advisory R407.2 Running Slope. Ramps with the least possible running slope accommodate the widest range of users. Providing stairways along with ramps, where possible, benefits pedestrians with heart disease, limited stamina, and others for whom distance presents a greater barrier than steps.

R407.3 Cross Slope. The cross slope of ramp runs shall be 2 percent maximum.

R407.4 Width. The clear width of a ramp run and, where handrails are provided, the clear width between handrails shall be 915 mm (3.0 ft) minimum.

R407.5 Rise. The rise for any ramp run shall be 760 mm (2.5 ft) maximum.

R407.6 Landings. Ramps shall have landings at the top and the bottom of each ramp run. Landings shall comply with R407.6.

R407.6.1 Slope. Landing slopes shall be 2 percent maximum in any direction.

R407.6.2 Width. The landing clear width shall be at least as wide as the widest ramp run leading to the landing.

R407.6.3 Length. The landing clear length shall be 1.5 m (5.0 ft) long minimum.

R407.6.4 Change in Direction. Ramps that change direction between runs at landings shall have a clear landing 1.5 m (5.0 ft) minimum by 1.5 m (5.0 ft) minimum.




Figure R407.6
Landings

R407.7 Surfaces. Surfaces of ramp runs and landings shall comply with R302.7.

R407.8 Handrails. Ramp runs with a rise greater than 150 mm (6 in) shall have handrails complying with R409.

R407.9 Edge Protection. Edge protection complying with R407.9.1 or R407.9.2 shall be provided on each side of ramp runs and ramp landings.

R407.9.1 Extended Ramp Surface. The surface of the ramp run or landing shall extend 305 mm (1.0 ft) minimum beyond the inside face of a handrail complying with R409.

Advisory R407.9.1 Extended Ramp Surface. The extended surface prevents wheelchair casters and crutch tips from slipping off the ramp surface.




Figure R407.9.1
Extended Ramp Surface

R407.9.2 Curb or Barrier. A curb or barrier shall be provided that prevents the passage of a 100 mm (4 in) diameter sphere, where any portion of the sphere is within 100 mm (4 in) of the finish surface.

R408 Stairways

R408.1 General. Stairways shall comply with R408.

R408.2 Treads and Risers. All steps on a flight of stairs shall have uniform riser heights and uniform tread depths. Risers shall be 100 mm (4 in) high minimum and 180 mm (7 in) high maximum. Treads shall be 280 mm (11 in) deep minimum.

R408.3 Open Risers. Open risers are not permitted.

R408.4 Tread Surface. Stairway treads shall comply with R302.7. Changes in level are not permitted.

R408.5 Nosings. The radius of curvature at the leading edge of the tread shall be 13 mm (0.5 inch) maximum. Nosings that project beyond risers shall have the underside of the leading edge curved or beveled. Risers shall be permitted to slope under the tread at an angle of 30 degrees maximum from vertical. The permitted projection of the nosing shall extend 38 mm (1.5 in) maximum over the tread below.

R408.6 Handrails. Stairways shall have handrails complying with R409.

R409 Handrails

R409.1 General. Handrails required at ramps and stairways, and handrails provided on pedestrian circulation paths shall comply with R409.

Advisory R409.1 General. Handrails are required on ramp runs with a rise greater than 150 mm (6 in) (see R407.8) and stairways (see R408.6). Handrails are not required on pedestrian circulation paths. However, if handrails are provided on pedestrian circulation paths, the handrails must comply with R409 (see R217). The requirements in R409.2, R409.3, and R409.10 apply only to handrails at ramps and stairways, and do not apply to handrails provided on pedestrian circulation paths.

R409.2 Where Required. Handrails shall be provided on both sides of ramps and stairways.

R409.3 Continuity. Handrails shall be continuous within the full length of each ramp run or stair flight. Inside handrails on switchback or dogleg ramps and stairways shall be continuous between ramp runs or stair flights.

R409.4 Height. Top of gripping surfaces of handrails shall be 865 mm (2.8 ft) minimum and 965 mm (3.2 ft) maximum vertically above walking surfaces, ramp surfaces, and stair nosings. Handrails shall be at a consistent height above walking surfaces, ramp surfaces, and stair nosings.




Figure R409.4
Height

R409.5 Clearance. Clearance between handrail gripping surfaces and adjacent surfaces shall be 38 mm (1.5 in) minimum.

R409.6 Gripping Surface. Handrail gripping surfaces shall be continuous along their length and shall not be obstructed along their tops or sides. The bottoms of handrail gripping surfaces shall not be obstructed for more than 20 percent of their length. Where provided, horizontal projections shall occur 38 mm (1.5 in) minimum below the bottom of the handrail gripping surface.

Advisory R409.6 Gripping Surface. Pedestrians with disabilities and others benefit from continuous gripping surfaces that permit users to reach the fingers outward or downward to grasp the handrail.

R409.7 Cross Section. Handrail gripping surfaces shall have a cross section complying with R409.7.1 or R409.7.2. Where expansion joints are necessary for large spans of handrails, the expansion joint is permitted to be smaller than the specified cross section diameters for a 25mm (1 in) length.

R409.7.1 Circular Cross Section. Handrail gripping surfaces with a circular cross section shall have an outside diameter of 32 mm (1.25 in) minimum and 51 mm (2 in) maximum.

R409.7.2 Non-Circular Cross Sections. Handrail gripping surfaces with a non-circular cross section shall have a perimeter dimension of 100 mm (4 in) minimum and 160 mm (6.25 in) maximum, and a cross-section dimension of 57 mm (2.25 in) maximum.




Figure R409.7.2
Non-Circular Cross Sections

R409.8 Surfaces. Handrail gripping surfaces and any surfaces adjacent to them shall be free of sharp or abrasive elements and shall have rounded edges.

R409.9 Fittings. Handrails shall not rotate within their fittings. Where expansion joints are necessary for large spans of handrails, the expansion joint is permitted to rotate in its fitting.

R409.10 Handrail Extensions. Handrail gripping surfaces shall extend beyond and in the same direction of ramp runs and stair flights in accordance with R409.10. Extensions shall not be required for continuous handrails at the inside turn of switchback or dogleg ramps and stairways. In alterations where handrail extensions would reduce the clear width required for pedestrian access routes, handrail extensions shall not be required.

R409.10.1 Top and Bottom Extension at Ramps. Ramp handrails shall extend horizontally above the landing for 305 mm (1.0 ft) minimum beyond the top and bottom of ramp runs. Extensions shall return to a wall, guard, or the landing surface, or shall be continuous to the handrail of an adjacent ramp run.




Figure R409.10.1
Top and Bottom Extension at Ramps

R409.10.2 Top Extension at Stairways. At the top of a stair flight, handrails shall extend horizontally above the landing for 305 mm (1.0 ft) minimum beginning directly above the first riser nosing. Extensions shall return to a wall, guard, or the landing surface, or shall be continuous to the handrail of an adjacent stair flight.




Figure R409.10.2
Top Extension at Stairways

R409.10.3 Bottom Extension at Stairways. At the bottom of a stair flight, handrails shall extend at the slope of the stair flight for a horizontal distance at least equal to one tread depth beyond the last riser nosing. Extensions shall return to a wall, guard, or the landing surface, or shall be continuous to the handrail of an adjacent stair flight.




Figure R409.10.3
Bottom Extension at Stairways

R410 Visual Characters on Signs

R410.1 General. Visual characters on signs shall comply with R410.

R410.2 Finish and Contrast. Characters and their background shall have a non-glare finish. Characters shall contrast with their background with either light characters on a dark background or dark characters on a light background.

Advisory R410.2 Finish and Contrast. Signs are more legible for pedestrians with low vision when characters contrast as much as possible with their background. Additional factors affecting the ease with which the text can be distinguished from its background include shadows cast by lighting sources, surface glare, and the uniformity of the text and its background colors and textures.

R410.3 Case. Characters shall be uppercase or lowercase or a combination of both.

R410.4 Style. Characters shall be conventional in form. Characters shall not be italic, oblique, script, highly decorative, or of other unusual forms.

R410.5 Character Proportions. Characters shall be selected from fonts where the width of the uppercase letter "O" is 55 percent minimum and 110 percent maximum of the height of the uppercase letter "I".

R410.6 Character Height. Minimum character height shall comply with Table R410.2.5. Viewing distance shall be measured as the horizontal distance between the character and an obstruction preventing further approach towards the sign. Character height shall be based on the uppercase letter "I".

Table R410.6 Visual Character Height

Height to Finish Surface from Baseline of Character	Horizontal Viewing Distance	Minimum Character Height
1.0 m (3.3 ft) to less than or equal to 1.8 m (5.8 ft)	Less than 1.8 m (6.0 ft)	16 mm (0.625 in)
	1.8 m (6.0 ft) and greater	16 mm (0.625 in), plus 3.2 mm (0.125 in) per 0.3 m (1.0 ft) of viewing distance above 1.8 m (6.0 ft)
Greater than 1.8 m (5.8 ft) to less than or equal to 3.0 m (10.0 ft)	Less than 4.6 m (15.0 ft)	51 mm (2 in)
	4.6 m (15.0 ft) and greater	16 mm (0.625 in), plus 3.2 mm (0.125 in) per 0.3 m (1.0 ft) of viewing distance above 1.8 m (6.0 ft)
Greater than 3.0 m (10.0 ft)	Less than 6.4 m (21.0 ft)	75 mm (3 in)
	6.4 m (21.0 ft) and greater	75 mm (3 in), plus 3.2 mm (0.125 in) per 0.3 m (1.0 ft) of viewing distance above 6.4 m (21.0 ft)

R410.7 Height from Finish Surface. Visual characters shall be 1.0 m (3.25 ft) minimum above the finish surface.

R410.8 Stroke Thickness. Stroke thickness of the uppercase letter "I" shall be 10 percent minimum and 30 percent maximum of the height of the character.

R410.9 Character Spacing. Character spacing shall be measured between the two closest points of adjacent characters, excluding word spaces. Spacing between individual characters shall be 10 percent minimum and 35 percent maximum of character height.

R410.10 Line Spacing. Spacing between the baselines of separate lines of characters within a message shall be 135 percent minimum and 170 percent maximum of the character height.

R411 International Symbol of Accessibility. The International Symbol of Accessibility shall comply with Figure 411. The symbol and its background shall have a non-glare finish. The symbol shall contrast with its background with either a light symbol on a dark background or a dark symbol on a light background.



Figure R411
International Symbol of Accessibility



TRANSITION PLAN

APPENDIX H

*DESIGN STANDARDS FOR
BUILDING FACILITIES*







Figure 307.2
of Protruding Objects

2010 ADA Standards for Accessible Design




Figure 703.2.5
Height of Raised Character

Figure 703.7.2.2
International Symbol of TTY

Department of Justice
September 15, 2010

Contents

1	Introduction.....	1
2	2010 Standards for State and Local Government Facilities: Title II.....	3
3	2010 Standards for Public Accommodations and Commercial Facilities: Title III.....	15
4	2010 Standards for Titles II and III Facilities: 2004 ADAAG.....	31

Adoption of the 2010 Standards also establishes a revised reference point for Title II entities that choose to make structural changes to existing facilities to meet their program accessibility requirements; and it establishes a similar reference for Title III entities undertaking readily achievable barrier removal.


- The 2010 Standards for State and local governments, which consist of the Title II regulations at 28 CFR 35.151 and the 2004 ADAAG at 36 CFR part 1191, appendices B and D;
- The 2010 Standards for public accommodations and commercial facilities, which consist of the Title III regulations at 28 CFR part 36, subpart D, and the 2004 ADAAG at 36 CFR part 1191, appendices B and D.

For More Information

Department of Justice

2010 Standards for State and Local Government Facilities: Title II

State and local government facilities must follow the requirements of the 2010 Standards, including both the Title II regulations at 28 CFR 35.151; and the 2004 ADAAG at 36 CFR part 1191, appendices B and D.



In the few places where requirements between the two differ, the requirements of 28 CFR 35.151 prevail.

Compliance Date for Title II

If the start date for construction is on or after March 15, 2012, all newly constructed or altered State and local government facilities must comply with the 2010 Standards. Before that date, the 1991 Standards (without the elevator exemption), the UFAS, or the 2010 Standards may be used for projects when the start of construction commences on or after September 15, 2010.

CONTENTS

28 CFR part 35.151 New Construction and Alterations

(a) Design and construction, including the exception for structural impracticability.....	6
(b) Alterations, including alterations to historic properties, path of travel, and primary function	6
(c) Accessibility standards and compliance date	9
(d) Scope of coverage.....	11
(e) Social service center establishments.....	11
(f) Housing at a place of education.....	11
(g) Assembly areas.....	12
(h) Medical care facilities	13
(i) Curb ramps.....	13
(j) Facilities with residential dwelling units for sale to individual owners.....	13
(k) Detention and correctional facilities.....	13

2004 ADAAG

Chapter 1: Application and Administration.....	37
Chapter 2: Scoping Requirements.....	50
Chapter 3: Building Blocks.....	104
Chapter 4: Accessible Routes.....	117
Chapter 5: General Site and Building Elements.....	149
Chapter 6: Plumbing Elements and Facilities.....	159
Chapter 7: Communication Elements.....	186
Chapter 8: Special Rooms, Spaces, and Elements.....	202
Chapter 9: Built-in Elements.....	219
Chapter 10: Recreational Facilities.....	224

§ 35.151 New construction and alterations.

(a) Design and construction.

- (1) Each facility or part of a facility constructed by, on behalf of, or for the use of a public entity shall be designed and constructed in such manner that the facility or part of the facility is readily accessible to and usable by individuals with disabilities, if the construction was commenced after January 26, 1992.

(2) Exception for structural impracticability.

- (i) Full compliance with the requirements of this section is not required where a public entity can demonstrate that it is structurally impracticable to meet the requirements. Full compliance will be considered structurally impracticable only in those rare circumstances when the unique characteristics of terrain prevent the incorporation of accessibility features.
- (ii) If full compliance with this section would be structurally impracticable, compliance with this section is required to the extent that it is not structurally impracticable. In that case, any portion of the facility that can be made accessible shall be made accessible to the extent that it is not structurally impracticable.
- (iii) If providing accessibility in conformance with this section to individuals with certain disabilities (e.g., those who use wheelchairs) would be structurally impracticable, accessibility shall nonetheless be ensured to persons with other types of disabilities, (e.g., those who use crutches or who have sight, hearing, or mental impairments) in accordance with this section.

(b) Alterations.

- (1) Each facility or part of a facility altered by, on behalf of, or for the use of a public entity in a manner that affects or could affect the usability of the facility or part of the facility shall, to the maximum extent feasible, be altered in such manner that the altered portion of the facility is readily accessible to and usable by individuals with disabilities, if the alteration was commenced after January 26, 1992.
- (2) The path of travel requirements of § 35.151(b)(4) shall apply only to alterations undertaken solely for purposes other than to meet the program accessibility requirements of § 35.150.

(3)

- (i) Alterations to historic properties shall comply, to the maximum extent feasible, with the provisions applicable to historic properties in the design standards specified in § 35.151(c).
- (ii) If it is not feasible to provide physical access to an historic property in a manner that will not threaten or destroy the historic significance of the building or facility, alternative methods of access shall be provided pursuant to the requirements of § 35.150.

(4) Path of travel. An alteration that affects or could affect the usability of or access to an area of a facility that contains a primary function shall be made so as to ensure that, to the maximum extent feasible, the path of travel to the altered area and the restrooms, telephones, and drinking fountains serving the altered area are readily accessible to and usable by individuals with disabilities, including individuals who use wheelchairs, unless the cost and scope of such alterations is disproportionate to the cost of the overall alteration.

(i) Primary function. A “primary function” is a major activity for which the facility is intended. Areas that contain a primary function include, but are not limited to, the dining area of a cafeteria, the meeting rooms in a conference center, as well as offices and other work areas in which the activities of the public entity using the facility are carried out.

(A) Mechanical rooms, boiler rooms, supply storage rooms, employee lounges or locker rooms, janitorial closets, entrances, and corridors are not areas containing a primary function. Restrooms are not areas containing a primary function unless the provision of restrooms is a primary purpose of the area, e.g., in highway rest stops.

(B) For the purposes of this section, alterations to windows, hardware, controls, electrical outlets, and signage shall not be deemed to be alterations that affect the usability of or access to an area containing a primary function.

(ii) A “path of travel” includes a continuous, unobstructed way of pedestrian passage by means of which the altered area may be approached, entered, and exited, and which connects the altered area with an exterior approach (including sidewalks, streets, and parking areas), an entrance to the facility, and other parts of the facility.

(A) An accessible path of travel may consist of walks and sidewalks, curb ramps

Section 35.151 of 28 CFR Part 35

and other interior or exterior pedestrian ramps; clear floor paths through lobbies, corridors, rooms, and other improved areas; parking access aisles; elevators and lifts; or a combination of these elements.

(B) For the purposes of this section, the term "path of travel" also includes the restrooms, telephones, and drinking fountains serving the altered area.

(C) **Safe harbor.** If a public entity has constructed or altered required elements of a path of travel in accordance with the specifications in either the 1991 Standards or the Uniform Federal Accessibility Standards before March 15, 2012, the public entity is not required to retrofit such elements to reflect incremental changes in the 2010 Standards solely because of an alteration to a primary function area served by that path of travel.

(iii) Disproportionality.

(A) Alterations made to provide an accessible path of travel to the altered area will be deemed disproportionate to the overall alteration when the cost exceeds 20% of the cost of the alteration to the primary function area.

(B) Costs that may be counted as expenditures required to provide an accessible path of travel may include:

(1) Costs associated with providing an accessible entrance and an accessible route to the altered area, for example, the cost of widening doorways or installing ramps;

(2) Costs associated with making restrooms accessible, such as installing grab bars, enlarging toilet stalls, insulating pipes, or installing accessible faucet controls;

(3) Costs associated with providing accessible telephones, such as relocating the telephone to an accessible height, installing amplification devices, or installing a text telephone (TTY); and

(4) Costs associated with relocating an inaccessible drinking fountain.

(iv) Duty to provide accessible features in the event of disproportionality.

(A) When the cost of alterations necessary to make the path of travel to the altered area fully accessible is disproportionate to the cost of the overall alteration, the path of travel shall be made accessible to the extent that it can be made accessible without incurring disproportionate costs.

(B) In choosing which accessible elements to provide, priority should be given to those elements that will provide the greatest access, in the following order—

- (1) An accessible entrance;
- (2) An accessible route to the altered area;
- (3) At least one accessible restroom for each sex or a single unisex restroom;
- (4) Accessible telephones;
- (5) Accessible drinking fountains; and
- (6) When possible, additional accessible elements such as parking, storage, and alarms.

(v) Series of smaller alterations.

(A) The obligation to provide an accessible path of travel may not be evaded by performing a series of small alterations to the area served by a single path of travel if those alterations could have been performed as a single undertaking.

(B)

(1) If an area containing a primary function has been altered without providing an accessible path of travel to that area, and subsequent alterations of that area, or a different area on the same path of travel, are undertaken within three years of the original alteration, the total cost of alterations to the primary function areas on that path of travel during the preceding three year period shall be considered in determining whether the cost of making that path of travel accessible is disproportionate.

(2) Only alterations undertaken on or after March 15, 2011, shall be considered in determining if the cost of providing an accessible path of travel is disproportionate to the overall cost of the alterations.

(c) Accessibility standards and compliance date.

(1) If physical construction or alterations commence after July 26, 1992, but prior to the September 15, 2010, then new construction and alterations subject to this section must comply with either the UFAS or the 1991 Standards except that the elevator exemption contained at section 4.1.3(5) and section 4.1.6(1)(k) of the 1991 Standards shall not apply. Departures from particular requirements of either standard by the use of other methods shall be permitted when it is clearly evident that equivalent access to the facility or part of the facility is thereby provided.

Section 35.151 of 28 CFR Part 35

- (2) If physical construction or alterations commence on or after September 15, 2010, and before March 15, 2012, then new construction and alterations subject to this section may comply with one of the following: the 2010 Standards, UFAS, or the 1991 Standards except that the elevator exemption contained at section 4.1.3(5) and section 4.1.6(1)(k) of the 1991 Standards shall not apply. Departures from particular requirements of either standard by the use of other methods shall be permitted when it is clearly evident that equivalent access to the facility or part of the facility is thereby provided.
- (3) If physical construction or alterations commence on or after March 15, 2012, then new construction and alterations subject to this section shall comply with the 2010 Standards.
- (4) For the purposes of this section, ceremonial groundbreaking or razing of structures prior to site preparation do not commence physical construction or alterations.
- (5) Noncomplying new construction and alterations.**
- (i) Newly constructed or altered facilities or elements covered by §§ 35.151(a) or (b) that were constructed or altered before March 15, 2012, and that do not comply with the 1991 Standards or with UFAS shall, before March 15, 2012, be made accessible in accordance with either the 1991 Standards, UFAS, or the 2010 Standards.
- (ii) Newly constructed or altered facilities or elements covered by §§ 35.151(a) or (b) that were constructed or altered before March 15, 2012 and that do not comply with the 1991 Standards or with UFAS shall, on or after March 15, 2012, be made accessible in accordance with the 2010 Standards.

Appendix to § 35.151(c)

Compliance Date for New Construction or Alterations	Applicable Standards
Before September 15, 2010	1991 Standards or UFAS
On or after September 15, 2010, and before March 15, 2012	1991 Standards, UFAS, or 2010 Standards
On or after March 15, 2012	2010 Standards

- (d) **Scope of coverage.** The 1991 Standards and the 2010 Standards apply to fixed or built-in elements of buildings, structures, site improvements, and pedestrian routes or vehicular ways located on a site. Unless specifically stated otherwise, the advisory notes, appendix notes, and figures contained in the 1991 Standards and the 2010 Standards explain or illustrate the requirements of the rule; they do not establish enforceable requirements.
- (e) **Social service center establishments.** Group homes, halfway houses, shelters, or similar social service center establishments that provide either temporary sleeping accommodations or residential dwelling units that are subject to this section shall comply with the provisions of the 2010 Standards applicable to residential facilities, including, but not limited to, the provisions in sections 233 and 809 (pp. 91 and 212).
- (1) In sleeping rooms with more than 25 beds covered by this section, a minimum of 5% of the beds shall have clear floor space complying with section 806.2.3 of the 2010 Standards (p. 209).
- (2) Facilities with more than 50 beds covered by this section that provide common use bathing facilities shall provide at least one roll-in shower with a seat that complies with the relevant provisions of section 608 of the 2010 Standards (p. 174). Transfer-type showers are not permitted in lieu of a roll-in shower with a seat, and the exceptions in sections 608.3 and 608.4 (pp. 177 and 178) for residential dwelling units are not permitted. When separate shower facilities are provided for men and for women, at least one roll-in shower shall be provided for each group.
- (f) **Housing at a place of education.** Housing at a place of education that is subject to this section shall comply with the provisions of the 2010 Standards applicable to transient lodging, including, but not limited to, the requirements for transient lodging guest rooms in sections 224 and 806 (pp. 82 and 210) subject to the following exceptions. For the purposes of the application of this section, the term "sleeping room" is intended to be used interchangeably with the term "guest room" as it is used in the transient lodging standards.
- (1) Kitchens within housing units containing accessible sleeping rooms with mobility features (including suites and clustered sleeping rooms) or on floors containing accessible sleeping rooms with mobility features shall provide turning spaces that comply with section 809.2.2 of the 2010 Standards (p. 213) and kitchen work surfaces that comply with section 804.3 of the 2010 Standards (p. 208).
- (2) Multi-bedroom housing units containing accessible sleeping rooms with mobility features shall have an accessible route throughout the unit in accordance with section 809.2 of the 2010 Standards (p. 212).

Section 35.151 of 28 CFR Part 35

- (3) Apartments or townhouse facilities that are provided by or on behalf of a place of education, which are leased on a year-round basis exclusively to graduate students or faculty, and do not contain any public use or common use areas available for educational programming, are not subject to the transient lodging standards and shall comply with the requirements for residential facilities in sections 233 and 809 of the 2010 Standards (pp. 91 and 212).
- (g) Assembly areas.** Assembly areas subject to this section shall comply with the provisions of the 2010 Standards applicable to assembly areas, including, but not limited to, sections 221 and 802 (pp. 78 and 202). In addition, assembly areas shall ensure that—
- (1) In stadiums, arenas, and grandstands, wheelchair spaces and companion seats are dispersed to all levels that include seating served by an accessible route;
- (2) Assembly areas that are required to horizontally disperse wheelchair spaces and companion seats by section 221.2.3.1 of the 2010 Standards (p. 79) and have seating encircling, in whole or in part, a field of play or performance area shall disperse wheelchair spaces and companion seats around that field of play or performance area;
- (3) Wheelchair spaces and companion seats are not located on (or obstructed by) temporary platforms or other movable structures, except that when an entire seating section is placed on temporary platforms or other movable structures in an area where fixed seating is not provided, in order to increase seating for an event, wheelchair spaces and companion seats may be placed in that section. When wheelchair spaces and companion seats are not required to accommodate persons eligible for those spaces and seats, individual, removable seats may be placed in those spaces and seats;
- (4) Stadium-style movie theaters shall locate wheelchair spaces and companion seats on a riser or cross-aisle in the stadium section that satisfies at least one of the following criteria—
- (i) It is located within the rear 60% of the seats provided in an auditorium; or
- (ii) It is located within the area of an auditorium in which the vertical viewing angles (as measured to the top of the screen) are from the 40th to the 100th percentile of vertical viewing angles for all seats as ranked from the seats in the first row (1st percentile) to seats in the back row (100th percentile).

(h) Medical care facilities. Medical care facilities that are subject to this section shall comply with the provisions of the 2010 Standards applicable to medical care facilities, including, but not limited to, sections 223 and 805 (pp. 81 and 209). In addition, medical care facilities that do not specialize in the treatment of conditions that affect mobility shall disperse the accessible patient bedrooms required by section 223.2.1 of the 2010 Standards (p. 82) in a manner that is proportionate by type of medical specialty.

(i) Curb ramps.

- (1) Newly constructed or altered streets, roads, and highways must contain curb ramps or other sloped areas at any intersection having curbs or other barriers to entry from a street level pedestrian walkway.
- (2) Newly constructed or altered street level pedestrian walkways must contain curb ramps or other sloped areas at intersections to streets, roads, or highways.

(j) Facilities with residential dwelling units for sale to individual owners.

- (1) Residential dwelling units designed and constructed or altered by public entities that will be offered for sale to individuals shall comply with the requirements for residential facilities in the 2010 Standards, including sections 233 and 809 (pp. 91 and 212).
- (2) The requirements of paragraph (1) also apply to housing programs that are operated by public entities where design and construction of particular residential dwelling units take place only after a specific buyer has been identified. In such programs, the covered entity must provide the units that comply with the requirements for accessible features to those pre-identified buyers with disabilities who have requested such a unit.

(k) Detention and correctional facilities.

- (1) New construction of jails, prisons, and other detention and correctional facilities shall comply with the 2010 Standards except that public entities shall provide accessible mobility features complying with section 807.2 of the 2010 Standards for a minimum of 3%, but no fewer than one, of the total number of cells in a facility (p. 211) Cells with mobility features shall be provided in each classification level.
- (2) **Alterations to detention and correctional facilities.** Alterations to jails, prisons, and other detention and correctional facilities shall comply with the 2010 Standards except that public entities shall provide accessible mobility features complying with section 807.2 of the 2010 Standards for a minimum of 3%, but no fewer than one, of the total number of cells being altered until at least 3%, but no fewer than one, of

Section 35.151 of 28 CFR Part 35


the total number of cells in a facility shall provide mobility features complying with section 807.2 (p. 211). Altered cells with mobility features shall be provided in each classification level. However, when alterations are made to specific cells, detention and correctional facility operators may satisfy their obligation to provide the required number of cells with mobility features by providing the required mobility features in substitute cells (cells other than those where alterations are originally planned), provided that each substitute cell—

- (i) Is located within the same prison site;
 - (ii) Is integrated with other cells to the maximum extent feasible;
 - (iii) Has, at a minimum, equal physical access as the altered cells to areas used by inmates or detainees for visitation, dining, recreation, educational programs, medical services, work programs, religious services, and participation in other programs that the facility offers to inmates or detainees; and
 - (iv) If it is technically infeasible to locate a substitute cell within the same prison site, a substitute cell must be provided at another prison site within the corrections system.
- (3) With respect to medical and long-term care facilities in jails, prisons, and other detention and correctional facilities, public entities shall apply the 2010 Standards technical and scoping requirements for those facilities irrespective of whether those facilities are licensed.

The remaining text of the 2010 Standards for Title II starts on page 31, under the heading 2010 Standards for Titles II and III: 2004 ADAAG.

2010 Standards for Public Accommodations and Commercial Facilities: Title III

Public accommodations and commercial facilities must follow the requirements of the 2010 Standards, including both the Title III regulations at 28 CFR part 36, subpart D; and the 2004 ADAAG at 36 CFR part 1191, appendices B and D.



In the few places where requirements between the two differ, the requirements of 28 CFR part 36, subpart D, prevail.

Compliance Date for Title III

The compliance date for the 2010 Standards for new construction and alterations is determined by:

- the date the last application for a building permit or permit extension is certified to be complete by a State, county, or local government;
- the date the last application for a building permit or permit extension is received by a State, county, or local government, where the government does not certify the completion applications; or
- the start of physical construction or alteration, if no permit is required.

If that date is on or after March 15, 2012, then new construction and alterations must comply with the 2010 Standards. If that date is on or after September 15, 2010, and before March 15, 2012, then new construction and alterations must comply with either the 1991 or the 2010 Standards.

CONTENTS

28 CFR part 36, subpart D — New Construction and Alterations

§ Sec.36.401 New construction.

(a) General.....	19
(b) Commercial facilities located in private residences.....	19
(c) Exception for structural impracticability.....	19
(d) Elevator exemption.....	20

§ 36.402 Alterations.

(a) General.....	21
(b) Alteration.....	21
(c) To the maximum extent feasible	22

§ 36.403 Alterations: Path of travel.

(a) General.....	22
(b) Primary function.....	22
(c) Alterations to an area containing a primary function.....	22
(d) Landlord/tenant.....	23
(e) Path of travel.....	23
(f) Disproportionality.....	23
(g) Duty to provide accessible features in the event of disproportionality.....	24
(h) Series of smaller alterations.....	24

§ 36.404 Alterations: Elevator exemption.....25

§ 36.405 Alterations: Historic preservation.....26

§ 36.406 Standards for new construction and alterations.

(a) Accessibility standards and compliance date.....	26
(b) Scope of coverage.....	27
(c) Places of lodging.....	28
(d) Social service center establishments.....	28
(e) Housing at a place of education.....	29

Subpart D of 28 CFR Part 36

(f) Assembly areas.....	29
(g) Medical care facilities.....	30
§ § 36.407—36.499 [Reserved].....	30

2004 ADAAG

Chapter 1: Application and Administration.....	37
Chapter 2: Scoping Requirements.....	50
Chapter 3: Building Blocks.....	104
Chapter 4: Accessible Routes.....	117
Chapter 5: General Site and Building Elements.....	149
Chapter 6: Plumbing Elements and Facilities.....	159
Chapter 7: Communication Elements.....	186
Chapter 8: Special Rooms, Spaces, and Elements.....	202
Chapter 9: Built-in Elements.....	219
Chapter 10: Recreational Facilities.....	224

§ 36.401 New construction.

(a) General.

- (1) Except as provided in paragraphs (b) and (c) of this section, discrimination for purposes of this part includes a failure to design and construct facilities for first occupancy after January 26, 1993, that are readily accessible to and usable by individuals with disabilities.
- (2) For purposes of this section, a facility is designed and constructed for first occupancy after January 26, 1993, only—
 - (i) If the last application for a building permit or permit extension for the facility is certified to be complete, by a State, County, or local government after January 26, 1992 (or, in those jurisdictions where the government does not certify completion of applications, if the last application for a building permit or permit extension for the facility is received by the State, County, or local government after January 26, 1992); and
 - (ii) If the first certificate of occupancy for the facility is issued after January 26, 1993.

(b) Commercial facilities located in private residences.

- (1) When a commercial facility is located in a private residence, the portion of the residence used exclusively as a residence is not covered by this subpart, but that portion used exclusively in the operation of the commercial facility or that portion used both for the commercial facility and for residential purposes is covered by the new construction and alterations requirements of this subpart.
- (2) The portion of the residence covered under paragraph (b)(1) of this section extends to those elements used to enter the commercial facility, including the homeowner's front sidewalk, if any, the door or entryway, and hallways; and those portions of the residence, interior or exterior, available to or used by employees or visitors of the commercial facility, including restrooms.

(c) Exception for structural impracticability.

- (1) Full compliance with the requirements of this section is not required where an entity can demonstrate that it is structurally impracticable to meet the requirements. Full compliance will be considered structurally impracticable only in those rare circumstances when the unique characteristics of terrain prevent the incorporation of accessibility features.

Subpart D of 28 CFR Part 36

- (2) If full compliance with this section would be structurally impracticable, compliance with this section is required to the extent that it is not structurally impracticable. In that case, any portion of the facility that can be made accessible shall be made accessible to the extent that it is not structurally impracticable.
- (3) If providing accessibility in conformance with this section to individuals with certain disabilities (e.g., those who use wheelchairs) would be structurally impracticable, accessibility shall nonetheless be ensured to persons with other types of disabilities (e.g., those who use crutches or who have sight, hearing, or mental impairments) in accordance with this section.

(d) Elevator exemption.

- (1) For purposes of this paragraph (d)—

- (i) **Professional office of a health care provider** means a location where a person or entity regulated by a State to provide professional services related to the physical or mental health of an individual makes such services available to the public. The facility housing the “professional office of a health care provider” only includes floor levels housing at least one health care provider, or any floor level designed or intended for use by at least one health care provider.

- (ii) **Shopping center or shopping mall** means—

- (A) A building housing five or more sales or rental establishments; or

- (B) A series of buildings on a common site, either under common ownership or common control or developed either as one project or as a series of related projects, housing five or more sales or rental establishments. For purposes of this section, places of public accommodation of the types listed in paragraph (5) of the definition of “place of public accommodation” in section § 36.104 are considered sales or rental establishments. The facility housing a “shopping center or shopping mall” only includes floor levels housing at least one sales or rental establishment, or any floor level designed or intended for use by at least one sales or rental establishment.

- (2) This section does not require the installation of an elevator in a facility that is less than three stories or has less than 3000 square feet per story, except with respect to any facility that houses one or more of the following:
 - (i) A shopping center or shopping mall, or a professional office of a health care provider.

- (ii) A terminal, depot, or other station used for specified public transportation, or an airport passenger terminal. In such a facility, any area housing passenger services, including boarding and debarking, loading and unloading, baggage claim, dining facilities, and other common areas open to the public, must be on an accessible route from an accessible entrance.
- (3) The elevator exemption set forth in this paragraph (d) does not obviate or limit, in any way the obligation to comply with the other accessibility requirements established in paragraph (a) of this section. For example, in a facility that houses a shopping center or shopping mall, or a professional office of a health care provider, the floors that are above or below an accessible ground floor and that do not house sales or rental establishments or a professional office of a health care provider, must meet the requirements of this section but for the elevator.

§ 36.402 Alterations.

(a) General.

- (1) Any alteration to a place of public accommodation or a commercial facility, after January 26, 1992, shall be made so as to ensure that, to the maximum extent feasible, the altered portions of the facility are readily accessible to and usable by individuals with disabilities, including individuals who use wheelchairs.
- (2) An alteration is deemed to be undertaken after January 26, 1992, if the physical alteration of the property begins after that date.

(b) Alteration. For the purposes of this part, an alteration is a change to a place of public accommodation or a commercial facility that affects or could affect the usability of the building or facility or any part thereof.

- (1) Alterations include, but are not limited to, remodeling, renovation, rehabilitation, reconstruction, historic restoration, changes or rearrangement in structural parts or elements, and changes or rearrangement in the plan configuration of walls and full-height partitions. Normal maintenance, reroofing, painting or wallpapering, asbestos removal, or changes to mechanical and electrical systems are not alterations unless they affect the usability of the building or facility.
- (2) If existing elements, spaces, or common areas are altered, then each such altered element, space, or area shall comply with the applicable provisions of appendix A to this part.

- (c) **To the maximum extent feasible.** The phrase “to the maximum extent feasible,” as used in this section, applies to the occasional case where the nature of an existing facility makes it virtually impossible to comply fully with applicable accessibility standards through a planned alteration. In these circumstances, the alteration shall provide the maximum physical accessibility feasible. Any altered features of the facility that can be made accessible shall be made accessible. If providing accessibility in conformance with this section to individuals with certain disabilities (e.g., those who use wheelchairs) would not be feasible, the facility shall be made accessible to persons with other types of disabilities (e.g., those who use crutches, those who have impaired vision or hearing, or those who have other impairments).

§ 36.403 Alterations: Path of travel.

(a) General.

- (1) An alteration that affects or could affect the usability of or access to an area of a facility that contains a primary function shall be made so as to ensure that, to the maximum extent feasible, the path of travel to the altered area and the restrooms, telephones, and drinking fountains serving the altered area, are readily accessible to and usable by individuals with disabilities, including individuals who use wheelchairs, unless the cost and scope of such alterations is disproportionate to the cost of the overall alteration.
- (2) If a private entity has constructed or altered required elements of a path of travel at a place of public accommodation or commercial facility in accordance with the specifications in the 1991 Standards, the private entity is not required to retrofit such elements to reflect the incremental changes in the 2010 Standards solely because of an alteration to a primary function area served by that path of travel.

- (b) Primary function.** A “primary function” is a major activity for which the facility is intended. Areas that contain a primary function include, but are not limited to, the customer services lobby of a bank, the dining area of a cafeteria, the meeting rooms in a conference center, as well as offices and other work areas in which the activities of the public accommodation or other private entity using the facility are carried out. Mechanical rooms, boiler rooms, supply storage rooms, employee lounges or locker rooms, janitorial closets, entrances, corridors, and restrooms are not areas containing a primary function.

(c) Alterations to an area containing a primary function.

- (1) Alterations that affect the usability of or access to an area containing a primary

function include, but are not limited to—

- (i) Remodeling merchandise display areas or employee work areas in a department store;
- (ii) Replacing an inaccessible floor surface in the customer service or employee work areas of a bank;
- (iii) Redesigning the assembly line area of a factory; or
- (iv) Installing a computer center in an accounting firm.

- (2) For the purposes of this section, alterations to windows, hardware, controls, electrical outlets, and signage shall not be deemed to be alterations that affect the usability of or access to an area containing a primary function.

(d) Landlord/tenant: If a tenant is making alterations as defined in § 36.402 that would trigger the requirements of this section, those alterations by the tenant in areas that only the tenant occupies do not trigger a path of travel obligation upon the landlord with respect to areas of the facility under the landlord's authority, if those areas are not otherwise being altered.

(e) Path of travel.

- (1) A "path of travel" includes a continuous, unobstructed way of pedestrian passage by means of which the altered area may be approached, entered, and exited, and which connects the altered area with an exterior approach (including sidewalks, streets, and parking areas), an entrance to the facility, and other parts of the facility.
- (2) An accessible path of travel may consist of walks and sidewalks, curb ramps and other interior or exterior pedestrian ramps; clear floor paths through lobbies, corridors, rooms, and other improved areas; parking access aisles; elevators and lifts; or a combination of these elements.
- (3) For the purposes of this part, the term "path of travel" also includes the restrooms, telephones, and drinking fountains serving the altered area.

(f) Disproportionality.

- (1) Alterations made to provide an accessible path of travel to the altered area will be deemed disproportionate to the overall alteration when the cost exceeds 20% of the cost of the alteration to the primary function area.

Subpart D of 28 CFR Part 36

(2) Costs that may be counted as expenditures required to provide an accessible path of travel may include:

- (i) Costs associated with providing an accessible entrance and an accessible route to the altered area, for example, the cost of widening doorways or installing ramps;
- (ii) Costs associated with making restrooms accessible, such as installing grab bars, enlarging toilet stalls, insulating pipes, or installing accessible faucet controls;
- (iii) Costs associated with providing accessible telephones, such as relocating the telephone to an accessible height, installing amplification devices, or installing a text telephone (TTY).
- (iv) Costs associated with relocating an inaccessible drinking fountain.

(g) Duty to provide accessible features in the event of disproportionality.

- (1) When the cost of alterations necessary to make the path of travel to the altered area fully accessible is disproportionate to the cost of the overall alteration, the path of travel shall be made accessible to the extent that it can be made accessible without incurring disproportionate costs.
- (2) In choosing which accessible elements to provide, priority should be given to those elements that will provide the greatest access, in the following order:
 - (i) An accessible entrance;
 - (ii) An accessible route to the altered area;
 - (iii) At least one accessible restroom for each sex or a single unisex restroom;
 - (iv) Accessible telephones;
 - (v) Accessible drinking fountains; and
 - (vi) When possible, additional accessible elements such as parking, storage, and alarms.

(h) Series of smaller alterations.

- (1) The obligation to provide an accessible path of travel may not be evaded by

performing a series of small alterations to the area served by a single path of travel if those alterations could have been performed as a single undertaking.

(2)

(i) If an area containing a primary function has been altered without providing an accessible path of travel to that area, and subsequent alterations of that area, or a different area on the same path of travel, are undertaken within three years of the original alteration, the total cost of alterations to the primary function areas on that path of travel during the preceding three year period shall be considered in determining whether the cost of making that path of travel accessible is disproportionate.

(ii) Only alterations undertaken after January 26, 1992, shall be considered in determining if the cost of providing an accessible path of travel is disproportionate to the overall cost of the alterations.

§ 36.404 Alterations: Elevator exemption.

(a) This section does not require the installation of an elevator in an altered facility that is less than three stories or has less than 3,000 square feet per story, except with respect to any facility that houses a shopping center, a shopping mall, the professional office of a health care provider, a terminal, depot, or other station used for specified public transportation, or an airport passenger terminal.

(1) For the purposes of this section, professional office of a health care provider means a location where a person or entity regulated by a State to provide professional services related to the physical or mental health of an individual makes such services available to the public. The facility that houses a professional office of a health care provider only includes floor levels housing by at least one health care provider, or any floor level designed or intended for use by at least one health care provider.

(2) For the purposes of this section, shopping center or shopping mall means—

(i) A building housing five or more sales or rental establishments; or

(ii) A series of buildings on a common site, connected by a common pedestrian access route above or below the ground floor, that is either under common ownership or common control or developed either as one project or as a series of related projects, housing five or more sales or rental establishments. For purposes of this section, places of public accommodation of the types listed in paragraph (5) of the definition of place of public accommodation in § 36.104 are

Subpart D of 28 CFR Part 36

considered sales or rental establishments. The facility housing a shopping center or shopping mall only includes floor levels housing at least one sales or rental establishment, or any floor level designed or intended for use by at least one sales or rental establishment.

- (b) The exemption provided in paragraph (a) of this section does not obviate or limit in any way the obligation to comply with the other accessibility requirements established in this subpart. For example, alterations to floors above or below the accessible ground floor must be accessible regardless of whether the altered facility has an elevator.

§ 36.405 Alterations: Historic preservation.

- (a) Alterations to buildings or facilities that are eligible for listing in the National Register of Historic Places under the National Historic Preservation Act (16 U.S.C. 470 *et seq.*), or are designated as historic under State or local law, shall comply to the maximum extent feasible with this part.
- (b) If it is determined that it is not feasible to provide physical access to an historic property that is a place of public accommodation in a manner that will not threaten or destroy the historic significance of the building or the facility, alternative methods of access shall be provided pursuant to the requirements of subpart C of this part.

§ 36.406 Standards for new construction and alterations.

(a) Accessibility standards and compliance date.

- (1) New construction and alterations subject to §§ 36.401 or 36.402 shall comply with the 1991 Standards if the date when the last application for a building permit or permit extension is certified to be complete by a State, county, or local government (or, in those jurisdictions where the government does not certify completion of applications, if the date when the last application for a building permit or permit extension is received by the State, county, or local government) is before September 15, 2010, or if no permit is required, if the start of physical construction or alterations occurs before September 15, 2010.
- (2) New construction and alterations subject to §§ 36.401 or 36.402 shall comply either with the 1991 Standards or with the 2010 Standards if the date when the last application for a building permit or permit extension is certified to be complete by a State, county, or local government (or, in those jurisdictions where the government does not certify completion of applications, if the date when the last application for a building permit or permit extension is received by the State, county, or local government) is on or after September 15, 2010, and before March 15, 2012,

or if no permit is required, if the start of physical construction or alterations occurs on or after September 15, 2010, and before March 15, 2012.

- (3) New construction and alterations subject to §§ 36.401 or 36.402 shall comply with the 2010 Standards if the date when the last application for a building permit or permit extension is certified to be complete by a State, county, or local government (or, in those jurisdictions where the government does not certify completion of applications, if the date when the last application for a building permit or permit extension is received by the State, county, or local government) is on or after March 15, 2012, or if no permit is required, if the start of physical construction or alterations occurs on or after March 15, 2012.
- (4) For the purposes of this section, “start of physical construction or alterations” does not mean ceremonial groundbreaking or razing of structures prior to site preparation.

(5) Noncomplying new construction and alterations.

- (i) Newly constructed or altered facilities or elements covered by §§ 36.401 or 36.402 that were constructed or altered before March 15, 2012, and that do not comply with the 1991 Standards shall, before March 15, 2012, be made accessible in accordance with either the 1991 Standards or the 2010 Standards.
- (ii) Newly constructed or altered facilities or elements covered by §§ 36.401 or 36.402 that were constructed or altered before March 15, 2012 and that do not comply with the 1991 Standards shall, on or after March 15, 2012, be made accessible in accordance with the 2010 Standards.

Appendix to § 36.406(a)

Compliance Dates for New Construction and Alterations	Applicable Standards
On or after January 26, 1993, and before September 15, 2010	1991 Standards
On or after September 15, 2010, and before March 15, 2012	1991 Standards or 2010 Standards
On or after March 15, 2012	2010 Standards

- (b) **Scope of coverage.** The 1991 Standards and the 2010 Standards apply to fixed or built-in elements of buildings, structures, site improvements, and pedestrian routes or vehicular ways located on a site. Unless specifically stated otherwise, advisory notes,

Subpart D of 28 CFR Part 36

appendix notes, and figures contained in the 1991 Standards and 2010 Standards explain or illustrate the requirements of the rule; they do not establish enforceable requirements.

(c) Places of lodging. Places of lodging subject to this part shall comply with the provisions of the 2010 Standards applicable to transient lodging, including, but not limited to, the requirements for transient lodging guest rooms in sections 224 and 806 of the 2010 Standards (pp. 82 and 210).

(1) Guest rooms. Guest rooms with mobility features in places of lodging subject to the transient lodging requirements of 2010 Standards shall be provided as follows—

(i) Facilities that are subject to the same permit application on a common site that each have 50 or fewer guest rooms may be combined for the purposes of determining the required number of accessible rooms and type of accessible bathing facility in accordance with table 224.2 to section 224.2 of the 2010 Standards (pp 83).

(ii) Facilities with more than 50 guest rooms shall be treated separately for the purposes of determining the required number of accessible rooms and type of accessible bathing facility in accordance with table 224.2 to section 224.2 of the 2010 Standards (p. 83).

(2) Exception. Alterations to guest rooms in places of lodging where the guest rooms are not owned or substantially controlled by the entity that owns, leases, or operates the overall facility and the physical features of the guest room interiors are controlled by their individual owners are not required to comply with § 36.402 or the alterations requirements in section 224.1.1 of the 2010 Standards (p. 83).

(3) Facilities with residential units and transient lodging units. Residential dwelling units that are designed and constructed for residential use exclusively are not subject to the transient lodging standards.

(d) Social service center establishments. Group homes, halfway houses, shelters, or similar social service center establishments that provide either temporary sleeping accommodations or residential dwelling units that are subject to this part shall comply with the provisions of the 2010 Standards applicable to residential facilities, including, but not limited to, the provisions in sections 233 and 809 (pp. 91 and 212) .

(1) In sleeping rooms with more than 25 beds covered by this part, a minimum of 5% of the beds shall have clear floor space complying with section 806.2.3 of the 2010 Standards (p. 210).

- (2) Facilities with more than 50 beds covered by this part that provide common use bathing facilities shall provide at least one roll-in shower with a seat that complies with the relevant provisions of section 608 of the 2010 Standards (p. 174). Transfer-type showers are not permitted in lieu of a roll-in shower with a seat, and the exceptions in sections 608.3 and 608.4 for residential dwelling units are not permitted. When separate shower facilities are provided for men and for women, at least one roll-in shower shall be provided for each group.

(e) Housing at a place of education. Housing at a place of education that is subject to this part shall comply with the provisions of the 2010 Standards applicable to transient lodging, including, but not limited to, the requirements for transient lodging guest rooms in sections 224 and 806 (pp. 82 and 210), subject to the following exceptions. For the purposes of the application of this section, the term “sleeping room” is intended to be used interchangeably with the term “guest room” as it is used in the transient lodging standards.

- (1) Kitchens within housing units containing accessible sleeping rooms with mobility features (including suites and clustered sleeping rooms) or on floors containing accessible sleeping rooms with mobility features shall provide turning spaces that comply with section 809.2.2 of the 2010 Standards (p. 213) and kitchen work surfaces that comply with section 804.3 of the 2010 Standards (p. 208).
- (2) Multi-bedroom housing units containing accessible sleeping rooms with mobility features shall have an accessible route throughout the unit in accordance with section 809.2 of the 2010 Standards (p. 212).
- (3) Apartments or townhouse facilities that are provided by or on behalf of a place of education, which are leased on a year-round basis exclusively to graduate students or faculty and do not contain any public use or common use areas available for educational programming, are not subject to the transient lodging standards and shall comply with the requirements for residential facilities in sections 233 and 809 of the 2010 Standards (pp. 91 and 212).

(f) Assembly areas. Assembly areas that are subject to this part shall comply with the provisions of the 2010 Standards applicable to assembly areas, including, but not limited to, sections 221 and 802 (p. 78 and 202). In addition, assembly areas shall ensure that—

- (1) In stadiums, arenas, and grandstands, wheelchair spaces and companion seats are dispersed to all levels that include seating served by an accessible route;
- (2) Assembly areas that are required to horizontally disperse wheelchair spaces and

Subpart D of 28 CFR Part 36

companion seats by section 221.2.3.1 of the 2010 Standards (p. 79) and that have seating encircling, in whole or in part, a field of play or performance, wheelchair spaces and companion seats are dispersed around that field of play or performance area;

- (3) Wheelchair spaces and companion seats are not located on (or obstructed by) temporary platforms or other movable structures, except that when an entire seating section is placed on temporary platforms or other movable structures in an area where fixed seating is not provided, in order to increase seating for an event, wheelchair spaces and companion seats may be placed in that section. When wheelchair spaces and companion seats are not required to accommodate persons eligible for those spaces and seats, individual, removable seats may be placed in those spaces and seats;
- (4) In stadium-style movie theaters, wheelchair spaces and companion seats are located on a riser or cross-aisle in the stadium section that satisfies at least one of the following criteria—
 - (i) It is located within the rear 60% of the seats provided in an auditorium; or
 - (ii) It is located within the area of an auditorium in which the vertical viewing angles (as measured to the top of the screen) are from the 40th to the 100th percentile of vertical viewing angles for all seats as ranked from the seats in the first row (1st percentile) to seats in the back row (100th percentile).
- (g) **Medical care facilities.** Medical care facilities that are subject to this part shall comply with the provisions of the 2010 Standards applicable to medical care facilities, including, but not limited to, sections 223 and 805 (pp. 81 and 209). In addition, medical care facilities that do not specialize in the treatment of conditions that affect mobility shall disperse the accessible patient bedrooms required by section 223.2.1 of the 2010 Standards (p. 82) in a manner that is proportionate by type of medical specialty.

§§ 36.407—36.499 [Reserved]

The remaining text of the 2010 Standards for Title III start on page 31, under the heading 2010 Standards for Titles II and III: 2004 ADAAG.

2010 Standards for Titles II and III Facilities: 2004 ADAAG

The following section applies to **both** State and local government facilities (Title II) and public accommodations and commercial facilities (Title III). The section consists of (ADA) Chapters 1 and 2 and Chapters 3 through 10, of the 2004 ADAAG (36 CFR part 1191, appendices B and D, adopted as part of both the Title II and Title III 2010 Standards).

State and local government facilities must follow the requirements of the 2010 Standards, including both the Title II regulations at 28 CFR 35.151; and the 2004 ADAAG at 36 CFR part 1191, appendices B and D.

Public accommodations and commercial facilities must follow the requirements of the 2010 Standards, including both the Title III regulations at 28 CFR part 36, subpart D; and the 2004 ADAAG at 36 CFR part 1191, appendices B and D.

In the few places where requirements between the regulation and the 2004 ADAAG differ, the requirements of 28 CFR 35.151 or 28 CFR part 36, subpart D, prevail.

ADA CHAPTER 1: APPLICATION AND ADMINISTRATION	37
101 Purpose	37
102 Dimensions for Adults and Children	37
103 Equivalent Facilitation	37
104 Conventions	37
105 Referenced Standards	40
106 Definitions	44
ADA CHAPTER 2: SCOPING REQUIREMENTS	50
201 Application	50
202 Existing Buildings and Facilities	50
203 General Exceptions	53
204 Protruding Objects	54
205 Operable Parts	55
206 Accessible Routes	55
207 Accessible Means of Egress	64
208 Parking Spaces	65
209 Passenger Loading Zones and Bus Stops	67
210 Stairways	68
211 Drinking Fountains	68
212 Kitchens, Kitchenettes, and Sinks	69
213 Toilet Facilities and Bathing Facilities	69
214 Washing Machines and Clothes Dryers	70
215 Fire Alarm Systems	71
216 Signs	71
217 Telephones	74
218 Transportation Facilities	76
219 Assistive Listening Systems	76
220 Automatic Teller Machines and Fare Machines	77
221 Assembly Areas	78
222 Dressing, Fitting, and Locker Rooms	81
223 Medical Care and Long-Term Care Facilities	81
224 Transient Lodging Guest Rooms	82
225 Storage	85
226 Dining Surfaces and Work Surfaces	86
227 Sales and Service	87
228 Depositories, Vending Machines, Change Machines, Mail Boxes, and Fuel Dispensers	88
229 Windows	88
230 Two-Way Communication Systems	88
231 Judicial Facilities	89
232 Detention Facilities and Correctional Facilities	89
233 Residential Facilities	91
234 Amusement Rides	94
235 Recreational Boating Facilities	95
236 Exercise Machines and Equipment	97
237 Fishing Piers and Platforms	97
238 Golf Facilities	97
239 Miniature Golf Facilities	98

TABLE OF CONTENTS

240 Play Areas	98
241 Saunas and Steam Rooms	102
242 Swimming Pools, Wading Pools, and Spas	102
243 Shooting Facilities with Firing Positions	103
CHAPTER 3: BUILDING BLOCKS	104
301 General	104
302 Floor or Ground Surfaces	104
303 Changes in Level	105
304 Turning Space	106
305 Clear Floor or Ground Space	107
306 Knee and Toe Clearance	109
307 Protruding Objects	111
308 Reach Ranges	113
309 Operable Parts	116
CHAPTER 4: ACCESSIBLE ROUTES	117
401 General	117
402 Accessible Routes	117
403 Walking Surfaces	117
404 Doors, Doorways, and Gates	119
405 Ramps	127
406 Curb Ramps	131
407 Elevators	133
408 Limited-Use/Limited-Application Elevators	143
409 Private Residence Elevators	145
410 Platform Lifts	147
CHAPTER 5: GENERAL SITE AND BUILDING ELEMENTS	149
501 General	149
502 Parking Spaces	149
503 Passenger Loading Zones	152
504 Stairways	153
505 Handrails	154
CHAPTER 6: PLUMBING ELEMENTS AND FACILITIES	159
601 General	159
602 Drinking Fountains	159
603 Toilet and Bathing Rooms	160
604 Water Closets and Toilet Compartments	161
605 Urinals	170
606 Lavatories and Sinks	170
607 Bathtubs	171
608 Shower Compartments	174
609 Grab Bars	181

TABLE OF CONTENTS

610 Seats	182
611 Washing Machines and Clothes Dryers	185
612 Saunas and Steam Rooms	185
CHAPTER 7: COMMUNICATION ELEMENTS AND FEATURES	186
701 General	186
702 Fire Alarm Systems	186
703 Signs	186
704 Telephones	194
705 Detectable Warnings	196
706 Assistive Listening Systems	197
707 Automatic Teller Machines and Fare Machines	198
708 Two-Way Communication Systems	201
CHAPTER 8: SPECIAL ROOMS, SPACES, AND ELEMENTS	202
801 General	202
802 Wheelchair Spaces, Companion Seats, and Designated Aisle Seats	202
803 Dressing, Fitting, and Locker Rooms	206
804 Kitchens and Kitchenettes	206
805 Medical Care and Long-Term Care Facilities	209
806 Transient Lodging Guest Rooms	210
807 Holding Cells and Housing Cells	211
808 Courtrooms	212
809 Residential Dwelling Units	212
810 Transportation Facilities	214
811 Storage	218
CHAPTER 9: BUILT-IN ELEMENTS	219
901 General	219
902 Dining Surfaces and Work Surfaces	219
903 Benches	219
904 Check-Out Aisles and Sales and Service Counters	220
CHAPTER 10: RECREATION FACILITIES	224
1001 General	224
1002 Amusement Rides	224
1003 Recreational Boating Facilities	228
1004 Exercise Machines and Equipment	233
1005 Fishing Piers and Platforms	234
1006 Golf Facilities	235
1007 Miniature Golf Facilities	236
1008 Play Areas	237
1009 Swimming Pools, Wading Pools, and Spas	242
1010 Shooting Facilities with Firing Positions	252
INDEX AND LIST OF FIGURES	253

page intentionally left blank

ADA CHAPTER 1: APPLICATION AND ADMINISTRATION

101 Purpose

101.1 General. This document contains scoping and technical requirements for *accessibility* to *sites, facilities, buildings, and elements* by individuals with disabilities. The requirements are to be applied during the design, construction, *additions* to, and *alteration* of *sites, facilities, buildings, and elements* to the extent required by regulations issued by Federal agencies under the Americans with Disabilities Act of 1990 (ADA).

Advisory 101.1 General. In addition to these requirements, covered entities must comply with the regulations issued by the Department of Justice and the Department of Transportation under the Americans with Disabilities Act. There are issues affecting individuals with disabilities which are not addressed by these requirements, but which are covered by the Department of Justice and the Department of Transportation regulations.

101.2 Effect on Removal of Barriers in Existing Facilities. This document does not address existing *facilities* unless *altered* at the discretion of a covered entity. The Department of Justice has authority over existing *facilities* that are subject to the requirement for removal of barriers under title III of the ADA. Any determination that this document applies to existing *facilities* subject to the barrier removal requirement is solely within the discretion of the Department of Justice and is effective only to the extent required by regulations issued by the Department of Justice.

102 Dimensions for Adults and Children

The technical requirements are based on adult dimensions and anthropometrics. In addition, this document includes technical requirements based on children's dimensions and anthropometrics for drinking fountains, water closets, toilet compartments, lavatories and sinks, dining surfaces, and work surfaces.

103 Equivalent Facilitation

Nothing in these requirements prevents the use of designs, products, or technologies as alternatives to those prescribed, provided they result in substantially equivalent or greater *accessibility* and usability.

Advisory 103 Equivalent Facilitation. The responsibility for demonstrating equivalent facilitation in the event of a challenge rests with the covered entity. With the exception of transit facilities, which are covered by regulations issued by the Department of Transportation, there is no process for certifying that an alternative design provides equivalent facilitation.

104 Conventions

104.1 Dimensions. Dimensions that are not stated as "maximum" or "minimum" are absolute.

104.1.1 Construction and Manufacturing Tolerances. All dimensions are subject to conventional industry tolerances except where the requirement is stated as a range with specific minimum and maximum end points.

Advisory 104.1.1 Construction and Manufacturing Tolerances. Conventional industry tolerances recognized by this provision include those for field conditions and those that may be a necessary consequence of a particular manufacturing process. Recognized tolerances are not intended to apply to design work.

It is good practice when specifying dimensions to avoid specifying a tolerance where dimensions are absolute. For example, if this document requires "1½ inches," avoid specifying "1½ inches plus or minus X inches."

Where the requirement states a specified range, such as in Section 609.4 where grab bars must be installed between 33 inches and 36 inches above the floor, the range provides an adequate tolerance and therefore no tolerance outside of the range at either end point is permitted.

Where a requirement is a minimum or a maximum dimension that does not have two specific minimum and maximum end points, tolerances may apply. Where an element is to be installed at the minimum or maximum permitted dimension, such as "15 inches minimum" or "5 pounds maximum", it would not be good practice to specify "5 pounds (plus X pounds) or 15 inches (minus X inches)." Rather, it would be good practice to specify a dimension less than the required maximum (or more than the required minimum) by the amount of the expected field or manufacturing tolerance and not to state any tolerance in conjunction with the specified dimension.

Specifying dimensions in design in the manner described above will better ensure that facilities and elements accomplish the level of accessibility intended by these requirements. It will also more often produce an end result of strict and literal compliance with the stated requirements and eliminate enforcement difficulties and issues that might otherwise arise. Information on specific tolerances may be available from industry or trade organizations, code groups and building officials, and published references.

104.2 Calculation of Percentages. Where the required number of *elements* or *facilities* to be provided is determined by calculations of ratios or percentages and remainders or fractions result, the next greater whole number of such *elements* or *facilities* shall be provided. Where the determination of the required size or dimension of an *element* or *facility* involves ratios or percentages, rounding down for values less than one half shall be permitted.

104.3 Figures. Unless specifically stated otherwise, figures are provided for informational purposes only.

Convention	Description
	dimension showing English units (in inches unless otherwise specified) above the line and SI units (in millimeters unless otherwise specified) below the line
	dimension for small measurements
	dimension showing a range with minimum - maximum
min	minimum
max	maximum
>	greater than
≥	greater than or equal to
<	less than
≤	less than or equal to
---	boundary of clear floor space or maneuvering clearance
---⌀---	centerline
---	a permitted element or its extension
➔	direction of travel or approach
▬	a wall, floor, ceiling or other element cut in section or plan
	a highlighted element in elevation or plan
	location zone of element, control or feature

Figure 104
Graphic Convention for Figures

105 Referenced Standards

105.1 General. The standards listed in 105.2 are incorporated by reference in this document and are part of the requirements to the prescribed extent of each such reference. The Director of the Federal Register has approved these standards for incorporation by reference in accordance with 5 U.S.C. 552(a) and 1 CFR part 51. Copies of the referenced standards may be inspected at the Architectural and Transportation Barriers Compliance Board, 1331 F Street, NW, Suite 1000, Washington, DC 20004; at the Department of Justice, Civil Rights Division, Disability Rights Section, 1425 New York Avenue, NW, Washington, DC; at the Department of Transportation, 400 Seventh Street, SW, Room 10424, Washington DC; or at the National Archives and Records Administration (NARA). For information on the availability of this material at NARA, call (202) 741-6030, or go to http://www.archives.gov/federal_register/code_of_federal_regulations/ibr_locations.html.

105.2 Referenced Standards. The specific edition of the standards listed below are referenced in this document. Where differences occur between this document and the referenced standards, this document applies.

105.2.1 ANSI/BHMA. Copies of the referenced standards may be obtained from the Builders Hardware Manufacturers Association, 355 Lexington Avenue, 17th floor, New York, NY 10017 (<http://www.buildershardware.com>).

ANSI/BHMA A156.10-1999 American National Standard for Power Operated Pedestrian Doors (see 404.3).

ANSI/BHMA A156.19-1997 American National Standard for Power Assist and Low Energy Power Operated Doors (see 404.3, 408.3.2.1, and 409.3.1).

ANSI/BHMA A156.19-2002 American National Standard for Power Assist and Low Energy Power Operated Doors (see 404.3, 408.3.2.1, and 409.3.1).

Advisory 105.2.1 ANSI/BHMA. ANSI/BHMA A156.10-1999 applies to power operated doors for pedestrian use which open automatically when approached by pedestrians. Included are provisions intended to reduce the chance of user injury or entrapment.

ANSI/BHMA A156.19-1997 and A156.19-2002 applies to power assist doors, low energy power operated doors or low energy power open doors for pedestrian use not provided for in ANSI/BHMA A156.10 for Power Operated Pedestrian Doors. Included are provisions intended to reduce the chance of user injury or entrapment.

105.2.2 ASME. Copies of the referenced standards may be obtained from the American Society of Mechanical Engineers, Three Park Avenue, New York, New York 10016 (<http://www.asme.org>).

ASME A17.1- 2000 Safety Code for Elevators and Escalators, including ASME A17.1a-2002 Addenda and ASME A17.1b-2003 Addenda (see 407.1, 408.1, 409.1, and 810.9).

ASME A18.1-1999 Safety Standard for Platform Lifts and Stairway Chairlifts, including ASME A18.1a-2001 Addenda and ASME A18.1b-2001 Addenda (see 410.1).

ASME A18.1-2003 Safety Standard for Platform Lifts and Stairway Chairlifts, (see 410.1).

Advisory 105.2.2 ASME. ASME A17.1-2000 is used by local jurisdictions throughout the United States for the design, construction, installation, operation, inspection, testing, maintenance, alteration, and repair of elevators and escalators. The majority of the requirements apply to the operational machinery not seen or used by elevator passengers. ASME A17.1 requires a two-way means of emergency communications in passenger elevators. This means of communication must connect with emergency or authorized personnel and not an automated answering system. The communication system must be push button activated. The activation button must be permanently identified with the word "HELP." A visual indication acknowledging the establishment of a communications link to authorized personnel must be provided. The visual indication must remain on until the call is terminated by authorized personnel. The building location, the elevator car number, and the need for assistance must be provided to authorized personnel answering the emergency call. The use of a handset by the communications system is prohibited. Only the authorized personnel answering the call can terminate the call. Operating instructions for the communications system must be provided in the elevator car.

The provisions for escalators require that at least two flat steps be provided at the entrance and exit of every escalator and that steps on escalators be demarcated by yellow lines 2 inches wide maximum along the back and sides of steps.

ASME A18.1-1999 and ASME A18.1-2003 address the design, construction, installation, operation, inspection, testing, maintenance and repair of lifts that are intended for transportation of persons with disabilities. Lifts are classified as: vertical platform lifts, inclined platform lifts, inclined stairway chairlifts, private residence vertical platform lifts, private residence inclined platform lifts, and private residence inclined stairway chairlifts.

This document does not permit the use of inclined stairway chairlifts which do not provide platforms because such lifts require the user to transfer to a seat.

ASME A18.1 contains requirements for runways, which are the spaces in which platforms or seats move. The standard includes additional provisions for runway enclosures, electrical equipment and wiring, structural support, headroom clearance (which is 80 inches minimum), lower level access ramps and pits. The enclosure walls not used for entry or exit are required to have a grab bar the full length of the wall on platform lifts. Access ramps are required to meet requirements similar to those for ramps in Chapter 4 of this document.

Each of the lift types addressed in ASME A18.1 must meet requirements for capacity, load, speed, travel, operating devices, and control equipment. The maximum permitted height for operable parts is consistent with Section 308 of this document. The standard also addresses attendant operation. However, Section 410.1 of this document does not permit attendant operation.

105.2.3 ASTM. Copies of the referenced standards may be obtained from the American Society for Testing and Materials, 100 Bar Harbor Drive, West Conshohocken, Pennsylvania 19428 (<http://www.astm.org>).

ASTM F 1292-99 Standard Specification for Impact Attenuation of Surface Systems Under and Around Playground Equipment (see 1008.2.6.2).

ASTM F 1292-04 Standard Specification for Impact Attenuation of Surfacing Materials Within the Use Zone of Playground Equipment (see 1008.2.6.2).

ASTM F 1487-01 Standard Consumer Safety Performance Specification for Playground Equipment for Public Use (see 106.5).

ASTM F 1951-99 Standard Specification for Determination of Accessibility of Surface Systems Under and Around Playground Equipment (see 1008.2.6.1).

Advisory 105.2.3 ASTM. ASTM F 1292-99 and ASTM F 1292-04 establish a uniform means to measure and compare characteristics of surfacing materials to determine whether materials provide a safe surface under and around playground equipment. These standards are referenced in the play areas requirements of this document when an accessible surface is required inside a play area use zone where a fall attenuating surface is also required. The standards cover the minimum impact attenuation requirements, when tested in accordance with Test Method F 355, for surface systems to be used under and around any piece of playground equipment from which a person may fall.

ASTM F 1487-01 establishes a nationally recognized safety standard for public playground equipment to address injuries identified by the U.S. Consumer Product Safety Commission. It defines the use zone, which is the ground area beneath and immediately adjacent to a play structure or play equipment designed for unrestricted circulation around the equipment and on whose surface it is predicted that a user would land when falling from or exiting a play structure or equipment. The play areas requirements in this document reference the ASTM F 1487 standard when defining accessible routes that overlap use zones requiring fall attenuating surfaces. If the use zone of a playground is not entirely surfaced with an accessible material, at least one accessible route within the use zone must be provided from the perimeter to all accessible play structures or components within the playground.

ASTM F 1951-99 establishes a uniform means to measure the characteristics of surface systems in order to provide performance specifications to select materials for use as an accessible surface under and around playground equipment. Surface materials that comply with this standard and are located in the use zone must also comply with ASTM F 1292. The test methods in this standard address access for children and adults who may traverse the surfacing to aid children who are playing. When a surface is tested it must have an average work per foot value for straight propulsion and for turning less than the average work per foot values for straight propulsion and for turning, respectively, on a hard, smooth surface with a grade of 7% (1:14).

105.2.4 ICC/IBC. Copies of the referenced standard may be obtained from the International Code Council, 5203 Leesburg Pike, Suite 600, Falls Church, Virginia 22041 (www.iccsafe.org).

International Building Code, 2000 Edition (see 207.1, 207.2, 216.4.2, 216.4.3, and 1005.2.1).

International Building Code, 2001 Supplement (see 207.1 and 207.2).

International Building Code, 2003 Edition (see 207.1, 207.2, 216.4.2, 216.4.3, and 1005.2.1).

Advisory 105.2.4 ICC/IBC. International Building Code (IBC)-2000 (including 2001 Supplement to the International Codes) and IBC-2003 are referenced for means of egress, areas of refuge, and railings provided on fishing piers and platforms. At least one accessible means of egress is required for every accessible space and at least two accessible means of egress are required where more than one means of egress is required. The technical criteria for accessible means of egress allow the use of exit stairways and evacuation elevators when provided in conjunction with horizontal exits or areas of refuge. While typical elevators are not designed to be used during an emergency evacuation, evacuation elevators are designed with standby power and other features according to the elevator safety standard and can be used for the evacuation of individuals with disabilities. The IBC also provides requirements for areas of refuge, which are fire-rated spaces on levels above or below the exit discharge levels where people unable to use stairs can go to register a call for assistance and wait for evacuation.

The recreation facilities requirements of this document references two sections in the IBC for fishing piers and platforms. An exception addresses the height of the railings, guards, or handrails where a fishing pier or platform is required to include a guard, railing, or handrail higher than 34 inches (865 mm) above the ground or deck surface.

105.2.5 NFPA. Copies of the referenced standards may be obtained from the National Fire Protection Association, 1 Batterymarch Park, Quincy, Massachusetts 02169-7471, (<http://www.nfpa.org>).

NFPA 72 National Fire Alarm Code, 1999 Edition (see 702.1 and 809.5.2).

NFPA 72 National Fire Alarm Code, 2002 Edition (see 702.1 and 809.5.2).

Advisory 105.2.5 NFPA. NFPA 72-1999 and NFPA 72-2002 address the application, installation, performance, and maintenance of protective signaling systems and their components. The NFPA 72 incorporates Underwriters Laboratory (UL) 1971 by reference. The standard specifies the characteristics of audible alarms, such as placement and sound levels. However, Section 702 of these requirements limits the volume of an audible alarm to 110 dBA, rather than the maximum 120 dBA permitted by NFPA 72-1999.

NFPA 72 specifies characteristics for visible alarms, such as flash frequency, color, intensity, placement, and synchronization. However, Section 702 of this document requires that visual alarm appliances be permanently installed. UL 1971 specifies intensity dispersion requirements for visible alarms. In particular, NFPA 72 requires visible alarms to have a light source that is clear or white and has polar dispersion complying with UL 1971.

106 Definitions

106.1 General. For the purpose of this document, the terms defined in 106.5 have the indicated meaning.

Advisory 106.1 General. Terms defined in Section 106.5 are italicized in the text of this document.

106.2 Terms Defined in Referenced Standards. Terms not defined in 106.5 or in regulations issued by the Department of Justice and the Department of Transportation to implement the Americans with Disabilities Act, but specifically defined in a referenced standard, shall have the specified meaning from the referenced standard unless otherwise stated.

106.3 Undefined Terms. The meaning of terms not specifically defined in 106.5 or in regulations issued by the Department of Justice and the Department of Transportation to implement the Americans with Disabilities Act or in referenced standards shall be as defined by collegiate dictionaries in the sense that the context implies.

106.4 Interchangeability. Words, terms and phrases used in the singular include the plural and those used in the plural include the singular.

106.5 Defined Terms.

Accessible. A *site, building, facility*, or portion thereof that complies with this part.

Accessible Means of Egress. A continuous and unobstructed way of egress travel from any point in a *building* or *facility* that provides an *accessible* route to an area of refuge, a horizontal exit, or a *public way*.

Addition. An expansion, extension, or increase in the gross floor area or height of a *building* or *facility*.

Administrative Authority. A governmental agency that adopts or enforces regulations and guidelines for the design, construction, or *alteration* of *buildings* and *facilities*.

Alteration. A change to a *building* or *facility* that affects or could affect the usability of the *building* or *facility* or portion thereof. *Alterations* include, but are not limited to, remodeling, renovation, rehabilitation, reconstruction, historic restoration, resurfacing of *circulation paths* or *vehicular ways*, changes or rearrangement of the structural parts or *elements*, and changes or rearrangement in the plan configuration of walls and full-height partitions. Normal maintenance, reroofing, painting or wallpapering, or changes to mechanical and electrical systems are not *alterations* unless they affect the usability of the *building* or *facility*.

Amusement Attraction. Any *facility*, or portion of a *facility*, located within an amusement park or theme park which provides amusement without the use of an amusement device. *Amusement attractions* include, but are not limited to, fun houses, barrels, and other attractions without seats.

Amusement Ride. A system that moves persons through a fixed course within a defined area for the purpose of amusement.

Amusement Ride Seat. A seat that is built-in or mechanically fastened to an *amusement ride* intended to be occupied by one or more passengers.

Area of Sport Activity. That portion of a room or *space* where the play or practice of a sport occurs.

Assembly Area. A *building* or *facility*, or portion thereof, used for the purpose of entertainment, educational or civic gatherings, or similar purposes. For the purposes of these requirements, *assembly areas* include, but are not limited to, classrooms, lecture halls, courtrooms, public meeting rooms, public hearing rooms, legislative chambers, motion picture houses, auditoria, theaters, playhouses, dinner theaters, concert halls, centers for the performing arts, amphitheaters, arenas, stadiums, grandstands, or convention centers.

Assistive Listening System (ALS). An amplification system utilizing transmitters, receivers, and coupling devices to bypass the acoustical *space* between a sound source and a listener by means of induction loop, radio frequency, infrared, or direct-wired equipment.

Boarding Pier. A portion of a pier where a boat is temporarily secured for the purpose of embarking or disembarking.

Boat Launch Ramp. A sloped surface designed for launching and retrieving trailered boats and other water craft to and from a body of water.

Boat Slip. That portion of a pier, main pier, finger pier, or float where a boat is moored for the purpose of berthing, embarking, or disembarking.

Building. Any structure used or intended for supporting or sheltering any use or occupancy.

Catch Pool. A pool or designated section of a pool used as a terminus for water slide flumes.

Characters. Letters, numbers, punctuation marks and typographic symbols.

Children's Use. Describes *spaces* and *elements* specifically designed for use primarily by people 12 years old and younger.

Circulation Path. An exterior or interior way of passage provided for pedestrian travel, including but not limited to, *walks*, hallways, courtyards, elevators, platform lifts, *ramps*, stairways, and landings.

Closed-Circuit Telephone. A telephone with a dedicated line such as a house phone, courtesy phone or phone that must be used to gain entry to a *facility*.

Common Use. Interior or exterior *circulation paths*, rooms, *spaces*, or *elements* that are not for *public use* and are made available for the shared use of two or more people.

Cross Slope. The slope that is perpendicular to the direction of travel (see *running slope*).

Curb Ramp. A short *ramp* cutting through a curb or built up to it.

Detectable Warning. A standardized surface feature built in or applied to walking surfaces or other *elements* to warn of hazards on a *circulation path*.

Element. An architectural or mechanical component of a *building, facility, space, or site*.

Elevated Play Component. A *play component* that is approached above or below grade and that is part of a composite play structure consisting of two or more *play components* attached or functionally linked to create an integrated unit providing more than one play activity.

Employee Work Area. All or any portion of a *space* used only by employees and used only for work. Corridors, toilet rooms, kitchenettes and break rooms are not *employee work areas*.

Entrance. Any access point to a *building* or portion of a *building* or *facility* used for the purpose of entering. An *entrance* includes the approach *walk*, the vertical access leading to the *entrance* platform, the *entrance* platform itself, vestibule if provided, the entry door or gate, and the hardware of the entry door or gate.

Facility. All or any portion of *buildings, structures, site improvements, elements, and pedestrian routes or vehicular ways* located on a *site*.

Gangway. A variable-sloped pedestrian walkway that links a fixed structure or land with a floating structure. *Gangways* that connect to vessels are not addressed by this document.

Golf Car Passage. A continuous passage on which a motorized golf car can operate.

Ground Level Play Component. A *play component* that is approached and exited at the ground level.

Key Station. Rapid and light rail stations, and commuter rail stations, as defined under criteria established by the Department of Transportation in 49 CFR 37.47 and 49 CFR 37.51, respectively.

Mail Boxes. Receptacles for the receipt of documents, packages, or other deliverable matter. *Mail boxes* include, but are not limited to, post office boxes and receptacles provided by commercial mail-receiving agencies, apartment *facilities*, or schools.

Marked Crossing. A crosswalk or other identified path intended for pedestrian use in crossing a *vehicular way*.

Mezzanine. An intermediate level or levels between the floor and ceiling of any *story* with an aggregate floor area of not more than one-third of the area of the room or *space* in which the level or levels are located. *Mezzanines* have sufficient elevation that *space* for human occupancy can be provided on the floor below.

Occupant Load. The number of persons for which the means of egress of a *building* or portion of a *building* is designed.

Operable Part. A component of an *element* used to insert or withdraw objects, or to activate, deactivate, or adjust the *element*.

Pictogram. A pictorial symbol that represents activities, *facilities*, or concepts.

Play Area. A portion of a *site* containing *play components* designed and constructed for children.

Play Component. An *element* intended to generate specific opportunities for play, socialization, or learning. *Play components* are manufactured or natural; and are stand-alone or part of a composite play structure.

Private Building or Facility. A place of public accommodation or a commercial *building* or *facility* subject to title III of the ADA and 28 CFR part 36 or a transportation *building* or *facility* subject to title III of the ADA and 49 CFR 37.45.

Public Building or Facility. A *building* or *facility* or portion of a *building* or *facility* designed, constructed, or *altered* by, on behalf of, or for the use of a public entity subject to title II of the ADA and 28 CFR part 35 or to title II of the ADA and 49 CFR 37.41 or 37.43.

Public Entrance. An *entrance* that is not a *service entrance* or a *restricted entrance*.

Public Use. Interior or exterior rooms, *spaces*, or *elements* that are made available to the public. *Public use* may be provided at a *building* or *facility* that is privately or publicly owned.

Public Way. Any street, alley or other parcel of land open to the outside air leading to a public street, which has been deeded, dedicated or otherwise permanently appropriated to the public for *public use* and which has a clear width and height of not less than 10 feet (3050 mm).

Qualified Historic Building or Facility. A *building* or *facility* that is listed in or eligible for listing in the National Register of Historic Places, or designated as historic under an appropriate State or local law.

Ramp. A walking surface that has a *running slope* steeper than 1:20.

Residential Dwelling Unit. A unit intended to be used as a residence, that is primarily long-term in nature. *Residential dwelling units* do not include *transient lodging*, inpatient medical care, licensed long-term care, and detention or correctional *facilities*.

Restricted Entrance. An *entrance* that is made available for *common use* on a controlled basis but not *public use* and that is not a *service entrance*.

Running Slope. The slope that is parallel to the direction of travel (see *cross slope*).

Self-Service Storage. *Building* or *facility* designed and used for the purpose of renting or leasing individual storage *spaces* to customers for the purpose of storing and removing personal property on a self-service basis.

Service Entrance. An *entrance* intended primarily for delivery of goods or services.

Site. A parcel of land bounded by a property line or a designated portion of a public right-of-way.

Soft Contained Play Structure. A play structure made up of one or more *play components* where the user enters a fully enclosed play environment that utilizes pliable materials, such as plastic, netting, or fabric.

Space. A definable area, such as a room, toilet room, hall, *assembly area*, *entrance*, storage room, alcove, courtyard, or lobby.

Story. That portion of a *building* or *facility* designed for human occupancy included between the upper surface of a floor and upper surface of the floor or roof next above. A *story* containing one or more *mezzanines* has more than one floor level.

Structural Frame. The columns and the girders, beams, and trusses having direct connections to the columns and all other members that are essential to the stability of the *building* or *facility* as a whole.

Tactile. An object that can be perceived using the sense of touch.

Technically Infeasible. With respect to an *alteration* of a *building* or a *facility*, something that has little likelihood of being accomplished because existing structural conditions would require removing or *altering* a load-bearing member that is an essential part of the *structural frame*; or because other existing physical or *site* constraints prohibit modification or *addition* of *elements*, *spaces*, or features that are in full and strict compliance with the minimum requirements.

Teeing Ground. In golf, the starting place for the hole to be played.

Transfer Device. Equipment designed to facilitate the transfer of a person from a wheelchair or other mobility aid to and from an *amusement ride seat*.

Transient Lodging. A *building* or *facility* containing one or more guest room(s) for sleeping that provides accommodations that are primarily short-term in nature. *Transient lodging* does not include *residential dwelling units* intended to be used as a residence, inpatient medical care *facilities*, licensed long-term care *facilities*, detention or correctional *facilities*, or *private buildings* or *facilities* that contain not more than five rooms for rent or hire and that are actually occupied by the proprietor as the residence of such proprietor.

Transition Plate. A sloping pedestrian walking surface located at the end(s) of a *gangway*.

TTY. An abbreviation for teletypewriter. Machinery that employs interactive text-based communication through the transmission of coded signals across the telephone network. *TTYs* may include, for example, devices known as TDDs (telecommunication display devices or telecommunication devices for deaf persons) or computers with special modems. *TTYs* are also called text telephones.

Use Zone. The ground level area beneath and immediately adjacent to a play structure or play equipment that is designated by ASTM F 1487 (incorporated by reference, see "Referenced Standards" in Chapter 1) for unrestricted circulation around the play equipment and where it is predicted that a user would land when falling from or exiting the play equipment.

Vehicular Way. A route provided for vehicular traffic, such as in a street, driveway, or parking *facility*.

Walk. An exterior prepared surface for pedestrian use, including pedestrian areas such as plazas and courts.

Wheelchair Space. *Space* for a single wheelchair and its occupant.

Work Area Equipment. Any machine, instrument, engine, motor, pump, conveyor, or other apparatus used to perform work. As used in this document, this term shall apply only to equipment that is permanently installed or built-in in *employee work areas*. *Work area equipment* does not include passenger elevators and other accessible means of vertical transportation.

ADA CHAPTER 2: SCOPING REQUIREMENTS

201 Application

201.1 Scope. All areas of newly designed and newly constructed *buildings* and *facilities* and *altered* portions of existing *buildings* and *facilities* shall comply with these requirements.

Advisory 201.1 Scope. These requirements are to be applied to all areas of a facility unless exempted, or where scoping limits the number of multiple elements required to be accessible. For example, not all medical care patient rooms are required to be accessible; those that are not required to be accessible are not required to comply with these requirements. However, common use and public use spaces such as recovery rooms, examination rooms, and cafeterias are not exempt from these requirements and must be accessible.

201.2 Application Based on Building or Facility Use. Where a *site*, *building*, *facility*, room, or *space* contains more than one use, each portion shall comply with the applicable requirements for that use.

201.3 Temporary and Permanent Structures. These requirements shall apply to temporary and permanent *buildings* and *facilities*.

Advisory 201.3 Temporary and Permanent Structures. Temporary buildings or facilities covered by these requirements include, but are not limited to, reviewing stands, temporary classrooms, bleacher areas, stages, platforms and daises, fixed furniture systems, wall systems, and exhibit areas, temporary banking facilities, and temporary health screening facilities. Structures and equipment directly associated with the actual processes of construction are not required to be accessible as permitted in 203.2.

202 Existing Buildings and Facilities

202.1 General. *Additions* and *alterations* to existing *buildings* or *facilities* shall comply with 202.

202.2 Additions. Each *addition* to an existing *building* or *facility* shall comply with the requirements for new construction. Each *addition* that affects or could affect the usability of or access to an area containing a primary function shall comply with 202.4.

202.3 Alterations. Where existing *elements* or *spaces* are *altered*, each *altered element* or *space* shall comply with the applicable requirements of Chapter 2.

EXCEPTIONS: 1. Unless required by 202.4, where *elements* or *spaces* are *altered* and the *circulation path* to the *altered element* or *space* is not *altered*, an *accessible* route shall not be required.

2. In *alterations*, where compliance with applicable requirements is *technically infeasible*, the *alteration* shall comply with the requirements to the maximum extent feasible.

3. *Residential dwelling units* not required to be *accessible* in compliance with a standard issued pursuant to the Americans with Disabilities Act or Section 504 of the Rehabilitation Act of 1973, as amended, shall not be required to comply with 202.3.

Advisory 202.3 Alterations. Although covered entities are permitted to limit the scope of an alteration to individual elements, the alteration of multiple elements within a room or space may provide a cost-effective opportunity to make the entire room or space accessible. Any elements or spaces of the building or facility that are required to comply with these requirements must be made accessible within the scope of the alteration, to the maximum extent feasible. If providing accessibility in compliance with these requirements for people with one type of disability (e.g., people who use wheelchairs) is not feasible, accessibility must still be provided in compliance with the requirements for people with other types of disabilities (e.g., people who have hearing impairments or who have vision impairments) to the extent that such accessibility is feasible.

202.3.1 Prohibited Reduction in Access. An *alteration* that decreases or has the effect of decreasing the *accessibility* of a *building* or *facility* below the requirements for new construction at the time of the *alteration* is prohibited.

202.3.2 Extent of Application. An *alteration* of an existing *element*, *space*, or area of a *building* or *facility* shall not impose a requirement for *accessibility* greater than required for new construction.

202.4 Alterations Affecting Primary Function Areas. In addition to the requirements of 202.3, an *alteration* that affects or could affect the usability of or access to an area containing a primary function shall be made so as to ensure that, to the maximum extent feasible, the path of travel to the *altered* area, including the rest rooms, telephones, and drinking fountains serving the *altered* area, are readily *accessible* to and usable by individuals with disabilities, unless such *alterations* are disproportionate to the overall *alterations* in terms of cost and scope as determined under criteria established by the Attorney General. In existing transportation *facilities*, an area of primary function shall be as defined under regulations published by the Secretary of the Department of Transportation or the Attorney General.

EXCEPTION: *Residential dwelling units* shall not be required to comply with 202.4.

Advisory 202.4 Alterations Affecting Primary Function Areas. An area of a building or facility containing a major activity for which the building or facility is intended is a primary function area. Department of Justice ADA regulations state, "Alterations made to provide an accessible path of travel to the altered area will be deemed disproportionate to the overall alteration when the cost exceeds 20% of the cost of the alteration to the primary function area." (28 CFR 36.403 (f)(1)). See also Department of Transportation ADA regulations, which use similar concepts in the context of public sector transportation facilities (49 CFR 37.43 (e)(1)).

There can be multiple areas containing a primary function in a single building. Primary function areas are not limited to public use areas. For example, both a bank lobby and the bank's employee areas such as the teller areas and walk-in safe are primary function areas.

Advisory 202.4 Alterations Affecting Primary Function Areas (Continued). Also, mixed use facilities may include numerous primary function areas for each use. Areas containing a primary function do not include: mechanical rooms, boiler rooms, supply storage rooms, employee lounges or locker rooms, janitorial closets, entrances, corridors, or restrooms.

202.5 Alterations to Qualified Historic Buildings and Facilities. *Alterations to a qualified historic building or facility shall comply with 202.3 and 202.4.*

EXCEPTION: Where the State Historic Preservation Officer or Advisory Council on Historic Preservation determines that compliance with the requirements for *accessible routes, entrances, or toilet facilities* would threaten or destroy the historic significance of the *building or facility*, the exceptions for *alterations to qualified historic buildings or facilities* for that *element* shall be permitted to apply.

Advisory 202.5 Alterations to Qualified Historic Buildings and Facilities Exception. State Historic Preservation Officers are State appointed officials who carry out certain responsibilities under the National Historic Preservation Act. State Historic Preservation Officers consult with Federal and State agencies, local governments, and private entities on providing access and protecting significant elements of qualified historic buildings and facilities. There are exceptions for alterations to qualified historic buildings and facilities for accessible routes (206.2.1 Exception 1 and 206.2.3 Exception 7); entrances (206.4 Exception 2); and toilet facilities (213.2 Exception 2). When an entity believes that compliance with the requirements for any of these elements would threaten or destroy the historic significance of the building or facility, the entity should consult with the State Historic Preservation Officer. If the State Historic Preservation Officer agrees that compliance with the requirements for a specific element would threaten or destroy the historic significance of the building or facility, use of the exception is permitted. Public entities have an additional obligation to achieve program accessibility under the Department of Justice ADA regulations. See 28 CFR 35.150. These regulations require public entities that operate historic preservation programs to give priority to methods that provide physical access to individuals with disabilities. If alterations to a qualified historic building or facility to achieve program accessibility would threaten or destroy the historic significance of the building or facility, fundamentally alter the program, or result in undue financial or administrative burdens, the Department of Justice ADA regulations allow alternative methods to be used to achieve program accessibility. In the case of historic preservation programs, such as an historic house museum, alternative methods include using audio-visual materials to depict portions of the house that cannot otherwise be made accessible. In the case of other qualified historic properties, such as an historic government office building, alternative methods include relocating programs and services to accessible locations. The Department of Justice ADA regulations also allow public entities to use alternative methods when altering qualified historic buildings or facilities in the rare situations where the State Historic Preservation Officer determines that it is not feasible to provide physical access using the exceptions permitted in Section 202.5 without threatening or destroying the historic significance of the building or facility. See 28 CFR 35.151(d).

Advisory 202.5 Alterations to Qualified Historic Buildings and Facilities Exception (Continued). The AccessAbility Office at the National Endowment for the Arts (NEA) provides a variety of resources for museum operators and historic properties including: the Design for Accessibility Guide and the Disability Symbols. Contact NEA about these and other resources at (202) 682-5532 or www.arts.gov.

203 General Exceptions

203.1 General. *Sites, buildings, facilities, and elements* are exempt from these requirements to the extent specified by 203.

203.2 Construction Sites. Structures and *sites* directly associated with the actual processes of construction, including but not limited to, scaffolding, bridging, materials hoists, materials storage, and construction trailers shall not be required to comply with these requirements or to be on an *accessible* route. Portable toilet units provided for use exclusively by construction personnel on a construction *site* shall not be required to comply with 213 or to be on an *accessible* route.

203.3 Raised Areas. Areas raised primarily for purposes of security, life safety, or fire safety, including but not limited to, observation or lookout galleries, prison guard towers, fire towers, or life guard stands shall not be required to comply with these requirements or to be on an *accessible* route.

203.4 Limited Access Spaces. *Spaces* accessed only by ladders, catwalks, crawl *spaces*, or very narrow passageways shall not be required to comply with these requirements or to be on an *accessible* route.

203.5 Machinery Spaces. *Spaces* frequented only by service personnel for maintenance, repair, or occasional monitoring of equipment shall not be required to comply with these requirements or to be on an *accessible* route. Machinery *spaces* include, but are not limited to, elevator pits or elevator penthouses; mechanical, electrical or communications equipment rooms; piping or equipment catwalks; water or sewage treatment pump rooms and stations; electric substations and transformer vaults; and highway and tunnel utility *facilities*.

203.6 Single Occupant Structures. Single occupant structures accessed only by passageways below grade or elevated above standard curb height, including but not limited to, toll booths that are accessed only by underground tunnels, shall not be required to comply with these requirements or to be on an *accessible* route.

203.7 Detention and Correctional Facilities. In detention and correctional *facilities*, *common use* areas that are used only by inmates or detainees and security personnel and that do not serve holding cells or housing cells required to comply with 232, shall not be required to comply with these requirements or to be on an *accessible* route.

203.8 Residential Facilities. In residential *facilities*, *common use* areas that do not serve *residential dwelling units* required to provide mobility features complying with 809.2 through 809.4 shall not be required to comply with these requirements or to be on an *accessible* route.

203.9 Employee Work Areas. *Spaces and elements within employee work areas* shall only be required to comply with 206.2.8, 207.1, and 215.3 and shall be designed and constructed so that individuals with disabilities can approach, enter, and exit the *employee work area*. *Employee work areas*, or portions of *employee work areas*, other than raised courtroom stations, that are less than 300 square feet (28 m²) and elevated 7 inches (180 mm) or more above the finish floor or ground where the elevation is essential to the function of the *space* shall not be required to comply with these requirements or to be on an *accessible* route.

Advisory 203.9 Employee Work Areas. Although areas used exclusively by employees for work are not required to be fully accessible, consider designing such areas to include non-required turning spaces, and provide accessible elements whenever possible. Under the ADA, employees with disabilities are entitled to reasonable accommodations in the workplace; accommodations can include alterations to spaces within the facility. Designing employee work areas to be more accessible at the outset will avoid more costly retrofits when current employees become temporarily or permanently disabled, or when new employees with disabilities are hired. Contact the Equal Employment Opportunity Commission (EEOC) at www.eeoc.gov for information about title I of the ADA prohibiting discrimination against people with disabilities in the workplace.

203.10 Raised Refereeing, Judging, and Scoring Areas. Raised structures used solely for refereeing, judging, or scoring a sport shall not be required to comply with these requirements or to be on an *accessible* route.

203.11 Water Slides. Water slides shall not be required to comply with these requirements or to be on an *accessible* route.

203.12 Animal Containment Areas. Animal containment areas that are not for *public use* shall not be required to comply with these requirements or to be on an *accessible* route.

Advisory 203.12 Animal Containment Areas. Public circulation routes where animals may travel, such as in petting zoos and passageways alongside animal pens in State fairs, are not eligible for the exception.

203.13 Raised Boxing or Wrestling Rings. Raised boxing or wrestling rings shall not be required to comply with these requirements or to be on an *accessible* route.

203.14 Raised Diving Boards and Diving Platforms. Raised diving boards and diving platforms shall not be required to comply with these requirements or to be on an *accessible* route.

204 Protruding Objects

204.1 General. Protruding objects on *circulation paths* shall comply with 307.

EXCEPTIONS: 1. Within *areas of sport activity*, protruding objects on *circulation paths* shall not be required to comply with 307.

2. Within *play areas*, protruding objects on *circulation paths* shall not be required to comply with 307 provided that ground level *accessible* routes provide vertical clearance in compliance with 1008.2.

205 Operable Parts

205.1 General. *Operable parts* on *accessible elements*, *accessible routes*, and in *accessible rooms* and *spaces* shall comply with 309.

- EXCEPTIONS:**
1. *Operable parts* that are intended for use only by service or maintenance personnel shall not be required to comply with 309.
 2. Electrical or communication receptacles serving a dedicated use shall not be required to comply with 309.
 3. Where two or more outlets are provided in a kitchen above a length of counter top that is uninterrupted by a sink or appliance, one outlet shall not be required to comply with 309.
 4. Floor electrical receptacles shall not be required to comply with 309.
 5. HVAC diffusers shall not be required to comply with 309.
 6. Except for light switches, where redundant controls are provided for a single *element*, one control in each *space* shall not be required to comply with 309.
 7. Cleats and other boat securement devices shall not be required to comply with 309.3.
 8. Exercise machines and exercise equipment shall not be required to comply with 309.

Advisory 205.1 General. Controls covered by 205.1 include, but are not limited to, light switches, circuit breakers, duplexes and other convenience receptacles, environmental and appliance controls, plumbing fixture controls, and security and intercom systems.

206 Accessible Routes

206.1 General. *Accessible routes* shall be provided in accordance with 206 and shall comply with Chapter 4.

206.2 Where Required. *Accessible routes* shall be provided where required by 206.2.

206.2.1 Site Arrival Points. At least one *accessible route* shall be provided within the *site* from *accessible parking spaces* and *accessible passenger loading zones*; public streets and sidewalks; and public transportation stops to the *accessible building* or *facility entrance* they serve.

- EXCEPTIONS:**
1. Where exceptions for *alterations to qualified historic buildings or facilities* are permitted by 202.5, no more than one *accessible route* from a *site arrival point* to an *accessible entrance* shall be required.
 2. An *accessible route* shall not be required between *site arrival points* and the *building* or *facility entrance* if the only means of access between them is a *vehicular way* not providing pedestrian access.

Advisory 206.2.1 Site Arrival Points. Each site arrival point must be connected by an accessible route to the accessible building entrance or entrances served. Where two or more similar site arrival points, such as bus stops, serve the same accessible entrance or entrances, both bus stops must be on accessible routes. In addition, the accessible routes must serve all of the accessible entrances on the site.

Advisory 206.2.1 Site Arrival Points Exception 2. Access from site arrival points may include vehicular ways. Where a vehicular way, or a portion of a vehicular way, is provided for pedestrian travel, such as within a shopping center or shopping mall parking lot, this exception does not apply.

206.2.2 Within a Site. At least one *accessible* route shall connect *accessible buildings*, *accessible facilities*, *accessible elements*, and *accessible spaces* that are on the same *site*.

EXCEPTION: An *accessible* route shall not be required between *accessible buildings*, *accessible facilities*, *accessible elements*, and *accessible spaces* if the only means of access between them is a *vehicular way* not providing pedestrian access.

Advisory 206.2.2 Within a Site. An accessible route is required to connect to the boundary of each area of sport activity. Examples of areas of sport activity include: soccer fields, basketball courts, baseball fields, running tracks, skating rinks, and the area surrounding a piece of gymnastic equipment. While the size of an area of sport activity may vary from sport to sport, each includes only the space needed to play. Where multiple sports fields or courts are provided, an accessible route is required to each field or area of sport activity.

206.2.3 Multi-Story Buildings and Facilities. At least one *accessible* route shall connect each *story* and *mezzanine* in multi-story buildings and facilities.

EXCEPTIONS: 1. In *private buildings or facilities* that are less than three *stories* or that have less than 3000 square feet (279 m²) per *story*, an *accessible* route shall not be required to connect *stories* provided that the *building* or *facility* is not a shopping center, a shopping mall, the professional office of a health care provider, a terminal, depot or other station used for specified public transportation, an airport passenger terminal, or another type of *facility* as determined by the Attorney General.

2. Where a two *story public building or facility* has one *story* with an *occupant load* of five or fewer persons that does not contain *public use space*, that *story* shall not be required to be connected to the *story* above or below.

3. In detention and correctional *facilities*, an *accessible* route shall not be required to connect *stories* where cells with mobility features required to comply with 807.2, all *common use* areas serving cells with mobility features required to comply with 807.2, and all *public use* areas are on an *accessible* route.

4. In residential *facilities*, an *accessible* route shall not be required to connect *stories* where *residential dwelling units* with mobility features required to comply with 809.2 through 809.4, all *common use* areas serving *residential dwelling units* with mobility features required to comply with 809.2 through 809.4, and *public use* areas serving *residential dwelling units* are on an *accessible* route.

5. Within multi-story *transient lodging* guest rooms with mobility features required to comply with 806.2, an *accessible* route shall not be required to connect *stories* provided that *spaces* complying with 806.2 are on an *accessible* route and sleeping accommodations for two persons minimum are provided on a *story* served by an accessible route.

6. In air traffic control towers, an *accessible* route shall not be required to serve the cab and the floor immediately below the cab.

7. Where exceptions for *alterations to qualified historic buildings or facilities* are permitted by 202.5, an *accessible* route shall not be required to *stories* located above or below the *accessible story*.

Advisory 206.2.3 Multi-Story Buildings and Facilities. Spaces and elements located on a level not required to be served by an accessible route must fully comply with this document. While a mezzanine may be a change in level, it is not a story. If an accessible route is required to connect stories within a building or facility, the accessible route must serve all mezzanines.

Advisory 206.2.3 Multi-Story Buildings and Facilities Exception 4. Where common use areas are provided for the use of residents, it is presumed that all such common use areas "serve" accessible dwelling units unless use is restricted to residents occupying certain dwelling units. For example, if all residents are permitted to use all laundry rooms, then all laundry rooms "serve" accessible dwelling units. However, if the laundry room on the first floor is restricted to use by residents on the first floor, and the second floor laundry room is for use by occupants of the second floor, then first floor accessible units are "served" only by laundry rooms on the first floor. In this example, an accessible route is not required to the second floor provided that all accessible units and all common use areas serving them are on the first floor.

206.2.3.1 Stairs and Escalators in Existing Buildings. In *alterations* and *additions*, where an escalator or stair is provided where none existed previously and major structural modifications are necessary for the installation, an *accessible* route shall be provided between the levels served by the escalator or stair unless exempted by 206.2.3 Exceptions 1 through 7.

206.2.4 Spaces and Elements. At least one *accessible* route shall connect *accessible building* or *facility entrances* with all *accessible spaces* and *elements* within the *building* or *facility* which are otherwise connected by a *circulation path* unless exempted by 206.2.3 Exceptions 1 through 7.

EXCEPTIONS: 1. Raised courtroom stations, including judges' benches, clerks' stations, bailiffs' stations, deputy clerks' stations, and court reporters' stations shall not be required to provide vertical access provided that the required clear floor *space*, maneuvering *space*, and, if appropriate, electrical service are installed at the time of initial construction to allow future installation of a means of vertical access complying with 405, 407, 408, or 410 without requiring substantial reconstruction of the *space*.

2. In *assembly areas* with fixed seating required to comply with 221, an *accessible* route shall not be required to serve fixed seating where *wheelchair spaces* required to be on an *accessible* route are not provided.

3. *Accessible* routes shall not be required to connect *mezzanines* where *buildings* or *facilities* have no more than one story. In addition, *accessible* routes shall not be required to connect stories or *mezzanines* where multi-story *buildings* or *facilities* are exempted by 206.2.3 Exceptions 1 through 7.

Advisory 206.2.4 Spaces and Elements. Accessible routes must connect all spaces and elements required to be accessible including, but not limited to, raised areas and speaker platforms.

Advisory 206.2.4 Spaces and Elements Exception 1. The exception does not apply to areas that are likely to be used by members of the public who are not employees of the court such as jury areas, attorney areas, or witness stands.

206.2.5 Restaurants and Cafeterias. In restaurants and cafeterias, an *accessible* route shall be provided to all dining areas, including raised or sunken dining areas, and outdoor dining areas.

EXCEPTIONS: 1. In *buildings or facilities* not required to provide an *accessible* route between *stories*, an *accessible* route shall not be required to a *mezzanine* dining area where the *mezzanine* contains less than 25 percent of the total combined area for seating and dining and where the same decor and services are provided in the *accessible* area.

2. In *alterations*, an *accessible* route shall not be required to existing raised or sunken dining areas, or to all parts of existing outdoor dining areas where the same services and decor are provided in an *accessible space* usable by the public and not restricted to use by people with disabilities.

3. In sports *facilities*, tiered dining areas providing seating required to comply with 221 shall be required to have *accessible* routes serving at least 25 percent of the dining area provided that *accessible* routes serve seating complying with 221 and each tier is provided with the same services.

Advisory 206.2.5 Restaurants and Cafeterias Exception 2. Examples of "same services" include, but are not limited to, bar service, rooms having smoking and non-smoking sections, lotto and other table games, carry-out, and buffet service. Examples of "same decor" include, but are not limited to, seating at or near windows and railings with views, areas designed with a certain theme, party and banquet rooms, and rooms where entertainment is provided.

206.2.6 Performance Areas. Where a *circulation path* directly connects a performance area to an assembly seating area, an *accessible* route shall directly connect the assembly seating area with the performance area. An *accessible* route shall be provided from performance areas to ancillary areas or *facilities* used by performers unless exempted by 206.2.3 Exceptions 1 through 7.

206.2.7 Press Boxes. Press boxes in *assembly areas* shall be on an *accessible* route.

EXCEPTIONS: 1. An *accessible* route shall not be required to press boxes in bleachers that have points of entry at only one level provided that the aggregate area of all press boxes is 500 square feet (46 m²) maximum.

2. An *accessible* route shall not be required to free-standing press boxes that are elevated above grade 12 feet (3660 mm) minimum provided that the aggregate area of all press boxes is 500 square feet (46 m²) maximum.

Advisory 206.2.7 Press Boxes Exception 2. Where a facility contains multiple assembly areas, the aggregate area of the press boxes in each assembly area is to be calculated separately. For example, if a university has a soccer stadium with three press boxes elevated 12 feet (3660 mm) or more above grade and each press box is 150 square feet (14 m²), then the aggregate area of the soccer stadium press boxes is less than 500 square feet (46 m²) and Exception 2 applies to the soccer stadium. If that same university also has a football stadium with two press boxes elevated 12 feet (3660 mm) or more above grade and one press box is 250 square feet (23 m²), and the second is 275 square feet (26 m²), then the aggregate area of the football stadium press boxes is more than 500 square feet (46 m²) and Exception 2 does not apply to the football stadium.

206.2.8 Employee Work Areas. *Common use circulation paths* within *employee work areas* shall comply with 402.

- EXCEPTIONS:**
- 1.** *Common use circulation paths* located within *employee work areas* that are less than 1000 square feet (93 m²) and defined by permanently installed partitions, counters, casework, or furnishings shall not be required to comply with 402.
 - 2.** *Common use circulation paths* located within *employee work areas* that are an integral component of *work area equipment* shall not be required to comply with 402.
 - 3.** *Common use circulation paths* located within exterior *employee work areas* that are fully exposed to the weather shall not be required to comply with 402.

Advisory 206.2.8 Employee Work Areas Exception 1. Modular furniture that is not permanently installed is not directly subject to these requirements. The Department of Justice ADA regulations provide additional guidance regarding the relationship between these requirements and elements that are not part of the built environment. Additionally, the Equal Employment Opportunity Commission (EEOC) implements title I of the ADA which requires non-discrimination in the workplace. EEOC can provide guidance regarding employers' obligations to provide reasonable accommodations for employees with disabilities.

Advisory 206.2.8 Employee Work Areas Exception 2. Large pieces of equipment, such as electric turbines or water pumping apparatus, may have stairs and elevated walkways used for overseeing or monitoring purposes which are physically part of the turbine or pump. However, passenger elevators used for vertical transportation between stories are not considered "work area equipment" as defined in Section 106.5.

206.2.9 Amusement Rides. *Amusement rides* required to comply with 234 shall provide *accessible* routes in accordance with 206.2.9. *Accessible* routes serving *amusement rides* shall comply with Chapter 4 except as modified by 1002.2.

206.2.9.1 Load and Unload Areas. Load and unload areas shall be on an *accessible* route. Where load and unload areas have more than one loading or unloading position, at least one loading and unloading position shall be on an *accessible* route.

206.2.9.2 Wheelchair Spaces, Ride Seats Designed for Transfer, and Transfer Devices.

When *amusement rides* are in the load and unload position, *wheelchair spaces* complying with 1002.4, *amusement ride seats* designed for transfer complying with 1002.5, and *transfer devices* complying with 1002.6 shall be on an *accessible* route.

206.2.10 Recreational Boating Facilities. *Boat slips* required to comply with 235.2 and *boarding piers* at *boat launch ramps* required to comply with 235.3 shall be on an *accessible* route. *Accessible* routes serving recreational boating *facilities* shall comply with Chapter 4, except as modified by 1003.2.

206.2.11 Bowling Lanes. Where bowling lanes are provided, at least 5 percent, but no fewer than one of each type of bowling lane, shall be on an *accessible* route.

206.2.12 Court Sports. In court sports, at least one *accessible* route shall directly connect both sides of the court.

206.2.13 Exercise Machines and Equipment. Exercise machines and equipment required to comply with 236 shall be on an *accessible* route.

206.2.14 Fishing Piers and Platforms. Fishing piers and platforms shall be on an *accessible* route. *Accessible* routes serving fishing piers and platforms shall comply with Chapter 4 except as modified by 1005.1.

206.2.15 Golf Facilities. At least one *accessible* route shall connect *accessible elements* and *spaces* within the boundary of the golf course. In addition, *accessible* routes serving golf car rental areas; bag drop areas; course weather shelters complying with 238.2.3; course toilet rooms; and practice putting greens, practice *teeing grounds*, and teeing stations at driving ranges complying with 238.3 shall comply with Chapter 4 except as modified by 1006.2.

EXCEPTION: *Golf car passages* complying with 1006.3 shall be permitted to be used for all or part of *accessible* routes required by 206.2.15.

206.2.16 Miniature Golf Facilities. Holes required to comply with 239.2, including the start of play, shall be on an *accessible* route. *Accessible* routes serving miniature golf *facilities* shall comply with Chapter 4 except as modified by 1007.2.

206.2.17 Play Areas. *Play areas* shall provide *accessible* routes in accordance with 206.2.17. *Accessible* routes serving *play areas* shall comply with Chapter 4 except as modified by 1008.2.

206.2.17.1 Ground Level and Elevated Play Components. At least one *accessible* route shall be provided within the *play area*. The *accessible* route shall connect *ground level play components* required to comply with 240.2.1 and *elevated play components* required to comply with 240.2.2, including entry and exit points of the *play components*.

206.2.17.2 Soft Contained Play Structures. Where three or fewer entry points are provided for *soft contained play structures*, at least one entry point shall be on an *accessible* route. Where

four or more entry points are provided for *soft contained play structures*, at least two entry points shall be on an *accessible* route.

206.3 Location. *Accessible* routes shall coincide with or be located in the same area as general *circulation paths*. Where *circulation paths* are interior, required *accessible* routes shall also be interior.

Advisory 206.3 Location. The accessible route must be in the same area as the general circulation path. This means that circulation paths, such as vehicular ways designed for pedestrian traffic, walks, and unpaved paths that are designed to be routinely used by pedestrians must be accessible or have an accessible route nearby. Additionally, accessible vertical interior circulation must be in the same area as stairs and escalators, not isolated in the back of the facility.

206.4 Entrances. *Entrances* shall be provided in accordance with 206.4. *Entrance* doors, doorways, and gates shall comply with 404 and shall be on an *accessible* route complying with 402.

EXCEPTIONS: 1. Where an *alteration* includes *alterations* to an *entrance*, and the *building* or *facility* has another *entrance* complying with 404 that is on an *accessible* route, the *altered entrance* shall not be required to comply with 206.4 unless required by 202.4.

2. Where exceptions for *alterations* to *qualified historic buildings or facilities* are permitted by 202.5, no more than one *public entrance* shall be required to comply with 206.4. Where no *public entrance* can comply with 206.4 under criteria established in 202.5 Exception, then either an unlocked *entrance* not used by the public shall comply with 206.4; or a locked *entrance* complying with 206.4 with a notification system or remote monitoring shall be provided.

206.4.1 Public Entrances. In addition to *entrances* required by 206.4.2 through 206.4.9, at least 60 percent of all *public entrances* shall comply with 404.

206.4.2 Parking Structure Entrances. Where direct access is provided for pedestrians from a parking structure to a *building* or *facility entrance*, each direct access to the *building* or *facility entrance* shall comply with 404.

206.4.3 Entrances from Tunnels or Elevated Walkways. Where direct access is provided for pedestrians from a pedestrian tunnel or elevated walkway to a *building* or *facility*, at least one direct *entrance* to the *building* or *facility* from each tunnel or walkway shall comply with 404.

206.4.4 Transportation Facilities. In addition to the requirements of 206.4.2, 206.4.3, and 206.4.5 through 206.4.9, transportation *facilities* shall provide *entrances* in accordance with 206.4.4.

206.4.4.1 Location. In transportation *facilities*, where different *entrances* serve different transportation fixed routes or groups of fixed routes, at least one *public entrance* serving each fixed route or group of fixed routes shall comply with 404.

EXCEPTION: *Entrances* to *key stations* and existing intercity rail stations retrofitted in accordance with 49 CFR 37.49 or 49 CFR 37.51 shall not be required to comply with 206.4.4.1.

206.4.4.2 Direct Connections. Direct connections to other *facilities* shall provide an *accessible* route complying with 404 from the point of connection to boarding platforms and all transportation system *elements* required to be *accessible*. Any *elements* provided to facilitate future direct connections shall be on an *accessible* route connecting boarding platforms and all transportation system *elements* required to be *accessible*.

EXCEPTION: In *key stations* and existing intercity rail stations, existing direct connections shall not be required to comply with 404.

206.4.4.3 Key Stations and Intercity Rail Stations. *Key stations* and existing intercity rail stations required by Subpart C of 49 CFR part 37 to be *altered*, shall have at least one *entrance* complying with 404.

206.4.5 Tenant Spaces. At least one *accessible entrance* to each tenancy in a *facility* shall comply with 404.

EXCEPTION: *Self-service storage facilities* not required to comply with 225.3 shall not be required to be on an accessible route.

206.4.6 Residential Dwelling Unit Primary Entrance. In *residential dwelling units*, at least one primary *entrance* shall comply with 404. The primary *entrance* to a *residential dwelling unit* shall not be to a bedroom.

206.4.7 Restricted Entrances. Where *restricted entrances* are provided to a *building* or *facility*, at least one *restricted entrance* to the *building* or *facility* shall comply with 404.

206.4.8 Service Entrances. If a *service entrance* is the only *entrance* to a *building* or to a tenancy in a *facility*, that *entrance* shall comply with 404.

206.4.9 Entrances for Inmates or Detainees. Where *entrances* used only by inmates or detainees and security personnel are provided at judicial *facilities*, detention *facilities*, or correctional *facilities*, at least one such *entrance* shall comply with 404.

206.5 Doors, Doorways, and Gates. Doors, doorways, and gates providing user passage shall be provided in accordance with 206.5.

206.5.1 Entrances. Each *entrance* to a *building* or *facility* required to comply with 206.4 shall have at least one door, doorway, or gate complying with 404.

206.5.2 Rooms and Spaces. Within a *building* or *facility*, at least one door, doorway, or gate serving each room or *space* complying with these requirements shall comply with 404.

206.5.3 Transient Lodging Facilities. In *transient lodging facilities*, *entrances*, doors, and doorways providing user passage into and within guest rooms that are not required to provide mobility features complying with 806.2 shall comply with 404.2.3.

EXCEPTION: Shower and sauna doors in guest rooms that are not required to provide mobility features complying with 806.2 shall not be required to comply with 404.2.3.

206.5.4 Residential Dwelling Units. In *residential dwelling units* required to provide mobility features complying with 809.2 through 809.4, all doors and doorways providing user passage shall comply with 404.

206.6 Elevators. Elevators provided for passengers shall comply with 407. Where multiple elevators are provided, each elevator shall comply with 407.

EXCEPTIONS: 1. In a *building* or *facility* permitted to use the exceptions to 206.2.3 or permitted by 206.7 to use a platform lift, elevators complying with 408 shall be permitted.

2. Elevators complying with 408 or 409 shall be permitted in *multi-story residential dwelling units*.

206.6.1 Existing Elevators. Where *elements* of existing elevators are *altered*, the same *element* shall also be *altered* in all elevators that are programmed to respond to the same hall call control as the *altered* elevator and shall comply with the requirements of 407 for the *altered element*.

206.7 Platform Lifts. Platform lifts shall comply with 410. Platform lifts shall be permitted as a component of an *accessible* route in new construction in accordance with 206.7. Platform lifts shall be permitted as a component of an *accessible* route in an existing *building* or *facility*.

206.7.1 Performance Areas and Speakers' Platforms. Platform lifts shall be permitted to provide *accessible* routes to performance areas and speakers' platforms.

206.7.2 Wheelchair Spaces. Platform lifts shall be permitted to provide an *accessible* route to comply with the *wheelchair space* dispersion and line-of-sight requirements of 221 and 802.

206.7.3 Incidental Spaces. Platform lifts shall be permitted to provide an *accessible* route to incidental *spaces* which are not *public use spaces* and which are occupied by five persons maximum.

206.7.4 Judicial Spaces. Platform lifts shall be permitted to provide an *accessible* route to: jury boxes and witness stands; raised courtroom stations including, judges' benches, clerks' stations, bailiffs' stations, deputy clerks' stations, and court reporters' stations; and to depressed areas such as the well of a court.

206.7.5 Existing Site Constraints. Platform lifts shall be permitted where existing exterior *site* constraints make use of a *ramp* or elevator infeasible.

Advisory 206.7.5 Existing Site Constraints. This exception applies where topography or other similar existing site constraints necessitate the use of a platform lift as the only feasible alternative. While the site constraint must reflect exterior conditions, the lift can be installed in the interior of a building. For example, a new building constructed between and connected to two existing buildings may have insufficient space to coordinate floor levels and also to provide ramped entry from the public way. In this example, an exterior or interior platform lift could be used to provide an accessible entrance or to coordinate one or more interior floor levels.

206.7.6 Guest Rooms and Residential Dwelling Units. Platform lifts shall be permitted to connect levels within *transient lodging* guest rooms required to provide mobility features complying with 806.2 or *residential dwelling units* required to provide mobility features complying with 809.2 through 809.4.

206.7.7 Amusement Rides. Platform lifts shall be permitted to provide *accessible* routes to load and unload areas serving *amusement rides*.

206.7.8 Play Areas. Platform lifts shall be permitted to provide *accessible* routes to *play components* or *soft contained play structures*.

206.7.9 Team or Player Seating. Platform lifts shall be permitted to provide *accessible* routes to team or player seating areas serving *areas of sport activity*.

Advisory 206.7.9 Team or Player Seating. While the use of platform lifts is allowed, ramps are recommended to provide access to player seating areas serving an area of sport activity.

206.7.10 Recreational Boating Facilities and Fishing Piers and Platforms. Platform lifts shall be permitted to be used instead of *gangways* that are part of *accessible* routes serving recreational boating *facilities* and fishing piers and platforms.

206.8 Security Barriers. Security barriers, including but not limited to, security bollards and security check points, shall not obstruct a required *accessible* route or *accessible means of egress*.

EXCEPTION: Where security barriers incorporate *elements* that cannot comply with these requirements such as certain metal detectors, fluoroscopes, or other similar devices, the *accessible* route shall be permitted to be located adjacent to security screening devices. The *accessible* route shall permit persons with disabilities passing around security barriers to maintain visual contact with their personal items to the same extent provided others passing through the security barrier.

207 Accessible Means of Egress

207.1 General. Means of egress shall comply with section 1003.2.13 of the International Building Code (2000 edition and 2001 Supplement) or section 1007 of the International Building Code (2003 edition) (incorporated by reference, see "Referenced Standards" in Chapter 1).

EXCEPTIONS: 1. Where means of egress are permitted by local *building* or life safety codes to share a common path of egress travel, *accessible means of egress* shall be permitted to share a common path of egress travel.

2. Areas of refuge shall not be required in detention and correctional *facilities*.

207.2 Platform Lifts. Standby power shall be provided for platform lifts permitted by section 1003.2.13.4 of the International Building Code (2000 edition and 2001 Supplement) or section 1007.5 of the International Building Code (2003 edition) (incorporated by reference, see "Referenced Standards" in Chapter 1) to serve as a part of an *accessible means of egress*.

208 Parking Spaces

208.1 General. Where parking *spaces* are provided, parking *spaces* shall be provided in accordance with 208.

EXCEPTION: Parking *spaces* used exclusively for buses, trucks, other delivery vehicles, law enforcement vehicles, or vehicular impound shall not be required to comply with 208 provided that lots accessed by the public are provided with a passenger loading zone complying with 503.

208.2 Minimum Number. Parking *spaces* complying with 502 shall be provided in accordance with Table 208.2 except as required by 208.2.1, 208.2.2, and 208.2.3. Where more than one parking *facility* is provided on a *site*, the number of *accessible spaces* provided on the *site* shall be calculated according to the number of *spaces* required for each parking *facility*.

Table 208.2 Parking Spaces

Total Number of Parking Spaces Provided in Parking Facility	Minimum Number of Required Accessible Parking Spaces
1 to 25	1
26 to 50	2
51 to 75	3
76 to 100	4
101 to 150	5
151 to 200	6
201 to 300	7
301 to 400	8
401 to 500	9
501 to 1000	2 percent of total
1001 and over	20, plus 1 for each 100, or fraction thereof, over 1000

Advisory 208.2 Minimum Number. The term "parking facility" is used Section 208.2 instead of the term "parking lot" so that it is clear that both parking lots and parking structures are required to comply with this section. The number of parking spaces required to be accessible is to be calculated separately for each parking facility; the required number is not to be based on the total number of parking spaces provided in all of the parking facilities provided on the site.

208.2.1 Hospital Outpatient Facilities. Ten percent of patient and visitor parking *spaces* provided to serve hospital outpatient *facilities* shall comply with 502.

Advisory 208.2.1 Hospital Outpatient Facilities. The term "outpatient facility" is not defined in this document but is intended to cover facilities or units that are located in hospitals and that provide regular and continuing medical treatment without an overnight stay. Doctors' offices, independent clinics, or other facilities not located in hospitals are not considered hospital outpatient facilities for purposes of this document.

208.2.2 Rehabilitation Facilities and Outpatient Physical Therapy Facilities. Twenty percent of patient and visitor parking *spaces* provided to serve rehabilitation *facilities* specializing in treating conditions that affect mobility and outpatient physical therapy *facilities* shall comply with 502.

Advisory 208.2.2 Rehabilitation Facilities and Outpatient Physical Therapy Facilities. Conditions that affect mobility include conditions requiring the use or assistance of a brace, cane, crutch, prosthetic device, wheelchair, or powered mobility aid; arthritic, neurological, or orthopedic conditions that severely limit one's ability to walk; respiratory diseases and other conditions which may require the use of portable oxygen; and cardiac conditions that impose significant functional limitations.

208.2.3 Residential Facilities. Parking *spaces* provided to serve residential *facilities* shall comply with 208.2.3.

208.2.3.1 Parking for Residents. Where at least one parking *space* is provided for each *residential dwelling unit*, at least one parking *space* complying with 502 shall be provided for each *residential dwelling unit* required to provide mobility features complying with 809.2 through 809.4.

208.2.3.2 Additional Parking Spaces for Residents. Where the total number of parking *spaces* provided for each *residential dwelling unit* exceeds one parking *space* per *residential dwelling unit*, 2 percent, but no fewer than one *space*, of all the parking *spaces* not covered by 208.2.3.1 shall comply with 502.

208.2.3.3 Parking for Guests, Employees, and Other Non-Residents. Where parking spaces are provided for persons other than residents, parking shall be provided in accordance with Table 208.2.

208.2.4 Van Parking Spaces. For every six or fraction of six parking *spaces* required by 208.2 to comply with 502, at least one shall be a van parking *space* complying with 502.

208.3 Location. Parking *facilities* shall comply with 208.3

208.3.1 General. Parking *spaces* complying with 502 that serve a particular *building* or *facility* shall be located on the shortest *accessible* route from parking to an *entrance* complying with 206.4. Where parking serves more than one *accessible entrance*, parking *spaces* complying with 502 shall be dispersed and located on the shortest *accessible* route to the *accessible entrances*. In parking

facilities that do not serve a particular *building* or *facility*, parking *spaces* complying with 502 shall be located on the shortest *accessible* route to an *accessible* pedestrian *entrance* of the parking *facility*.

EXCEPTIONS: 1. All van parking *spaces* shall be permitted to be grouped on one level within a multi-story parking *facility*.

2. Parking *spaces* shall be permitted to be located in different parking *facilities* if substantially equivalent or greater *accessibility* is provided in terms of distance from an *accessible entrance* or *entrances*, parking fee, and user convenience.

Advisory 208.3.1 General Exception 2. Factors that could affect "user convenience" include, but are not limited to, protection from the weather, security, lighting, and comparative maintenance of the alternative parking site.

208.3.2 Residential Facilities. In residential *facilities* containing *residential dwelling units* required to provide mobility features complying with 809.2 through 809.4, parking *spaces* provided in accordance with 208.2.3.1 shall be located on the shortest *accessible* route to the *residential dwelling unit entrance* they serve. *Spaces* provided in accordance with 208.2.3.2 shall be dispersed throughout all types of parking provided for the *residential dwelling units*.

EXCEPTION: Parking *spaces* provided in accordance with 208.2.3.2 shall not be required to be dispersed throughout all types of parking if substantially equivalent or greater *accessibility* is provided in terms of distance from an *accessible entrance*, parking fee, and user convenience.

Advisory 208.3.2 Residential Facilities Exception. Factors that could affect "user convenience" include, but are not limited to, protection from the weather, security, lighting, and comparative maintenance of the alternative parking site.

209 Passenger Loading Zones and Bus Stops

209.1 General. Passenger loading zones shall be provided in accordance with 209.

209.2 Type. Where provided, passenger loading zones shall comply with 209.2.

209.2.1 Passenger Loading Zones. Passenger loading zones, except those required to comply with 209.2.2 and 209.2.3, shall provide at least one passenger loading zone complying with 503 in every continuous 100 linear feet (30 m) of loading zone *space*, or fraction thereof.

209.2.2 Bus Loading Zones. In bus loading zones restricted to use by designated or specified public transportation vehicles, each bus bay, bus stop, or other area designated for lift or *ramp* deployment shall comply with 810.2.

Advisory 209.2.2 Bus Loading Zones. The terms "designated public transportation" and "specified public transportation" are defined by the Department of Transportation at 49 CFR 37.3 in regulations implementing the Americans with Disabilities Act. These terms refer to public transportation services provided by public or private entities, respectively. For example, designated public transportation vehicles include buses and vans operated by public transit agencies, while specified public transportation vehicles include tour and charter buses, taxis and limousines, and hotel shuttles operated by private entities.

209.2.3 On-Street Bus Stops. On-street bus stops shall comply with 810.2 to the maximum extent practicable.

209.3 Medical Care and Long-Term Care Facilities. At least one passenger loading zone complying with 503 shall be provided at an *accessible entrance* to licensed medical care and licensed long-term care *facilities* where the period of stay exceeds twenty-four hours.

209.4 Valet Parking. Parking *facilities* that provide valet parking services shall provide at least one passenger loading zone complying with 503.

209.5 Mechanical Access Parking Garages. Mechanical access parking garages shall provide at least one passenger loading zone complying with 503 at vehicle drop-off and vehicle pick-up areas.

210 Stairways

210.1 General. Interior and exterior stairs that are part of a means of egress shall comply with 504.

EXCEPTIONS: 1. In detention and correctional *facilities*, stairs that are not located in *public use* areas shall not be required to comply with 504.

2. In *alterations*, stairs between levels that are connected by an *accessible* route shall not be required to comply with 504, except that handrails complying with 505 shall be provided when the stairs are *altered*.

3. In *assembly areas*, aisle stairs shall not be required to comply with 504.

4. Stairs that connect *play components* shall not be required to comply with 504.

Advisory 210.1 General. Although these requirements do not mandate handrails on stairs that are not part of a means of egress, State or local building codes may require handrails or guards.

211 Drinking Fountains

211.1 General. Where drinking fountains are provided on an exterior *site*, on a floor, or within a secured area they shall be provided in accordance with 211.

EXCEPTION: In detention or correctional *facilities*, drinking fountains only serving holding or housing cells not required to comply with 232 shall not be required to comply with 211.

211.2 Minimum Number. No fewer than two drinking fountains shall be provided. One drinking fountain shall comply with 602.1 through 602.6 and one drinking fountain shall comply with 602.7.

EXCEPTION: Where a single drinking fountain complies with 602.1 through 602.6 and 602.7, it shall be permitted to be substituted for two separate drinking fountains.

211.3 More Than Minimum Number. Where more than the minimum number of drinking fountains specified in 211.2 are provided, 50 percent of the total number of drinking fountains provided shall comply with 602.1 through 602.6, and 50 percent of the total number of drinking fountains provided shall comply with 602.7.

EXCEPTION: Where 50 percent of the drinking fountains yields a fraction, 50 percent shall be permitted to be rounded up or down provided that the total number of drinking fountains complying with 211 equals 100 percent of drinking fountains.

212 Kitchens, Kitchenettes, and Sinks

212.1 General. Where provided, kitchens, kitchenettes, and sinks shall comply with 212.

212.2 Kitchens and Kitchenettes. Kitchens and kitchenettes shall comply with 804.

212.3 Sinks. Where sinks are provided, at least 5 percent, but no fewer than one, of each type provided in each *accessible* room or *space* shall comply with 606.

EXCEPTION: Mop or service sinks shall not be required to comply with 212.3.

213 Toilet Facilities and Bathing Facilities

213.1 General. Where toilet *facilities* and bathing *facilities* are provided, they shall comply with 213. Where toilet *facilities* and bathing *facilities* are provided in *facilities* permitted by 206.2.3 Exceptions 1 and 2 not to connect *stories* by an *accessible* route, toilet *facilities* and bathing *facilities* shall be provided on a *story* connected by an *accessible* route to an *accessible entrance*.

213.2 Toilet Rooms and Bathing Rooms. Where toilet rooms are provided, each toilet room shall comply with 603. Where bathing rooms are provided, each bathing room shall comply with 603.

EXCEPTIONS: 1. In *alterations* where it is *technically infeasible* to comply with 603, *altering* existing toilet or bathing rooms shall not be required where a single unisex toilet room or bathing room complying with 213.2.1 is provided and located in the same area and on the same floor as existing inaccessible toilet or bathing rooms.

2. Where exceptions for *alterations* to *qualified historic buildings or facilities* are permitted by 202.5, no fewer than one toilet room for each sex complying with 603 or one unisex toilet room complying with 213.2.1 shall be provided.

3. Where multiple single user portable toilet or bathing units are clustered at a single location, no more than 5 percent of the toilet units and bathing units at each cluster shall be required to comply with 603. Portable toilet units and bathing units complying with 603 shall be identified by the International Symbol of *Accessibility* complying with 703.7.2.1.

4. Where multiple single user toilet rooms are clustered at a single location, no more than 50 percent of the single user toilet rooms for each use at each cluster shall be required to comply with 603.

Advisory 213.2 Toilet Rooms and Bathing Rooms. These requirements allow the use of unisex (or single-user) toilet rooms in alterations when technical infeasibility can be demonstrated. Unisex toilet rooms benefit people who use opposite sex personal care assistants. For this reason, it is advantageous to install unisex toilet rooms in addition to accessible single-sex toilet rooms in new facilities.

Advisory 213.2 Toilet Rooms and Bathing Rooms Exceptions 3 and 4. A "cluster" is a group of toilet rooms proximate to one another. Generally, toilet rooms in a cluster are within sight of, or adjacent to, one another.

213.2.1 Unisex (Single-Use or Family) Toilet and Unisex Bathing Rooms. Unisex toilet rooms shall contain not more than one lavatory, and two water closets without urinals or one water closet and one urinal. Unisex bathing rooms shall contain one shower or one shower and one bathtub, one lavatory, and one water closet. Doors to unisex toilet rooms and unisex bathing rooms shall have privacy latches.

213.3 Plumbing Fixtures and Accessories. Plumbing fixtures and accessories provided in a toilet room or bathing room required to comply with 213.2 shall comply with 213.3.

213.3.1 Toilet Compartments. Where toilet compartments are provided, at least one toilet compartment shall comply with 604.8.1. In addition to the compartment required to comply with 604.8.1, at least one compartment shall comply with 604.8.2 where six or more toilet compartments are provided, or where the combination of urinals and water closets totals six or more fixtures.

Advisory 213.3.1 Toilet Compartments. A toilet compartment is a partitioned space that is located within a toilet room, and that normally contains no more than one water closet. A toilet compartment may also contain a lavatory. A lavatory is a sink provided for hand washing. Full-height partitions and door assemblies can comprise toilet compartments where the minimum required spaces are provided within the compartment.

213.3.2 Water Closets. Where water closets are provided, at least one shall comply with 604.

213.3.3 Urinals. Where more than one urinal is provided, at least one shall comply with 605.

213.3.4 Lavatories. Where lavatories are provided, at least one shall comply with 606 and shall not be located in a toilet compartment.

213.3.5 Mirrors. Where mirrors are provided, at least one shall comply with 603.3.

213.3.6 Bathing Facilities. Where bathtubs or showers are provided, at least one bathtub complying with 607 or at least one shower complying with 608 shall be provided.

213.3.7 Coat Hooks and Shelves. Where coat hooks or shelves are provided in toilet rooms without toilet compartments, at least one of each type shall comply with 603.4. Where coat hooks or shelves are provided in toilet compartments, at least one of each type complying with 604.8.3 shall be provided in toilet compartments required to comply with 213.3.1. Where coat hooks or shelves are provided in bathing *facilities*, at least one of each type complying with 603.4 shall serve fixtures required to comply with 213.3.6.

214 Washing Machines and Clothes Dryers

214.1 General. Where provided, washing machines and clothes dryers shall comply with 214.

214.2 Washing Machines. Where three or fewer washing machines are provided, at least one shall comply with 611. Where more than three washing machines are provided, at least two shall comply with 611.

214.3 Clothes Dryers. Where three or fewer clothes dryers are provided, at least one shall comply with 611. Where more than three clothes dryers are provided, at least two shall comply with 611.

215 Fire Alarm Systems

215.1 General. Where fire alarm systems provide audible alarm coverage, alarms shall comply with 215.

EXCEPTION: In existing *facilities*, visible alarms shall not be required except where an existing fire alarm system is upgraded or replaced, or a new fire alarm system is installed.

Advisory 215.1 General. Unlike audible alarms, visible alarms must be located within the space they serve so that the signal is visible. Facility alarm systems (other than fire alarm systems) such as those used for tornado warnings and other emergencies are not required to comply with the technical criteria for alarms in Section 702. Every effort should be made to ensure that such alarms can be differentiated in their signal from fire alarms systems and that people who need to be notified of emergencies are adequately safeguarded. Consult local fire departments and prepare evacuation plans taking into consideration the needs of every building occupant, including people with disabilities.

215.2 Public and Common Use Areas. Alarms in *public use* areas and *common use* areas shall comply with 702.

215.3 Employee Work Areas. Where *employee work areas* have audible alarm coverage, the wiring system shall be designed so that visible alarms complying with 702 can be integrated into the alarm system.

215.4 Transient Lodging. Guest rooms required to comply with 224.4 shall provide alarms complying with 702.

215.5 Residential Facilities. Where provided in *residential dwelling units* required to comply with 809.5, alarms shall comply with 702.

216 Signs

216.1 General. Signs shall be provided in accordance with 216 and shall comply with 703.

EXCEPTIONS: 1. *Building* directories, menus, seat and row designations in *assembly areas*, occupant names, *building* addresses, and company names and logos shall not be required to comply with 216.

2. In parking *facilities*, signs shall not be required to comply with 216.2, 216.3, and 216.6 through 216.12.

3. Temporary, 7 days or less, signs shall not be required to comply with 216.

4. In detention and correctional *facilities*, signs not located in *public use* areas shall not be required to comply with 216.

216.2 Designations. Interior and exterior signs identifying permanent rooms and *spaces* shall comply with 703.1, 703.2, and 703.5. Where *pictograms* are provided as designations of permanent interior

rooms and *spaces*, the *pictograms* shall comply with 703.6 and shall have text descriptors complying with 703.2 and 703.5.

EXCEPTION: Exterior signs that are not located at the door to the *space* they serve shall not be required to comply with 703.2.

Advisory 216.2 Designations. Section 216.2 applies to signs that provide designations, labels, or names for interior rooms or spaces where the sign is not likely to change over time. Examples include interior signs labeling restrooms, room and floor numbers or letters, and room names. Tactile text descriptors are required for pictograms that are provided to label or identify a permanent room or space. Pictograms that provide information about a room or space, such as "no smoking," occupant logos, and the International Symbol of Accessibility, are not required to have text descriptors.

216.3 Directional and Informational Signs. Signs that provide direction to or information about interior *spaces* and *facilities* of the *site* shall comply with 703.5.

Advisory 216.3 Directional and Informational Signs. Information about interior spaces and facilities includes rules of conduct, occupant load, and similar signs. Signs providing direction to rooms or spaces include those that identify egress routes.

216.4 Means of Egress. Signs for means of egress shall comply with 216.4.

216.4.1 Exit Doors. Doors at exit passageways, exit discharge, and exit stairways shall be identified by *tactile* signs complying with 703.1, 703.2, and 703.5.

Advisory 216.4.1 Exit Doors. An exit passageway is a horizontal exit component that is separated from the interior spaces of the building by fire-resistance-rated construction and that leads to the exit discharge or public way. The exit discharge is that portion of an egress system between the termination of an exit and a public way.

216.4.2 Areas of Refuge. Signs required by section 1003.2.13.5.4 of the International Building Code (2000 edition) or section 1007.6.4 of the International Building Code (2003 edition) (incorporated by reference, see "Referenced Standards" in Chapter 1) to provide instructions in areas of refuge shall comply with 703.5.

216.4.3 Directional Signs. Signs required by section 1003.2.13.6 of the International Building Code (2000 edition) or section 1007.7 of the International Building Code (2003 edition) (incorporated by reference, see "Referenced Standards" in Chapter 1) to provide directions to *accessible means of egress* shall comply with 703.5.

216.5 Parking. Parking *spaces* complying with 502 shall be identified by signs complying with 502.6.

EXCEPTIONS: 1. Where a total of four or fewer parking *spaces*, including *accessible* parking *spaces*, are provided on a *site*, identification of *accessible* parking *spaces* shall not be required.

2. In residential *facilities*, where parking *spaces* are assigned to specific *residential dwelling units*, identification of *accessible* parking *spaces* shall not be required.

216.6 Entrances. Where not all *entrances* comply with 404, *entrances* complying with 404 shall be identified by the International Symbol of *Accessibility* complying with 703.7.2.1. Directional signs complying with 703.5 that indicate the location of the nearest *entrance* complying with 404 shall be provided at *entrances* that do not comply with 404.

Advisory 216.6 Entrances. Where a directional sign is required, it should be located to minimize backtracking. In some cases, this could mean locating a sign at the beginning of a route, not just at the inaccessible entrances to a building.

216.7 Elevators. Where existing elevators do not comply with 407, elevators complying with 407 shall be clearly identified with the International Symbol of *Accessibility* complying with 703.7.2.1.

216.8 Toilet Rooms and Bathing Rooms. Where existing toilet rooms or bathing rooms do not comply with 603, directional signs indicating the location of the nearest toilet room or bathing room complying with 603 within the *facility* shall be provided. Signs shall comply with 703.5 and shall include the International Symbol of *Accessibility* complying with 703.7.2.1. Where existing toilet rooms or bathing rooms do not comply with 603, the toilet rooms or bathing rooms complying with 603 shall be identified by the International Symbol of *Accessibility* complying with 703.7.2.1. Where clustered single user toilet rooms or bathing *facilities* are permitted to use exceptions to 213.2, toilet rooms or bathing *facilities* complying with 603 shall be identified by the International Symbol of *Accessibility* complying with 703.7.2.1 unless all toilet rooms and bathing *facilities* comply with 603.

216.9 TTYs. Identification and directional signs for public *TTYs* shall be provided in accordance with 216.9.

216.9.1 Identification Signs. Public *TTYs* shall be identified by the International Symbol of *TTY* complying with 703.7.2.2.

216.9.2 Directional Signs. Directional signs indicating the location of the nearest public *TTY* shall be provided at all banks of public pay telephones not containing a public *TTY*. In addition, where signs provide direction to public pay telephones, they shall also provide direction to public *TTYs*. Directional signs shall comply with 703.5 and shall include the International Symbol of *TTY* complying with 703.7.2.2.

216.10 Assistive Listening Systems. Each *assembly area* required by 219 to provide *assistive listening systems* shall provide signs informing patrons of the availability of the *assistive listening system*. Assistive listening signs shall comply with 703.5 and shall include the International Symbol of Access for Hearing Loss complying with 703.7.2.4.

EXCEPTION: Where ticket offices or windows are provided, signs shall not be required at each *assembly area* provided that signs are displayed at each ticket office or window informing patrons of the availability of *assistive listening systems*.

216.11 Check-Out Aisles. Where more than one check-out aisle is provided, check-out aisles complying with 904.3 shall be identified by the International Symbol of *Accessibility* complying with 703.7.2.1. Where check-out aisles are identified by numbers, letters, or functions, signs identifying

check-out aisles complying with 904.3 shall be located in the same location as the check-out aisle identification.

EXCEPTION: Where all check-out aisles serving a single function comply with 904.3, signs complying with 703.7.2.1 shall not be required.

216.12 Amusement Rides. Signs identifying the type of access provided on *amusement rides* shall be provided at entries to queues and waiting lines. In addition, where *accessible* unload areas also serve as *accessible* load areas, signs indicating the location of the *accessible* load and unload areas shall be provided at entries to queues and waiting lines.

Advisory 216.12 Amusement Rides. Amusement rides designed primarily for children, amusement rides that are controlled or operated by the rider, and amusement rides without seats, are not required to provide wheelchair spaces, transfer seats, or transfer systems, and need not meet the sign requirements in 216.12. The load and unload areas of these rides must, however, be on an accessible route and must provide turning space.

217 Telephones

217.1 General. Where coin-operated public pay telephones, coinless public pay telephones, public *closed-circuit telephones*, public courtesy phones, or other types of public telephones are provided, public telephones shall be provided in accordance with 217 for each type of public telephone provided. For purposes of this section, a bank of telephones shall be considered to be two or more adjacent telephones.

Advisory 217.1 General. These requirements apply to all types of public telephones including courtesy phones at airports and rail stations that provide a free direct connection to hotels, transportation services, and tourist attractions.

217.2 Wheelchair Accessible Telephones. Where public telephones are provided, wheelchair *accessible* telephones complying with 704.2 shall be provided in accordance with Table 217.2.

EXCEPTION: Drive-up only public telephones shall not be required to comply with 217.2.

Table 217.2 Wheelchair Accessible Telephones

Number of Telephones Provided on a Floor, Level, or Exterior Site	Minimum Number of Required Wheelchair Accessible Telephones
1 or more single units	1 per floor, level, and exterior <i>site</i>
1 bank	1 per floor, level, and exterior <i>site</i>
2 or more banks	1 per bank

217.3 Volume Controls. All public telephones shall have volume controls complying with 704.3.

217.4 TTYs. TTYs complying with 704.4 shall be provided in accordance with 217.4.

Advisory 217.4 TTYs. Separate requirements are provided based on the number of public pay telephones provided at a bank of telephones, within a floor, a building, or on a site. In some instances one TTY can be used to satisfy more than one of these requirements. For example, a TTY required for a bank can satisfy the requirements for a building. However, the requirement for at least one TTY on an exterior site cannot be met by installing a TTY in a bank inside a building. Consideration should be given to phone systems that can accommodate both digital and analog transmissions for compatibility with digital and analog TTYs.

217.4.1 Bank Requirement. Where four or more public pay telephones are provided at a bank of telephones, at least one public TTY complying with 704.4 shall be provided at that bank.

EXCEPTION: TTYs shall not be required at banks of telephones located within 200 feet (61 m) of, and on the same floor as, a bank containing a public TTY.

217.4.2 Floor Requirement. TTYs in *public buildings* shall be provided in accordance with 217.4.2.1. TTYs in *private buildings* shall be provided in accordance with 217.4.2.2.

217.4.2.1 Public Buildings. Where at least one public pay telephone is provided on a floor of a *public building*, at least one public TTY shall be provided on that floor.

217.4.2.2 Private Buildings. Where four or more public pay telephones are provided on a floor of a *private building*, at least one public TTY shall be provided on that floor.

217.4.3 Building Requirement. TTYs in *public buildings* shall be provided in accordance with 217.4.3.1. TTYs in *private buildings* shall be provided in accordance with 217.4.3.2.

217.4.3.1 Public Buildings. Where at least one public pay telephone is provided in a *public building*, at least one public TTY shall be provided in the *building*. Where at least one public pay telephone is provided in a *public use* area of a *public building*, at least one public TTY shall be provided in the *public building* in a *public use* area.

217.4.3.2 Private Buildings. Where four or more public pay telephones are provided in a *private building*, at least one public TTY shall be provided in the *building*.

217.4.4 Exterior Site Requirement. Where four or more public pay telephones are provided on an exterior *site*, at least one public TTY shall be provided on the *site*.

217.4.5 Rest Stops, Emergency Roadside Stops, and Service Plazas. Where at least one public pay telephone is provided at a public rest stop, emergency roadside stop, or service plaza, at least one public TTY shall be provided.

217.4.6 Hospitals. Where at least one public pay telephone is provided serving a hospital emergency room, hospital recovery room, or hospital waiting room, at least one public TTY shall be provided at each location.

217.4.7 Transportation Facilities. In transportation *facilities*, in addition to the requirements of 217.4.1 through 217.4.4, where at least one public pay telephone serves a particular *entrance* to a bus or rail *facility*, at least one public TTY shall be provided to serve that *entrance*. In airports, in addition to the requirements of 217.4.1 through 217.4.4, where four or more public pay telephones are located in a terminal outside the security areas, a concourse within the security areas, or a baggage claim area in a terminal, at least one public TTY shall be provided in each location.

217.4.8 Detention and Correctional Facilities. In detention and correctional *facilities*, where at least one pay telephone is provided in a secured area used only by detainees or inmates and security personnel, at least one TTY shall be provided in at least one secured area.

217.5 Shelves for Portable TTYs. Where a bank of telephones in the interior of a *building* consists of three or more public pay telephones, at least one public pay telephone at the bank shall be provided with a shelf and an electrical outlet in accordance with 704.5.

EXCEPTIONS: 1. Secured areas of detention and correctional *facilities* where shelves and outlets are prohibited for purposes of security or safety shall not be required to comply with 217.5.

2. The shelf and electrical outlet shall not be required at a bank of telephones with a TTY.

218 Transportation Facilities

218.1 General. Transportation *facilities* shall comply with 218.

218.2 New and Altered Fixed Guideway Stations. New and *altered* stations in rapid rail, light rail, commuter rail, intercity rail, high speed rail, and other fixed guideway systems shall comply with 810.5 through 810.10.

218.3 Key Stations and Existing Intercity Rail Stations. *Key stations* and existing intercity rail stations shall comply with 810.5 through 810.10.

218.4 Bus Shelters. Where provided, bus shelters shall comply with 810.3.

218.5 Other Transportation Facilities. In other transportation *facilities*, public address systems shall comply with 810.7 and clocks shall comply with 810.8.

219 Assistive Listening Systems

219.1 General. *Assistive listening systems* shall be provided in accordance with 219 and shall comply with 706.

219.2 Required Systems. In each *assembly area* where audible communication is integral to the use of the *space*, an *assistive listening system* shall be provided.

EXCEPTION: Other than in courtrooms, *assistive listening systems* shall not be required where audio amplification is not provided.

219.3 Receivers. Receivers complying with 706.2 shall be provided for *assistive listening systems* in each *assembly area* in accordance with Table 219.3. Twenty-five percent minimum of receivers provided, but no fewer than two, shall be hearing-aid compatible in accordance with 706.3.

EXCEPTIONS: 1. Where a *building* contains more than one *assembly area* and the *assembly areas* required to provide *assistive listening systems* are under one management, the total number of required receivers shall be permitted to be calculated according to the total number of seats in the *assembly areas* in the *building* provided that all receivers are usable with all systems.

2. Where all seats in an *assembly area* are served by an induction loop *assistive listening system*, the minimum number of receivers required by Table 219.3 to be hearing-aid compatible shall not be required to be provided.

Table 219.3 Receivers for Assistive Listening Systems

Capacity of Seating in Assembly Area	Minimum Number of Required Receivers	Minimum Number of Required Receivers Required to be Hearing-aid Compatible
50 or less	2	2
51 to 200	2, plus 1 per 25 seats over 50 seats ¹	2
201 to 500	2, plus 1 per 25 seats over 50 seats ¹	1 per 4 receivers ¹
501 to 1000	20, plus 1 per 33 seats over 500 seats ¹	1 per 4 receivers ¹
1001 to 2000	35, plus 1 per 50 seats over 1000 seats ¹	1 per 4 receivers ¹
2001 and over	55 plus 1 per 100 seats over 2000 seats ¹	1 per 4 receivers ¹

1. Or fraction thereof.

220 Automatic Teller Machines and Fare Machines

220.1 General. Where automatic teller machines or self-service fare vending, collection, or adjustment machines are provided, at least one of each type provided at each location shall comply with 707. Where bins are provided for envelopes, waste paper, or other purposes, at least one of each type shall comply with 811.

Advisory 220.1 General. If a bank provides both interior and exterior ATMs, each such installation is considered a separate location. Accessible ATMs, including those with speech and those that are within reach of people who use wheelchairs, must provide all the functions provided to customers at that location at all times. For example, it is unacceptable for the accessible ATM only to provide cash withdrawals while inaccessible ATMs also sell theater tickets.

221 Assembly Areas

221.1 General. *Assembly areas* shall provide *wheelchair spaces*, companion seats, and designated aisle seats complying with 221 and 802. In addition, lawn seating shall comply with 221.5.

[See additional requirements at 28 CFR 35.151(g), p. 12, and 28 CFR 36.406(f), p. 29.]

221.2 Wheelchair Spaces. *Wheelchair spaces* complying with 221.2 shall be provided in *assembly areas* with fixed seating.

221.2.1 Number and Location. *Wheelchair spaces* shall be provided complying with 221.2.1.

221.2.1.1 General Seating. *Wheelchair spaces* complying with 802.1 shall be provided in accordance with Table 221.2.1.1.

Table 221.2.1.1 Number of Wheelchair Spaces in Assembly Areas

Number of Seats	Minimum Number of Required Wheelchair Spaces
4 to 25	1
26 to 50	2
51 to 150	4
151 to 300	5
301 to 500	6
501 to 5000	6, plus 1 for each 150, or fraction thereof, between 501 through 5000
5001 and over	36, plus 1 for each 200, or fraction thereof, over 5000

221.2.1.2 Luxury Boxes, Club Boxes, and Suites in Arenas, Stadiums, and Grandstands.

In each luxury box, club box, and suite within arenas, stadiums, and grandstands, *wheelchair spaces* complying with 802.1 shall be provided in accordance with Table 221.2.1.1.

Advisory 221.2.1.2 Luxury Boxes, Club Boxes, and Suites in Arenas, Stadiums, and Grandstands. The number of wheelchair spaces required in luxury boxes, club boxes, and suites within an arena, stadium, or grandstand is to be calculated box by box and suite by suite.

221.2.1.3 Other Boxes. In boxes other than those required to comply with 221.2.1.2, the total number of *wheelchair spaces* required shall be determined in accordance with Table 221.2.1.1. *Wheelchair spaces* shall be located in not less than 20 percent of all boxes provided. *Wheelchair spaces* shall comply with 802.1.

Advisory 221.2.1.3 Other Boxes. The provision for seating in “other boxes” includes box seating provided in facilities such as performing arts auditoria where tiered boxes are designed for spatial and acoustical purposes. The number of wheelchair spaces required in boxes covered by 221.2.1.3 is calculated based on the total number of seats provided in these other boxes. The resulting number of wheelchair spaces must be located in no fewer than 20% of the boxes covered by this section. For example, a concert hall has 20 boxes, each of which contains 10 seats, totaling 200 seats. In this example, 5 wheelchair spaces would be required, and they must be placed in at least 4 of the boxes. Additionally, because the wheelchair spaces must also meet the dispersion requirements of 221.2.3, the boxes containing these wheelchair spaces cannot all be located in one area unless an exception to the dispersion requirements applies.

221.2.1.4 Team or Player Seating. At least one *wheelchair space* complying with 802.1 shall be provided in team or player seating areas serving *areas of sport activity*.

EXCEPTION: *Wheelchair spaces* shall not be required in team or player seating areas serving bowling lanes not required to comply with 206.2.11.

221.2.2 Integration. *Wheelchair spaces* shall be an integral part of the seating plan.

Advisory 221.2.2 Integration. The requirement that wheelchair spaces be an “integral part of the seating plan” means that wheelchair spaces must be placed within the footprint of the seating area. Wheelchair spaces cannot be segregated from seating areas. For example, it would be unacceptable to place only the wheelchair spaces, or only the wheelchair spaces and their associated companion seats, outside the seating areas defined by risers in an assembly area.

221.2.3 Lines of Sight and Dispersion. *Wheelchair spaces* shall provide lines of sight complying with 802.2 and shall comply with 221.2.3. In providing lines of sight, *wheelchair spaces* shall be dispersed. *Wheelchair spaces* shall provide spectators with choices of seating locations and viewing angles that are substantially equivalent to, or better than, the choices of seating locations and viewing angles available to all other spectators. When the number of *wheelchair spaces* required by 221.2.1 has been met, further dispersion shall not be required.

EXCEPTION: *Wheelchair spaces* in team or player seating areas serving *areas of sport activity* shall not be required to comply with 221.2.3.

Advisory 221.2.3 Lines of Sight and Dispersion. Consistent with the overall intent of the ADA, individuals who use wheelchairs must be provided equal access so that their experience is substantially equivalent to that of other members of the audience. Thus, while individuals who use wheelchairs need not be provided with the best seats in the house, neither may they be relegated to the worst.

221.2.3.1 Horizontal Dispersion. *Wheelchair spaces* shall be dispersed horizontally.

EXCEPTIONS: **1.** Horizontal dispersion shall not be required in *assembly areas* with 300 or fewer seats if the companion seats required by 221.3 and *wheelchair spaces* are located within the 2nd or 3rd quartile of the total row length. Intermediate aisles shall be included in

determining the total row length. If the row length in the 2nd and 3rd quartile of a row is insufficient to accommodate the required number of companion seats and *wheelchair spaces*, the additional companion seats and *wheelchair spaces* shall be permitted to be located in the 1st and 4th quartile of the row.

2. In row seating, two *wheelchair spaces* shall be permitted to be located side-by-side.

Advisory 221.2.3.1 Horizontal Dispersion. Horizontal dispersion of wheelchair spaces is the placement of spaces in an assembly facility seating area from side-to-side or, in the case of an arena or stadium, around the field of play or performance area.

221.2.3.2 Vertical Dispersion. *Wheelchair spaces* shall be dispersed vertically at varying distances from the screen, performance area, or playing field. In addition, *wheelchair spaces* shall be located in each balcony or *mezzanine* that is located on an *accessible* route.

EXCEPTIONS: 1. Vertical dispersion shall not be required in *assembly areas* with 300 or fewer seats if the *wheelchair spaces* provide viewing angles that are equivalent to, or better than, the average viewing angle provided in the *facility*.

2. In bleachers, *wheelchair spaces* shall not be required to be provided in rows other than rows at points of entry to bleacher seating.

Advisory 221.2.3.2 Vertical Dispersion. When wheelchair spaces are dispersed vertically in an assembly facility they are placed at different locations within the seating area from front-to-back so that the distance from the screen, stage, playing field, area of sports activity, or other focal point is varied among wheelchair spaces.

Advisory 221.2.3.2 Vertical Dispersion Exception 2. Points of entry to bleacher seating may include, but are not limited to, cross aisles, concourses, vomitories, and entrance ramps and stairs. Vertical, center, or side aisles adjoining bleacher seating that are stepped or tiered are not considered entry points.

221.3 Companion Seats. At least one companion seat complying with 802.3 shall be provided for each *wheelchair space* required by 221.2.1.

221.4 Designated Aisle Seats. At least 5 percent of the total number of aisle seats provided shall comply with 802.4 and shall be the aisle seats located closest to *accessible* routes.

EXCEPTION: Team or player seating areas serving *areas of sport activity* shall not be required to comply with 221.4.

Advisory 221.4 Designated Aisle Seats. When selecting which aisle seats will meet the requirements of 802.4, those aisle seats which are closest to, not necessarily on, accessible routes must be selected first. For example, an assembly area has two aisles (A and B) serving seating areas with an accessible route connecting to the top and bottom of Aisle A only. The aisle seats chosen to meet 802.4 must be those at the top and bottom of Aisle A, working toward the middle. Only when all seats on Aisle A would not meet the five percent minimum would seats on Aisle B be designated.

221.5 Lawn Seating. Lawn seating areas and exterior overflow seating areas, where fixed seats are not provided, shall connect to an *accessible* route.

222 Dressing, Fitting, and Locker Rooms

222.1 General. Where dressing rooms, fitting rooms, or locker rooms are provided, at least 5 percent, but no fewer than one, of each type of use in each cluster provided shall comply with 803.

EXCEPTION: In *alterations*, where it is *technically infeasible* to provide rooms in accordance with 222.1, one room for each sex on each level shall comply with 803. Where only unisex rooms are provided, unisex rooms shall be permitted.

Advisory 222.1 General. A "cluster" is a group of rooms proximate to one another. Generally, rooms in a cluster are within sight of, or adjacent to, one another. Different styles of design provide users varying levels of privacy and convenience. Some designs include private changing facilities that are close to core areas of the facility, while other designs use space more economically and provide only group dressing facilities. Regardless of the type of facility, dressing, fitting, and locker rooms should provide people with disabilities rooms that are equally private and convenient to those provided others. For example, in a physician's office, if people without disabilities must traverse the full length of the office suite in clothing other than their street clothes, it is acceptable for people with disabilities to be asked to do the same.

222.2 Coat Hooks and Shelves. Where coat hooks or shelves are provided in dressing, fitting or locker rooms without individual compartments, at least one of each type shall comply with 803.5. Where coat hooks or shelves are provided in individual compartments at least one of each type complying with 803.5 shall be provided in individual compartments in dressing, fitting, or locker rooms required to comply with 222.1.

223 Medical Care and Long-Term Care Facilities

223.1 General. In licensed medical care *facilities* and licensed long-term care *facilities* where the period of stay exceeds twenty-four hours, patient or resident sleeping rooms shall be provided in accordance with 223. [See additional requirements at 28 CFR 35.151(h), p. 13, and 28 CFR 36.406(g), p. 30.]

EXCEPTION: Toilet rooms that are part of critical or intensive care patient sleeping rooms shall not be required to comply with 603.

Advisory 223.1 General. Because medical facilities frequently reconfigure spaces to reflect changes in medical specialties, Section 223.1 does not include a provision for dispersion of accessible patient or resident sleeping rooms. The lack of a design requirement does not mean that covered entities are not required to provide services to people with disabilities where accessible rooms are not dispersed in specialty areas. Locate accessible rooms near core areas that are less likely to change over time. While dispersion is not required, the flexibility it provides can be a critical factor in ensuring cost effective compliance with applicable civil rights laws, including titles II and III of the ADA and Section 504 of the Rehabilitation Act of 1973, as amended.

Advisory 223.1 General (Continued). Additionally, all types of features and amenities should be dispersed among accessible sleeping rooms to ensure equal access to and a variety of choices for all patients and residents.

223.1.1 Alterations. Where sleeping rooms are *altered* or *added*, the requirements of 223 shall apply only to the sleeping rooms being *altered* or *added* until the number of sleeping rooms complies with the minimum number required for new construction.

Advisory 223.1.1 Alterations. In alterations and additions, the minimum required number is based on the total number of sleeping rooms altered or added instead of on the total number of sleeping rooms provided in a facility. As a facility is altered over time, every effort should be made to disperse accessible sleeping rooms among patient care areas such as pediatrics, cardiac care, maternity, and other units. In this way, people with disabilities can have access to the full-range of services provided by a medical care facility.

223.2 Hospitals, Rehabilitation Facilities, Psychiatric Facilities and Detoxification Facilities.

Hospitals, rehabilitation *facilities*, psychiatric *facilities* and detoxification *facilities* shall comply with 223.2.

223.2.1 Facilities Not Specializing in Treating Conditions That Affect Mobility. In *facilities* not specializing in treating conditions that affect mobility, at least 10 percent, but no fewer than one, of the patient sleeping rooms shall provide mobility features complying with 805.

223.2.2 Facilities Specializing in Treating Conditions That Affect Mobility. In *facilities* specializing in treating conditions that affect mobility, 100 percent of the patient sleeping rooms shall provide mobility features complying with 805.

Advisory 223.2.2 Facilities Specializing in Treating Conditions That Affect Mobility. Conditions that affect mobility include conditions requiring the use or assistance of a brace, cane, crutch, prosthetic device, wheelchair, or powered mobility aid; arthritic, neurological, or orthopedic conditions that severely limit one's ability to walk; respiratory diseases and other conditions which may require the use of portable oxygen; and cardiac conditions that impose significant functional limitations. Facilities that may provide treatment for, but that do not specialize in treatment of such conditions, such as general rehabilitation hospitals, are not subject to this requirement but are subject to Section 223.2.1.

223.3 Long-Term Care Facilities. In licensed long-term care *facilities*, at least 50 percent, but no fewer than one, of each type of resident sleeping room shall provide mobility features complying with 805.

224 Transient Lodging Guest Rooms

224.1 General. *Transient lodging facilities* shall provide guest rooms in accordance with 224.

[See additional requirements for places of lodging at 28 CFR 36.406(c), p. 28. and for housing at a place of education at 28 CFR 35.151(f), p. 11, and 28 CFR 36.406(e), p. 29.]

Advisory 224.1 General. Certain facilities used for transient lodging, including time shares, dormitories, and town homes may be covered by both these requirements and the Fair Housing Amendments Act. The Fair Housing Amendments Act requires that certain residential structures having four or more multi-family dwelling units, regardless of whether they are privately owned or federally assisted, include certain features of accessible and adaptable design according to guidelines established by the U.S. Department of Housing and Urban Development (HUD). This law and the appropriate regulations should be consulted before proceeding with the design and construction of residential housing.

224.1.1 Alterations. Where guest rooms are *altered* or *added*, the requirements of 224 shall apply only to the guest rooms being *altered* or *added* until the number of guest rooms complies with the minimum number required for new construction.

Advisory 224.1.1 Alterations. In alterations and additions, the minimum required number of accessible guest rooms is based on the total number of guest rooms altered or added instead of the total number of guest rooms provided in a facility. Typically, each alteration of a facility is limited to a particular portion of the facility. When accessible guest rooms are added as a result of subsequent alterations, compliance with 224.5 (Dispersion) is more likely to be achieved if all of the accessible guest rooms are not provided in the same area of the facility.

224.1.2 Guest Room Doors and Doorways. *Entrances*, doors, and doorways providing user passage into and within guest rooms that are not required to provide mobility features complying with 806.2 shall comply with 404.2.3.

EXCEPTION: Shower and sauna doors in guest rooms that are not required to provide mobility features complying with 806.2 shall not be required to comply with 404.2.3.

Advisory 224.1.2 Guest Room Doors and Doorways. Because of the social interaction that often occurs in lodging facilities, an accessible clear opening width is required for doors and doorways to and within all guest rooms, including those not required to be accessible. This applies to all doors, including bathroom doors, that allow full user passage. Other requirements for doors and doorways in Section 404 do not apply to guest rooms not required to provide mobility features.

224.2 Guest Rooms with Mobility Features. In *transient lodging facilities*, guest rooms with mobility features complying with 806.2 shall be provided in accordance with Table 224.2.

Table 224.2 Guest Rooms with Mobility Features

Total Number of Guest Rooms Provided	Minimum Number of Required Rooms Without Roll-in Showers	Minimum Number of Required Rooms With Roll-in Showers	Total Number of Required Rooms
1 to 25	1	0	1
26 to 50	2	0	2
51 to 75	3	1	4
76 to 100	4	1	5
101 to 150	5	2	7
151 to 200	6	2	8
201 to 300	7	3	10
301 to 400	8	4	12
401 to 500	9	4	13
501 to 1000	2 percent of total	1 percent of total	3 percent of total
1001 and over	20, plus 1 for each 100, or fraction thereof, over 1000	10, plus 1 for each 100, or fraction thereof, over 1000	30, plus 2 for each 100, or fraction thereof, over 1000

224.3 Beds. In guest rooms having more than 25 beds, 5 percent minimum of the beds shall have clear floor space complying with 806.2.3.

224.4 Guest Rooms with Communication Features. In *transient lodging facilities*, guest rooms with communication features complying with 806.3 shall be provided in accordance with Table 224.4.

Table 224.4 Guest Rooms with Communication Features

Total Number of Guest Rooms Provided	Minimum Number of Required Guest Rooms With Communication Features
2 to 25	2
26 to 50	4
51 to 75	7
76 to 100	9
101 to 150	12

Table 224.4 Guest Rooms with Communication Features

Total Number of Guest Rooms Provided	Minimum Number of Required Guest Rooms With Communication Features
151 to 200	14
201 to 300	17
301 to 400	20
401 to 500	22
501 to 1000	5 percent of total
1001 and over	50, plus 3 for each 100 over 1000

224.5 Dispersion. Guest rooms required to provide mobility features complying with 806.2 and guest rooms required to provide communication features complying with 806.3 shall be dispersed among the various classes of guest rooms, and shall provide choices of types of guest rooms, number of beds, and other amenities comparable to the choices provided to other guests. Where the minimum number of guest rooms required to comply with 806 is not sufficient to allow for complete dispersion, guest rooms shall be dispersed in the following priority: guest room type, number of beds, and amenities. At least one guest room required to provide mobility features complying with 806.2 shall also provide communication features complying with 806.3. Not more than 10 percent of guest rooms required to provide mobility features complying with 806.2 shall be used to satisfy the minimum number of guest rooms required to provide communication features complying with 806.3.

Advisory 224.5 Dispersion. Factors to be considered in providing an equivalent range of options may include, but are not limited to, room size, bed size, cost, view, bathroom fixtures such as hot tubs and spas, smoking and nonsmoking, and the number of rooms provided.

225 Storage

225.1 General. Storage *facilities* shall comply with 225.

225.2 Storage. Where storage is provided in accessible *spaces*, at least one of each type shall comply with 811.

Advisory 225.2 Storage. Types of storage include, but are not limited to, closets, cabinets, shelves, clothes rods, hooks, and drawers. Where provided, at least one of each type of storage must be within the reach ranges specified in 308; however, it is permissible to install additional storage outside the reach ranges.

225.2.1 Lockers. Where lockers are provided, at least 5 percent, but no fewer than one of each type, shall comply with 811.

Advisory 225.2.1 Lockers. Different types of lockers may include full-size and half-size lockers, as well as those specifically designed for storage of various sports equipment.

225.2.2 Self-Service Shelving. Self-service shelves shall be located on an *accessible* route complying with 402. Self-service shelving shall not be required to comply with 308.

Advisory 225.2.2 Self-Service Shelving. Self-service shelves include, but are not limited to, library, store, or post office shelves.

225.3 Self-Service Storage Facilities. *Self-service storage facilities* shall provide individual *self-service storage spaces* complying with these requirements in accordance with Table 225.3.

Table 225.3 Self-Service Storage Facilities

Total Spaces in Facility	Minimum Number of Spaces Required to be Accessible
1 to 200	5 percent, but no fewer than 1
201 and over	10, plus 2 percent of total number of units over 200

Advisory 225.3 Self-Service Storage Facilities. Although there are no technical requirements that are unique to self-service storage facilities, elements and spaces provided in facilities containing self-service storage spaces required to comply with these requirements must comply with this document where applicable. For example: the number of storage spaces required to comply with these requirements must provide Accessible Routes complying with Section 206; Accessible Means of Egress complying with Section 207; Parking Spaces complying with Section 208; and, where provided, other public use or common use elements and facilities such as toilet rooms, drinking fountains, and telephones must comply with the applicable requirements of this document.

225.3.1 Dispersion. Individual *self-service storage spaces* shall be dispersed throughout the various classes of *spaces* provided. Where more classes of *spaces* are provided than the number required to be *accessible*, the number of *spaces* shall not be required to exceed that required by Table 225.3. *Self-service storage spaces* complying with Table 225.3 shall not be required to be dispersed among *buildings* in a multi-*building facility*.

226 Dining Surfaces and Work Surfaces

226.1 General. Where dining surfaces are provided for the consumption of food or drink, at least 5 percent of the seating *spaces* and standing *spaces* at the dining surfaces shall comply with 902. In addition, where work surfaces are provided for use by other than employees, at least 5 percent shall comply with 902.

EXCEPTIONS: 1. Sales counters and service counters shall not be required to comply with 902.

2. Check writing surfaces provided at check-out aisles not required to comply with 904.3 shall not be required to comply with 902.

Advisory 226.1 General. In facilities covered by the ADA, this requirement does not apply to work surfaces used only by employees. However, the ADA and, where applicable, Section 504 of the Rehabilitation Act of 1973, as amended, provide that employees are entitled to "reasonable accommodations." With respect to work surfaces, this means that employers may need to procure or adjust work stations such as desks, laboratory and work benches, fume hoods, reception counters, teller windows, study carrels, commercial kitchen counters, and conference tables to accommodate the individual needs of employees with disabilities on an "as needed" basis. Consider work surfaces that are flexible and permit installation at variable heights and clearances.

226.2 Dispersion. Dining surfaces and work surfaces required to comply with 902 shall be dispersed throughout the *space* or *facility* containing dining surfaces and work surfaces.

227 Sales and Service

227.1 General. Where provided, check-out aisles, sales counters, service counters, food service lines, queues, and waiting lines shall comply with 227 and 904.

227.2 Check-Out Aisles. Where check-out aisles are provided, check-out aisles complying with 904.3 shall be provided in accordance with Table 227.2. Where check-out aisles serve different functions, check-out aisles complying with 904.3 shall be provided in accordance with Table 227.2 for each function. Where check-out aisles are dispersed throughout the *building* or *facility*, check-out aisles complying with 904.3 shall be dispersed.

EXCEPTION: Where the selling *space* is under 5000 square feet (465 m²) no more than one check-out aisle complying with 904.3 shall be required.

Table 227.2 Check-Out Aisles

Number of Check-Out Aisles of Each Function	Minimum Number of Check-Out Aisles of Each Function Required to Comply with 904.3
1 to 4	1
5 to 8	2
9 to 15	3
16 and over	3, plus 20 percent of additional aisles

227.2.1 Altered Check-Out Aisles. Where check-out aisles are *altered*, at least one of each check-out aisle serving each function shall comply with 904.3 until the number of check-out aisles complies with 227.2.

227.3 Counters. Where provided, at least one of each type of sales counter and service counter shall comply with 904.4. Where counters are dispersed throughout the *building or facility*, counters complying with 904.4 also shall be dispersed.

Advisory 227.3 Counters. Types of counters that provide different services in the same facility include, but are not limited to, order, pick-up, express, and returns. One continuous counter can be used to provide different types of service. For example, order and pick-up are different services. It would not be acceptable to provide access only to the part of the counter where orders are taken when orders are picked-up at a different location on the same counter. Both the order and pick-up section of the counter must be accessible.

227.4 Food Service Lines. Food service lines shall comply with 904.5. Where self-service shelves are provided, at least 50 percent, but no fewer than one, of each type provided shall comply with 308.

227.5 Queues and Waiting Lines. Queues and waiting lines servicing counters or check-out aisles required to comply with 904.3 or 904.4 shall comply with 403.

228 Depositories, Vending Machines, Change Machines, Mail Boxes, and Fuel Dispensers

228.1 General. Where provided, at least one of each type of depository, vending machine, change machine, and fuel dispenser shall comply with 309.

EXCEPTION: Drive-up only depositories shall not be required to comply with 309.

Advisory 228.1 General. Depositories include, but are not limited to, night receptacles in banks, post offices, video stores, and libraries.

228.2 Mail Boxes. Where *mail boxes* are provided in an interior location, at least 5 percent, but no fewer than one, of each type shall comply with 309. In residential *facilities*, where *mail boxes* are provided for each *residential dwelling unit*, *mail boxes* complying with 309 shall be provided for each *residential dwelling unit* required to provide mobility features complying with 809.2 through 809.4.

229 Windows

229.1 General. Where glazed openings are provided in *accessible* rooms or *spaces* for operation by occupants, at least one opening shall comply with 309. Each glazed opening required by an *administrative authority* to be operable shall comply with 309.

EXCEPTION: 1. Glazed openings in *residential dwelling units* required to comply with 809 shall not be required to comply with 229.

2. Glazed openings in guest rooms required to provide communication features and in guest rooms required to comply with 206.5.3 shall not be required to comply with 229.

230 Two-Way Communication Systems

230.1 General. Where a two-way communication system is provided to gain admittance to a *building or facility* or to restricted areas within a *building or facility*, the system shall comply with 708.

Advisory 230.1 General. This requirement applies to facilities such as office buildings, courthouses, and other facilities where admittance to the building or restricted spaces is dependent on two-way communication systems.

231 Judicial Facilities

231.1 General. Judicial *facilities* shall comply with 231.

231.2 Courtrooms. Each courtroom shall comply with 808.

231.3 Holding Cells. Where provided, central holding cells and court-floor holding cells shall comply with 231.3.

231.3.1 Central Holding Cells. Where separate central holding cells are provided for adult male, juvenile male, adult female, or juvenile female, one of each type shall comply with 807.2. Where central holding cells are provided and are not separated by age or sex, at least one cell complying with 807.2 shall be provided.

231.3.2 Court-Floor Holding Cells. Where separate court-floor holding cells are provided for adult male, juvenile male, adult female, or juvenile female, each courtroom shall be served by one cell of each type complying with 807.2. Where court-floor holding cells are provided and are not separated by age or sex, courtrooms shall be served by at least one cell complying with 807.2. Cells may serve more than one courtroom.

231.4 Visiting Areas. Visiting areas shall comply with 231.4.

231.4.1 Cubicles and Counters. At least 5 percent, but no fewer than one, of cubicles shall comply with 902 on both the visitor and detainee sides. Where counters are provided, at least one shall comply with 904.4.2 on both the visitor and detainee sides.

EXCEPTION: The detainee side of cubicles or counters at non-contact visiting areas not serving holding cells required to comply with 231 shall not be required to comply with 902 or 904.4.2.

231.4.2 Partitions. Where solid partitions or security glazing separate visitors from detainees at least one of each type of cubicle or counter partition shall comply with 904.6.

232 Detention Facilities and Correctional Facilities

232.1 General. *Buildings, facilities, or portions thereof*, in which people are detained for penal or correction purposes, or in which the liberty of the inmates is restricted for security reasons shall comply with 232. [See additional requirements at 28 CFR 35.151(k), p. 13.]

Advisory 232.1 General. Detention facilities include, but are not limited to, jails, detention centers, and holding cells in police stations. Correctional facilities include, but are not limited to, prisons, reformatories, and correctional centers.

232.2 General Holding Cells and General Housing Cells. General holding cells and general housing cells shall be provided in accordance with 232.2.

EXCEPTION: *Alterations* to cells shall not be required to comply except to the extent determined by the Attorney General.

Advisory 232.2 General Holding Cells and General Housing Cells. Accessible cells or rooms should be dispersed among different levels of security, housing categories, and holding classifications (e.g., male/female and adult/juvenile) to facilitate access. Many detention and correctional facilities are designed so that certain areas (e.g., "shift" areas) can be adapted to serve as different types of housing according to need. For example, a shift area serving as a medium-security housing unit might be redesignated for a period of time as a high-security housing unit to meet capacity needs. Placement of accessible cells or rooms in shift areas may allow additional flexibility in meeting requirements for dispersion of accessible cells or rooms.

Advisory 232.2 General Holding Cells and General Housing Cells Exception. Although these requirements do not specify that cells be accessible as a consequence of an alteration, title II of the ADA requires that each service, program, or activity conducted by a public entity, when viewed in its entirety, be readily accessible to and usable by individuals with disabilities. This requirement must be met unless doing so would fundamentally alter the nature of a service, program, or activity or would result in undue financial and administrative burdens.

232.2.1 Cells with Mobility Features. At least 2 percent, but no fewer than one, of the total number of cells in a *facility* shall provide mobility features complying with 807.2.

232.2.1.1 Beds. In cells having more than 25 beds, at least 5 percent of the beds shall have clear floor *space* complying with 807.2.3.

232.2.2 Cells with Communication Features. At least 2 percent, but no fewer than one, of the total number of general holding cells and general housing cells equipped with audible emergency alarm systems and permanently installed telephones within the cell shall provide communication features complying with 807.3.

232.3 Special Holding Cells and Special Housing Cells. Where special holding cells or special housing cells are provided, at least one cell serving each purpose shall provide mobility features complying with 807.2. Cells subject to this requirement include, but are not limited to, those used for purposes of orientation, protective custody, administrative or disciplinary detention or segregation, detoxification, and medical isolation.

EXCEPTION: *Alterations* to cells shall not be required to comply except to the extent determined by the Attorney General.

232.4 Medical Care Facilities. Patient bedrooms or cells required to comply with 223 shall be provided in addition to any medical isolation cells required to comply with 232.3.

232.5 Visiting Areas. Visiting areas shall comply with 232.5.

232.5.1 Cubicles and Counters. At least 5 percent, but no fewer than one, of cubicles shall comply with 902 on both the visitor and detainee sides. Where counters are provided, at least one shall comply with 904.4.2 on both the visitor and detainee or inmate sides.

EXCEPTION: The inmate or detainee side of cubicles or counters at non-contact visiting areas not serving holding cells or housing cells required to comply with 232 shall not be required to comply with 902 or 904.4.2.

232.5.2 Partitions. Where solid partitions or security glazing separate visitors from detainees or inmates at least one of each type of cubicle or counter partition shall comply with 904.6.

233 Residential Facilities

233.1 General. *Facilities with residential dwelling units* shall comply with 233. [See additional requirements at 28 CFR 35.151(e) and (f), p. 11, and 28 CFR 36.406(d) and (e), pp. 28 and 29.]

Advisory 233.1 General. Section 233 outlines the requirements for residential facilities subject to the Americans with Disabilities Act of 1990. The facilities covered by Section 233, as well as other facilities not covered by this section, may still be subject to other Federal laws such as the Fair Housing Act and Section 504 of the Rehabilitation Act of 1973, as amended. For example, the Fair Housing Act requires that certain residential structures having four or more multi-family dwelling units, regardless of whether they are privately owned or federally assisted, include certain features of accessible and adaptable design according to guidelines established by the U.S. Department of Housing and Urban Development (HUD). These laws and the appropriate regulations should be consulted before proceeding with the design and construction of residential facilities.

Residential facilities containing residential dwelling units provided by entities subject to HUD's Section 504 regulations and residential dwelling units covered by Section 233.3 must comply with the technical and scoping requirements in Chapters 1 through 10 included in this document. Section 233 is not a stand-alone section; this section only addresses the minimum number of residential dwelling units within a facility required to comply with Chapter 8. However, residential facilities must also comply with the requirements of this document. For example: Section 206.5.4 requires all doors and doorways providing user passage in residential dwelling units providing mobility features to comply with Section 404; Section 206.7.6 permits platform lifts to be used to connect levels within residential dwelling units providing mobility features; Section 208 provides general scoping for accessible parking and Section 208.2.3.1 specifies the required number of accessible parking spaces for each residential dwelling unit providing mobility features; Section 228.2 requires mail boxes to be within reach ranges when they serve residential dwelling units providing mobility features; play areas are addressed in Section 240; and swimming pools are addressed in Section 242. There are special provisions applicable to facilities containing residential dwelling units at: Exception 3 to 202.3; Exception to 202.4; 203.8; and Exception 4 to 206.2.3.

233.2 Residential Dwelling Units Provided by Entities Subject to HUD Section 504 Regulations. Where *facilities with residential dwelling units* are provided by entities subject to regulations issued by the Department of Housing and Urban Development (HUD) under Section 504 of the Rehabilitation Act

of 1973, as amended, such entities shall provide *residential dwelling units* with mobility features complying with 809.2 through 809.4 in a number required by the applicable HUD regulations. *Residential dwelling units* required to provide mobility features complying with 809.2 through 809.4 shall be on an *accessible* route as required by 206. In addition, such entities shall provide *residential dwelling units* with communication features complying with 809.5 in a number required by the applicable HUD regulations. Entities subject to 233.2 shall not be required to comply with 233.3.

Advisory 233.2 Residential Dwelling Units Provided by Entities Subject to HUD Section 504 Regulations. Section 233.2 requires that entities subject to HUD's regulations implementing Section 504 of the Rehabilitation Act of 1973, as amended, provide residential dwelling units containing mobility features and residential dwelling units containing communication features complying with these regulations in a number specified in HUD's Section 504 regulations. Further, the residential dwelling units provided must be dispersed according to HUD's Section 504 criteria. In addition, Section 233.2 defers to HUD the specification of criteria by which the technical requirements of this document will apply to alterations of existing facilities subject to HUD's Section 504 regulations.

233.3 Residential Dwelling Units Provided by Entities Not Subject to HUD Section 504 Regulations. *Facilities* with *residential dwelling units* provided by entities not subject to regulations issued by the Department of Housing and Urban Development (HUD) under Section 504 of the Rehabilitation Act of 1973, as amended, shall comply with 233.3.

233.3.1 Minimum Number: New Construction. Newly constructed *facilities* with *residential dwelling units* shall comply with 233.3.1.

EXCEPTION: Where *facilities* contain 15 or fewer *residential dwelling units*, the requirements of 233.3.1.1 and 233.3.1.2 shall apply to the total number of *residential dwelling units* that are constructed under a single contract, or are developed as a whole, whether or not located on a common *site*.

233.3.1.1 Residential Dwelling Units with Mobility Features. In *facilities* with *residential dwelling units*, at least 5 percent, but no fewer than one unit, of the total number of *residential dwelling units* shall provide mobility features complying with 809.2 through 809.4 and shall be on an *accessible* route as required by 206.

233.3.1.2 Residential Dwelling Units with Communication Features. In *facilities* with *residential dwelling units*, at least 2 percent, but no fewer than one unit, of the total number of *residential dwelling units* shall provide communication features complying with 809.5.

233.3.2 Residential Dwelling Units for Sale. *Residential dwelling units* offered for sale shall provide *accessible* features to the extent required by regulations issued by Federal agencies under the Americans with Disabilities Act or Section 504 of the Rehabilitation Act of 1973, as amended. **[See additional requirements at 28 CFR 35.151(j), p. 13.]**

Advisory 233.3.2 Residential Dwelling Units for Sale. A public entity that conducts a program to build housing for purchase by individual home buyers must provide access according to the requirements of the ADA regulations and a program receiving Federal financial assistance must comply with the applicable Section 504 regulation.

233.3.3 Additions. Where an *addition* to an existing *building* results in an increase in the number of *residential dwelling units*, the requirements of 233.3.1 shall apply only to the *residential dwelling units* that are *added* until the total number of *residential dwelling units* complies with the minimum number required by 233.3.1. *Residential dwelling units* required to comply with 233.3.1.1 shall be on an *accessible* route as required by 206.

233.3.4 Alterations. *Alterations* shall comply with 233.3.4.

EXCEPTION: Where compliance with 809.2, 809.3, or 809.4 is *technically infeasible*, or where it is *technically infeasible* to provide an *accessible* route to a *residential dwelling unit*, the entity shall be permitted to *alter* or construct a comparable *residential dwelling unit* to comply with 809.2 through 809.4 provided that the minimum number of *residential dwelling units* required by 233.3.1.1 and 233.3.1.2, as applicable, is satisfied.

Advisory 233.3.4 Alterations Exception. A substituted dwelling unit must be comparable to the dwelling unit that is not made accessible. Factors to be considered in comparing one dwelling unit to another should include the number of bedrooms; amenities provided within the dwelling unit; types of common spaces provided within the facility; and location with respect to community resources and services, such as public transportation and civic, recreational, and mercantile facilities.

233.3.4.1 Alterations to Vacated Buildings. Where a *building* is vacated for the purposes of *alteration*, and the *altered building* contains more than 15 *residential dwelling units*, at least 5 percent of the *residential dwelling units* shall comply with 809.2 through 809.4 and shall be on an *accessible* route as required by 206. In addition, at least 2 percent of the *residential dwelling units* shall comply with 809.5.

Advisory 233.3.4.1 Alterations to Vacated Buildings. This provision is intended to apply where a building is vacated with the intent to alter the building. Buildings that are vacated solely for pest control or asbestos removal are not subject to the requirements to provide residential dwelling units with mobility features or communication features.

233.3.4.2 Alterations to Individual Residential Dwelling Units. In individual *residential dwelling units*, where a bathroom or a kitchen is substantially *altered*, and at least one other room is *altered*, the requirements of 233.3.1 shall apply to the *altered residential dwelling units* until the total number of *residential dwelling units* complies with the minimum number required by 233.3.1.1 and 233.3.1.2. *Residential dwelling units* required to comply with 233.3.1.1 shall be on an *accessible* route as required by 206.

EXCEPTION: Where *facilities* contain 15 or fewer *residential dwelling units*, the requirements of 233.3.1.1 and 233.3.1.2 shall apply to the total number of *residential dwelling units* that are *altered* under a single contract, or are developed as a whole, whether or not located on a common *site*.

Advisory 233.3.4.2 Alterations to Individual Residential Dwelling Units. Section 233.3.4.2 uses the terms "substantially altered" and "altered." A substantial alteration to a kitchen or bathroom includes, but is not limited to, alterations that are changes to or rearrangements in the plan configuration, or replacement of cabinetry. Substantial alterations do not include normal maintenance or appliance and fixture replacement, unless such maintenance or replacement requires changes to or rearrangements in the plan configuration, or replacement of cabinetry. The term "alteration" is defined both in Section 106 of these requirements and in the Department of Justice ADA regulations.

233.3.5 Dispersion. *Residential dwelling units* required to provide mobility features complying with 809.2 through 809.4 and *residential dwelling units* required to provide communication features complying with 809.5 shall be dispersed among the various types of *residential dwelling units* in the *facility* and shall provide choices of *residential dwelling units* comparable to, and integrated with, those available to other residents.

EXCEPTION: Where multi-story *residential dwelling units* are one of the types of *residential dwelling units* provided, one-story *residential dwelling units* shall be permitted as a substitute for multi-story *residential dwelling units* where equivalent spaces and amenities are provided in the one-story *residential dwelling unit*.

234 Amusement Rides

234.1 General. *Amusement rides* shall comply with 234.

EXCEPTION: Mobile or portable *amusement rides* shall not be required to comply with 234.

Advisory 234.1 General. These requirements apply generally to newly designed and constructed amusement rides and attractions. A custom designed and constructed ride is new upon its first use, which is the first time amusement park patrons take the ride. With respect to amusement rides purchased from other entities, new refers to the first permanent installation of the ride, whether it is used off the shelf or modified before it is installed. Where amusement rides are moved after several seasons to another area of the park or to another park, the ride would not be considered newly designed or newly constructed.

Some amusement rides and attractions that have unique designs and features are not addressed by these requirements. In those situations, these requirements are to be applied to the extent possible. An example of an amusement ride not specifically addressed by these requirements includes "virtual reality" rides where the device does not move through a fixed course within a defined area. An accessible route must be provided to these rides. Where an attraction or ride has unique features for which there are no applicable scoping provisions, then a reasonable number, but at least one, of the features must be located on an accessible route. Where there are appropriate technical provisions, they must be applied to the elements that are covered by the scoping provisions.

Advisory 234.1 General Exception. Mobile or temporary rides are those set up for short periods of time such as traveling carnivals, State and county fairs, and festivals. The amusement rides that are covered by 234.1 are ones that are not regularly assembled and disassembled.

234.2 Load and Unload Areas. Load and unload areas serving *amusement rides* shall comply with 1002.3.

234.3 Minimum Number. *Amusement rides* shall provide at least one *wheelchair space* complying with 1002.4, or at least one *amusement ride seat* designed for transfer complying with 1002.5, or at least one *transfer device* complying with 1002.6.

EXCEPTIONS: 1. *Amusement rides* that are controlled or operated by the rider shall not be required to comply with 234.3.

2. *Amusement rides* designed primarily for children, where children are assisted on and off the ride by an adult, shall not be required to comply with 234.3.

3. *Amusement rides* that do not provide *amusement ride seats* shall not be required to comply with 234.3.

Advisory 234.3 Minimum Number Exceptions 1 through 3. Amusement rides controlled or operated by the rider, designed for children, or rides without ride seats are not required to comply with 234.3. These rides are not exempt from the other provisions in 234 requiring an accessible route to the load and unload areas and to the ride. The exception does not apply to those rides where patrons may cause the ride to make incidental movements, but where the patron otherwise has no control over the ride.

Advisory 234.3 Minimum Number Exception 2. The exception is limited to those rides designed "primarily" for children, where children are assisted on and off the ride by an adult. This exception is limited to those rides designed for children and not for the occasional adult user. An accessible route to and turning space in the load and unload area will provide access for adults and family members assisting children on and off these rides.

234.4 Existing Amusement Rides. Where existing *amusement rides* are *altered*, the *alteration* shall comply with 234.4.

Advisory 234.4 Existing Amusement Rides. Routine maintenance, painting, and changing of theme boards are examples of activities that do not constitute an alteration subject to this section.

234.4.1 Load and Unload Areas. Where load and unload areas serving existing *amusement rides* are newly designed and constructed, the load and unload areas shall comply with 1002.3.

234.4.2 Minimum Number. Where the structural or operational characteristics of an *amusement ride* are *altered* to the extent that the *amusement ride's* performance differs from that specified by the manufacturer or the original design, the *amusement ride* shall comply with 234.3.

235 Recreational Boating Facilities

235.1 General. Recreational boating *facilities* shall comply with 235.

235.2 Boat Slips. *Boat slips* complying with 1003.3.1 shall be provided in accordance with Table 235.2. Where the number of *boat slips* is not identified, each 40 feet (12 m) of *boat slip* edge provided along the perimeter of the pier shall be counted as one *boat slip* for the purpose of this section.

Table 235.2 Boat Slips

Total Number of Boat Slips Provided in Facility	Minimum Number of Required Accessible Boat Slips
1 to 25	1
26 to 50	2
51 to 100	3
101 to 150	4
151 to 300	5
301 to 400	6
401 to 500	7
501 to 600	8
601 to 700	9
701 to 800	10
801 to 900	11
901 to 1000	12
1001 and over	12, plus 1 for every 100, or fraction thereof, over 1000

Advisory 235.2 Boat Slips. The requirement for boat slips also applies to piers where boat slips are not demarcated. For example, a single pier 25 feet (7620 mm) long and 5 feet (1525 mm) wide (the minimum width specified by Section 1003.3) allows boats to moor on three sides. Because the number of boat slips is not demarcated, the total length of boat slip edge (55 feet, 17 m) must be used to determine the number of boat slips provided (two). This number is based on the specification in Section 235.2 that each 40 feet (12 m) of boat slip edge, or fraction thereof, counts as one boat slip. In this example, Table 235.2 would require one boat slip to be accessible.

235.2.1 Dispersion. *Boat slips* complying with 1003.3.1 shall be dispersed throughout the various types of *boat slips* provided. Where the minimum number of *boat slips* required to comply with 1003.3.1 has been met, no further dispersion shall be required.

Advisory 235.2.1 Dispersion. Types of boat slips are based on the size of the boat slips; whether single berths or double berths, shallow water or deep water, transient or longer-term lease, covered or uncovered; and whether slips are equipped with features such as telephone, water, electricity or cable connections. The term "boat slip" is intended to cover any pier area other than launch ramp boarding piers where recreational boats are moored for purposes of berthing, embarking, or disembarking. For example, a fuel pier may contain boat slips, and this type of short term slip would be included in determining compliance with 235.2.

235.3 Boarding Piers at Boat Launch Ramps. Where *boarding piers* are provided at *boat launch ramps*, at least 5 percent, but no fewer than one, of the *boarding piers* shall comply with 1003.3.2.

236 Exercise Machines and Equipment

236.1 General. At least one of each type of exercise machine and equipment shall comply with 1004.

Advisory 236.1 General. Most strength training equipment and machines are considered different types. Where operators provide a biceps curl machine and cable-cross-over machine, both machines are required to meet the provisions in this section, even though an individual may be able to work on their biceps through both types of equipment.

Similarly, there are many types of cardiovascular exercise machines, such as stationary bicycles, rowing machines, stair climbers, and treadmills. Each machine provides a cardiovascular exercise and is considered a different type for purposes of these requirements.

237 Fishing Piers and Platforms

237.1 General. Fishing piers and platforms shall comply with 1005.

238 Golf Facilities

238.1 General. Golf *facilities* shall comply with 238.

238.2 Golf Courses. Golf courses shall comply with 238.2.

238.2.1 Teeing Grounds. Where one *teeing ground* is provided for a hole, the *teeing ground* shall be designed and constructed so that a golf car can enter and exit the *teeing ground*. Where two *teeing grounds* are provided for a hole, the forward *teeing ground* shall be designed and constructed so that a golf car can enter and exit the *teeing ground*. Where three or more *teeing grounds* are provided for a hole, at least two *teeing grounds*, including the forward *teeing ground*, shall be designed and constructed so that a golf car can enter and exit each *teeing ground*.

EXCEPTION: In existing golf courses, the forward *teeing ground* shall not be required to be one of the *teeing grounds* on a hole designed and constructed so that a golf car can enter and exit the *teeing ground* where compliance is not feasible due to terrain.

238.2.2 Putting Greens. Putting greens shall be designed and constructed so that a golf car can enter and exit the putting green.

238.2.3 Weather Shelters. Where provided, weather shelters shall be designed and constructed so that a golf car can enter and exit the weather shelter and shall comply with 1006.4.

238.3 Practice Putting Greens, Practice Teeing Grounds, and Teeing Stations at Driving Ranges. At least 5 percent, but no fewer than one, of practice putting greens, practice *teeing grounds*, and teeing stations at driving ranges shall be designed and constructed so that a golf car can enter and exit the practice putting greens, practice *teeing grounds*, and teeing stations at driving ranges.

239 Miniature Golf Facilities

239.1 General. Miniature golf *facilities* shall comply with 239.

239.2 Minimum Number. At least 50 percent of holes on miniature golf courses shall comply with 1007.3.

Advisory 239.2 Minimum Number. Where possible, providing access to all holes on a miniature golf course is recommended. If a course is designed with the minimum 50 percent accessible holes, designers or operators are encouraged to select holes which provide for an equivalent experience to the maximum extent possible.

239.3 Miniature Golf Course Configuration. Miniature golf courses shall be configured so that the holes complying with 1007.3 are consecutive. Miniature golf courses shall provide an *accessible* route from the last hole complying with 1007.3 to the course *entrance* or exit without requiring travel through any other holes on the course.

EXCEPTION: One break in the sequence of consecutive holes shall be permitted provided that the last hole on the miniature golf course is the last hole in the sequence.

Advisory 239.3 Miniature Golf Course Configuration. Where only the minimum 50 percent of the holes are accessible, an accessible route from the last accessible hole to the course exit or entrance must not require travel back through other holes. In some cases, this may require an additional accessible route. Other options include increasing the number of accessible holes in a way that limits the distance needed to connect the last accessible hole with the course exit or entrance.

240 Play Areas

240.1 General. *Play areas* for children ages 2 and over shall comply with 240. Where separate *play areas* are provided within a *site* for specific age groups, each *play area* shall comply with 240.

EXCEPTIONS: 1. *Play areas* located in family child care *facilities* where the proprietor actually resides shall not be required to comply with 240.

2. In existing *play areas*, where *play components* are relocated for the purposes of creating safe *use zones* and the ground surface is not *altered* or extended for more than one *use zone*, the *play area* shall not be required to comply with 240.

3. *Amusement attractions* shall not be required to comply with 240.
4. Where *play components* are *altered* and the ground surface is not *altered*, the ground surface shall not be required to comply with 1008.2.6 unless required by 202.4.

Advisory 240.1 General. Play areas may be located on exterior sites or within a building. Where separate play areas are provided within a site for children in specified age groups (e.g., preschool (ages 2 to 5) and school age (ages 5 to 12)), each play area must comply with this section. Where play areas are provided for the same age group on a site but are geographically separated (e.g., one is located next to a picnic area and another is located next to a softball field), they are considered separate play areas and each play area must comply with this section.

240.1.1 Additions. Where *play areas* are designed and constructed in phases, the requirements of 240 shall apply to each successive *addition* so that when the *addition* is completed, the entire *play area* complies with all the applicable requirements of 240.

Advisory 240.1.1 Additions. These requirements are to be applied so that when each successive addition is completed, the entire play area complies with all applicable provisions. For example, a play area is built in two phases. In the first phase, there are 10 elevated play components and 10 elevated play components are added in the second phase for a total of 20 elevated play components in the play area. When the first phase was completed, at least 5 elevated play components, including at least 3 different types, were to be provided on an accessible route. When the second phase is completed, at least 10 elevated play components must be located on an accessible route, and at least 7 ground level play components, including 4 different types, must be provided on an accessible route. At the time the second phase is complete, ramps must be used to connect at least 5 of the elevated play components and transfer systems are permitted to be used to connect the rest of the elevated play components required to be located on an accessible route.

240.2 Play Components. Where provided, *play components* shall comply with 240.2.

240.2.1 Ground Level Play Components. *Ground level play components* shall be provided in the number and types required by 240.2.1. *Ground level play components* that are provided to comply with 240.2.1.1 shall be permitted to satisfy the additional number required by 240.2.1.2 if the minimum required types of *play components* are satisfied. Where two or more required *ground level play components* are provided, they shall be dispersed throughout the *play area* and integrated with other *play components*.

Advisory 240.2.1 Ground Level Play Components. Examples of ground level play components may include spring rockers, swings, diggers, and stand-alone slides. When distinguishing between the different types of ground level play components, consider the general experience provided by the play component. Examples of different types of experiences include, but are not limited to, rocking, swinging, climbing, spinning, and sliding.

Advisory 240.2.1 Ground Level Play Components (Continued). A spiral slide may provide a slightly different experience from a straight slide, but sliding is the general experience and therefore a spiral slide is not considered a different type of play component from a straight slide.

Ground level play components accessed by children with disabilities must be integrated into the play area. Designers should consider the optimal layout of ground level play components accessed by children with disabilities to foster interaction and socialization among all children. Grouping all ground level play components accessed by children with disabilities in one location is not considered integrated.

Where a stand-alone slide is provided, an accessible route must connect the base of the stairs at the entry point to the exit point of the slide. A ramp or transfer system to the top of the slide is not required. Where a sand box is provided, an accessible route must connect to the border of the sand box. Accessibility to the sand box would be enhanced by providing a transfer system into the sand or by providing a raised sand table with knee clearance complying with 1008.4.3.

Ramps are preferred over transfer systems since not all children who use wheelchairs or other mobility devices may be able to use, or may choose not to use, transfer systems. Where ramps connect elevated play components, the maximum rise of any ramp run is limited to 12 inches (305 mm). Where possible, designers and operators are encouraged to provide ramps with a slope less than the 1:12 maximum. Berms or sculpted dirt may be used to provide elevation and may be part of an accessible route to composite play structures.

Platform lifts are permitted as a part of an accessible route. Because lifts must be independently operable, operators should carefully consider the appropriateness of their use in unsupervised settings.

240.2.1.1 Minimum Number and Types. Where *ground level play components* are provided, at least one of each type shall be on an *accessible* route and shall comply with 1008.4.

240.2.1.2 Additional Number and Types. Where *elevated play components* are provided, *ground level play components* shall be provided in accordance with Table 240.2.1.2 and shall comply with 1008.4.

EXCEPTION: If at least 50 percent of the *elevated play components* are connected by a *ramp* and at least 3 of the *elevated play components* connected by the *ramp* are different types of *play components*, the *play area* shall not be required to comply with 240.2.1.2.

Table 240.2.1.2 Number and Types of Ground Level Play Components Required to be on Accessible Routes

Number of Elevated Play Components Provided	Minimum Number of Ground Level Play Components Required to be on an Accessible Route	Minimum Number of Different Types of Ground Level Play Components Required to be on an Accessible Route
1	Not applicable	Not applicable
2 to 4	1	1
5 to 7	2	2
8 to 10	3	3
11 to 13	4	3
14 to 16	5	3
17 to 19	6	3
20 to 22	7	4
23 to 25	8	4
26 and over	8, plus 1 for each additional 3, or fraction thereof, over 25	5

Advisory 240.2.1.2 Additional Number and Types. Where a large play area includes two or more composite play structures designed for the same age group, the total number of elevated play components on all the composite play structures must be added to determine the additional number and types of ground level play components that must be provided on an accessible route.

240.2.2 Elevated Play Components. Where *elevated play components* are provided, at least 50 percent shall be on an *accessible* route and shall comply with 1008.4.

Advisory 240.2.2 Elevated Play Components. A double or triple slide that is part of a composite play structure is one elevated play component. For purposes of this section, ramps, transfer systems, steps, decks, and roofs are not considered elevated play components. Although socialization and pretend play can occur on these elements, they are not primarily intended for play.

Some play components that are attached to a composite play structure can be approached or exited at the ground level or above grade from a platform or deck. For example, a climber attached to a composite play structure can be approached or exited at the ground level or above grade from a platform or deck on a composite play structure.

Advisory 240.2.2 Elevated Play Components (Continued). Play components that are attached to a composite play structure and can be approached from a platform or deck (e.g., climbers and overhead play components) are considered elevated play components. These play components are not considered ground level play components and do not count toward the requirements in 240.2.1.2 regarding the number of ground level play components that must be located on an accessible route.

241 Saunas and Steam Rooms

241 General. Where provided, saunas and steam rooms shall comply with 612.

EXCEPTION: Where saunas or steam rooms are clustered at a single location, no more than 5 percent of the saunas and steam rooms, but no fewer than one, of each type in each cluster shall be required to comply with 612.

242 Swimming Pools, Wading Pools, and Spas

242.1 General. Swimming pools, wading pools, and spas shall comply with 242.

242.2 Swimming Pools. At least two *accessible* means of entry shall be provided for swimming pools. *Accessible* means of entry shall be swimming pool lifts complying with 1009.2; sloped entries complying with 1009.3; transfer walls complying with 1009.4; transfer systems complying with 1009.5; and pool stairs complying with 1009.6. At least one *accessible* means of entry provided shall comply with 1009.2 or 1009.3.

EXCEPTIONS: 1. Where a swimming pool has less than 300 linear feet (91 m) of swimming pool wall, no more than one *accessible* means of entry shall be required provided that the *accessible* means of entry is a swimming pool lift complying with 1009.2 or sloped entry complying with 1009.3. 2. Wave action pools, leisure rivers, sand bottom pools, and other pools where user access is limited to one area shall not be required to provide more than one *accessible* means of entry provided that the *accessible* means of entry is a swimming pool lift complying with 1009.2, a sloped entry complying with 1009.3, or a transfer system complying with 1009.5. 3. *Catch pools* shall not be required to provide an *accessible* means of entry provided that the *catch pool* edge is on an *accessible* route.

Advisory 242.2 Swimming Pools. Where more than one means of access is provided into the water, it is recommended that the means be different. Providing different means of access will better serve the varying needs of people with disabilities in getting into and out of a swimming pool. It is also recommended that where two or more means of access are provided, they not be provided in the same location in the pool. Different locations will provide increased options for entry and exit, especially in larger pools.

Advisory 242.2 Swimming Pools Exception 1. Pool walls at diving areas and areas along pool walls where there is no pool entry because of landscaping or adjacent structures are to be counted when determining the number of accessible means of entry required.

242.3 Wading Pools. At least one *accessible* means of entry shall be provided for wading pools. *Accessible* means of entry shall comply with sloped entries complying with 1009.3.

242.4 Spas. At least one *accessible* means of entry shall be provided for spas. *Accessible* means of entry shall comply with swimming pool lifts complying with 1009.2; transfer walls complying with 1009.4; or transfer systems complying with 1009.5.

EXCEPTION: Where spas are provided in a cluster, no more than 5 percent, but no fewer than one, spa in each cluster shall be required to comply with 242.4.

243 Shooting Facilities with Firing Positions

243.1 General. Where shooting *facilities* with firing positions are designed and constructed at a *site*, at least 5 percent, but no fewer than one, of each type of firing position shall comply with 1010.

CHAPTER 3: BUILDING BLOCKS

301 General

301.1 Scope. The provisions of Chapter 3 shall apply where required by Chapter 2 or where referenced by a requirement in this document.

302 Floor or Ground Surfaces

302.1 General. Floor and ground surfaces shall be stable, firm, and slip resistant and shall comply with 302.

EXCEPTIONS: 1. Within animal containment areas, floor and ground surfaces shall not be required to be stable, firm, and slip resistant.

2. *Areas of sport activity* shall not be required to comply with 302.

Advisory 302.1 General. A stable surface is one that remains unchanged by contaminants or applied force, so that when the contaminant or force is removed, the surface returns to its original condition. A firm surface resists deformation by either indentations or particles moving on its surface. A slip-resistant surface provides sufficient frictional counterforce to the forces exerted in walking to permit safe ambulation.

302.2 Carpet. Carpet or carpet tile shall be securely attached and shall have a firm cushion, pad, or backing or no cushion or pad. Carpet or carpet tile shall have a level loop, textured loop, level cut pile, or level cut/uncut pile texture. Pile height shall be $\frac{1}{2}$ inch (13 mm) maximum. Exposed edges of carpet shall be fastened to floor surfaces and shall have trim on the entire length of the exposed edge. Carpet edge trim shall comply with 303.

Advisory 302.2 Carpet. Carpets and permanently affixed mats can significantly increase the amount of force (roll resistance) needed to propel a wheelchair over a surface. The firmer the carpeting and backing, the lower the roll resistance. A pile thickness up to $\frac{1}{2}$ inch (13 mm) (measured to the backing, cushion, or pad) is allowed, although a lower pile provides easier wheelchair maneuvering. If a backing, cushion or pad is used, it must be firm. Preferably, carpet pad should not be used because the soft padding increases roll resistance.




Figure 302.2
Carpet Pile Height

302.3 Openings. Openings in floor or ground surfaces shall not allow passage of a sphere more than $\frac{1}{2}$ inch (13 mm) diameter except as allowed in 407.4.3, 409.4.3, 410.4, 810.5.3 and 810.10. Elongated openings shall be placed so that the long dimension is perpendicular to the dominant direction of travel.




Figure 302.3
Elongated Openings in Floor or Ground Surfaces

303 Changes in Level

303.1 General. Where changes in level are permitted in floor or ground surfaces, they shall comply with 303.

EXCEPTIONS: 1. Animal containment areas shall not be required to comply with 303.

2. *Areas of sport activity* shall not be required to comply with 303.

303.2 Vertical. Changes in level of $\frac{1}{4}$ inch (6.4 mm) high maximum shall be permitted to be vertical.



Figure 303.2
Vertical Change in Level

303.3 Beveled. Changes in level between $\frac{1}{4}$ inch (6.4 mm) high minimum and $\frac{1}{2}$ inch (13 mm) high maximum shall be beveled with a slope not steeper than 1:2.

Advisory 303.3 Beveled. A change in level of $\frac{1}{2}$ inch (13 mm) is permitted to be $\frac{1}{4}$ inch (6.4 mm) vertical plus $\frac{1}{4}$ inch (6.4 mm) beveled. However, in no case may the combined change in level exceed $\frac{1}{2}$ inch (13 mm). Changes in level exceeding $\frac{1}{2}$ inch (13 mm) must comply with 405 (Ramps) or 406 (Curb Ramps).




Figure 303.3
Beveled Change in Level

303.4 Ramps. Changes in level greater than $\frac{1}{2}$ inch (13 mm) high shall be *ramped*, and shall comply with 405 or 406.

304 Turning Space

304.1 General. Turning *space* shall comply with 304.

304.2 Floor or Ground Surfaces. Floor or ground surfaces of a turning *space* shall comply with 302. Changes in level are not permitted.

EXCEPTION: Slopes not steeper than 1:48 shall be permitted.

Advisory 304.2 Floor or Ground Surface Exception. As used in this section, the phrase "changes in level" refers to surfaces with slopes and to surfaces with abrupt rise exceeding that permitted in Section 303.3. Such changes in level are prohibited in required clear floor and ground spaces, turning spaces, and in similar spaces where people using wheelchairs and other mobility devices must park their mobility aids such as in wheelchair spaces, or maneuver to use elements such as at doors, fixtures, and telephones. The exception permits slopes not steeper than 1:48.

304.3 Size. Turning *space* shall comply with 304.3.1 or 304.3.2.

304.3.1 Circular Space. The turning *space* shall be a *space* of 60 inches (1525 mm) diameter minimum. The *space* shall be permitted to include knee and toe clearance complying with 306.

304.3.2 T-Shaped Space. The turning *space* shall be a T-shaped *space* within a 60 inch (1525 mm) square minimum with arms and base 36 inches (915 mm) wide minimum. Each arm of the T shall be clear of obstructions 12 inches (305 mm) minimum in each direction and the base shall be clear of

obstructions 24 inches (610 mm) minimum. The *space* shall be permitted to include knee and toe clearance complying with 306 only at the end of either the base or one arm.




Figure 304.3.2
T-Shaped Turning Space

304.4 Door Swing. Doors shall be permitted to swing into turning *spaces*.

305 Clear Floor or Ground Space

305.1 General. Clear floor or ground *space* shall comply with 305.

305.2 Floor or Ground Surfaces. Floor or ground surfaces of a clear floor or ground *space* shall comply with 302. Changes in level are not permitted.

EXCEPTION: Slopes not steeper than 1:48 shall be permitted.

305.3 Size. The clear floor or ground *space* shall be 30 inches (760 mm) minimum by 48 inches (1220 mm) minimum.




Figure 305.3
Clear Floor or Ground Space

305.4 Knee and Toe Clearance. Unless otherwise specified, clear floor or ground *space* shall be permitted to include knee and toe clearance complying with 306.

305.5 Position. Unless otherwise specified, clear floor or ground *space* shall be positioned for either forward or parallel approach to an *element*.




Figure 305.5
Position of Clear Floor or Ground Space

305.6 Approach. One full unobstructed side of the clear floor or ground *space* shall adjoin an *accessible* route or adjoin another clear floor or ground *space*.

305.7 Maneuvering Clearance. Where a clear floor or ground *space* is located in an alcove or otherwise confined on all or part of three sides, additional maneuvering clearance shall be provided in accordance with 305.7.1 and 305.7.2.

305.7.1 Forward Approach. Alcoves shall be 36 inches (915 mm) wide minimum where the depth exceeds 24 inches (610 mm).




Figure 305.7.1
Maneuvering Clearance in an Alcove, Forward Approach

305.7.2 Parallel Approach. Alcoves shall be 60 inches (1525 mm) wide minimum where the depth exceeds 15 inches (380 mm).




Figure 305.7.2
Maneuvering Clearance in an Alcove, Parallel Approach

306 Knee and Toe Clearance

306.1 General. Where *space* beneath an *element* is included as part of clear floor or ground *space* or turning *space*, the *space* shall comply with 306. Additional *space* shall not be prohibited beneath an *element* but shall not be considered as part of the clear floor or ground *space* or turning *space*.

Advisory 306.1 General. Clearances are measured in relation to the usable clear floor space, not necessarily to the vertical support for an element. When determining clearance under an object for required turning or maneuvering space, care should be taken to ensure the space is clear of any obstructions.

306.2 Toe Clearance.

306.2.1 General. Space under an *element* between the finish floor or ground and 9 inches (230 mm) above the finish floor or ground shall be considered toe clearance and shall comply with 306.2.

306.2.2 Maximum Depth. Toe clearance shall extend 25 inches (635 mm) maximum under an *element*.

306.2.3 Minimum Required Depth. Where toe clearance is required at an *element* as part of a clear floor *space*, the toe clearance shall extend 17 inches (430 mm) minimum under the *element*.

306.2.4 Additional Clearance. Space extending greater than 6 inches (150 mm) beyond the available knee clearance at 9 inches (230 mm) above the finish floor or ground shall not be considered toe clearance.

306.2.5 Width. Toe clearance shall be 30 inches (760 mm) wide minimum.




Figure 306.2
Toe Clearance

306.3 Knee Clearance.

306.3.1 General. Space under an *element* between 9 inches (230 mm) and 27 inches (685 mm) above the finish floor or ground shall be considered knee clearance and shall comply with 306.3.

306.3.2 Maximum Depth. Knee clearance shall extend 25 inches (635 mm) maximum under an *element* at 9 inches (230 mm) above the finish floor or ground.

306.3.3 Minimum Required Depth. Where knee clearance is required under an *element* as part of a clear floor *space*, the knee clearance shall be 11 inches (280 mm) deep minimum at 9 inches (230 mm) above the finish floor or ground, and 8 inches (205 mm) deep minimum at 27 inches (685 mm) above the finish floor or ground.

306.3.4 Clearance Reduction. Between 9 inches (230 mm) and 27 inches (685 mm) above the finish floor or ground, the knee clearance shall be permitted to reduce at a rate of 1 inch (25 mm) in depth for each 6 inches (150 mm) in height.

306.3.5 Width. Knee clearance shall be 30 inches (760 mm) wide minimum.




Figure 306.3
Knee Clearance

307 Protruding Objects

307.1 General. Protruding objects shall comply with 307.

307.2 Protrusion Limits. Objects with leading edges more than 27 inches (685 mm) and not more than 80 inches (2030 mm) above the finish floor or ground shall protrude 4 inches (100 mm) maximum horizontally into the *circulation path*.

EXCEPTION: Handrails shall be permitted to protrude 4½ inches (115 mm) maximum.

Advisory 307.2 Protrusion Limits. When a cane is used and the element is in the detectable range, it gives a person sufficient time to detect the element with the cane before there is body contact. Elements located on circulation paths, including operable elements, must comply with requirements for protruding objects. For example, awnings and their supporting structures cannot reduce the minimum required vertical clearance. Similarly, casement windows, when open, cannot encroach more than 4 inches (100 mm) into circulation paths above 27 inches (685 mm).




Figure 307.2
Limits of Protruding Objects

307.3 Post-Mounted Objects. Free-standing objects mounted on posts or pylons shall overhang *circulation paths* 12 inches (305 mm) maximum when located 27 inches (685 mm) minimum and 80 inches (2030 mm) maximum above the finish floor or ground. Where a sign or other obstruction is mounted between posts or pylons and the clear distance between the posts or pylons is greater than 12 inches (305 mm), the lowest edge of such sign or obstruction shall be 27 inches (685 mm) maximum or 80 inches (2030 mm) minimum above the finish floor or ground.

EXCEPTION: The sloping portions of handrails serving stairs and *ramps* shall not be required to comply with 307.3.




Figure 307.3
Post-Mounted Protruding Objects

307.4 Vertical Clearance. Vertical clearance shall be 80 inches (2030 mm) high minimum. Guardrails or other barriers shall be provided where the vertical clearance is less than 80 inches (2030 mm) high. The leading edge of such guardrail or barrier shall be located 27 inches (685 mm) maximum above the finish floor or ground.

EXCEPTION: Door closers and door stops shall be permitted to be 78 inches (1980 mm) minimum above the finish floor or ground.




Figure 307.4
Vertical Clearance

307.5 Required Clear Width. Protruding objects shall not reduce the clear width required for *accessible* routes.

308 Reach Ranges

308.1 General. Reach ranges shall comply with 308.

Advisory 308.1 General. The following table provides guidance on reach ranges for children according to age where building elements such as coat hooks, lockers, or operable parts are designed for use primarily by children. These dimensions apply to either forward or side reaches. Accessible elements and operable parts designed for adult use or children over age 12 can be located outside these ranges but must be within the adult reach ranges required by 308.

Children's Reach Ranges			
Forward or Side Reach	Ages 3 and 4	Ages 5 through 8	Ages 9 through 12
High (maximum)	36 in (915 mm)	40 in (1015 mm)	44 in (1120 mm)
Low (minimum)	20 in (510 mm)	18 in (455 mm)	16 in (405 mm)

308.2 Forward Reach.

308.2.1 Unobstructed. Where a forward reach is unobstructed, the high forward reach shall be 48 inches (1220 mm) maximum and the low forward reach shall be 15 inches (380 mm) minimum above the finish floor or ground.




Figure 308.2.1
Unobstructed Forward Reach

308.2.2 Obstructed High Reach. Where a high forward reach is over an obstruction, the clear floor space shall extend beneath the *element* for a distance not less than the required reach depth over the obstruction. The high forward reach shall be 48 inches (1220 mm) maximum where the reach depth is 20 inches (510 mm) maximum. Where the reach depth exceeds 20 inches (510 mm), the high forward reach shall be 44 inches (1120 mm) maximum and the reach depth shall be 25 inches (635 mm) maximum.




Figure 308.2.2
Obstructed High Forward Reach

308.3 Side Reach.

308.3.1 Unobstructed. Where a clear floor or ground space allows a parallel approach to an *element* and the side reach is unobstructed, the high side reach shall be 48 inches (1220 mm)

maximum and the low side reach shall be 15 inches (380 mm) minimum above the finish floor or ground.

- EXCEPTIONS:** 1. An obstruction shall be permitted between the clear floor or ground *space* and the *element* where the depth of the obstruction is 10 inches (255 mm) maximum.
2. *Operable parts* of fuel dispensers shall be permitted to be 54 inches (1370 mm) maximum measured from the surface of the *vehicular way* where fuel dispensers are installed on existing curbs.




Figure 308.3.1
Unobstructed Side Reach

308.3.2 Obstructed High Reach. Where a clear floor or ground *space* allows a parallel approach to an *element* and the high side reach is over an obstruction, the height of the obstruction shall be 34 inches (865 mm) maximum and the depth of the obstruction shall be 24 inches (610 mm) maximum. The high side reach shall be 48 inches (1220 mm) maximum for a reach depth of 10 inches (255 mm) maximum. Where the reach depth exceeds 10 inches (255 mm), the high side reach shall be 46 inches (1170 mm) maximum for a reach depth of 24 inches (610 mm) maximum.

- EXCEPTIONS:** 1. The top of washing machines and clothes dryers shall be permitted to be 36 inches (915 mm) maximum above the finish floor.
2. *Operable parts* of fuel dispensers shall be permitted to be 54 inches (1370 mm) maximum measured from the surface of the *vehicular way* where fuel dispensers are installed on existing curbs.




Figure 308.3.2
Obstructed High Side Reach

309 Operable Parts

309.1 General. *Operable parts* shall comply with 309.

309.2 Clear Floor Space. A clear floor or ground *space* complying with 305 shall be provided.

309.3 Height. *Operable parts* shall be placed within one or more of the reach ranges specified in 308.

309.4 Operation. *Operable parts* shall be operable with one hand and shall not require tight grasping, pinching, or twisting of the wrist. The force required to activate *operable parts* shall be 5 pounds (22.2 N) maximum.

EXCEPTION: Gas pump nozzles shall not be required to provide *operable parts* that have an activating force of 5 pounds (22.2 N) maximum.

CHAPTER 4: ACCESSIBLE ROUTES

401 General

401.1 Scope. The provisions of Chapter 4 shall apply where required by Chapter 2 or where referenced by a requirement in this document.

402 Accessible Routes

402.1 General. *Accessible* routes shall comply with 402.

402.2 Components. *Accessible* routes shall consist of one or more of the following components: walking surfaces with a *running slope* not steeper than 1:20, doorways, *ramps*, *curb ramps* excluding the flared sides, elevators, and platform lifts. All components of an *accessible* route shall comply with the applicable requirements of Chapter 4.

Advisory 402.2 Components. Walking surfaces must have running slopes not steeper than 1:20, see 403.3. Other components of accessible routes, such as ramps (405) and curb ramps (406), are permitted to be more steeply sloped.

403 Walking Surfaces

403.1 General. Walking surfaces that are a part of an *accessible* route shall comply with 403.

403.2 Floor or Ground Surface. Floor or ground surfaces shall comply with 302.

403.3 Slope. The *running slope* of walking surfaces shall not be steeper than 1:20. The *cross slope* of walking surfaces shall not be steeper than 1:48.

403.4 Changes in Level. Changes in level shall comply with 303.

403.5 Clearances. Walking surfaces shall provide clearances complying with 403.5.

EXCEPTION: Within *employee work areas*, clearances on *common use circulation paths* shall be permitted to be decreased by *work area equipment* provided that the decrease is essential to the function of the work being performed.

403.5.1 Clear Width. Except as provided in 403.5.2 and 403.5.3, the clear width of walking surfaces shall be 36 inches (915 mm) minimum.

EXCEPTION: The clear width shall be permitted to be reduced to 32 inches (815 mm) minimum for a length of 24 inches (610 mm) maximum provided that reduced width segments are separated by segments that are 48 inches (1220 mm) long minimum and 36 inches (915 mm) wide minimum.




Figure 403.5.1
Clear Width of an Accessible Route

403.5.2 Clear Width at Turn. Where the *accessible* route makes a 180 degree turn around an *element* which is less than 48 inches (1220 mm) wide, clear width shall be 42 inches (1065 mm) minimum approaching the turn, 48 inches (1220 mm) minimum at the turn and 42 inches (1065 mm) minimum leaving the turn.

EXCEPTION: Where the clear width at the turn is 60 inches (1525 mm) minimum compliance with 403.5.2 shall not be required.




Figure 403.5.2
Clear Width at Turn

403.5.3 Passing Spaces. An *accessible* route with a clear width less than 60 inches (1525 mm) shall provide passing *spaces* at intervals of 200 feet (61 m) maximum. Passing *spaces* shall be either: a *space* 60 inches (1525 mm) minimum by 60 inches (1525 mm) minimum; or, an intersection of two walking surfaces providing a T-shaped *space* complying with 304.3.2 where the base and arms of the T-shaped *space* extend 48 inches (1220 mm) minimum beyond the intersection.

403.6 Handrails. Where handrails are provided along walking surfaces with *running slopes* not steeper than 1:20 they shall comply with 505.

Advisory 403.6 Handrails. Handrails provided in elevator cabs and platform lifts are not required to comply with the requirements for handrails on walking surfaces.

404 Doors, Doorways, and Gates

404.1 General. Doors, doorways, and gates that are part of an *accessible* route shall comply with 404.

EXCEPTION: Doors, doorways, and gates designed to be operated only by security personnel shall not be required to comply with 404.2.7, 404.2.8, 404.2.9, 404.3.2 and 404.3.4 through 404.3.7.

Advisory 404.1 General Exception. Security personnel must have sole control of doors that are eligible for the Exception at 404.1. It would not be acceptable for security personnel to operate the doors for people with disabilities while allowing others to have independent access.

404.2 Manual Doors, Doorways, and Manual Gates. Manual doors and doorways and manual gates intended for user passage shall comply with 404.2.

404.2.1 Revolving Doors, Gates, and Turnstiles. Revolving doors, revolving gates, and turnstiles shall not be part of an *accessible* route.

404.2.2 Double-Leaf Doors and Gates. At least one of the active leaves of doorways with two leaves shall comply with 404.2.3 and 404.2.4.

404.2.3 Clear Width. Door openings shall provide a clear width of 32 inches (815 mm) minimum. Clear openings of doorways with swinging doors shall be measured between the face of the door and the stop, with the door open 90 degrees. Openings more than 24 inches (610 mm) deep shall provide a clear opening of 36 inches (915 mm) minimum. There shall be no projections into the required clear opening width lower than 34 inches (865 mm) above the finish floor or ground. Projections into the clear opening width between 34 inches (865 mm) and 80 inches (2030 mm) above the finish floor or ground shall not exceed 4 inches (100 mm).

EXCEPTIONS: 1. In *alterations*, a projection of 5/8 inch (16 mm) maximum into the required clear width shall be permitted for the latch side stop.

2. Door closers and door stops shall be permitted to be 78 inches (1980 mm) minimum above the finish floor or ground.




Figure 404.2.3
Clear Width of Doorways

404.2.4 Maneuvering Clearances. Minimum maneuvering clearances at doors and gates shall comply with 404.2.4. Maneuvering clearances shall extend the full width of the doorway and the required latch side or hinge side clearance.

EXCEPTION: Entry doors to hospital patient rooms shall not be required to provide the clearance beyond the latch side of the door.

404.2.4.1 Swinging Doors and Gates. Swinging doors and gates shall have maneuvering clearances complying with Table 404.2.4.1.

Table 404.2.4.1 Maneuvering Clearances at Manual Swinging Doors and Gates

Type of Use		Minimum Maneuvering Clearance	
Approach Direction	Door or Gate Side	Perpendicular to Doorway	Parallel to Doorway (beyond latch side unless noted)
From front	Pull	60 inches (1525 mm)	18 inches (455 mm)
From front	Push	48 inches (1220 mm)	0 inches (0 mm) ¹
From hinge side	Pull	60 inches (1525 mm)	36 inches (915 mm)
From hinge side	Pull	54 inches (1370 mm)	42 inches (1065 mm)
From hinge side	Push	42 inches (1065 mm) ²	22 inches (560 mm) ³
From latch side	Pull	48 inches (1220 mm) ⁴	24 inches (610 mm)
From latch side	Push	42 inches (1065 mm) ⁴	24 inches (610 mm)

1. Add 12 inches (305 mm) if closer and latch are provided.

2. Add 6 inches (150 mm) if closer and latch are provided.

3. Beyond hinge side.

4. Add 6 inches (150 mm) if closer is provided.




Figure 404.2.4.1
Maneuvering Clearances at Manual Swinging Doors and Gates




Figure 404.2.4.1
Maneuvering Clearances at Manual Swinging Doors and Gates

404.2.4.2 Doorways without Doors or Gates, Sliding Doors, and Folding Doors. Doorways less than 36 inches (915 mm) wide without doors or gates, sliding doors, or folding doors shall have maneuvering clearances complying with Table 404.2.4.2.

Table 404.2.4.2 Maneuvering Clearances at Doorways without Doors or Gates, Manual Sliding Doors, and Manual Folding Doors

Approach Direction	Minimum Maneuvering Clearance	
	Perpendicular to Doorway	Parallel to Doorway (beyond stop/latch side unless noted)
From Front	48 inches (1220 mm)	0 inches (0 mm)
From side ¹	42 inches (1065 mm)	0 inches (0 mm)
From pocket/hinge side	42 inches (1065 mm)	22 inches (560 mm) ²
From stop/latch side	42 inches (1065 mm)	24 inches (610 mm)

1. Doorway with no door only.

2. Beyond pocket/hinge side.




Figure 404.2.4.2
Maneuvering Clearances at Doorways without Doors, Sliding Doors, Gates, and Folding Doors

404.2.4.3 Recessed Doors and Gates. Maneuvering clearances for forward approach shall be provided when any obstruction within 18 inches (455 mm) of the latch side of a doorway projects more than 8 inches (205 mm) beyond the face of the door, measured perpendicular to the face of the door or gate.

Advisory 404.2.4.3 Recessed Doors and Gates. A door can be recessed due to wall thickness or because of the placement of casework and other fixed elements adjacent to the doorway. This provision must be applied wherever doors are recessed.




Figure 404.2.4.3
Maneuvering Clearances at Recessed Doors and Gates

404.2.4.4 Floor or Ground Surface. Floor or ground surface within required maneuvering clearances shall comply with 302. Changes in level are not permitted.

- EXCEPTIONS:**
1. Slopes not steeper than 1:48 shall be permitted.
 2. Changes in level at thresholds complying with 404.2.5 shall be permitted.

404.2.5 Thresholds. Thresholds, if provided at doorways, shall be ½ inch (13 mm) high maximum. Raised thresholds and changes in level at doorways shall comply with 302 and 303.

EXCEPTION: Existing or *altered* thresholds ¾ inch (19 mm) high maximum that have a beveled edge on each side with a slope not steeper than 1:2 shall not be required to comply with 404.2.5.

404.2.6 Doors in Series and Gates in Series. The distance between two hinged or pivoted doors in series and gates in series shall be 48 inches (1220 mm) minimum plus the width of doors or gates swinging into the *space*.




Figure 404.2.6
Doors in Series and Gates in Series

404.2.7 Door and Gate Hardware. Handles, pulls, latches, locks, and other *operable parts* on doors and gates shall comply with 309.4. *Operable parts* of such hardware shall be 34 inches (865 mm) minimum and 48 inches (1220 mm) maximum above the finish floor or ground. Where sliding doors are in the fully open position, operating hardware shall be exposed and usable from both sides.

EXCEPTIONS: 1. Existing locks shall be permitted in any location at existing glazed doors without stiles, existing overhead rolling doors or grilles, and similar existing doors or grilles that are designed with locks that are activated only at the top or bottom rail.

2. Access gates in barrier walls and fences protecting pools, spas, and hot tubs shall be permitted to have *operable parts* of the release of latch on self-latching devices at 54 inches (1370 mm) maximum above the finish floor or ground provided the self-latching devices are not also self-locking devices and operated by means of a key, electronic opener, or integral combination lock.

Advisory 404.2.7 Door and Gate Hardware. Door hardware that can be operated with a closed fist or a loose grip accommodates the greatest range of users. Hardware that requires simultaneous hand and finger movements require greater dexterity and coordination, and is not recommended.

404.2.8 Closing Speed. Door and gate closing speed shall comply with 404.2.8.

404.2.8.1 Door Closers and Gate Closers. Door closers and gate closers shall be adjusted so that from an open position of 90 degrees, the time required to move the door to a position of 12 degrees from the latch is 5 seconds minimum.

404.2.8.2 Spring Hinges. Door and gate spring hinges shall be adjusted so that from the open position of 70 degrees, the door or gate shall move to the closed position in 1.5 seconds minimum.

404.2.9 Door and Gate Opening Force. Fire doors shall have a minimum opening force allowable by the appropriate *administrative authority*. The force for pushing or pulling open a door or gate other than fire doors shall be as follows:

1. Interior hinged doors and gates: 5 pounds (22.2 N) maximum.
2. Sliding or folding doors: 5 pounds (22.2 N) maximum.

These forces do not apply to the force required to retract latch bolts or disengage other devices that hold the door or gate in a closed position.

Advisory 404.2.9 Door and Gate Opening Force. The maximum force pertains to the continuous application of force necessary to fully open a door, not the initial force needed to overcome the inertia of the door. It does not apply to the force required to retract bolts or to disengage other devices used to keep the door in a closed position.

404.2.10 Door and Gate Surfaces. Swinging door and gate surfaces within 10 inches (255 mm) of the finish floor or ground measured vertically shall have a smooth surface on the push side extending the full width of the door or gate. Parts creating horizontal or vertical joints in these surfaces shall be within 1/16 inch (1.6 mm) of the same plane as the other. Cavities created by added kick plates shall be capped.

- EXCEPTIONS:**
1. Sliding doors shall not be required to comply with 404.2.10.
 2. Tempered glass doors without stiles and having a bottom rail or shoe with the top leading edge tapered at 60 degrees minimum from the horizontal shall not be required to meet the 10 inch (255 mm) bottom smooth surface height requirement.
 3. Doors and gates that do not extend to within 10 inches (255 mm) of the finish floor or ground shall not be required to comply with 404.2.10.
 4. Existing doors and gates without smooth surfaces within 10 inches (255 mm) of the finish floor or ground shall not be required to provide smooth surfaces complying with 404.2.10 provided that if added kick plates are installed, cavities created by such kick plates are capped.

404.2.11 Vision Lights. Doors, gates, and side lights adjacent to doors or gates, containing one or more glazing panels that permit viewing through the panels shall have the bottom of at least one glazed panel located 43 inches (1090 mm) maximum above the finish floor.

EXCEPTION: Vision lights with the lowest part more than 66 inches (1675 mm) from the finish floor or ground shall not be required to comply with 404.2.11.

404.3 Automatic and Power-Assisted Doors and Gates. Automatic doors and automatic gates shall comply with 404.3. Full-powered automatic doors shall comply with ANSI/BHMA A156.10 (incorporated

by reference, see "Referenced Standards" in Chapter 1). Low-energy and power-assisted doors shall comply with ANSI/BHMA A156.19 (1997 or 2002 edition) (incorporated by reference, see "Referenced Standards" in Chapter 1).

404.3.1 Clear Width. Doorways shall provide a clear opening of 32 inches (815 mm) minimum in power-on and power-off mode. The minimum clear width for automatic door systems in a doorway shall be based on the clear opening provided by all leaves in the open position.

404.3.2 Maneuvering Clearance. Clearances at power-assisted doors and gates shall comply with 404.2.4. Clearances at automatic doors and gates without standby power and serving an *accessible means of egress* shall comply with 404.2.4.

EXCEPTION: Where automatic doors and gates remain open in the power-off condition, compliance with 404.2.4 shall not be required.

404.3.3 Thresholds. Thresholds and changes in level at doorways shall comply with 404.2.5.

404.3.4 Doors in Series and Gates in Series. Doors in series and gates in series shall comply with 404.2.6.

404.3.5 Controls. Manually operated controls shall comply with 309. The clear floor *space* adjacent to the control shall be located beyond the arc of the door swing.

404.3.6 Break Out Opening. Where doors and gates without standby power are a part of a means of egress, the clear break out opening at swinging or sliding doors and gates shall be 32 inches (815 mm) minimum when operated in emergency mode.

EXCEPTION: Where manual swinging doors and gates comply with 404.2 and serve the same means of egress compliance with 404.3.6 shall not be required.

404.3.7 Revolving Doors, Revolving Gates, and Turnstiles. Revolving doors, revolving gates, and turnstiles shall not be part of an *accessible* route.

405 Ramps

405.1 General. *Ramps* on *accessible* routes shall comply with 405.

EXCEPTION: In *assembly areas*, aisle *ramps* adjacent to seating and not serving *elements* required to be on an *accessible* route shall not be required to comply with 405.

405.2 Slope. *Ramp* runs shall have a *running slope* not steeper than 1:12.

EXCEPTION: In existing *sites, buildings, and facilities*, *ramps* shall be permitted to have *running slopes* steeper than 1:12 complying with Table 405.2 where such slopes are necessary due to *space* limitations.

Table 405.2 Maximum Ramp Slope and Rise for Existing Sites, Buildings, and Facilities

Slope ¹	Maximum Rise
Steeper than 1:10 but not steeper than 1:8	3 inches (75 mm)
Steeper than 1:12 but not steeper than 1:10	6 inches (150 mm)

1. A slope steeper than 1:8 is prohibited.

Advisory 405.2 Slope. To accommodate the widest range of users, provide ramps with the least possible running slope and, wherever possible, accompany ramps with stairs for use by those individuals for whom distance presents a greater barrier than steps, e.g., people with heart disease or limited stamina.

405.3 Cross Slope. *Cross slope of ramp runs shall not be steeper than 1:48.*

Advisory 405.3 Cross Slope. Cross slope is the slope of the surface perpendicular to the direction of travel. Cross slope is measured the same way as slope is measured (i.e., the rise over the run).

405.4 Floor or Ground Surfaces. Floor or ground surfaces of *ramp runs* shall comply with 302. Changes in level other than the *running slope* and *cross slope* are not permitted on *ramp runs*.

405.5 Clear Width. The clear width of a *ramp run* and, where handrails are provided, the clear width between handrails shall be 36 inches (915 mm) minimum.

EXCEPTION: Within *employee work areas*, the required clear width of *ramps* that are a part of *common use circulation paths* shall be permitted to be decreased by *work area equipment* provided that the decrease is essential to the function of the work being performed.

405.6 Rise. The rise for any *ramp run* shall be 30 inches (760 mm) maximum.

405.7 Landings. *Ramps* shall have landings at the top and the bottom of each *ramp run*. Landings shall comply with 405.7.

Advisory 405.7 Landings. Ramps that do not have level landings at changes in direction can create a compound slope that will not meet the requirements of this document. Circular or curved ramps continually change direction. Curvilinear ramps with small radii also can create compound cross slopes and cannot, by their nature, meet the requirements for accessible routes. A level landing is needed at the accessible door to permit maneuvering and simultaneously door operation.




Figure 405.7
Ramp Landings

405.7.1 Slope. Landings shall comply with 302. Changes in level are not permitted.

EXCEPTION: Slopes not steeper than 1:48 shall be permitted.

405.7.2 Width. The landing clear width shall be at least as wide as the widest *ramp* run leading to the landing.

405.7.3 Length. The landing clear length shall be 60 inches (1525 mm) long minimum.

405.7.4 Change in Direction. *Ramps* that change direction between runs at landings shall have a clear landing 60 inches (1525 mm) minimum by 60 inches (1525 mm) minimum.

405.7.5 Doorways. Where doorways are located adjacent to a *ramp* landing, maneuvering clearances required by 404.2.4 and 404.3.2 shall be permitted to overlap the required landing area.

405.8 Handrails. *Ramp* runs with a rise greater than 6 inches (150 mm) shall have handrails complying with 505.

EXCEPTION: Within *employee work areas*, handrails shall not be required where *ramps* that are part of *common use circulation paths* are designed to permit the installation of handrails complying with 505. *Ramps* not subject to the exception to 405.5 shall be designed to maintain a 36 inch (915 mm) minimum clear width when handrails are installed.

405.9 Edge Protection. Edge protection complying with 405.9.1 or 405.9.2 shall be provided on each side of *ramp* runs and at each side of *ramp* landings.

- EXCEPTIONS:** 1. Edge protection shall not be required on *ramps* that are not required to have handrails and have sides complying with 406.3.
2. Edge protection shall not be required on the sides of *ramp* landings serving an adjoining *ramp* run or stairway.
3. Edge protection shall not be required on the sides of *ramp* landings having a vertical drop-off of $\frac{1}{2}$ inch (13 mm) maximum within 10 inches (255 mm) horizontally of the minimum landing area specified in 405.7.

405.9.1 Extended Floor or Ground Surface. The floor or ground surface of the *ramp* run or landing shall extend 12 inches (305 mm) minimum beyond the inside face of a handrail complying with 505.

Advisory 405.9.1 Extended Floor or Ground Surface. The extended surface prevents wheelchair casters and crutch tips from slipping off the ramp surface.




Figure 405.9.1
Extended Floor or Ground Surface Edge Protection

405.9.2 Curb or Barrier. A curb or barrier shall be provided that prevents the passage of a 4 inch (100 mm) diameter sphere, where any portion of the sphere is within 4 inches (100 mm) of the finish floor or ground surface.




Figure 405.9.2
Curb or Barrier Edge Protection

405.10 Wet Conditions. Landings subject to wet conditions shall be designed to prevent the accumulation of water.

406 Curb Ramps

406.1 General. *Curb ramps* on *accessible* routes shall comply with 406, 405.2 through 405.5, and 405.10.

406.2 Counter Slope. Counter slopes of adjoining gutters and road surfaces immediately adjacent to the *curb ramp* shall not be steeper than 1:20. The adjacent surfaces at transitions at *curb ramps* to *walks*, gutters, and streets shall be at the same level.




Figure 406.2
Counter Slope of Surfaces Adjacent to Curb Ramps

406.3 Sides of Curb Ramps. Where provided, *curb ramp* flares shall not be steeper than 1:10.




Figure 406.3
Sides of Curb Ramps

406.4 Landings. Landings shall be provided at the tops of *curb ramps*. The landing clear length shall be 36 inches (915 mm) minimum. The landing clear width shall be at least as wide as the *curb ramp*, excluding flared sides, leading to the landing.

EXCEPTION: In *alterations*, where there is no landing at the top of *curb ramps*, *curb ramp* flares shall be provided and shall not be steeper than 1:12.




Figure 406.4
Landings at the Top of Curb Ramps

406.5 Location. *Curb ramps* and the flared sides of *curb ramps* shall be located so that they do not project into vehicular traffic lanes, parking *spaces*, or parking access aisles. *Curb ramps* at *marked crossings* shall be wholly contained within the markings, excluding any flared sides.

406.6 Diagonal Curb Ramps. Diagonal or corner type *curb ramps* with returned curbs or other well-defined edges shall have the edges parallel to the direction of pedestrian flow. The bottom of diagonal *curb ramps* shall have a clear *space* 48 inches (1220 mm) minimum outside active traffic lanes of the roadway. Diagonal *curb ramps* provided at *marked crossings* shall provide the 48 inches (1220 mm) minimum clear *space* within the markings. Diagonal *curb ramps* with flared sides shall have a segment of curb 24 inches (610 mm) long minimum located on each side of the *curb ramp* and within the *marked crossing*.




Figure 406.6
Diagonal or Corner Type Curb Ramps

406.7 Islands. Raised islands in crossings shall be cut through level with the street or have *curb ramps* at both sides. Each *curb ramp* shall have a level area 48 inches (1220 mm) long minimum by 36 inches (915 mm) wide minimum at the top of the *curb ramp* in the part of the island intersected by the crossings. Each 48 inch (1220 mm) minimum by 36 inch (915 mm) minimum area shall be oriented so that the 48 inch (1220 mm) minimum length is in the direction of the *running slope* of the *curb ramp* it serves. The 48 inch (1220 mm) minimum by 36 inch (915 mm) minimum areas and the *accessible* route shall be permitted to overlap.




Figure 406.7
Islands in Crossings

407 Elevators

407.1 General. Elevators shall comply with 407 and with ASME A17.1 (incorporated by reference, see "Referenced Standards" in Chapter 1). They shall be passenger elevators as classified by ASME A17.1. Elevator operation shall be automatic.

Advisory 407.1 General. The ADA and other Federal civil rights laws require that accessible features be maintained in working order so that they are accessible to and usable by those people they are intended to benefit. Building owners should note that the ASME Safety Code for Elevators and Escalators requires routine maintenance and inspections. Isolated or temporary interruptions in service due to maintenance or repairs may be unavoidable; however, failure to take prompt action to effect repairs could constitute a violation of Federal laws and these requirements.

407.2 Elevator Landing Requirements. Elevator landings shall comply with 407.2.

407.2.1 Call Controls. Where elevator call buttons or keypads are provided, they shall comply with 407.2.1 and 309.4. Call buttons shall be raised or flush.

EXCEPTION: Existing elevators shall be permitted to have recessed call buttons.

407.2.1.1 Height. Call buttons and keypads shall be located within one of the reach ranges specified in 308, measured to the centerline of the highest *operable part*.

EXCEPTION: Existing call buttons and existing keypads shall be permitted to be located at 54 inches (1370 mm) maximum above the finish floor, measured to the centerline of the highest *operable part*.

407.2.1.2 Size. Call buttons shall be $\frac{3}{4}$ inch (19 mm) minimum in the smallest dimension.

EXCEPTION: Existing elevator call buttons shall not be required to comply with 407.2.1.2.

407.2.1.3 Clear Floor or Ground Space. A clear floor or ground *space* complying with 305 shall be provided at call controls.

Advisory 407.2.1.3 Clear Floor or Ground Space. The clear floor or ground space required at elevator call buttons must remain free of obstructions including ashtrays, plants, and other decorative elements that prevent wheelchair users and others from reaching the call buttons. The height of the clear floor or ground space is considered to be a volume from the floor to 80 inches (2030 mm) above the floor. Recessed ashtrays should not be placed near elevator call buttons so that persons who are blind or visually impaired do not inadvertently contact them or their contents as they reach for the call buttons.

407.2.1.4 Location. The call button that designates the up direction shall be located above the call button that designates the down direction.

EXCEPTION: Destination-oriented elevators shall not be required to comply with 407.2.1.4.

Advisory 407.2.1.4 Location Exception. A destination-oriented elevator system provides lobby controls enabling passengers to select floor stops, lobby indicators designating which elevator to use, and a car indicator designating the floors at which the car will stop. Responding cars are programmed for maximum efficiency by reducing the number of stops any passenger experiences.

407.2.1.5 Signals. Call buttons shall have visible signals to indicate when each call is registered and when each call is answered.

EXCEPTIONS: 1. Destination-oriented elevators shall not be required to comply with 407.2.1.5 provided that visible and audible signals complying with 407.2.2 indicating which elevator car to enter are provided.

2. Existing elevators shall not be required to comply with 407.2.1.5.

407.2.1.6 Keypads. Where keypads are provided, keypads shall be in a standard telephone keypad arrangement and shall comply with 407.4.7.2.

407.2.2 Hall Signals. Hall signals, including in-car signals, shall comply with 407.2.2.

407.2.2.1 Visible and Audible Signals. A visible and audible signal shall be provided at each hoistway entrance to indicate which car is answering a call and the car's direction of travel. Where in-car signals are provided, they shall be visible from the floor area adjacent to the hall call buttons.

- EXCEPTIONS:** 1. Visible and audible signals shall not be required at each destination-oriented elevator where a visible and audible signal complying with 407.2.2 is provided indicating the elevator car designation information.
2. In existing elevators, a signal indicating the direction of car travel shall not be required.

407.2.2.2 Visible Signals. Visible signal fixtures shall be centered at 72 inches (1830 mm) minimum above the finish floor or ground. The visible signal *elements* shall be 2-½ inches (64 mm) minimum measured along the vertical centerline of the *element*. Signals shall be visible from the floor area adjacent to the hall call button.

- EXCEPTIONS:** 1. Destination-oriented elevators shall be permitted to have signals visible from the floor area adjacent to the hoistway entrance.
2. Existing elevators shall not be required to comply with 407.2.2.2.




Figure 407.2.2.2
Visible Hall Signals

407.2.2.3 Audible Signals. Audible signals shall sound once for the up direction and twice for the down direction, or shall have verbal annunciators that indicate the direction of elevator car travel. Audible signals shall have a frequency of 1500 Hz maximum. Verbal annunciators shall have a frequency of 300 Hz minimum and 3000 Hz maximum. The audible signal and verbal annunciator shall be 10 dB minimum above ambient, but shall not exceed 80 dB, measured at the hall call button.

- EXCEPTIONS:** 1. Destination-oriented elevators shall not be required to comply with 407.2.2.3 provided that the audible tone and verbal announcement is the same as those given at the call button or call button keypad.
2. Existing elevators shall not be required to comply with the requirements for frequency and dB range of audible signals.

407.2.2.4 Differentiation. Each destination-oriented elevator in a bank of elevators shall have audible and visible means for differentiation.

407.2.3 Hoistway Signs. Signs at elevator hoistways shall comply with 407.2.3.

407.2.3.1 Floor Designation. Floor designations complying with 703.2 and 703.4.1 shall be provided on both jambs of elevator hoistway entrances. Floor designations shall be provided in both *tactile characters* and braille. *Tactile characters* shall be 2 inches (51 mm) high minimum. A *tactile* star shall be provided on both jambs at the main entry level.




Figure 407.2.3.1
Floor Designations on Jambs of Elevator Hoistway Entrances

407.2.3.2 Car Designations. Destination-oriented elevators shall provide *tactile* car identification complying with 703.2 on both jambs of the hoistway immediately below the floor designation. Car designations shall be provided in both *tactile characters* and braille. *Tactile characters* shall be 2 inches (51 mm) high minimum.




Figure 407.2.3.2
Car Designations on Jambs of Destination-Oriented Elevator Hoistway Entrances

407.3 Elevator Door Requirements. Hoistway and car doors shall comply with 407.3.

407.3.1 Type. Elevator doors shall be the horizontal sliding type. Car gates shall be prohibited.

407.3.2 Operation. Elevator hoistway and car doors shall open and close automatically.

EXCEPTION: Existing manually operated hoistway swing doors shall be permitted provided that they comply with 404.2.3 and 404.2.9. Car door closing shall not be initiated until the hoistway door is closed.

407.3.3 Reopening Device. Elevator doors shall be provided with a reopening device complying with 407.3.3 that shall stop and reopen a car door and hoistway door automatically if the door becomes obstructed by an object or person.

EXCEPTION: Existing elevators with manually operated doors shall not be required to comply with 407.3.3.

407.3.3.1 Height. The device shall be activated by sensing an obstruction passing through the opening at 5 inches (125 mm) nominal and 29 inches (735 mm) nominal above the finish floor.

407.3.3.2 Contact. The device shall not require physical contact to be activated, although contact is permitted to occur before the door reverses.

407.3.3.3 Duration. Door reopening devices shall remain effective for 20 seconds minimum.

407.3.4 Door and Signal Timing. The minimum acceptable time from notification that a car is answering a call or notification of the car assigned at the means for the entry of destination information until the doors of that car start to close shall be calculated from the following equation:

$T = D / (1.5 \text{ ft/s})$ or $T = D / (455 \text{ mm/s}) = 5 \text{ seconds minimum}$ where T equals the total time in seconds and D equals the distance (in feet or millimeters) from the point in the lobby or corridor 60 inches (1525 mm) directly in front of the farthest call button controlling that car to the centerline of its hoistway door.

EXCEPTIONS: 1. For cars with in-car lanterns, T shall be permitted to begin when the signal is visible from the point 60 inches (1525 mm) directly in front of the farthest hall call button and the audible signal is sounded.

2. Destination-oriented elevators shall not be required to comply with 407.3.4.

407.3.5 Door Delay. Elevator doors shall remain fully open in response to a car call for 3 seconds minimum.

407.3.6 Width. The width of elevator doors shall comply with Table 407.4.1.

EXCEPTION: In existing elevators, a power-operated car door complying with 404.2.3 shall be permitted.

407.4 Elevator Car Requirements. Elevator cars shall comply with 407.4.

407.4.1 Car Dimensions. Inside dimensions of elevator cars and clear width of elevator doors shall comply with Table 407.4.1.

EXCEPTION: Existing elevator car configurations that provide a clear floor area of 16 square feet (1.5 m²) minimum and also provide an inside clear depth 54 inches (1370 mm) minimum and a clear width 36 inches (915 mm) minimum shall be permitted.

Table 407.4.1 Elevator Car Dimensions

Door Location	Minimum Dimensions			
	Door Clear Width	Inside Car, Side to Side	Inside Car, Back Wall to Front Return	Inside Car, Back Wall to Inside Face of Door
Centered	42 inches (1065 mm)	80 inches (2030 mm)	51 inches (1295 mm)	54 inches (1370 mm)
Side (off-centered)	36 inches (915 mm) ¹	68 inches (1725 mm)	51 inches (1295 mm)	54 inches (1370 mm)
Any	36 inches (915 mm) ¹	54 inches (1370 mm)	80 inches (2030 mm)	80 inches (2030 mm)
Any	36 inches (915 mm) ¹	60 inches (1525 mm) ²	60 inches (1525 mm) ²	60 inches (1525 mm) ²

1. A tolerance of minus 5/8 inch (16 mm) is permitted.

2. Other car configurations that provide a turning space complying with 304 with the door closed shall be permitted.




**Figure 407.4.1
Elevator Car Dimensions**




Figure 407.4.1
Elevator Car Dimensions

407.4.2 Floor Surfaces. Floor surfaces in elevator cars shall comply with 302 and 303.

407.4.3 Platform to Hoistway Clearance. The clearance between the car platform sill and the edge of any hoistway landing shall be 1¼ inch (32 mm) maximum.

407.4.4 Leveling. Each car shall be equipped with a self-leveling feature that will automatically bring and maintain the car at floor landings within a tolerance of ½ inch (13 mm) under rated loading to zero loading conditions.

407.4.5 Illumination. The level of illumination at the car controls, platform, car threshold and car landing sill shall be 5 foot candles (54 lux) minimum.

407.4.6 Elevator Car Controls. Where provided, elevator car controls shall comply with 407.4.6 and 309.4.

EXCEPTION: In existing elevators, where a new car operating panel complying with 407.4.6 is provided, existing car operating panels shall not be required to comply with 407.4.6.

407.4.6.1 Location. Controls shall be located within one of the reach ranges specified in 308.

EXCEPTIONS: 1. Where the elevator panel serves more than 16 openings and a parallel approach is provided, buttons with floor designations shall be permitted to be 54 inches (1370 mm) maximum above the finish floor.

2. In existing elevators, car control buttons with floor designations shall be permitted to be located 54 inches (1370 mm) maximum above the finish floor where a parallel approach is provided.

407.4.6.2 Buttons. Car control buttons with floor designations shall comply with 407.4.6.2 and shall be raised or flush.

EXCEPTION: In existing elevators, buttons shall be permitted to be recessed.

407.4.6.2.1 Size. Buttons shall be ¾ inch (19 mm) minimum in their smallest dimension.

407.4.6.2.2 Arrangement. Buttons shall be arranged with numbers in ascending order. When two or more columns of buttons are provided they shall read from left to right.

407.4.6.3 Keypads. Car control keypads shall be in a standard telephone keypad arrangement and shall comply with 407.4.7.2.

407.4.6.4 Emergency Controls. Emergency controls shall comply with 407.4.6.4.

407.4.6.4.1 Height. Emergency control buttons shall have their centerlines 35 inches (890 mm) minimum above the finish floor.

407.4.6.4.2 Location. Emergency controls, including the emergency alarm, shall be grouped at the bottom of the panel.

407.4.7 Designations and Indicators of Car Controls. Designations and indicators of car controls shall comply with 407.4.7.

EXCEPTION: In existing elevators, where a new car operating panel complying with 407.4.7 is provided, existing car operating panels shall not be required to comply with 407.4.7.

407.4.7.1 Buttons. Car control buttons shall comply with 407.4.7.1.

407.4.7.1.1 Type. Control buttons shall be identified by *tactile characters* complying with 703.2.

407.4.7.1.2 Location. Raised *character* and braille designations shall be placed immediately to the left of the control button to which the designations apply.

EXCEPTION: Where *space* on an existing car operating panel precludes *tactile* markings to the left of the controls, markings shall be placed as near to the control as possible.

407.4.7.1.3 Symbols. The control button for the emergency stop, alarm, door open, door close, main entry floor, and phone, shall be identified with *tactile* symbols as shown in Table 407.4.7.1.3.

Table 407.4.7.1.3 Elevator Control Button Identification

Control Button	Tactile Symbol	Braille Message
Emergency Stop		 ⠠⠠⠠⠠⠠⠠ "ST"OP Three cells
Alarm		 ⠠⠠⠠⠠⠠⠠ AL"AR"M Four cells
Door Open		 ⠠⠠⠠⠠⠠⠠ OP"EN" Three cells
Door Close		 ⠠⠠⠠⠠⠠⠠ CLOSE Five cells
Main Entry Floor		 ⠠⠠⠠⠠⠠⠠ MA"IN" Three cells
Phone		 ⠠⠠⠠⠠⠠⠠ PH"ONE" Four cells

407.4.7.1.4 Visible Indicators. Buttons with floor designations shall be provided with visible indicators to show that a call has been registered. The visible indication shall extinguish when the car arrives at the designated floor.

407.4.7.2 Keypads. Keypads shall be identified by *characters* complying with 703.5 and shall be centered on the corresponding keypad button. The number five key shall have a single raised dot. The dot shall be 0.118 inch (3 mm) to 0.120 inch (3.05 mm) base diameter and in other aspects comply with Table 703.3.1.

407.4.8 Car Position Indicators. Audible and visible car position indicators shall be provided in elevator cars.

407.4.8.1 Visible Indicators. Visible indicators shall comply with 407.4.8.1.

407.4.8.1.1 Size. *Characters* shall be ½ inch (13 mm) high minimum.

407.4.8.1.2 Location. Indicators shall be located above the car control panel or above the door.

407.4.8.1.3 Floor Arrival. As the car passes a floor and when a car stops at a floor served by the elevator, the corresponding *character* shall illuminate.

EXCEPTION: Destination-oriented elevators shall not be required to comply with 407.4.8.1.3 provided that the visible indicators extinguish when the call has been answered.

407.4.8.1.4 Destination Indicator. In destination-oriented elevators, a display shall be provided in the car with visible indicators to show car destinations.

407.4.8.2 Audible Indicators. Audible indicators shall comply with 407.4.8.2.

407.4.8.2.1 Signal Type. The signal shall be an automatic verbal annunciator which announces the floor at which the car is about to stop.

EXCEPTION: For elevators other than destination-oriented elevators that have a rated speed of 200 feet per minute (1 m/s) or less, a non-verbal audible signal with a frequency of 1500 Hz maximum which sounds as the car passes or is about to stop at a floor served by the elevator shall be permitted.

407.4.8.2.2 Signal Level. The verbal annunciator shall be 10 dB minimum above ambient, but shall not exceed 80 dB, measured at the annunciator.

407.4.8.2.3 Frequency. The verbal annunciator shall have a frequency of 300 Hz minimum to 3000 Hz maximum.

407.4.9 Emergency Communication. Emergency two-way communication systems shall comply with 308. *Tactile* symbols and *characters* shall be provided adjacent to the device and shall comply with 703.2.

408 Limited-Use/Limited-Application Elevators

408.1 General. Limited-use/limited-application elevators shall comply with 408 and with ASME A17.1 (incorporated by reference, see "Referenced Standards" in Chapter 1). They shall be passenger elevators as classified by ASME A17.1. Elevator operation shall be automatic.

408.2 Elevator Landings. Landings serving limited-use/limited-application elevators shall comply with 408.2.

408.2.1 Call Buttons. Elevator call buttons and keypads shall comply with 407.2.1.

408.2.2 Hall Signals. Hall signals shall comply with 407.2.2.

408.2.3 Hoistway Signs. Signs at elevator hoistways shall comply with 407.2.3.1.

408.3 Elevator Doors. Elevator hoistway doors shall comply with 408.3.

408.3.1 Sliding Doors. Sliding hoistway and car doors shall comply with 407.3.1 through 407.3.3 and 408.4.1.

408.3.2 Swinging Doors. Swinging hoistway doors shall open and close automatically and shall comply with 404, 407.3.2 and 408.3.2.

408.3.2.1 Power Operation. Swinging doors shall be power-operated and shall comply with ANSI/BHMA A156.19 (1997 or 2002 edition) (incorporated by reference, see "Referenced Standards" in Chapter 1).

408.3.2.2 Duration. Power-operated swinging doors shall remain open for 20 seconds minimum when activated.

408.4 Elevator Cars. Elevator cars shall comply with 408.4.

408.4.1 Car Dimensions and Doors. Elevator cars shall provide a clear width 42 inches (1065 mm) minimum and a clear depth 54 inches (1370 mm) minimum. Car doors shall be positioned at the narrow ends of cars and shall provide 32 inches (815 mm) minimum clear width.

EXCEPTIONS: 1. Cars that provide a clear width 51 inches (1295 mm) minimum shall be permitted to provide a clear depth 51 inches (1295 mm) minimum provided that car doors provide a clear opening 36 inches (915 mm) wide minimum.

2. Existing elevator cars shall be permitted to provide a clear width 36 inches (915 mm) minimum, clear depth 54 inches (1370 mm) minimum, and a net clear platform area 15 square feet (1.4 m²) minimum.




Figure 408.4.1
Limited-Use/Limited-Application (LULA) Elevator Car Dimensions

408.4.2 Floor Surfaces. Floor surfaces in elevator cars shall comply with 302 and 303.

408.4.3 Platform to Hoistway Clearance. The platform to hoistway clearance shall comply with 407.4.3.

408.4.4 Leveling. Elevator car leveling shall comply with 407.4.4.

408.4.5 Illumination. Elevator car illumination shall comply with 407.4.5.

408.4.6 Car Controls. Elevator car controls shall comply with 407.4.6. Control panels shall be centered on a side wall.

408.4.7 Designations and Indicators of Car Controls. Designations and indicators of car controls shall comply with 407.4.7.

408.4.8 Emergency Communications. Car emergency signaling devices complying with 407.4.9 shall be provided.

409 Private Residence Elevators

409.1 General. Private residence elevators that are provided within a *residential dwelling unit* required to provide mobility features complying with 809.2 through 809.4 shall comply with 409 and with ASME A17.1 (incorporated by reference, see "Referenced Standards" in Chapter 1). They shall be passenger elevators as classified by ASME A17.1. Elevator operation shall be automatic.

409.2 Call Buttons. Call buttons shall be ¾ inch (19 mm) minimum in the smallest dimension and shall comply with 309.

409.3 Elevator Doors. Hoistway doors, car doors, and car gates shall comply with 409.3 and 404.

EXCEPTION: Doors shall not be required to comply with the maneuvering clearance requirements in 404.2.4.1 for approaches to the push side of swinging doors.

409.3.1 Power Operation. Elevator car and hoistway doors and gates shall be power operated and shall comply with ANSI/BHMA A156.19 (1997 or 2002 edition) (incorporated by reference, see "Referenced Standards" in Chapter 1). Power operated doors and gates shall remain open for 20 seconds minimum when activated.

EXCEPTION: In elevator cars with more than one opening, hoistway doors and gates shall be permitted to be of the manual-open, self-close type.

409.3.2 Location. Elevator car doors or gates shall be positioned at the narrow end of the clear floor spaces required by 409.4.1.

409.4 Elevator Cars. Private residence elevator cars shall comply with 409.4.

409.4.1 Inside Dimensions of Elevator Cars. Elevator cars shall provide a clear floor space of 36 inches (915 mm) minimum by 48 inches (1220 mm) minimum and shall comply with 305.

409.4.2 Floor Surfaces. Floor surfaces in elevator cars shall comply with 302 and 303.

409.4.3 Platform to Hoistway Clearance. The clearance between the car platform and the edge of any landing sill shall be 1½ inch (38 mm) maximum.

409.4.4 Leveling. Each car shall automatically stop at a floor landing within a tolerance of ½ inch (13 mm) under rated loading to zero loading conditions.

409.4.5 Illumination Levels. Elevator car illumination shall comply with 407.4.5.

409.4.6 Car Controls. Elevator car control buttons shall comply with 409.4.6, 309.3, 309.4, and shall be raised or flush.

409.4.6.1 Size. Control buttons shall be 3/4 inch (19 mm) minimum in their smallest dimension.

409.4.6.2 Location. Control panels shall be on a side wall, 12 inches (305 mm) minimum from any adjacent wall.




Figure 409.4.6.2
Location of Private Residence Elevator Control Panel

409.4.7 Emergency Communications. Emergency two-way communication systems shall comply with 409.4.7.

409.4.7.1 Type. A telephone and emergency signal device shall be provided in the car.

409.4.7.2 Operable Parts. The telephone and emergency signaling device shall comply with 309.3 and 309.4.

409.4.7.3 Compartment. If the telephone or device is in a closed compartment, the compartment door hardware shall comply with 309.

409.4.7.4 Cord. The telephone cord shall be 29 inches (735 mm) long minimum.

410 Platform Lifts

410.1 General. Platform lifts shall comply with ASME A18.1 (1999 edition or 2003 edition) (incorporated by reference, see "Referenced Standards" in Chapter 1). Platform lifts shall not be attendant-operated and shall provide unassisted entry and exit from the lift.

Advisory 410.1 General. Inclined stairway chairlifts and inclined and vertical platform lifts are available for short-distance vertical transportation. Because an accessible route requires an 80 inch (2030 mm) vertical clearance, care should be taken in selecting lifts as they may not be equally suitable for use by people using wheelchairs and people standing. If a lift does not provide 80 inch (2030 mm) vertical clearance, it cannot be considered part of an accessible route in new construction.

The ADA and other Federal civil rights laws require that accessible features be maintained in working order so that they are accessible to and usable by those people they are intended to benefit. Building owners are reminded that the ASME A18 Safety Standard for Platform Lifts and Stairway Chairlifts requires routine maintenance and inspections. Isolated or temporary interruptions in service due to maintenance or repairs may be unavoidable; however, failure to take prompt action to effect repairs could constitute a violation of Federal laws and these requirements.

410.2 Floor Surfaces. Floor surfaces in platform lifts shall comply with 302 and 303.

410.3 Clear Floor Space. Clear floor space in platform lifts shall comply with 305.

410.4 Platform to Runway Clearance. The clearance between the platform sill and the edge of any runway landing shall be 1¼ inch (32 mm) maximum.

410.5 Operable Parts. Controls for platform lifts shall comply with 309.

410.6 Doors and Gates. Platform lifts shall have low-energy power-operated doors or gates complying with 404.3. Doors shall remain open for 20 seconds minimum. End doors and gates shall provide a clear width 32 inches (815 mm) minimum. Side doors and gates shall provide a clear width 42 inches (1065 mm) minimum.

EXCEPTION: Platform lifts serving two landings maximum and having doors or gates on opposite sides shall be permitted to have self-closing manual doors or gates.




Figure 410.6
Platform Lift Doors and Gates

CHAPTER 5: GENERAL SITE AND BUILDING ELEMENTS

501 General

501.1 Scope. The provisions of Chapter 5 shall apply where required by Chapter 2 or where referenced by a requirement in this document.

502 Parking Spaces

502.1 General. Car and van parking spaces shall comply with 502. Where parking spaces are marked with lines, width measurements of parking spaces and access aisles shall be made from the centerline of the markings.

EXCEPTION: Where parking spaces or access aisles are not adjacent to another parking space or access aisle, measurements shall be permitted to include the full width of the line defining the parking space or access aisle.

502.2 Vehicle Spaces. Car parking spaces shall be 96 inches (2440 mm) wide minimum and van parking spaces shall be 132 inches (3350 mm) wide minimum, shall be marked to define the width, and shall have an adjacent access aisle complying with 502.3.

EXCEPTION: Van parking spaces shall be permitted to be 96 inches (2440 mm) wide minimum where the access aisle is 96 inches (2440 mm) wide minimum.




Figure 502.2
Vehicle Parking Spaces

502.3 Access Aisle. Access aisles serving parking *spaces* shall comply with 502.3. Access aisles shall adjoin an *accessible* route. Two parking *spaces* shall be permitted to share a common access aisle.

Advisory 502.3 Access Aisle. Accessible routes must connect parking spaces to accessible entrances. In parking facilities where the accessible route must cross vehicular traffic lanes, marked crossings enhance pedestrian safety, particularly for people using wheelchairs and other mobility aids. Where possible, it is preferable that the accessible route not pass behind parked vehicles.




Figure 502.3
Parking Space Access Aisle

502.3.1 Width. Access aisles serving car and van parking *spaces* shall be 60 inches (1525 mm) wide minimum.

502.3.2 Length. Access aisles shall extend the full length of the parking *spaces* they serve.

502.3.3 Marking. Access aisles shall be marked so as to discourage parking in them.

Advisory 502.3.3 Marking. The method and color of marking are not specified by these requirements but may be addressed by State or local laws or regulations. Because these requirements permit the van access aisle to be as wide as a parking space, it is important that the aisle be clearly marked.

502.3.4 Location. Access aisles shall not overlap the *vehicular way*. Access aisles shall be permitted to be placed on either side of the parking *space* except for angled van parking *spaces* which shall have access aisles located on the passenger side of the parking *spaces*.

Advisory 502.3.4 Location. Wheelchair lifts typically are installed on the passenger side of vans. Many drivers, especially those who operate vans, find it more difficult to back into parking spaces than to back out into comparatively unrestricted vehicular lanes. For this reason, where a van and car share an access aisle, consider locating the van space so that the access aisle is on the passenger side of the van space.

502.4 Floor or Ground Surfaces. Parking *spaces* and access aisles serving them shall comply with 302. Access aisles shall be at the same level as the parking *spaces* they serve. Changes in level are not permitted.

EXCEPTION: Slopes not steeper than 1:48 shall be permitted.

Advisory 502.4 Floor or Ground Surfaces. Access aisles are required to be nearly level in all directions to provide a surface for wheelchair transfer to and from vehicles. The exception allows sufficient slope for drainage. Built-up curb ramps are not permitted to project into access aisles and parking spaces because they would create slopes greater than 1:48.

502.5 Vertical Clearance. Parking *spaces* for vans and access aisles and vehicular routes serving them shall provide a vertical clearance of 98 inches (2490 mm) minimum.

Advisory 502.5 Vertical Clearance. Signs provided at entrances to parking facilities informing drivers of clearances and the location of van accessible parking spaces can provide useful customer assistance.

502.6 Identification. Parking *space* identification signs shall include the International Symbol of *Accessibility* complying with 703.7.2.1. Signs identifying van parking *spaces* shall contain the designation "van accessible." Signs shall be 60 inches (1525 mm) minimum above the finish floor or ground surface measured to the bottom of the sign.

Advisory 502.6 Identification. The required "van accessible" designation is intended to be informative, not restrictive, in identifying those spaces that are better suited for van use. Enforcement of motor vehicle laws, including parking privileges, is a local matter.

502.7 Relationship to Accessible Routes. Parking *spaces* and access aisles shall be designed so that cars and vans, when parked, cannot obstruct the required clear width of adjacent *accessible* routes.

Advisory 502.7 Relationship to Accessible Routes. Wheel stops are an effective way to prevent vehicle overhangs from reducing the clear width of accessible routes.

503 Passenger Loading Zones

503.1 General. Passenger loading zones shall comply with 503.

503.2 Vehicle Pull-Up Space. Passenger loading zones shall provide a vehicular pull-up space 96 inches (2440 mm) wide minimum and 20 feet (6100 mm) long minimum.

503.3 Access Aisle. Passenger loading zones shall provide access aisles complying with 503 adjacent to the vehicle pull-up space. Access aisles shall adjoin an *accessible* route and shall not overlap the *vehicular way*.

503.3.1 Width. Access aisles serving vehicle pull-up spaces shall be 60 inches (1525 mm) wide minimum.

503.3.2 Length. Access aisles shall extend the full length of the vehicle pull-up spaces they serve.

503.3.3 Marking. Access aisles shall be marked so as to discourage parking in them.




Figure 503.3
Passenger Loading Zone Access Aisle

503.4 Floor and Ground Surfaces. Vehicle pull-up spaces and access aisles serving them shall comply with 302. Access aisles shall be at the same level as the vehicle pull-up space they serve. Changes in level are not permitted.

EXCEPTION: Slopes not steeper than 1:48 shall be permitted.

503.5 Vertical Clearance. Vehicle pull-up spaces, access aisles serving them, and a vehicular route from an *entrance* to the passenger loading zone, and from the passenger loading zone to a vehicular exit shall provide a vertical clearance of 114 inches (2895 mm) minimum.

504 Stairways

504.1 General. Stairs shall comply with 504.

504.2 Treads and Risers. All steps on a flight of stairs shall have uniform riser heights and uniform tread depths. Risers shall be 4 inches (100 mm) high minimum and 7 inches (180 mm) high maximum. Treads shall be 11 inches (280 mm) deep minimum.

504.3 Open Risers. Open risers are not permitted.

504.4 Tread Surface. Stair treads shall comply with 302. Changes in level are not permitted.

EXCEPTION: Treads shall be permitted to have a slope not steeper than 1:48.

Advisory 504.4 Tread Surface. Consider providing visual contrast on tread nosings, or at the leading edges of treads without nosings, so that stair treads are more visible for people with low vision.

504.5 Nosings. The radius of curvature at the leading edge of the tread shall be ½ inch (13 mm) maximum. Nosings that project beyond risers shall have the underside of the leading edge curved or beveled. Risers shall be permitted to slope under the tread at an angle of 30 degrees maximum from vertical. The permitted projection of the nosing shall extend 1½ inches (38 mm) maximum over the tread below.




Figure 504.5
Stair Nosings

504.6 Handrails. Stairs shall have handrails complying with 505.

504.7 Wet Conditions. Stair treads and landings subject to wet conditions shall be designed to prevent the accumulation of water.

505 Handrails

505.1 General. Handrails provided along walking surfaces complying with 403, required at *ramps* complying with 405, and required at stairs complying with 504 shall comply with 505.

Advisory 505.1 General. Handrails are required on ramp runs with a rise greater than 6 inches (150 mm) (see 405.8) and on certain stairways (see 504). Handrails are not required on walking surfaces with running slopes less than 1:20. However, handrails are required to comply with 505 when they are provided on walking surfaces with running slopes less than 1:20 (see 403.6). Sections 505.2, 505.3, and 505.10 do not apply to handrails provided on walking surfaces with running slopes less than 1:20 as these sections only reference requirements for ramps and stairs.

505.2 Where Required. Handrails shall be provided on both sides of stairs and *ramps*.

EXCEPTION: In *assembly areas*, handrails shall not be required on both sides of aisle *ramps* where a handrail is provided at either side or within the aisle width.

505.3 Continuity. Handrails shall be continuous within the full length of each stair flight or *ramp* run. Inside handrails on switchback or dogleg stairs and *ramps* shall be continuous between flights or runs.

EXCEPTION: In *assembly areas*, handrails on *ramps* shall not be required to be continuous in aisles serving seating.

505.4 Height. Top of gripping surfaces of handrails shall be 34 inches (865 mm) minimum and 38 inches (965 mm) maximum vertically above walking surfaces, stair nosings, and *ramp* surfaces. Handrails shall be at a consistent height above walking surfaces, stair nosings, and *ramp* surfaces.

Advisory 505.4 Height. The requirements for stair and ramp handrails in this document are for adults. When children are the principal users in a building or facility (e.g., elementary schools), a second set of handrails at an appropriate height can assist them and aid in preventing accidents. A maximum height of 28 inches (710 mm) measured to the top of the gripping surface from the ramp surface or stair nosing is recommended for handrails designed for children. Sufficient vertical clearance between upper and lower handrails, 9 inches (230 mm) minimum, should be provided to help prevent entrapment.




Figure 505.4
Handrail Height

505.5 Clearance. Clearance between handrail gripping surfaces and adjacent surfaces shall be 1½ inches (38 mm) minimum.




Figure 505.5
Handrail Clearance

505.6 Gripping Surface. Handrail gripping surfaces shall be continuous along their length and shall not be obstructed along their tops or sides. The bottoms of handrail gripping surfaces shall not be obstructed for more than 20 percent of their length. Where provided, horizontal projections shall occur 1½ inches (38 mm) minimum below the bottom of the handrail gripping surface.

- EXCEPTIONS:** 1. Where handrails are provided along walking surfaces with slopes not steeper than 1:20, the bottoms of handrail gripping surfaces shall be permitted to be obstructed along their entire length where they are integral to crash rails or bumper guards.
2. The distance between horizontal projections and the bottom of the gripping surface shall be permitted to be reduced by 1/8 inch (3.2 mm) for each ½ inch (13 mm) of additional handrail perimeter dimension that exceeds 4 inches (100 mm).

Advisory 505.6 Gripping Surface. People with disabilities, older people, and others benefit from continuous gripping surfaces that permit users to reach the fingers outward or downward to grasp the handrail, particularly as the user senses a loss of equilibrium or begins to fall.




Figure 505.6
Horizontal Projections Below Gripping Surface

505.7 Cross Section. Handrail gripping surfaces shall have a cross section complying with 505.7.1 or 505.7.2.

505.7.1 Circular Cross Section. Handrail gripping surfaces with a circular cross section shall have an outside diameter of 1¼ inches (32 mm) minimum and 2 inches (51 mm) maximum.

505.7.2 Non-Circular Cross Sections. Handrail gripping surfaces with a non-circular cross section shall have a perimeter dimension of 4 inches (100 mm) minimum and 6¼ inches (160 mm) maximum, and a cross-section dimension of 2¼ inches (57 mm) maximum.




Figure 505.7.2
Handrail Non-Circular Cross Section

505.8 Surfaces. Handrail gripping surfaces and any surfaces adjacent to them shall be free of sharp or abrasive *elements* and shall have rounded edges.

505.9 Fittings. Handrails shall not rotate within their fittings.

505.10 Handrail Extensions. Handrail gripping surfaces shall extend beyond and in the same direction of stair flights and *ramp* runs in accordance with 505.10.

EXCEPTIONS: 1. Extensions shall not be required for continuous handrails at the inside turn of switchback or dogleg stairs and *ramps*.

2. In *assembly areas*, extensions shall not be required for *ramp* handrails in aisles serving seating where the handrails are discontinuous to provide access to seating and to permit crossovers within aisles.

3. In *alterations*, full extensions of handrails shall not be required where such extensions would be hazardous due to plan configuration.

505.10.1 Top and Bottom Extension at Ramps. *Ramp* handrails shall extend horizontally above the landing for 12 inches (305 mm) minimum beyond the top and bottom of *ramp* runs. Extensions shall return to a wall, guard, or the landing surface, or shall be continuous to the handrail of an adjacent *ramp* run.




Figure 505.10.1
Top and Bottom Handrail Extension at Ramps

505.10.2 Top Extension at Stairs. At the top of a stair flight, handrails shall extend horizontally above the landing for 12 inches (305 mm) minimum beginning directly above the first riser nosing. Extensions shall return to a wall, guard, or the landing surface, or shall be continuous to the handrail of an adjacent stair flight.





Figure 505.10.2
Top Handrail Extension at Stairs

505.10.3 Bottom Extension at Stairs. At the bottom of a stair flight, handrails shall extend at the slope of the stair flight for a horizontal distance at least equal to one tread depth beyond the last riser nosing. Extension shall return to a wall, guard, or the landing surface, or shall be continuous to the handrail of an adjacent stair flight.



Note: X = tread depth

Figure 505.10.3
Bottom Handrail Extension at Stairs

CHAPTER 6: PLUMBING ELEMENTS AND FACILITIES

601 General

601.1 Scope. The provisions of Chapter 6 shall apply where required by Chapter 2 or where referenced by a requirement in this document.

602 Drinking Fountains

602.1 General. Drinking fountains shall comply with 307 and 602.

602.2 Clear Floor Space. Units shall have a clear floor or ground space complying with 305 positioned for a forward approach and centered on the unit. Knee and toe clearance complying with 306 shall be provided.

EXCEPTION: A parallel approach complying with 305 shall be permitted at units for *children's use* where the spout is 30 inches (760 mm) maximum above the finish floor or ground and is 3½ inches (90 mm) maximum from the front edge of the unit, including bumpers.

602.3 Operable Parts. *Operable parts* shall comply with 309.

602.4 Spout Height. Spout outlets shall be 36 inches (915 mm) maximum above the finish floor or ground.

602.5 Spout Location. The spout shall be located 15 inches (380 mm) minimum from the vertical support and 5 inches (125 mm) maximum from the front edge of the unit, including bumpers.




Figure 602.5
Drinking Fountain Spout Location

602.6 Water Flow. The spout shall provide a flow of water 4 inches (100 mm) high minimum and shall be located 5 inches (125 mm) maximum from the front of the unit. The angle of the water stream shall be measured horizontally relative to the front face of the unit. Where spouts are located less than 3 inches (75 mm) of the front of the unit, the angle of the water stream shall be 30 degrees maximum. Where spouts are located between 3 inches (75 mm) and 5 inches (125 mm) maximum from the front of the unit, the angle of the water stream shall be 15 degrees maximum.

Advisory 602.6 Water Flow. The purpose of requiring the drinking fountain spout to produce a flow of water 4 inches (100 mm) high minimum is so that a cup can be inserted under the flow of water to provide a drink of water for an individual who, because of a disability, would otherwise be incapable of using the drinking fountain.

602.7 Drinking Fountains for Standing Persons. Spout outlets of drinking fountains for standing persons shall be 38 inches (965 mm) minimum and 43 inches (1090 mm) maximum above the finish floor or ground.

603 Toilet and Bathing Rooms

603.1 General. Toilet and bathing rooms shall comply with 603.

603.2 Clearances. Clearances shall comply with 603.2.

603.2.1 Turning Space. Turning *space* complying with 304 shall be provided within the room.

603.2.2 Overlap. Required clear floor *spaces*, clearance at fixtures, and turning *space* shall be permitted to overlap.

603.2.3 Door Swing. Doors shall not swing into the clear floor *space* or clearance required for any fixture. Doors shall be permitted to swing into the required turning *space*.

EXCEPTIONS: 1. Doors to a toilet room or bathing room for a single occupant accessed only through a private office and not for *common use* or *public use* shall be permitted to swing into the clear floor *space* or clearance provided the swing of the door can be reversed to comply with 603.2.3.

2. Where the toilet room or bathing room is for individual use and a clear floor *space* complying with 305.3 is provided within the room beyond the arc of the door swing, doors shall be permitted to swing into the clear floor *space* or clearance required for any fixture.

Advisory 603.2.3 Door Swing Exception 1. At the time the door is installed, and if the door swing is reversed in the future, the door must meet all the requirements specified in 404. Additionally, the door swing cannot reduce the required width of an accessible route. Also, avoid violating other building or life safety codes when the door swing is reversed.

603.3 Mirrors. Mirrors located above lavatories or countertops shall be installed with the bottom edge of the reflecting surface 40 inches (1015 mm) maximum above the finish floor or ground. Mirrors not located above lavatories or countertops shall be installed with the bottom edge of the reflecting surface 35 inches (890 mm) maximum above the finish floor or ground.

Advisory 603.3 Mirrors. A single full-length mirror can accommodate a greater number of people, including children. In order for mirrors to be usable by people who are ambulatory and people who use wheelchairs, the top edge of mirrors should be 74 inches (1880 mm) minimum from the floor or ground.

603.4 Coat Hooks and Shelves. Coat hooks shall be located within one of the reach ranges specified in 308. Shelves shall be located 40 inches (1015 mm) minimum and 48 inches (1220 mm) maximum above the finish floor.

604 Water Closets and Toilet Compartments

604.1 General. Water closets and toilet compartments shall comply with 604.2 through 604.8.

EXCEPTION: Water closets and toilet compartments for *children's use* shall be permitted to comply with 604.9.

604.2 Location. The water closet shall be positioned with a wall or partition to the rear and to one side. The centerline of the water closet shall be 16 inches (405 mm) minimum to 18 inches (455 mm) maximum from the side wall or partition, except that the water closet shall be 17 inches (430 mm) minimum and 19 inches (485 mm) maximum from the side wall or partition in the ambulatory *accessible* toilet compartment specified in 604.8.2. Water closets shall be arranged for a left-hand or right-hand approach.




Figure 604.2
Water Closet Location

604.3 Clearance. Clearances around water closets and in toilet compartments shall comply with 604.3.

604.3.1 Size. Clearance around a water closet shall be 60 inches (1525 mm) minimum measured perpendicular from the side wall and 56 inches (1420 mm) minimum measured perpendicular from the rear wall.




Figure 604.3.1
Size of Clearance at Water Closets

604.3.2 Overlap. The required clearance around the water closet shall be permitted to overlap the water closet, associated grab bars, dispensers, sanitary napkin disposal units, coat hooks, shelves, *accessible* routes, clear floor *space* and clearances required at other fixtures, and the turning *space*. No other fixtures or obstructions shall be located within the required water closet clearance.

EXCEPTION: In *residential dwelling units*, a lavatory complying with 606 shall be permitted on the rear wall 18 inches (455 mm) minimum from the water closet centerline where the clearance at the water closet is 66 inches (1675 mm) minimum measured perpendicular from the rear wall.

Advisory 604.3.2 Overlap. When the door to the toilet room is placed directly in front of the water closet, the water closet cannot overlap the required maneuvering clearance for the door inside the room.




Figure 604.3.2 (Exception)
Overlap of Water Closet Clearance in Residential Dwelling Units

604.4 Seats. The seat height of a water closet above the finish floor shall be 17 inches (430 mm) minimum and 19 inches (485 mm) maximum measured to the top of the seat. Seats shall not be sprung to return to a lifted position.

EXCEPTIONS: 1. A water closet in a toilet room for a single occupant accessed only through a private office and not for *common use* or *public use* shall not be required to comply with 604.4.

2. In *residential dwelling units*, the height of water closets shall be permitted to be 15 inches (380 mm) minimum and 19 inches (485 mm) maximum above the finish floor measured to the top of the seat.

604.5 Grab Bars. Grab bars for water closets shall comply with 609. Grab bars shall be provided on the side wall closest to the water closet and on the rear wall.

EXCEPTIONS: 1. Grab bars shall not be required to be installed in a toilet room for a single occupant accessed only through a private office and not for *common use* or *public use* provided that reinforcement has been installed in walls and located so as to permit the installation of grab bars complying with 604.5.

2. In *residential dwelling units*, grab bars shall not be required to be installed in toilet or bathrooms provided that reinforcement has been installed in walls and located so as to permit the installation of grab bars complying with 604.5.

3. In detention or correction *facilities*, grab bars shall not be required to be installed in housing or holding cells that are specially designed without protrusions for purposes of suicide prevention.

Advisory 604.5 Grab Bars Exception 2. Reinforcement must be sufficient to permit the installation of rear and side wall grab bars that fully meet all accessibility requirements including, but not limited to, required length, installation height, and structural strength.

604.5.1 Side Wall. The side wall grab bar shall be 42 inches (1065 mm) long minimum, located 12 inches (305 mm) maximum from the rear wall and extending 54 inches (1370 mm) minimum from the rear wall.




Figure 604.5.1
Side Wall Grab Bar at Water Closets

604.5.2 Rear Wall. The rear wall grab bar shall be 36 inches (915 mm) long minimum and extend from the centerline of the water closet 12 inches (305 mm) minimum on one side and 24 inches (610 mm) minimum on the other side.

EXCEPTIONS: 1. The rear grab bar shall be permitted to be 24 inches (610 mm) long minimum, centered on the water closet, where wall *space* does not permit a length of 36 inches (915 mm) minimum due to the location of a recessed fixture adjacent to the water closet.

2. Where an *administrative authority* requires flush controls for flush valves to be located in a position that conflicts with the location of the rear grab bar, then the rear grab bar shall be permitted to be split or shifted to the open side of the toilet area.




Figure 604.5.2
Rear Wall Grab Bar at Water Closets

604.6 Flush Controls. Flush controls shall be hand operated or automatic. Hand operated flush controls shall comply with 309. Flush controls shall be located on the open side of the water closet except in ambulatory *accessible* compartments complying with 604.8.2.

Advisory 604.6 Flush Controls. If plumbing valves are located directly behind the toilet seat, flush valves and related plumbing can cause injury or imbalance when a person leans back against them. To prevent causing injury or imbalance, the plumbing can be located behind walls or to the side of the toilet; or if approved by the local authority having jurisdiction, provide a toilet seat lid.

604.7 Dispensers. Toilet paper dispensers shall comply with 309.4 and shall be 7 inches (180 mm) minimum and 9 inches (230 mm) maximum in front of the water closet measured to the centerline of the dispenser. The outlet of the dispenser shall be 15 inches (380 mm) minimum and 48 inches (1220 mm) maximum above the finish floor and shall not be located behind grab bars. Dispensers shall not be of a type that controls delivery or that does not allow continuous paper flow.

Advisory 604.7 Dispensers. If toilet paper dispensers are installed above the side wall grab bar, the outlet of the toilet paper dispenser must be 48 inches (1220 mm) maximum above the finish floor and the top of the gripping surface of the grab bar must be 33 inches (840 mm) minimum and 36 inches (915 mm) maximum above the finish floor.




Figure 604.7
Dispenser Outlet Location

604.8 Toilet Compartments. Wheelchair *accessible* toilet compartments shall meet the requirements of 604.8.1 and 604.8.3. Compartments containing more than one plumbing fixture shall comply with 603. Ambulatory *accessible* compartments shall comply with 604.8.2 and 604.8.3.

604.8.1 Wheelchair Accessible Compartments. Wheelchair *accessible* compartments shall comply with 604.8.1.

604.8.1.1 Size. Wheelchair *accessible* compartments shall be 60 inches (1525 mm) wide minimum measured perpendicular to the side wall, and 56 inches (1420 mm) deep minimum for wall hung water closets and 59 inches (1500 mm) deep minimum for floor mounted water closets measured perpendicular to the rear wall. Wheelchair *accessible* compartments for *children's use* shall be 60 inches (1525 mm) wide minimum measured perpendicular to the side wall, and 59 inches (1500 mm) deep minimum for wall hung and floor mounted water closets measured perpendicular to the rear wall.

Advisory 604.8.1.1 Size. The minimum space required in toilet compartments is provided so that a person using a wheelchair can maneuver into position at the water closet. This space cannot be obstructed by baby changing tables or other fixtures or conveniences, except as specified at 604.3.2 (Overlap). If toilet compartments are to be used to house fixtures other than those associated with the water closet, they must be designed to exceed the minimum space requirements. Convenience fixtures such as baby changing tables must also be accessible to people with disabilities as well as to other users. Toilet compartments that are designed to meet, and not exceed, the minimum space requirements may not provide adequate space for maneuvering into position at a baby changing table.




Figure 604.8.1.1
Size of Wheelchair Accessible Toilet Compartment

604.8.1.2 Doors. Toilet compartment doors, including door hardware, shall comply with 404 except that if the approach is to the latch side of the compartment door, clearance between the door side of the compartment and any obstruction shall be 42 inches (1065 mm) minimum. Doors shall be located in the front partition or in the side wall or partition farthest from the water closet. Where located in the front partition, the door opening shall be 4 inches (100 mm) maximum from the side wall or partition farthest from the water closet. Where located in the side wall or partition, the door opening shall be 4 inches (100 mm) maximum from the front partition. The door shall be self-closing. A door pull complying with 404.2.7 shall be placed on both sides of the door near the latch. Toilet compartment doors shall not swing into the minimum required compartment area.




Figure 604.8.1.2
Wheelchair Accessible Toilet Compartment Doors

604.8.1.3 Approach. Compartments shall be arranged for left-hand or right-hand approach to the water closet.

604.8.1.4 Toe Clearance. The front partition and at least one side partition shall provide a toe clearance of 9 inches (230 mm) minimum above the finish floor and 6 inches (150 mm) deep minimum beyond the compartment-side face of the partition, exclusive of partition support members. Compartments for *children's use* shall provide a toe clearance of 12 inches (305 mm) minimum above the finish floor.

EXCEPTION: Toe clearance at the front partition is not required in a compartment greater than 62 inches (1575 mm) deep with a wall-hung water closet or 65 inches (1650 mm) deep with a floor-mounted water closet. Toe clearance at the side partition is not required in a compartment greater than 66 inches (1675 mm) wide. Toe clearance at the front partition is not required in a compartment for *children's use* that is greater than 65 inches (1650 mm) deep.




Figure 604.8.1.4
Wheelchair Accessible Toilet Compartment Toe Clearance

604.8.1.5 Grab Bars. Grab bars shall comply with 609. A side-wall grab bar complying with 604.5.1 shall be provided and shall be located on the wall closest to the water closet. In addition, a rear-wall grab bar complying with 604.5.2 shall be provided.

604.8.2 Ambulatory Accessible Compartments. Ambulatory *accessible* compartments shall comply with 604.8.2.

604.8.2.1 Size. Ambulatory *accessible* compartments shall have a depth of 60 inches (1525 mm) minimum and a width of 35 inches (890 mm) minimum and 37 inches (940 mm) maximum.

604.8.2.2 Doors. Toilet compartment doors, including door hardware, shall comply with 404, except that if the approach is to the latch side of the compartment door, clearance between the door side of the compartment and any obstruction shall be 42 inches (1065 mm) minimum. The door shall be self-closing. A door pull complying with 404.2.7 shall be placed on both sides of the door near the latch. Toilet compartment doors shall not swing into the minimum required compartment area.

604.8.2.3 Grab Bars. Grab bars shall comply with 609. A side-wall grab bar complying with 604.5.1 shall be provided on both sides of the compartment.




Figure 604.8.2
Ambulatory Accessible Toilet Compartment

604.8.3 Coat Hooks and Shelves. Coat hooks shall be located within one of the reach ranges specified in 308. Shelves shall be located 40 inches (1015 mm) minimum and 48 inches (1220 mm) maximum above the finish floor.

604.9 Water Closets and Toilet Compartments for Children's Use. Water closets and toilet compartments for *children's use* shall comply with 604.9.

Advisory 604.9 Water Closets and Toilet Compartments for Children's Use. The requirements in 604.9 are to be followed where the exception for children's water closets in 604.1 is used. The following table provides additional guidance in applying the specifications for water closets for children according to the age group served and reflects the differences in the size, stature, and reach ranges of children ages 3 through 12. The specifications chosen should correspond to the age of the primary user group. The specifications of one age group should be applied consistently in the installation of a water closet and related elements.

Advisory Specifications for Water Closets Serving Children Ages 3 through 12			
	Ages 3 and 4	Ages 5 through 8	Ages 9 through 12
Water Closet Centerline	12 inches (305 mm)	12 to 15 inches (305 to 380 mm)	15 to 18 inches (380 to 455 mm)
Toilet Seat Height	11 to 12 inches (280 to 305 mm)	12 to 15 inches (305 to 380 mm)	15 to 17 inches (380 to 430 mm)
Grab Bar Height	18 to 20 inches (455 to 510 mm)	20 to 25 inches (510 to 635 mm)	25 to 27 inches (635 to 685 mm)
Dispenser Height	14 inches (355 mm)	14 to 17 inches (355 to 430 mm)	17 to 19 inches (430 to 485 mm)

604.9.1 Location. The water closet shall be located with a wall or partition to the rear and to one side. The centerline of the water closet shall be 12 inches (305 mm) minimum and 18 inches (455 mm) maximum from the side wall or partition, except that the water closet shall be 17 inches (430 mm) minimum and 19 inches (485 mm) maximum from the side wall or partition in the ambulatory *accessible* toilet compartment specified in 604.8.2. Compartments shall be arranged for left-hand or right-hand approach to the water closet.

604.9.2 Clearance. Clearance around a water closet shall comply with 604.3.

604.9.3 Height. The height of water closets shall be 11 inches (280 mm) minimum and 17 inches (430 mm) maximum measured to the top of the seat. Seats shall not be sprung to return to a lifted position.

604.9.4 Grab Bars. Grab bars for water closets shall comply with 604.5.

604.9.5 Flush Controls. Flush controls shall be hand operated or automatic. Hand operated flush controls shall comply with 309.2 and 309.4 and shall be installed 36 inches (915 mm) maximum above the finish floor. Flush controls shall be located on the open side of the water closet except in ambulatory *accessible* compartments complying with 604.8.2.

604.9.6 Dispensers. Toilet paper dispensers shall comply with 309.4 and shall be 7 inches (180 mm) minimum and 9 inches (230 mm) maximum in front of the water closet measured to the centerline of the dispenser. The outlet of the dispenser shall be 14 inches (355 mm) minimum and 19 inches (485 mm) maximum above the finish floor. There shall be a clearance of 1½ inches (38 mm) minimum below the grab bar. Dispensers shall not be of a type that controls delivery or that does not allow continuous paper flow.

604.9.7 Toilet Compartments. Toilet compartments shall comply with 604.8.

605 Urinals

605.1 General. Urinals shall comply with 605.

Advisory 605.1 General. Stall-type urinals provide greater accessibility for a broader range of persons, including people of short stature.

605.2 Height and Depth. Urinals shall be the stall-type or the wall-hung type with the rim 17 inches (430 mm) maximum above the finish floor or ground. Urinals shall be 13½ inches (345 mm) deep minimum measured from the outer face of the urinal rim to the back of the fixture.




Figure 605.2
Height and Depth of Urinals

605.3 Clear Floor Space. A clear floor or ground *space* complying with 305 positioned for forward approach shall be provided.

605.4 Flush Controls. Flush controls shall be hand operated or automatic. Hand operated flush controls shall comply with 309.

606 Lavatories and Sinks

606.1 General. Lavatories and sinks shall comply with 606.

Advisory 606.1 General. If soap and towel dispensers are provided, they must be located within the reach ranges specified in 308. Locate soap and towel dispensers so that they are conveniently usable by a person at the accessible lavatory.

606.2 Clear Floor Space. A clear floor *space* complying with 305, positioned for a forward approach, and knee and toe clearance complying with 306 shall be provided.

EXCEPTIONS: 1. A parallel approach complying with 305 shall be permitted to a kitchen sink in a *space* where a cook top or conventional range is not provided and to wet bars.

2. A lavatory in a toilet room or bathing *facility* for a single occupant accessed only through a private office and not for *common use* or *public use* shall not be required to provide knee and toe clearance complying with 306.
3. In *residential dwelling units*, cabinetry shall be permitted under lavatories and kitchen sinks provided that all of the following conditions are met:
 - (a) the cabinetry can be removed without removal or replacement of the fixture;
 - (b) the finish floor extends under the cabinetry; and
 - (c) the walls behind and surrounding the cabinetry are finished.
4. A knee clearance of 24 inches (610 mm) minimum above the finish floor or ground shall be permitted at lavatories and sinks used primarily by children 6 through 12 years where the rim or counter surface is 31 inches (785 mm) maximum above the finish floor or ground.
5. A parallel approach complying with 305 shall be permitted to lavatories and sinks used primarily by children 5 years and younger.
6. The dip of the overflow shall not be considered in determining knee and toe clearances.
7. No more than one bowl of a multi-bowl sink shall be required to provide knee and toe clearance complying with 306.

606.3 Height. Lavatories and sinks shall be installed with the front of the higher of the rim or counter surface 34 inches (865 mm) maximum above the finish floor or ground.

EXCEPTIONS: 1. A lavatory in a toilet or bathing *facility* for a single occupant accessed only through a private office and not for *common use* or *public use* shall not be required to comply with 606.3.

2. In *residential dwelling unit* kitchens, sinks that are adjustable to variable heights, 29 inches (735 mm) minimum and 36 inches (915 mm) maximum, shall be permitted where rough-in plumbing permits connections of supply and drain pipes for sinks mounted at the height of 29 inches (735 mm).

606.4 Faucets. Controls for faucets shall comply with 309. Hand-operated metering faucets shall remain open for 10 seconds minimum.

606.5 Exposed Pipes and Surfaces. Water supply and drain pipes under lavatories and sinks shall be insulated or otherwise configured to protect against contact. There shall be no sharp or abrasive surfaces under lavatories and sinks.

607 Bathtubs

607.1 General. Bathtubs shall comply with 607.

607.2 Clearance. Clearance in front of bathtubs shall extend the length of the bathtub and shall be 30 inches (760 mm) wide minimum. A lavatory complying with 606 shall be permitted at the control end of the clearance. Where a permanent seat is provided at the head end of the bathtub, the clearance shall extend 12 inches (305 mm) minimum beyond the wall at the head end of the bathtub.




Figure 607.2
Clearance for Bathtubs

607.3 Seat. A permanent seat at the head end of the bathtub or a removable in-tub seat shall be provided. Seats shall comply with 610.

607.4 Grab Bars. Grab bars for bathtubs shall comply with 609 and shall be provided in accordance with 607.4.1 or 607.4.2.

EXCEPTIONS: 1. Grab bars shall not be required to be installed in a bathtub located in a bathing facility for a single occupant accessed only through a private office and not for *common use or public use* provided that reinforcement has been installed in walls and located so as to permit the installation of grab bars complying with 607.4.

2. In *residential dwelling units*, grab bars shall not be required to be installed in bathtubs located in bathing facilities provided that reinforcement has been installed in walls and located so as to permit the installation of grab bars complying with 607.4.

607.4.1 Bathtubs With Permanent Seats. For bathtubs with permanent seats, grab bars shall be provided in accordance with 607.4.1.

607.4.1.1 Back Wall. Two grab bars shall be installed on the back wall, one located in accordance with 609.4 and the other located 8 inches (205 mm) minimum and 10 inches (255 mm) maximum above the rim of the bathtub. Each grab bar shall be installed 15 inches (380 mm) maximum from the head end wall and 12 inches (305 mm) maximum from the control end wall.

607.4.1.2 Control End Wall. A grab bar 24 inches (610 mm) long minimum shall be installed on the control end wall at the front edge of the bathtub.




Figure 607.4.1
Grab Bars for Bathtubs with Permanent Seats

607.4.2 Bathtubs Without Permanent Seats. For bathtubs without permanent seats, grab bars shall comply with 607.4.2.

607.4.2.1 Back Wall. Two grab bars shall be installed on the back wall, one located in accordance with 609.4 and other located 8 inches (205 mm) minimum and 10 inches (255 mm) maximum above the rim of the bathtub. Each grab bar shall be 24 inches (610 mm) long minimum and shall be installed 24 inches (610 mm) maximum from the head end wall and 12 inches (305 mm) maximum from the control end wall.

607.4.2.2 Control End Wall. A grab bar 24 inches (610 mm) long minimum shall be installed on the control end wall at the front edge of the bathtub.

607.4.2.3 Head End Wall. A grab bar 12 inches (305 mm) long minimum shall be installed on the head end wall at the front edge of the bathtub.




Figure 607.4.2
Grab Bars for Bathtubs with Removable In-Tub Seats

607.5 Controls. Controls, other than drain stoppers, shall be located on an end wall. Controls shall be between the bathtub rim and grab bar, and between the open side of the bathtub and the centerline of the width of the bathtub. Controls shall comply with 309.4.




Figure 607.5
Bathtub Control Location

607.6 Shower Spray Unit and Water. A shower spray unit with a hose 59 inches (1500 mm) long minimum that can be used both as a fixed-position shower head and as a hand-held shower shall be provided. The shower spray unit shall have an on/off control with a non-positive shut-off. If an adjustable-height shower head on a vertical bar is used, the bar shall be installed so as not to obstruct the use of grab bars. Bathtub shower spray units shall deliver water that is 120°F (49°C) maximum.

Advisory 607.6 Shower Spray Unit and Water. Ensure that hand-held shower spray units are capable of delivering water pressure substantially equivalent to fixed shower heads.

607.7 Bathtub Enclosures. Enclosures for bathtubs shall not obstruct controls, faucets, shower and spray units or obstruct transfer from wheelchairs onto bathtub seats or into bathtubs. Enclosures on bathtubs shall not have tracks installed on the rim of the open face of the bathtub.

608 Shower Compartments


608.1 General. Shower compartments shall comply with 608.

Advisory 608.1 General. Shower stalls that are 60 inches (1525 mm) wide and have no curb may increase the usability of a bathroom because the shower area provides additional maneuvering space.

608.2 Size and Clearances for Shower Compartments. Shower compartments shall have sizes and clearances complying with 608.2.

608.2.1 Transfer Type Shower Compartments. Transfer type shower compartments shall be 36 inches (915 mm) by 36 inches (915 mm) clear inside dimensions measured at the center points of opposing sides and shall have a 36 inch (915 mm) wide minimum entry on the face of the shower

compartment. Clearance of 36 inches (915 mm) wide minimum by 48 inches (1220 mm) long minimum measured from the control wall shall be provided.




Note: inside finished dimensions measured at the center points of opposing sides

Figure 608.2.1
Transfer Type Shower Compartment Size and Clearance

608.2.2 Standard Roll-In Type Shower Compartments. Standard roll-in type shower compartments shall be 30 inches (760 mm) wide minimum by 60 inches (1525 mm) deep minimum clear inside dimensions measured at center points of opposing sides and shall have a 60 inches (1525 mm) wide minimum entry on the face of the shower compartment.

608.2.2.1 Clearance. A 30 inch (760 mm) wide minimum by 60 inch (1525 mm) long minimum clearance shall be provided adjacent to the open face of the shower compartment.


EXCEPTION: A lavatory complying with 606 shall be permitted on one 30 inch (760 mm) wide minimum side of the clearance provided that it is not on the side of the clearance adjacent to the controls or, where provided, not on the side of the clearance adjacent to the shower seat.



Note: inside finished dimensions measured at the center points of opposing sides

Figure 608.2.2
Standard Roll-In Type Shower Compartment Size and Clearance

608.2.3 Alternate Roll-In Type Shower Compartments. Alternate roll-in type shower compartments shall be 36 inches (915 mm) wide and 60 inches (1525 mm) deep minimum clear inside dimensions measured at center points of opposing sides. A 36 inch (915 mm) wide minimum entry shall be provided at one end of the long side of the compartment.



Note: inside finished dimensions measured at the center points of opposing sides

Figure 608.2.3
Alternate Roll-In Type Shower Compartment Size and Clearance

608.3 Grab Bars. Grab bars shall comply with 609 and shall be provided in accordance with 608.3. Where multiple grab bars are used, required horizontal grab bars shall be installed at the same height above the finish floor.

EXCEPTIONS: 1. Grab bars shall not be required to be installed in a shower located in a bathing facility for a single occupant accessed only through a private office, and not for *common use* or *public use* provided that reinforcement has been installed in walls and located so as to permit the installation of grab bars complying with 608.3.

2. In *residential dwelling units*, grab bars shall not be required to be installed in showers located in bathing facilities provided that reinforcement has been installed in walls and located so as to permit the installation of grab bars complying with 608.3.

608.3.1 Transfer Type Shower Compartments. In transfer type compartments, grab bars shall be provided across the control wall and back wall to a point 18 inches (455 mm) from the control wall.




Figure 608.3.1
Grab Bars for Transfer Type Showers

608.3.2 Standard Roll-In Type Shower Compartments. Where a seat is provided in standard roll-in type shower compartments, grab bars shall be provided on the back wall and the side wall opposite the seat. Grab bars shall not be provided above the seat. Where a seat is not provided in standard roll-in type shower compartments, grab bars shall be provided on three walls. Grab bars shall be installed 6 inches (150 mm) maximum from adjacent walls.




Figure 608.3.2
Grab Bars for Standard Roll-In Type Showers

608.3.3 Alternate Roll-In Type Shower Compartments. In alternate roll-in type shower compartments, grab bars shall be provided on the back wall and the side wall farthest from the compartment entry. Grab bars shall not be provided above the seat. Grab bars shall be installed 6 inches (150 mm) maximum from adjacent walls.




Figure 608.3.3
Grab Bars for Alternate Roll-In Type Showers

608.4 Seats. A folding or non-folding seat shall be provided in transfer type shower compartments. A folding seat shall be provided in roll-in type showers required in *transient lodging* guest rooms with mobility features complying with 806.2. Seats shall comply with 610.

EXCEPTION: In *residential dwelling units*, seats shall not be required in transfer type shower compartments provided that reinforcement has been installed in walls so as to permit the installation of seats complying with 608.4.

608.5 Controls. Controls, faucets, and shower spray units shall comply with 309.4.

608.5.1 Transfer Type Shower Compartments. In transfer type shower compartments, the controls, faucets, and shower spray unit shall be installed on the side wall opposite the seat 38 inches (965 mm) minimum and 48 inches (1220 mm) maximum above the shower floor and shall be located on the control wall 15 inches (380 mm) maximum from the centerline of the seat toward the shower opening.




Figure 608.5.1
Transfer Type Shower Compartment Control Location

608.5.2 Standard Roll-In Type Shower Compartments. In standard roll-in type shower compartments, the controls, faucets, and shower spray unit shall be located above the grab bar, but no higher than 48 inches (1220 mm) above the shower floor. Where a seat is provided, the controls, faucets, and shower spray unit shall be installed on the back wall adjacent to the seat wall and shall be located 27 inches (685 mm) maximum from the seat wall.

Advisory 608.5.2 Standard Roll-in Type Shower Compartments. In standard roll-in type showers without seats, the shower head and operable parts can be located on any of the three walls of the shower without adversely affecting accessibility.




Figure 608.5.2
Standard Roll-In Type Shower Compartment Control Location

608.5.3 Alternate Roll-In Type Shower Compartments. In alternate roll-in type shower compartments, the controls, faucets, and shower spray unit shall be located above the grab bar, but no higher than 48 inches (1220 mm) above the shower floor. Where a seat is provided, the controls, faucets, and shower spray unit shall be located on the side wall adjacent to the seat 27 inches (685 mm) maximum from the side wall behind the seat or shall be located on the back wall opposite the seat 15 inches (380 mm) maximum, left or right, of the centerline of the seat. Where a seat is not provided, the controls, faucets, and shower spray unit shall be installed on the side wall farthest from the compartment entry.




Figure 608.5.3
Alternate Roll-In Type Shower Compartment Control Location

608.6 Shower Spray Unit and Water. A shower spray unit with a hose 59 inches (1500 mm) long minimum that can be used both as a fixed-position shower head and as a hand-held shower shall be provided. The shower spray unit shall have an on/off control with a non-positive shut-off. If an adjustable-height shower head on a vertical bar is used, the bar shall be installed so as not to obstruct the use of grab bars. Shower spray units shall deliver water that is 120°F (49°C) maximum.

EXCEPTION: A fixed shower head located at 48 inches (1220 mm) maximum above the shower finish floor shall be permitted instead of a hand-held spray unit in *facilities* that are not medical care *facilities*, long-term care *facilities*, *transient lodging* guest rooms, or *residential dwelling units*.

Advisory 608.6 Shower Spray Unit and Water. Ensure that hand-held shower spray units are capable of delivering water pressure substantially equivalent to fixed shower heads.

608.7 Thresholds. Thresholds in roll-in type shower compartments shall be ½ inch (13 mm) high maximum in accordance with 303. In transfer type shower compartments, thresholds ½ inch (13 mm) high maximum shall be beveled, rounded, or vertical.

EXCEPTION: A threshold 2 inches (51 mm) high maximum shall be permitted in transfer type shower compartments in existing *facilities* where provision of a ½ inch (13 mm) high threshold would disturb the structural reinforcement of the floor slab.

608.8 Shower Enclosures. Enclosures for shower compartments shall not obstruct controls, faucets, and shower spray units or obstruct transfer from wheelchairs onto shower seats.

609 Grab Bars

609.1 General. Grab bars in toilet *facilities* and bathing *facilities* shall comply with 609.

609.2 Cross Section. Grab bars shall have a cross section complying with 609.2.1 or 609.2.2.

609.2.1 Circular Cross Section. Grab bars with circular cross sections shall have an outside diameter of 1¼ inches (32 mm) minimum and 2 inches (51 mm) maximum.

609.2.2 Non-Circular Cross Section. Grab bars with non-circular cross sections shall have a cross-section dimension of 2 inches (51 mm) maximum and a perimeter dimension of 4 inches (100 mm) minimum and 4.8 inches (120 mm) maximum.




Figure 609.2.2
Grab Bar Non-Circular Cross Section

609.3 Spacing. The *space* between the wall and the grab bar shall be 1½ inches (38 mm). The *space* between the grab bar and projecting objects below and at the ends shall be 1½ inches (38 mm) minimum. The *space* between the grab bar and projecting objects above shall be 12 inches (305 mm) minimum.

EXCEPTION: The *space* between the grab bars and shower controls, shower fittings, and other grab bars above shall be permitted to be 1½ inches (38 mm) minimum.




Figure 609.3
Spacing of Grab Bars

609.4 Position of Grab Bars. Grab bars shall be installed in a horizontal position, 33 inches (840 mm) minimum and 36 inches (915 mm) maximum above the finish floor measured to the top of the gripping surface, except that at water closets for *children's use* complying with 604.9, grab bars shall be installed in a horizontal position 18 inches (455 mm) minimum and 27 inches (685 mm) maximum above the finish floor measured to the top of the gripping surface. The height of the lower grab bar on the back wall of a bathtub shall comply with 607.4.1.1 or 607.4.2.1.

609.5 Surface Hazards. Grab bars and any wall or other surfaces adjacent to grab bars shall be free of sharp or abrasive *elements* and shall have rounded edges.

609.6 Fittings. Grab bars shall not rotate within their fittings.

609.7 Installation. Grab bars shall be installed in any manner that provides a gripping surface at the specified locations and that does not obstruct the required clear floor *space*.

609.8 Structural Strength. Allowable stresses shall not be exceeded for materials used when a vertical or horizontal force of 250 pounds (1112 N) is applied at any point on the grab bar, fastener, mounting device, or supporting structure.

610 Seats

610.1 General. Seats in bathtubs and shower compartments shall comply with 610.

610.2 Bathtub Seats. The top of bathtub seats shall be 17 inches (430 mm) minimum and 19 inches (485 mm) maximum above the bathroom finish floor. The depth of a removable in-tub seat shall be 15 inches (380 mm) minimum and 16 inches (405 mm) maximum. The seat shall be capable of secure placement. Permanent seats at the head end of the bathtub shall be 15 inches (380 mm) deep minimum and shall extend from the back wall to or beyond the outer edge of the bathtub.




Figure 610.2
Bathtub Seats

610.3 Shower Compartment Seats. Where a seat is provided in a standard roll-in shower compartment, it shall be a folding type, shall be installed on the side wall adjacent to the controls, and shall extend from the back wall to a point within 3 inches (75 mm) of the compartment entry. Where a seat is provided in an alternate roll-in type shower compartment, it shall be a folding type, shall be installed on the front wall opposite the back wall, and shall extend from the adjacent side wall to a point within 3 inches (75 mm) of the compartment entry. In transfer-type showers, the seat shall extend from the back wall to a point within 3 inches (75 mm) of the compartment entry. The top of the seat shall be 17 inches (430 mm) minimum and 19 inches (485 mm) maximum above the bathroom finish floor. Seats shall comply with 610.3.1 or 610.3.2.




Figure 610.3
Extent of Seat

610.3.1 Rectangular Seats. The rear edge of a rectangular seat shall be 2½ inches (64 mm) maximum and the front edge 15 inches (380 mm) minimum and 16 inches (405 mm) maximum from

the seat wall. The side edge of the seat shall be $1\frac{1}{2}$ inches (38 mm) maximum from the adjacent wall.




Figure 610.3.1
Rectangular Shower Seat

610.3.2 L-Shaped Seats. The rear edge of an L-shaped seat shall be $2\frac{1}{2}$ inches (64 mm) maximum and the front edge 15 inches (380 mm) minimum and 16 inches (405 mm) maximum from the seat wall. The rear edge of the "L" portion of the seat shall be $1\frac{1}{2}$ inches (38 mm) maximum from the wall and the front edge shall be 14 inches (355 mm) minimum and 15 inches (380 mm) maximum from the wall. The end of the "L" shall be 22 inches (560 mm) minimum and 23 inches maximum (585 mm) from the main seat wall.




Figure 610.3.2
L-Shaped Shower Seat

610.4 Structural Strength. Allowable stresses shall not be exceeded for materials used when a vertical or horizontal force of 250 pounds (1112 N) is applied at any point on the seat, fastener, mounting device, or supporting structure.

611 Washing Machines and Clothes Dryers

611.1 General. Washing machines and clothes dryers shall comply with 611.

611.2 Clear Floor Space. A clear floor or ground *space* complying with 305 positioned for parallel approach shall be provided. The clear floor or ground *space* shall be centered on the appliance.

611.3 Operable Parts. *Operable parts*, including doors, lint screens, and detergent and bleach compartments shall comply with 309.

611.4 Height. Top loading machines shall have the door to the laundry compartment located 36 inches (915 mm) maximum above the finish floor. Front loading machines shall have the bottom of the opening to the laundry compartment located 15 inches (380 mm) minimum and 36 inches (915 mm) maximum above the finish floor.




Figure 611.4
Height of Laundry Compartment Opening

612 Saunas and Steam Rooms

612.1 General. Saunas and steam rooms shall comply with 612.

612.2 Bench. Where seating is provided in saunas and steam rooms, at least one bench shall comply with 903. Doors shall not swing into the clear floor *space* required by 903.2.

EXCEPTION: A readily removable bench shall be permitted to obstruct the turning *space* required by 612.3 and the clear floor or ground *space* required by 903.2.

612.3 Turning Space. A turning *space* complying with 304 shall be provided within saunas and steam rooms.

CHAPTER 7: COMMUNICATION ELEMENTS AND FEATURES

701 General

701.1 Scope. The provisions of Chapter 7 shall apply where required by Chapter 2 or where referenced by a requirement in this document.

702 Fire Alarm Systems

702.1 General. Fire alarm systems shall have permanently installed audible and visible alarms complying with NFPA 72 (1999 or 2002 edition) (incorporated by reference, see "Referenced Standards" in Chapter 1), except that the maximum allowable sound level of audible notification appliances complying with section 4-3.2.1 of NFPA 72 (1999 edition) shall have a sound level no more than 110 dB at the minimum hearing distance from the audible appliance. In addition, alarms in guest rooms required to provide communication features shall comply with sections 4-3 and 4-4 of NFPA 72 (1999 edition) or sections 7.4 and 7.5 of NFPA 72 (2002 edition).

EXCEPTION: Fire alarm systems in medical care *facilities* shall be permitted to be provided in accordance with industry practice.

703 Signs

703.1 General. Signs shall comply with 703. Where both visual and *tactile characters* are required, either one sign with both visual and *tactile characters*, or two separate signs, one with visual, and one with *tactile characters*, shall be provided.

703.2 Raised Characters. Raised *characters* shall comply with 703.2 and shall be duplicated in braille complying with 703.3. Raised *characters* shall be installed in accordance with 703.4.

Advisory 703.2 Raised Characters. Signs that are designed to be read by touch should not have sharp or abrasive edges.

703.2.1 Depth. Raised *characters* shall be 1/32 inch (0.8 mm) minimum above their background.

703.2.2 Case. *Characters* shall be uppercase.

703.2.3 Style. *Characters* shall be sans serif. *Characters* shall not be italic, oblique, script, highly decorative, or of other unusual forms.

703.2.4 Character Proportions. *Characters* shall be selected from fonts where the width of the uppercase letter "O" is 55 percent minimum and 110 percent maximum of the height of the uppercase letter "I".

703.2.5 Character Height. *Character* height measured vertically from the baseline of the *character* shall be 5/8 inch (16 mm) minimum and 2 inches (51 mm) maximum based on the height of the uppercase letter "I".

EXCEPTION: Where separate raised and visual *characters* with the same information are provided, raised *character* height shall be permitted to be ½ inch (13 mm) minimum.




Figure 703.2.5
Height of Raised Characters

703.2.6 Stroke Thickness. Stroke thickness of the uppercase letter "I" shall be 15 percent maximum of the height of the *character*.

703.2.7 Character Spacing. *Character* spacing shall be measured between the two closest points of adjacent raised *characters* within a message, excluding word *spaces*. Where *characters* have rectangular cross sections, spacing between individual raised *characters* shall be 1/8 inch (3.2 mm) minimum and 4 times the raised *character* stroke width maximum. Where *characters* have other cross sections, spacing between individual raised *characters* shall be 1/16 inch (1.6 mm) minimum and 4 times the raised *character* stroke width maximum at the base of the cross sections, and 1/8 inch (3.2 mm) minimum and 4 times the raised *character* stroke width maximum at the top of the cross sections. *Characters* shall be separated from raised borders and decorative *elements* 3/8 inch (9.5 mm) minimum.

703.2.8 Line Spacing. Spacing between the baselines of separate lines of raised *characters* within a message shall be 135 percent minimum and 170 percent maximum of the raised *character* height.

703.3 Braille. Braille shall be contracted (Grade 2) and shall comply with 703.3 and 703.4.

703.3.1 Dimensions and Capitalization. Braille dots shall have a domed or rounded shape and shall comply with Table 703.3.1. The indication of an uppercase letter or letters shall only be used before the first word of sentences, proper nouns and names, individual letters of the alphabet, initials, and acronyms.

Table 703.3.1 Braille Dimensions

Measurement Range	Minimum in Inches Maximum in Inches
Dot base diameter	0.059 (1.5 mm) to 0.063 (1.6 mm)
Distance between two dots in the same cell ¹	0.090 (2.3 mm) to 0.100 (2.5 mm)
Distance between corresponding dots in adjacent cells ¹	0.241 (6.1 mm) to 0.300 (7.6 mm)
Dot height	0.025 (0.6 mm) to 0.037 (0.9 mm)
Distance between corresponding dots from one cell directly below ¹	0.395 (10 mm) to 0.400 (10.2 mm)

1. Measured center to center.




Figure 703.3.1
Braille Measurement

703.3.2 Position. Braille shall be positioned below the corresponding text. If text is multi-lined, braille shall be placed below the entire text. Braille shall be separated 3/8 inch (9.5 mm) minimum from any other *tactile characters* and 3/8 inch (9.5 mm) minimum from raised borders and decorative *elements*.

EXCEPTION: Braille provided on elevator car controls shall be separated 3/16 inch (4.8 mm) minimum and shall be located either directly below or adjacent to the corresponding raised *characters* or symbols.




Figure 703.3.2
Position of Braille

703.4 Installation Height and Location. Signs with *tactile characters* shall comply with 703.4.

703.4.1 Height Above Finish Floor or Ground. *Tactile characters* on signs shall be located 48 inches (1220 mm) minimum above the finish floor or ground surface, measured from the baseline of the lowest *tactile character* and 60 inches (1525 mm) maximum above the finish floor or ground surface, measured from the baseline of the highest *tactile character*.

EXCEPTION: *Tactile characters* for elevator car controls shall not be required to comply with 703.4.1.




Figure 703.4.1
Height of Tactile Characters Above Finish Floor or Ground

703.4.2 Location. Where a *tactile* sign is provided at a door, the sign shall be located alongside the door at the latch side. Where a *tactile* sign is provided at double doors with one active leaf, the sign shall be located on the inactive leaf. Where a *tactile* sign is provided at double doors with two active leaves, the sign shall be located to the right of the right hand door. Where there is no wall space at the latch side of a single door or at the right side of double doors, signs shall be located on the nearest adjacent wall. Signs containing *tactile characters* shall be located so that a clear floor space of 18 inches (455 mm) minimum by 18 inches (455 mm) minimum, centered on the *tactile characters*, is provided beyond the arc of any door swing between the closed position and 45 degree open position.

EXCEPTION: Signs with *tactile characters* shall be permitted on the push side of doors with closers and without hold-open devices.




Figure 703.4.2
Location of Tactile Signs at Doors

703.5 Visual Characters. Visual *characters* shall comply with 703.5.

EXCEPTION: Where visual *characters* comply with 703.2 and are accompanied by braille complying with 703.3, they shall not be required to comply with 703.5.2 through 703.5.9.

703.5.1 Finish and Contrast. *Characters* and their background shall have a non-glare finish. *Characters* shall contrast with their background with either light *characters* on a dark background or dark *characters* on a light background.

Advisory 703.5.1 Finish and Contrast. Signs are more legible for persons with low vision when characters contrast as much as possible with their background. Additional factors affecting the ease with which the text can be distinguished from its background include shadows cast by lighting sources, surface glare, and the uniformity of the text and its background colors and textures.

703.5.2 Case. *Characters* shall be uppercase or lowercase or a combination of both.

703.5.3 Style. *Characters* shall be conventional in form. *Characters* shall not be italic, oblique, script, highly decorative, or of other unusual forms.

703.5.4 Character Proportions. *Characters* shall be selected from fonts where the width of the uppercase letter "O" is 55 percent minimum and 110 percent maximum of the height of the uppercase letter "I".

703.5.5 Character Height. Minimum *character* height shall comply with Table 703.5.5. Viewing distance shall be measured as the horizontal distance between the *character* and an obstruction preventing further approach towards the sign. *Character* height shall be based on the uppercase letter "I".

Table 703.5.5 Visual Character Height

Height to Finish Floor or Ground From Baseline of Character	Horizontal Viewing Distance	Minimum Character Height
40 inches (1015 mm) to less than or equal to 70 inches (1780 mm)	less than 72 inches (1830 mm)	5/8 inch (16 mm)
	72 inches (1830 mm) and greater	5/8 inch (16 mm), plus 1/8 inch (3.2 mm) per foot (305 mm) of viewing distance above 72 inches (1830 mm)
Greater than 70 inches (1780 mm) to less than or equal to 120 inches (3050 mm)	less than 180 inches (4570 mm)	2 inches (51 mm)
	180 inches (4570 mm) and greater	2 inches (51 mm), plus 1/8 inch (3.2 mm) per foot (305 mm) of viewing distance above 180 inches (4570 mm)
greater than 120 inches (3050 mm)	less than 21 feet (6400 mm)	3 inches (75 mm)
	21 feet (6400 mm) and greater	3 inches (75 mm), plus 1/8 inch (3.2 mm) per foot (305 mm) of viewing distance above 21 feet (6400 mm)

703.5.6 Height From Finish Floor or Ground. Visual *characters* shall be 40 inches (1015 mm) minimum above the finish floor or ground.

EXCEPTION: Visual *characters* indicating elevator car controls shall not be required to comply with 703.5.6.

703.5.7 Stroke Thickness. Stroke thickness of the uppercase letter "I" shall be 10 percent minimum and 30 percent maximum of the height of the *character*.

703.5.8 Character Spacing. *Character* spacing shall be measured between the two closest points of adjacent *characters*, excluding word *spaces*. Spacing between individual *characters* shall be 10 percent minimum and 35 percent maximum of *character* height.

703.5.9 Line Spacing. Spacing between the baselines of separate lines of *characters* within a message shall be 135 percent minimum and 170 percent maximum of the *character* height.

703.6 Pictograms. *Pictograms* shall comply with 703.6.

703.6.1 Pictogram Field. *Pictograms* shall have a field height of 6 inches (150 mm) minimum. *Characters* and braille shall not be located in the *pictogram* field.




Figure 703.6.1
Pictogram Field

703.6.2 Finish and Contrast. *Pictograms* and their field shall have a non-glare finish. *Pictograms* shall contrast with their field with either a light *pictogram* on a dark field or a dark *pictogram* on a light field.

Advisory 703.6.2 Finish and Contrast. Signs are more legible for persons with low vision when characters contrast as much as possible with their background. Additional factors affecting the ease with which the text can be distinguished from its background include shadows cast by lighting sources, surface glare, and the uniformity of the text and background colors and textures.

703.6.3 Text Descriptors. *Pictograms* shall have text descriptors located directly below the *pictogram* field. Text descriptors shall comply with 703.2, 703.3 and 703.4.

703.7 Symbols of Accessibility. Symbols of *accessibility* shall comply with 703.7.

703.7.1 Finish and Contrast. Symbols of *accessibility* and their background shall have a non-glare finish. Symbols of *accessibility* shall contrast with their background with either a light symbol on a dark background or a dark symbol on a light background.

Advisory 703.7.1 Finish and Contrast. Signs are more legible for persons with low vision when characters contrast as much as possible with their background. Additional factors affecting the ease with which the text can be distinguished from its background include shadows cast by lighting sources, surface glare, and the uniformity of the text and background colors and textures.

703.7.2 Symbols.

703.7.2.1 International Symbol of Accessibility. The International Symbol of *Accessibility* shall comply with Figure 703.7.2.1.



Figure 703.7.2.1
International Symbol of Accessibility

703.7.2.2 International Symbol of TTY. The International Symbol of *TTY* shall comply with Figure 703.7.2.2.




Figure 703.7.2.2
International Symbol of TTY

703.7.2.3 Volume Control Telephones. Telephones with a volume control shall be identified by a *pictogram* of a telephone handset with radiating sound waves on a square field such as shown in Figure 703.7.2.3.



Figure 703.7.2.3
Volume Control Telephone

703.7.2.4 Assistive Listening Systems. *Assistive listening systems* shall be identified by the International Symbol of Access for Hearing Loss complying with Figure 703.7.2.4.



Figure 703.7.2.4
International Symbol of Access for Hearing Loss

704 Telephones

704.1 General. Public telephones shall comply with 704.

704.2 Wheelchair Accessible Telephones. Wheelchair *accessible* telephones shall comply with 704.2.

704.2.1 Clear Floor or Ground Space. A clear floor or ground *space* complying with 305 shall be provided. The clear floor or ground *space* shall not be obstructed by bases, enclosures, or seats.

Advisory 704.2.1 Clear Floor or Ground Space. Because clear floor and ground space is required to be unobstructed, telephones, enclosures and related telephone book storage cannot encroach on the required clear floor or ground space and must comply with the provisions for protruding objects. (See Section 307).

704.2.1.1 Parallel Approach. Where a parallel approach is provided, the distance from the edge of the telephone enclosure to the face of the telephone unit shall be 10 inches (255 mm) maximum.




Figure 704.2.1.1
Parallel Approach to Telephone

704.2.1.2 Forward Approach. Where a forward approach is provided, the distance from the front edge of a counter within the telephone enclosure to the face of the telephone unit shall be 20 inches (510 mm) maximum.




Figure 704.2.1.2
Forward Approach to Telephone

704.2.2 Operable Parts. *Operable parts* shall comply with 309. Telephones shall have push-button controls where such service is available.

704.2.3 Telephone Directories. Telephone directories, where provided, shall be located in accordance with 309.

704.2.4 Cord Length. The cord from the telephone to the handset shall be 29 inches (735 mm) long minimum.

704.3 Volume Control Telephones. Public telephones required to have volume controls shall be equipped with a receive volume control that provides a gain adjustable up to 20 dB minimum. For incremental volume control, provide at least one intermediate step of 12 dB of gain minimum. An automatic reset shall be provided.

Advisory 704.3 Volume Control Telephones. Amplifiers on pay phones are located in the base or the handset or are built into the telephone. Most are operated by pressing a button or key. If the microphone in the handset is not being used, a mute button that temporarily turns off the microphone can also reduce the amount of background noise which the person hears in the earpiece. If a volume adjustment is provided that allows the user to set the level anywhere from the base volume to the upper requirement of 20 dB, there is no need to specify a lower limit. If a stepped volume control is provided, one of the intermediate levels must provide 12 dB of gain. Consider compatibility issues when matching an amplified handset with a phone or phone system. Amplified handsets that can be switched with pay telephone handsets are available. Portable and in-line amplifiers can be used with some phones but are not practical at most public phones covered by these requirements.

704.4 TTYs. *TTYs* required at a public pay telephone shall be permanently affixed within, or adjacent to, the telephone enclosure. Where an acoustic coupler is used, the telephone cord shall be sufficiently long to allow connection of the *TTY* and the telephone receiver.

Advisory 704.4 TTYs. Ensure that sufficient electrical service is available where *TTYs* are to be installed.

704.4.1 Height. When in use, the touch surface of *TTY* keypads shall be 34 inches (865 mm) minimum above the finish floor.

EXCEPTION: Where seats are provided, *TTYs* shall not be required to comply with 704.4.1.

Advisory 704.4.1 Height. A telephone with a *TTY* installed underneath cannot also be a wheelchair accessible telephone because the required 34 inches (865 mm) minimum keypad height can cause the highest operable part of the telephone, usually the coin slot, to exceed the maximum permitted side and forward reach ranges. (See Section 308).

Advisory 704.4.1 Height Exception. While seats are not required at *TTYs*, reading and typing at a *TTY* is more suited to sitting than standing. Facilities that often provide seats at *TTYs* include, but are not limited to, airports and other passenger terminals or stations, courts, art galleries, and convention centers.

704.5 TTY Shelf. Public pay telephones required to accommodate portable *TTYs* shall be equipped with a shelf and an electrical outlet within or adjacent to the telephone enclosure. The telephone handset shall be capable of being placed flush on the surface of the shelf. The shelf shall be capable of accommodating a *TTY* and shall have 6 inches (150 mm) minimum vertical clearance above the area where the *TTY* is to be placed.

705 Detectable Warnings

705.1 General. *Detectable warnings* shall consist of a surface of truncated domes and shall comply with 705.

705.1.1 Dome Size. Truncated domes in a *detectable warning* surface shall have a base diameter of 0.9 inch (23 mm) minimum and 1.4 inches (36 mm) maximum, a top diameter of 50 percent of the base diameter minimum to 65 percent of the base diameter maximum, and a height of 0.2 inch (5.1 mm).

705.1.2 Dome Spacing. Truncated domes in a *detectable warning* surface shall have a center-to-center spacing of 1.6 inches (41 mm) minimum and 2.4 inches (61 mm) maximum, and a base-to-base spacing of 0.65 inch (17 mm) minimum, measured between the most adjacent domes on a square grid.

705.1.3 Contrast. *Detectable warning* surfaces shall contrast visually with adjacent walking surfaces either light-on-dark, or dark-on-light.




Figure 705.1
Size and Spacing of Truncated Domes

705.2 Platform Edges. *Detectable warning surfaces* at platform boarding edges shall be 24 inches (610 mm) wide and shall extend the full length of the *public use areas* of the platform.

706 Assistive Listening Systems

706.1 General. *Assistive listening systems* required in *assembly areas* shall comply with 706.

Advisory 706.1 General. Assistive listening systems are generally categorized by their mode of transmission. There are hard-wired systems and three types of wireless systems: induction loop, infrared, and FM radio transmission. Each has different advantages and disadvantages that can help determine which system is best for a given application. For example, an FM system may be better than an infrared system in some open-air assemblies since infrared signals are less effective in sunlight. On the other hand, an infrared system is typically a better choice than an FM system where confidential transmission is important because it will be contained within a given space.

The technical standards for assistive listening systems describe minimum performance levels for volume, interference, and distortion. Sound pressure levels (SPL), expressed in decibels, measure output sound volume. Signal-to-noise ratio (SNR or S/N), also expressed in decibels, represents the relationship between the loudness of a desired sound (the signal) and the background noise in a space or piece of equipment. The higher the SNR, the more intelligible the signal. The peak clipping level limits the distortion in signal output produced when high-volume sound waves are manipulated to serve assistive listening devices.

Selecting or specifying an effective assistive listening system for a large or complex venue requires assistance from a professional sound engineer. The Access Board has published technical assistance on assistive listening devices and systems.

706.2 Receiver Jacks. Receivers required for use with an *assistive listening system* shall include a 1/8 inch (3.2 mm) standard mono jack.

706.3 Receiver Hearing-Aid Compatibility. Receivers required to be hearing-aid compatible shall interface with telecoils in hearing aids through the provision of neckloops.

Advisory 706.3 Receiver Hearing-Aid Compatibility. Neckloops and headsets that can be worn as neckloops are compatible with hearing aids. Receivers that are not compatible include earbuds, which may require removal of hearing aids, earphones, and headsets that must be worn over the ear, which can create disruptive interference in the transmission and can be uncomfortable for people wearing hearing aids.

706.4 Sound Pressure Level. *Assistive listening systems* shall be capable of providing a sound pressure level of 110 dB minimum and 118 dB maximum with a dynamic range on the volume control of 50 dB.

706.5 Signal-to-Noise Ratio. The signal-to-noise ratio for internally generated noise in *assistive listening systems* shall be 18 dB minimum.

706.6 Peak Clipping Level. Peak clipping shall not exceed 18 dB of clipping relative to the peaks of speech.

707 Automatic Teller Machines and Fare Machines

Advisory 707 Automatic Teller Machines and Fare Machines. Interactive transaction machines (ITMs), other than ATMs, are not covered by Section 707. However, for entities covered by the ADA, the Department of Justice regulations that implement the ADA provide additional guidance regarding the relationship between these requirements and elements that are not directly addressed by these requirements. Federal procurement law requires that ITMs purchased by the Federal government comply with standards issued by the Access Board under Section 508 of the Rehabilitation Act of 1973, as amended. This law covers a variety of products, including computer hardware and software, websites, phone systems, fax machines, copiers, and similar technologies. For more information on Section 508 consult the Access Board's website at www.access-board.gov.

707.1 General. Automatic teller machines and fare machines shall comply with 707.

Advisory 707.1 General. If farecards have one tactually distinctive corner they can be inserted with greater accuracy. Token collection devices that are designed to accommodate tokens which are perforated can allow a person to distinguish more readily between tokens and common coins. Place accessible gates and fare vending machines in close proximity to other accessible elements when feasible so the facility is easier to use.

707.2 Clear Floor or Ground Space. A clear floor or ground *space* complying with 305 shall be provided.

EXCEPTION: Clear floor or ground *space* shall not be required at drive-up only automatic teller machines and fare machines.

707.3 Operable Parts. *Operable parts* shall comply with 309. Unless a clear or correct key is provided, each *operable part* shall be able to be differentiated by sound or touch, without activation.

EXCEPTION: Drive-up only automatic teller machines and fare machines shall not be required to comply with 309.2 and 309.3.

707.4 Privacy. Automatic teller machines shall provide the opportunity for the same degree of privacy of input and output available to all individuals.

Advisory 707.4 Privacy. In addition to people who are blind or visually impaired, people with limited reach who use wheelchairs or have short stature, who cannot effectively block the ATM screen with their bodies, may prefer to use speech output. Speech output users can benefit from an option to render the visible screen blank, thereby affording them greater personal security and privacy.

707.5 Speech Output. Machines shall be speech enabled. Operating instructions and orientation, visible transaction prompts, user input verification, error messages, and all displayed information for full use shall be *accessible* to and independently usable by individuals with vision impairments. Speech shall be delivered through a mechanism that is readily available to all users, including but not limited to, an industry standard connector or a telephone handset. Speech shall be recorded or digitized human, or synthesized.

EXCEPTIONS: 1. Audible tones shall be permitted instead of speech for visible output that is not displayed for security purposes, including but not limited to, asterisks representing personal identification numbers.

2. Advertisements and other similar information shall not be required to be audible unless they convey information that can be used in the transaction being conducted.

3. Where speech synthesis cannot be supported, dynamic alphabetic output shall not be required to be audible.

Advisory 707.5 Speech Output. If an ATM provides additional functions such as dispensing coupons, selling theater tickets, or providing copies of monthly statements, all such functions must be available to customers using speech output. To avoid confusion at the ATM, the method of initiating the speech mode should be easily discoverable and should not require specialized training. For example, if a telephone handset is provided, lifting the handset can initiate the speech mode.

707.5.1 User Control. Speech shall be capable of being repeated or interrupted. Volume control shall be provided for the speech function.

EXCEPTION: Speech output for any single function shall be permitted to be automatically interrupted when a transaction is selected.

707.5.2 Receipts. Where receipts are provided, speech output devices shall provide audible balance inquiry information, error messages, and all other information on the printed receipt necessary to complete or verify the transaction.

EXCEPTIONS: 1. Machine location, date and time of transaction, customer account number, and the machine identifier shall not be required to be audible.

2. Information on printed receipts that duplicates information available on-screen shall not be required to be presented in the form of an audible receipt.
3. Printed copies of bank statements and checks shall not be required to be audible.

707.6 Input. Input devices shall comply with 707.6.

707.6.1 Input Controls. At least one *tactilely* discernible input control shall be provided for each function. Where provided, key surfaces not on active areas of display screens, shall be raised above surrounding surfaces. Where membrane keys are the only method of input, each shall be *tactilely* discernable from surrounding surfaces and adjacent keys.

707.6.2 Numeric Keys. Numeric keys shall be arranged in a 12-key ascending or descending telephone keypad layout. The number five key shall be *tactilely* distinct from the other keys.

Advisory 707.6.2 Numeric Keys. Telephone keypads and computer keyboards differ in one significant feature, ascending versus descending numerical order. Both types of keypads are acceptable, provided the computer-style keypad is organized similarly to the number pad located at the right on most computer keyboards, and does not resemble the line of numbers located above the computer keys.




Figure 707.6.2
Numeric Key Layout

707.6.3 Function Keys. Function keys shall comply with 707.6.3.

707.6.3.1 Contrast. Function keys shall contrast visually from background surfaces. *Characters* and symbols on key surfaces shall contrast visually from key surfaces. Visual contrast shall be either light-on-dark or dark-on-light.

EXCEPTION: *Tactile* symbols required by 707.6.3.2 shall not be required to comply with 707.6.3.1.

707.6.3.2 Tactile Symbols. Function key surfaces shall have *tactile* symbols as follows: Enter or Proceed key: raised circle; Clear or Correct key: raised left arrow; Cancel key: raised letter ex; Add Value key: raised plus sign; Decrease Value key: raised minus sign.

707.7 Display Screen. The display screen shall comply with 707.7.

EXCEPTION: Drive-up only automatic teller machines and fare machines shall not be required to comply with 707.7.1.

707.7.1 Visibility. The display screen shall be visible from a point located 40 inches (1015 mm) above the center of the clear floor *space* in front of the machine.

707.7.2 Characters. *Characters* displayed on the screen shall be in a sans serif font. *Characters* shall be 3/16 inch (4.8 mm) high minimum based on the uppercase letter "I". *Characters* shall contrast with their background with either light *characters* on a dark background or dark *characters* on a light background.

707.8 Braille Instructions. Braille instructions for initiating the speech mode shall be provided. Braille shall comply with 703.3.

708 Two-Way Communication Systems

708.1 General. Two-way communication systems shall comply with 708.

Advisory 708.1 General. Devices that do not require handsets are easier to use by people who have a limited reach.

708.2 Audible and Visual Indicators. The system shall provide both audible and visual signals.

Advisory 708.2 Audible and Visual Indicators. A light can be used to indicate visually that assistance is on the way. Signs indicating the meaning of visual signals should be provided.

708.3 Handsets. Handset cords, if provided, shall be 29 inches (735 mm) long minimum.

708.4 Residential Dwelling Unit Communication Systems. Communications systems between a *residential dwelling unit* and a *site, building, or floor entrance* shall comply with 708.4.

708.4.1 Common Use or Public Use System Interface. The *common use* or *public use* system interface shall include the capability of supporting voice and *TTY* communication with the *residential dwelling unit* interface.

708.4.2 Residential Dwelling Unit Interface. The *residential dwelling unit* system interface shall include a telephone jack capable of supporting voice and *TTY* communication with the *common use* or *public use* system interface.

CHAPTER 8: SPECIAL ROOMS, SPACES, AND ELEMENTS

801 General

801.1 Scope. The provisions of Chapter 8 shall apply where required by Chapter 2 or where referenced by a requirement in this document.

Advisory 801.1 Scope. Facilities covered by these requirements are also subject to the requirements of the other chapters. For example, 806 addresses guest rooms in transient lodging facilities while 902 contains the technical specifications for dining surfaces. If a transient lodging facility contains a restaurant, the restaurant must comply with requirements in other chapters such as those applicable to certain dining surfaces.

802 Wheelchair Spaces, Companion Seats, and Designated Aisle Seats

802.1 Wheelchair Spaces. *Wheelchair spaces* shall comply with 802.1.

802.1.1 Floor or Ground Surface. The floor or ground surface of *wheelchair spaces* shall comply with 302. Changes in level are not permitted.

EXCEPTION: Slopes not steeper than 1:48 shall be permitted.

802.1.2 Width. A single *wheelchair space* shall be 36 inches (915 mm) wide minimum. Where two adjacent *wheelchair spaces* are provided, each *wheelchair space* shall be 33 inches (840 mm) wide minimum.




Figure 802.1.2
Width of Wheelchair Spaces

802.1.3 Depth. Where a *wheelchair space* can be entered from the front or rear, the *wheelchair space* shall be 48 inches (1220 mm) deep minimum. Where a *wheelchair space* can be entered only from the side, the *wheelchair space* shall be 60 inches (1525 mm) deep minimum.




Figure 802.1.3
Depth of Wheelchair Spaces

802.1.4 Approach. *Wheelchair spaces shall adjoin accessible routes. Accessible routes shall not overlap wheelchair spaces.*

Advisory 802.1.4 Approach. Because accessible routes serving wheelchair spaces are not permitted to overlap the clear floor space at wheelchair spaces, access to any wheelchair space cannot be through another wheelchair space.

802.1.5 Overlap. *Wheelchair spaces shall not overlap circulation paths.*

Advisory 802.1.5 Overlap. The term "circulation paths" used in Section 802.1.5 means aisle width required by applicable building or life safety codes for the specific assembly occupancy. Where the circulation path provided is wider than the required aisle width, the wheelchair space may intrude into that portion of the circulation path that is provided in excess of the required aisle width.

802.2 Lines of Sight. Lines of sight to the screen, performance area, or playing field for spectators in *wheelchair spaces* shall comply with 802.2.

802.2.1 Lines of Sight Over Seated Spectators. Where spectators are expected to remain seated during events, spectators in *wheelchair spaces* shall be afforded lines of sight complying with 802.2.1.

802.2.1.1 Lines of Sight Over Heads. Where spectators are provided lines of sight over the heads of spectators seated in the first row in front of their seats, spectators seated in *wheelchair spaces* shall be afforded lines of sight over the heads of seated spectators in the first row in front of *wheelchair spaces*.




Figure 802.2.1.1
Lines of Sight Over the Heads of Seated Spectators

802.2.1.2 Lines of Sight Between Heads. Where spectators are provided lines of sight over the shoulders and between the heads of spectators seated in the first row in front of their seats, spectators seated in *wheelchair spaces* shall be afforded lines of sight over the shoulders and between the heads of seated spectators in the first row in front of *wheelchair spaces*.




Figure 802.2.1.2
Lines of Sight Between the Heads of Seated Spectators

802.2.2 Lines of Sight Over Standing Spectators. Where spectators are expected to stand during events, spectators in *wheelchair spaces* shall be afforded lines of sight complying with 802.2.2.

802.2.2.1 Lines of Sight Over Heads. Where standing spectators are provided lines of sight over the heads of spectators standing in the first row in front of their seats, spectators seated in

wheelchair spaces shall be afforded lines of sight over the heads of standing spectators in the first row in front of *wheelchair spaces*.




Figure 802.2.2.1
Lines of Sight Over the Heads of Standing Spectators

802.2.2.2 Lines of Sight Between Heads. Where standing spectators are provided lines of sight over the shoulders and between the heads of spectators standing in the first row in front of their seats, spectators seated in *wheelchair spaces* shall be afforded lines of sight over the shoulders and between the heads of standing spectators in the first row in front of *wheelchair spaces*.




Figure 802.2.2.2
Lines of Sight Between the Heads of Standing Spectators

802.3 Companion Seats. Companion seats shall comply with 802.3.

802.3.1 Alignment. In row seating, companion seats shall be located to provide shoulder alignment with adjacent *wheelchair spaces*. The shoulder alignment point of the *wheelchair space* shall be measured 36 inches (915 mm) from the front of the *wheelchair space*. The floor surface of the companion seat shall be at the same elevation as the floor surface of the *wheelchair space*.

802.3.2 Type. Companion seats shall be equivalent in size, quality, comfort, and amenities to the seating in the immediate area. Companion seats shall be permitted to be movable.

802.4 Designated Aisle Seats. Designated aisle seats shall comply with 802.4.

802.4.1 Armrests. Where armrests are provided on the seating in the immediate area, folding or retractable armrests shall be provided on the aisle side of the seat.

802.4.2 Identification. Each designated aisle seat shall be identified by a sign or marker.

Advisory 802.4.2 Identification. Seats with folding or retractable armrests are intended for use by individuals who have difficulty walking. Consider identifying such seats with signs that contrast (light-on-dark or dark-on-light) and that are also photo luminescent.

803 Dressing, Fitting, and Locker Rooms**803.1 General.** Dressing, fitting, and locker rooms shall comply with 803.

Advisory 803.1 General. Partitions and doors should be designed to ensure people using accessible dressing and fitting rooms privacy equivalent to that afforded other users of the facility. Section 903.5 requires dressing room bench seats to be installed so that they are at the same height as a typical wheelchair seat, 17 inches (430 mm) to 19 inches (485 mm). However, wheelchair seats can be lower than dressing room benches for people of short stature or children using wheelchairs.

803.2 Turning Space. Turning *space* complying with 304 shall be provided within the room.

803.3 Door Swing. Doors shall not swing into the room unless a clear floor or ground *space* complying with 305.3 is provided beyond the arc of the door swing.

803.4 Benches. A bench complying with 903 shall be provided within the room.

803.5 Coat Hooks and Shelves. Coat hooks provided within the room shall be located within one of the reach ranges specified in 308. Shelves shall be 40 inches (1015 mm) minimum and 48 inches (1220 mm) maximum above the finish floor or ground.

804 Kitchens and Kitchenettes**804.1 General.** Kitchens and kitchenettes shall comply with 804.

804.2 Clearance. Where a pass through kitchen is provided, clearances shall comply with 804.2.1. Where a U-shaped kitchen is provided, clearances shall comply with 804.2.2.

EXCEPTION: Spaces that do not provide a cooktop or conventional range shall not be required to comply with 804.2.

Advisory 804.2 Clearance. Clearances are measured from the furthest projecting face of all opposing base cabinets, counter tops, appliances, or walls, excluding hardware.

804.2.1 Pass Through Kitchen. In pass through kitchens where counters, appliances or cabinets are on two opposing sides, or where counters, appliances or cabinets are opposite a parallel wall, clearance between all opposing base cabinets, counter tops, appliances, or walls within kitchen work areas shall be 40 inches (1015 mm) minimum. Pass through kitchens shall have two entries.




Figure 804.2.1
Pass Through Kitchens

804.2.2 U-Shaped. In U-shaped kitchens enclosed on three contiguous sides, clearance between all opposing base cabinets, counter tops, appliances, or walls within kitchen work areas shall be 60 inches (1525 mm) minimum.




Figure 804.2.2
U-Shaped Kitchens

804.3 Kitchen Work Surface. In *residential dwelling units* required to comply with 809, at least one 30 inches (760 mm) wide minimum section of counter shall provide a kitchen work surface that complies with 804.3.

804.3.1 Clear Floor or Ground Space. A clear floor *space* complying with 305 positioned for a forward approach shall be provided. The clear floor or ground *space* shall be centered on the kitchen work surface and shall provide knee and toe clearance complying with 306.

EXCEPTION: Cabinetry shall be permitted under the kitchen work surface provided that all of the following conditions are met:

- (a) the cabinetry can be removed without removal or replacement of the kitchen work surface;
- (b) the finish floor extends under the cabinetry; and
- (c) the walls behind and surrounding the cabinetry are finished.

804.3.2 Height. The kitchen work surface shall be 34 inches (865 mm) maximum above the finish floor or ground.

EXCEPTION: A counter that is adjustable to provide a kitchen work surface at variable heights, 29 inches (735 mm) minimum and 36 inches (915 mm) maximum, shall be permitted.

804.3.3 Exposed Surfaces. There shall be no sharp or abrasive surfaces under the work surface counters.

804.4 Sinks. Sinks shall comply with 606.

804.5 Storage. At least 50 percent of shelf *space* in storage *facilities* shall comply with 811.

804.6 Appliances. Where provided, kitchen appliances shall comply with 804.6.

804.6.1 Clear Floor or Ground Space. A clear floor or ground *space* complying with 305 shall be provided at each kitchen appliance. Clear floor or ground *spaces* shall be permitted to overlap.

804.6.2 Operable Parts. All appliance controls shall comply with 309.

EXCEPTIONS: 1. Appliance doors and door latching devices shall not be required to comply with 309.4.

2. Bottom-hinged appliance doors, when in the open position, shall not be required to comply with 309.3.

804.6.3 Dishwasher. Clear floor or ground *space* shall be positioned adjacent to the dishwasher door. The dishwasher door, in the open position, shall not obstruct the clear floor or ground *space* for the dishwasher or the sink.

804.6.4 Range or Cooktop. Where a forward approach is provided, the clear floor or ground *space* shall provide knee and toe clearance complying with 306. Where knee and toe *space* is provided, the underside of the range or cooktop shall be insulated or otherwise configured to prevent burns, abrasions, or electrical shock. The location of controls shall not require reaching across burners.

804.6.5 Oven. Ovens shall comply with 804.6.5.

804.6.5.1 Side-Hinged Door Ovens. Side-hinged door ovens shall have the work surface required by 804.3 positioned adjacent to the latch side of the oven door.

804.6.5.2 Bottom-Hinged Door Ovens. Bottom-hinged door ovens shall have the work surface required by 804.3 positioned adjacent to one side of the door.

804.6.5.3 Controls. Ovens shall have controls on front panels.

804.6.6 Refrigerator/Freezer. Combination refrigerators and freezers shall have at least 50 percent of the freezer *space* 54 inches (1370 mm) maximum above the finish floor or ground. The clear floor or ground *space* shall be positioned for a parallel approach to the *space* dedicated to a refrigerator/freezer with the centerline of the clear floor or ground *space* offset 24 inches (610 mm) maximum from the centerline of the dedicated *space*.

805 Medical Care and Long-Term Care Facilities

805.1 General. Medical care *facility* and long-term care *facility* patient or resident sleeping rooms required to provide mobility features shall comply with 805.

805.2 Turning Space. Turning *space* complying with 304 shall be provided within the room.

805.3 Clear Floor or Ground Space. A clear floor *space* complying with 305 shall be provided on each side of the bed. The clear floor *space* shall be positioned for parallel approach to the side of the bed.

805.4 Toilet and Bathing Rooms. Toilet and bathing rooms that are provided as part of a patient or resident sleeping room shall comply with 603. Where provided, no fewer than one water closet, one lavatory, and one bathtub or shower shall comply with the applicable requirements of 603 through 610.

806 Transient Lodging Guest Rooms

806.1 General. *Transient lodging* guest rooms shall comply with 806. Guest rooms required to provide mobility features shall comply with 806.2. Guest rooms required to provide communication features shall comply with 806.3.

806.2 Guest Rooms with Mobility Features. Guest rooms required to provide mobility features shall comply with 806.2.

Advisory 806.2 Guest Rooms. The requirements in Section 806.2 do not include requirements that are common to all accessible spaces. For example, closets in guest rooms must comply with the applicable provisions for storage specified in scoping.

806.2.1 Living and Dining Areas. Living and dining areas shall be *accessible*.

806.2.2 Exterior Spaces. Exterior *spaces*, including patios, terraces and balconies, that serve the guest room shall be *accessible*.

806.2.3 Sleeping Areas. At least one sleeping area shall provide a clear floor *space* complying with 305 on both sides of a bed. The clear floor *space* shall be positioned for parallel approach to the side of the bed.

EXCEPTION: Where a single clear floor *space* complying with 305 positioned for parallel approach is provided between two beds, a clear floor or ground *space* shall not be required on both sides of a bed.

806.2.4 Toilet and Bathing Facilities. At least one bathroom that is provided as part of a guest room shall comply with 603. No fewer than one water closet, one lavatory, and one bathtub or shower shall comply with applicable requirements of 603 through 610. In addition, required roll-in shower compartments shall comply with 608.2.2 or 608.2.3. Toilet and bathing fixtures required to comply with 603 through 610 shall be permitted to be located in more than one toilet or bathing area, provided that travel between fixtures does not require travel between other parts of the guest room.

806.2.4.1 Vanity Counter Top Space. If vanity counter top *space* is provided in non-accessible guest toilet or bathing rooms, comparable vanity counter top *space*, in terms of size and proximity to the lavatory, shall also be provided in *accessible* guest toilet or bathing rooms.

Advisory 806.2.4.1 Vanity Counter Top Space. This provision is intended to ensure that accessible guest rooms are provided with comparable vanity counter top space.

806.2.5 Kitchens and Kitchenettes. Kitchens and kitchenettes shall comply with 804.

806.2.6 Turning Space. Turning *space* complying with 304 shall be provided within the guest room.

806.3 Guest Rooms with Communication Features. Guest rooms required to provide communication features shall comply with 806.3.

Advisory 806.3 Guest Rooms with Communication Features. In guest rooms required to have accessible communication features, consider ensuring compatibility with adaptive equipment used by people with hearing impairments. To ensure communication within the facility, as well as on commercial lines, provide telephone interface jacks that are compatible with both digital and analog signal use. If an audio headphone jack is provided on a speaker phone, a cutoff switch can be included in the jack so that insertion of the jack cuts off the speaker. If a telephone-like handset is used, the external speakers can be turned off when the handset is removed from the cradle. For headset or external amplification system compatibility, a standard subminiature jack installed in the telephone will provide the most flexibility.

806.3.1 Alarms. Where emergency warning systems are provided, alarms complying with 702 shall be provided.

806.3.2 Notification Devices. Visible notification devices shall be provided to alert room occupants of incoming telephone calls and a door knock or bell. Notification devices shall not be connected to visible alarm signal appliances. Telephones shall have volume controls compatible with the telephone system and shall comply with 704.3. Telephones shall be served by an electrical outlet complying with 309 located within 48 inches (1220 mm) of the telephone to facilitate the use of a TTY.

807 Holding Cells and Housing Cells

807.1 General. Holding cells and housing cells shall comply with 807.

807.2 Cells with Mobility Features. Cells required to provide mobility features shall comply with 807.2.

807.2.1 Turning Space. Turning *space* complying with 304 shall be provided within the cell.

807.2.2 Benches. Where benches are provided, at least one bench shall comply with 903.

807.2.3 Beds. Where beds are provided, clear floor *space* complying with 305 shall be provided on at least one side of the bed. The clear floor *space* shall be positioned for parallel approach to the side of the bed.

807.2.4 Toilet and Bathing Facilities. Toilet *facilities* or bathing *facilities* that are provided as part of a cell shall comply with 603. Where provided, no fewer than one water closet, one lavatory, and one bathtub or shower shall comply with the applicable requirements of 603 through 610.

Advisory 807.2.4 Toilet and Bathing Facilities. In holding cells, housing cells, or rooms required to be accessible, these requirements do not require a separate toilet room.

807.3 Cells with Communication Features. Cells required to provide communication features shall comply with 807.3.

807.3.1 Alarms. Where audible emergency alarm systems are provided to serve the occupants of cells, visible alarms complying with 702 shall be provided.

EXCEPTION: Visible alarms shall not be required where inmates or detainees are not allowed independent means of egress.

807.3.2 Telephones. Telephones, where provided within cells, shall have volume controls complying with 704.3.

808 Courtrooms

808.1 General. Courtrooms shall comply with 808.

808.2 Turning Space. Where provided, areas that are raised or depressed and accessed by *ramps* or platform lifts with entry *ramps* shall provide unobstructed turning *space* complying with 304.

808.3 Clear Floor Space. Each jury box and witness stand shall have, within its defined area, clear floor *space* complying with 305.

EXCEPTION: In *alterations*, *wheelchair spaces* are not required to be located within the defined area of raised jury boxes or witness stands and shall be permitted to be located outside these *spaces* where *ramp* or platform lift access poses a hazard by restricting or projecting into a means of egress required by the appropriate *administrative authority*.

808.4 Judges' Benches and Courtroom Stations. Judges' benches, clerks' stations, bailiffs' stations, deputy clerks' stations, court reporters' stations and litigants' and counsel stations shall comply with 902.

809 Residential Dwelling Units

809.1 General. *Residential dwelling units* shall comply with 809. *Residential dwelling units* required to provide mobility features shall comply with 809.2 through 809.4. *Residential dwelling units* required to provide communication features shall comply with 809.5.

809.2 Accessible Routes. *Accessible* routes complying with Chapter 4 shall be provided within *residential dwelling units* in accordance with 809.2.

EXCEPTION: *Accessible* routes shall not be required to or within unfinished attics or unfinished basements.

809.2.1 Location. At least one *accessible* route shall connect all *spaces* and *elements* which are a part of the *residential dwelling unit*. Where only one *accessible* route is provided, it shall not pass through bathrooms, closets, or similar *spaces*.

809.2.2 Turning Space. All rooms served by an *accessible* route shall provide a turning space complying with 304.

EXCEPTION: Turning space shall not be required in exterior spaces 30 inches (760 mm) maximum in depth or width.

Advisory 809.2.2 Turning Space. It is generally acceptable to use required clearances to provide wheelchair turning space. For example, in kitchens, 804.3.1 requires at least one work surface with clear floor space complying with 306 to be centered beneath. If designers elect to provide clear floor space that is at least 36 inches (915 mm) wide, as opposed to the required 30 inches (760 mm) wide, that clearance can be part of a T-turn, thereby maximizing efficient use of the kitchen area. However, the overlap of turning space must be limited to one segment of the T-turn so that back-up maneuvering is not restricted. It would, therefore, be unacceptable to use both the clearances under the work surface and the sink as part of a T-turn. See Section 304.3.2 regarding T-turns.

809.3 Kitchen. Where a kitchen is provided, it shall comply with 804.

809.4 Toilet Facilities and Bathing Facilities. At least one bathroom shall comply with 603. No fewer than one of each type of fixture provided shall comply with applicable requirements of 603 through 610. Toilet and bathing fixtures required to comply with 603 through 610 shall be located in the same toilet and bathing area, such that travel between fixtures does not require travel between other parts of the *residential dwelling unit*.

Advisory 809.4 Toilet Facilities and Bathing Facilities. In an effort to promote space efficiency, vanity counter top space in accessible residential dwelling units is often omitted. This omission does not promote equal access or equal enjoyment of the unit. Where comparable units have vanity counter tops, accessible units should also have vanity counter tops located as close as possible to the lavatory for convenient access to toiletries.

809.5 Residential Dwelling Units with Communication Features. *Residential dwelling units* required to provide communication features shall comply with 809.5.

809.5.1 Building Fire Alarm System. Where a *building* fire alarm system is provided, the system wiring shall be extended to a point within the *residential dwelling unit* in the vicinity of the *residential dwelling unit* smoke detection system.

809.5.1.1 Alarm Appliances. Where alarm appliances are provided within a *residential dwelling unit* as part of the *building* fire alarm system, they shall comply with 702.

809.5.1.2 Activation. All visible alarm appliances provided within the *residential dwelling unit* for *building* fire alarm notification shall be activated upon activation of the *building* fire alarm in the portion of the *building* containing the *residential dwelling unit*.

809.5.2 Residential Dwelling Unit Smoke Detection System. *Residential dwelling unit* smoke detection systems shall comply with NFPA 72 (1999 or 2002 edition) (incorporated by reference, see "Referenced Standards" in Chapter 1).

809.5.2.1 Activation. All visible alarm appliances provided within the *residential dwelling unit* for smoke detection notification shall be activated upon smoke detection.

809.5.3 Interconnection. The same visible alarm appliances shall be permitted to provide notification of *residential dwelling unit* smoke detection and *building* fire alarm activation.

809.5.4 Prohibited Use. Visible alarm appliances used to indicate *residential dwelling unit* smoke detection or *building* fire alarm activation shall not be used for any other purpose within the *residential dwelling unit*.

809.5.5 Residential Dwelling Unit Primary Entrance. Communication features shall be provided at the *residential dwelling unit* primary entrance complying with 809.5.5.

809.5.5.1 Notification. A hard-wired electric doorbell shall be provided. A button or switch shall be provided outside the *residential dwelling unit* primary entrance. Activation of the button or switch shall initiate an audible tone and visible signal within the *residential dwelling unit*. Where visible doorbell signals are located in sleeping areas, they shall have controls to deactivate the signal.

809.5.5.2 Identification. A means for visually identifying a visitor without opening the *residential dwelling unit* entry door shall be provided and shall allow for a minimum 180 degree range of view.

Advisory 809.5.5.2 Identification. In doors, peepholes that include prisms clarify the image and should offer a wide-angle view of the hallway or exterior for both standing persons and wheelchair users. Such peepholes can be placed at a standard height and permit a view from several feet from the door.

809.5.6 Site, Building, or Floor Entrance. Where a system, including a closed-circuit system, permitting voice communication between a visitor and the occupant of the *residential dwelling unit* is provided, the system shall comply with 708.4.

810 Transportation Facilities

810.1 General. Transportation *facilities* shall comply with 810.

810.2 Bus Boarding and Alighting Areas. Bus boarding and alighting areas shall comply with 810.2.

Advisory 810.2 Bus Boarding and Alighting Areas. At bus stops where a shelter is provided, the bus stop pad can be located either within or outside of the shelter.

810.2.1 Surface. Bus stop boarding and alighting areas shall have a firm, stable surface.

810.2.2 Dimensions. Bus stop boarding and alighting areas shall provide a clear length of 96 inches (2440 mm) minimum, measured perpendicular to the curb or vehicle roadway edge, and a clear width of 60 inches (1525 mm) minimum, measured parallel to the vehicle roadway.




Figure 810.2.2
Dimensions of Bus Boarding and Alighting Areas

810.2.3 Connection. Bus stop boarding and alighting areas shall be connected to streets, sidewalks, or pedestrian paths by an *accessible* route complying with 402.

810.2.4 Slope. Parallel to the roadway, the slope of the bus stop boarding and alighting area shall be the same as the roadway, to the maximum extent practicable. Perpendicular to the roadway, the slope of the bus stop boarding and alighting area shall not be steeper than 1:48.

810.3 Bus Shelters. Bus shelters shall provide a minimum clear floor or ground *space* complying with 305 entirely within the shelter. Bus shelters shall be connected by an *accessible* route complying with 402 to a boarding and alighting area complying with 810.2.




Figure 810.3
Bus Shelters

810.4 Bus Signs. Bus route identification signs shall comply with 703.5.1 through 703.5.4, and 703.5.7 and 703.5.8. In addition, to the maximum extent practicable, bus route identification signs shall comply with 703.5.5.

EXCEPTION: Bus schedules, timetables and maps that are posted at the bus stop or bus bay shall not be required to comply.

810.5 Rail Platforms. Rail platforms shall comply with 810.5.

810.5.1 Slope. Rail platforms shall not exceed a slope of 1:48 in all directions.

EXCEPTION: Where platforms serve vehicles operating on existing track or track laid in existing roadway, the slope of the platform parallel to the track shall be permitted to be equal to the slope (grade) of the roadway or existing track.

810.5.2 Detectable Warnings. Platform boarding edges not protected by platform screens or guards shall have *detectable warnings* complying with 705 along the full length of the *public use* area of the platform.

810.5.3 Platform and Vehicle Floor Coordination. Station platforms shall be positioned to coordinate with vehicles in accordance with the applicable requirements of 36 CFR Part 1192. Low-level platforms shall be 8 inches (205 mm) minimum above top of rail.

EXCEPTION: Where vehicles are boarded from sidewalks or street-level, low-level platforms shall be permitted to be less than 8 inches (205 mm).

Advisory 810.5.3 Platform and Vehicle Floor Coordination. The height and position of a platform must be coordinated with the floor of the vehicles it serves to minimize the vertical and horizontal gaps, in accordance with the ADA Accessibility Guidelines for Transportation Vehicles (36 CFR Part 1192). The vehicle guidelines, divided by bus, van, light rail, rapid rail, commuter rail, intercity rail, are available at www.access-board.gov. The preferred alignment is a high platform, level with the vehicle floor. In some cases, the vehicle guidelines permit use of a low platform in conjunction with a lift or ramp. Most such low platforms must have a minimum height of eight inches above the top of the rail. Some vehicles are designed to be boarded from a street or the sidewalk along the street and the exception permits such boarding areas to be less than eight inches high.

810.6 Rail Station Signs. Rail station signs shall comply with 810.6.

EXCEPTION. Signs shall not be required to comply with 810.6.1 and 810.6.2 where audible signs are remotely transmitted to hand-held receivers, or are user- or proximity-actuated.

Advisory 810.6 Rail Station Signs Exception. Emerging technologies such as an audible sign systems using infrared transmitters and receivers may provide greater accessibility in the transit environment than traditional Braille and raised letter signs. The transmitters are placed on or next to print signs and transmit their information to an infrared receiver that is held by a person. By scanning an area, the person will hear the sign. This means that signs can be placed well out of reach of Braille readers, even on parapet walls and on walls beyond barriers. Additionally, such signs can be used to provide wayfinding information that cannot be efficiently conveyed on Braille signs.

810.6.1 Entrances. Where signs identify a station or its *entrance*, at least one sign at each *entrance* shall comply with 703.2 and shall be placed in uniform locations to the maximum extent practicable. Where signs identify a station that has no defined *entrance*, at least one sign shall comply with 703.2 and shall be placed in a central location.

810.6.2 Routes and Destinations. Lists of stations, routes and destinations served by the station which are located on boarding areas, platforms, or *mezzanines* shall comply with 703.5. At least one *tactile* sign identifying the specific station and complying with 703.2 shall be provided on each platform or boarding area. Signs covered by this requirement shall, to the maximum extent practicable, be placed in uniform locations within the system.

EXCEPTION: Where sign *space* is limited, *characters* shall not be required to exceed 3 inches (75 mm).

Advisory 810.6.2 Routes and Destinations. Route maps are not required to comply with the informational sign requirements in this document.

810.6.3 Station Names. Stations covered by this section shall have identification signs complying with 703.5. Signs shall be clearly visible and within the sight lines of standing and sitting passengers from within the vehicle on both sides when not obstructed by another vehicle.

Advisory 810.6.3 Station Names. It is also important to place signs at intervals in the station where passengers in the vehicle will be able to see a sign when the vehicle is either stopped at the station or about to come to a stop in the station. The number of signs necessary may be directly related to the size of the lettering displayed on the sign.

810.7 Public Address Systems. Where public address systems convey audible information to the public, the same or equivalent information shall be provided in a visual format.

810.8 Clocks. Where clocks are provided for use by the public, the clock face shall be uncluttered so that its *elements* are clearly visible. Hands, numerals and digits shall contrast with the background either light-on-dark or dark-on-light. Where clocks are installed overhead, numerals and digits shall comply with 703.5.

810.9 Escalators. Where provided, escalators shall comply with the sections 6.1.3.5.6 and 6.1.3.6.5 of ASME A17.1 (incorporated by reference, see "Referenced Standards" in Chapter 1) and shall have a clear width of 32 inches (815 mm) minimum.

EXCEPTION: Existing escalators in *key stations* shall not be required to comply with 810.9.

810.10 Track Crossings. Where a *circulation path* serving boarding platforms crosses tracks, it shall comply with 402.

EXCEPTION: Openings for wheel flanges shall be permitted to be 2½ inches (64 mm) maximum.




Figure 810.10 (Exception)
Track Crossings

811 Storage

811.1 General. Storage shall comply with 811.

811.2 Clear Floor or Ground Space. A clear floor or ground *space* complying with 305 shall be provided.

811.3 Height. Storage *elements* shall comply with at least one of the reach ranges specified in 308.

811.4 Operable Parts. *Operable parts* shall comply with 309.

CHAPTER 9: BUILT-IN ELEMENTS

901 General

901.1 Scope. The provisions of Chapter 9 shall apply where required by Chapter 2 or where referenced by a requirement in this document.

902 Dining Surfaces and Work Surfaces

902.1 General. Dining surfaces and work surfaces shall comply with 902.2 and 902.3.

EXCEPTION: Dining surfaces and work surfaces for *children's use* shall be permitted to comply with 902.4.

Advisory 902.1 General. Dining surfaces include, but are not limited to, bars, tables, lunch counters, and booths. Examples of work surfaces include writing surfaces, study carrels, student laboratory stations, baby changing and other tables or fixtures for personal grooming, coupon counters, and where covered by the ABA scoping provisions, employee work stations.

902.2 Clear Floor or Ground Space. A clear floor *space* complying with 305 positioned for a forward approach shall be provided. Knee and toe clearance complying with 306 shall be provided.

902.3 Height. The tops of dining surfaces and work surfaces shall be 28 inches (710 mm) minimum and 34 inches (865 mm) maximum above the finish floor or ground.

902.4 Dining Surfaces and Work Surfaces for Children's Use. *Accessible* dining surfaces and work surfaces for *children's use* shall comply with 902.4.

EXCEPTION: Dining surfaces and work surfaces that are used primarily by children 5 years and younger shall not be required to comply with 902.4 where a clear floor or ground *space* complying with 305 positioned for a parallel approach is provided.

902.4.1 Clear Floor or Ground Space. A clear floor *space* complying with 305 positioned for forward approach shall be provided. Knee and toe clearance complying with 306 shall be provided, except that knee clearance 24 inches (610 mm) minimum above the finish floor or ground shall be permitted.

902.4.2 Height. The tops of tables and counters shall be 26 inches (660 mm) minimum and 30 inches (760 mm) maximum above the finish floor or ground.

903 Benches

903.1 General. Benches shall comply with 903.

903.2 Clear Floor or Ground Space. Clear floor or ground *space* complying with 305 shall be provided and shall be positioned at the end of the bench seat and parallel to the short axis of the bench.

903.3 Size. Benches shall have seats that are 42 inches (1065 mm) long minimum and 20 inches (510 mm) deep minimum and 24 inches (610 mm) deep maximum.

903.4 Back Support. The bench shall provide for back support or shall be affixed to a wall. Back support shall be 42 inches (1065 mm) long minimum and shall extend from a point 2 inches (51 mm) maximum above the seat surface to a point 18 inches (455 mm) minimum above the seat surface. Back support shall be 2½ inches (64 mm) maximum from the rear edge of the seat measured horizontally.

Advisory 903.4 Back Support. To assist in transferring to the bench, consider providing grab bars on a wall adjacent to the bench, but not on the seat back. If provided, grab bars cannot obstruct transfer to the bench.




Figure 903.4
Bench Back Support

903.5 Height. The top of the bench seat surface shall be 17 inches (430 mm) minimum and 19 inches (485 mm) maximum above the finish floor or ground.

903.6 Structural Strength. Allowable stresses shall not be exceeded for materials used when a vertical or horizontal force of 250 pounds (1112 N) is applied at any point on the seat, fastener, mounting device, or supporting structure.

903.7 Wet Locations. Where installed in wet locations, the surface of the seat shall be slip resistant and shall not accumulate water.

904 Check-Out Aisles and Sales and Service Counters

904.1 General. Check-out aisles and sales and service counters shall comply with the applicable requirements of 904.

904.2 Approach. All portions of counters required to comply with 904 shall be located adjacent to a walking surface complying with 403.

Advisory 904.2 Approach. If a cash register is provided at the sales or service counter, locate the accessible counter close to the cash register so that a person using a wheelchair is visible to sales or service personnel and to minimize the reach for a person with a disability.

904.3 Check-Out Aisles. Check-out aisles shall comply with 904.3.

904.3.1 Aisle. Aisles shall comply with 403.

904.3.2 Counter. The counter surface height shall be 38 inches (965 mm) maximum above the finish floor or ground. The top of the counter edge protection shall be 2 inches (51 mm) maximum above the top of the counter surface on the aisle side of the check-out counter.




Figure 904.3.2
Check-Out Aisle Counters

904.3.3 Check Writing Surfaces. Where provided, check writing surfaces shall comply with 902.3.

904.4 Sales and Service Counters. Sales counters and service counters shall comply with 904.4.1 or 904.4.2. The *accessible* portion of the counter top shall extend the same depth as the sales or service counter top.

EXCEPTION: In *alterations*, when the provision of a counter complying with 904.4 would result in a reduction of the number of existing counters at work stations or a reduction of the number of existing *mail boxes*, the counter shall be permitted to have a portion which is 24 inches (610 mm) long minimum complying with 904.4.1 provided that the required clear floor or ground *space* is centered on the *accessible* length of the counter.




Figure 904.4 (Exception)
Alteration of Sales and Service Counters

904.4.1 Parallel Approach. A portion of the counter surface that is 36 inches (915 mm) long minimum and 36 inches (915 mm) high maximum above the finish floor shall be provided. A clear floor or ground *space* complying with 305 shall be positioned for a parallel approach adjacent to the 36 inch (915 mm) minimum length of counter.

EXCEPTION: Where the provided counter surface is less than 36 inches (915 mm) long, the entire counter surface shall be 36 inches (915 mm) high maximum above the finish floor.

904.4.2 Forward Approach. A portion of the counter surface that is 30 inches (760 mm) long minimum and 36 inches (915 mm) high maximum shall be provided. Knee and toe *space* complying with 306 shall be provided under the counter. A clear floor or ground *space* complying with 305 shall be positioned for a forward approach to the counter.

904.5 Food Service Lines. Counters in food service lines shall comply with 904.5.

904.5.1 Self-Service Shelves and Dispensing Devices. Self-service shelves and dispensing devices for tableware, dishware, condiments, food and beverages shall comply with 308.

904.5.2 Tray Slides. The tops of tray slides shall be 28 inches (710 mm) minimum and 34 inches (865 mm) maximum above the finish floor or ground.

904.6 Security Glazing. Where counters or teller windows have security glazing to separate personnel from the public, a method to facilitate voice communication shall be provided. Telephone handset devices, if provided, shall comply with 704.3.

Advisory 904.6 Security Glazing. Assistive listening devices complying with 706 can facilitate voice communication at counters or teller windows where there is security glazing which promotes distortion in audible information. Where assistive listening devices are installed, place signs complying with 703.7.2.4 to identify those facilities which are so equipped. Other voice communication methods include, but are not limited to, grilles, slats, talk-through baffles, intercoms, or telephone handset devices.

CHAPTER 10: RECREATION FACILITIES

1001 General

1001.1 Scope. The provisions of Chapter 10 shall apply where required by Chapter 2 or where referenced by a requirement in this document.

Advisory 1001.1 Scope. Unless otherwise modified or specifically addressed in Chapter 10, all other ADAAG provisions apply to the design and construction of recreation facilities and elements. The provisions in Section 1001.1 apply wherever these elements are provided. For example, office buildings may contain a room with exercise equipment to which these sections would apply.

1002 Amusement Rides

1002.1 General. *Amusement rides* shall comply with 1002.

1002.2 Accessible Routes. *Accessible* routes serving *amusement rides* shall comply with Chapter 4.

EXCEPTIONS: 1. In load or unload areas and on *amusement rides*, where compliance with 405.2 is not structurally or operationally feasible, *ramp* slope shall be permitted to be 1:8 maximum.

2. In load or unload areas and on *amusement rides*, handrails provided along walking surfaces complying with 403 and required on *ramps* complying with 405 shall not be required to comply with 505 where compliance is not structurally or operationally feasible.

Advisory 1002.2 Accessible Routes Exception 1. Steeper slopes are permitted on accessible routes connecting the amusement ride in the load and unload position where it is "structurally or operationally infeasible." In most cases, this will be limited to areas where the accessible route leads directly to the amusement ride and where there are space limitations on the ride, not the queue line. Where possible, the least possible slope should be used on the accessible route that serves the amusement ride.

1002.3 Load and Unload Areas. A turning *space* complying with 304.2 and 304.3 shall be provided in load and unload areas.

1002.4 Wheelchair Spaces in Amusement Rides. *Wheelchair spaces* in *amusement rides* shall comply with 1002.4.

1002.4.1 Floor or Ground Surface. The floor or ground surface of *wheelchair spaces* shall be stable and firm.

1002.4.2 Slope. The floor or ground surface of *wheelchair spaces* shall have a slope not steeper than 1:48 when in the load and unload position.

1002.4.3 Gaps. Floors of *amusement rides* with *wheelchair spaces* and floors of load and unload areas shall be coordinated so that, when *amusement rides* are at rest in the load and unload

position, the vertical difference between the floors shall be within plus or minus 5/8 inches (16 mm) and the horizontal gap shall be 3 inches (75 mm) maximum under normal passenger load conditions.

EXCEPTION: Where compliance is not operationally or structurally feasible, *ramps*, bridge plates, or similar devices complying with the applicable requirements of 36 CFR 1192.83(c) shall be provided.

Advisory 1002.4.3 Gaps Exception. 36 CFR 1192.83(c) ADA Accessibility Guidelines for Transportation Vehicles - Light Rail Vehicles and Systems - Mobility Aid Accessibility is available at www.access-board.gov. It includes provisions for bridge plates and ramps that can be used at gaps between wheelchair spaces and floors of load and unload areas.

1002.4.4 Clearances. Clearances for *wheelchair spaces* shall comply with 1002.4.4.

EXCEPTIONS: 1. Where provided, securement devices shall be permitted to overlap required clearances.

2. *Wheelchair spaces* shall be permitted to be mechanically or manually repositioned.

3. *Wheelchair spaces* shall not be required to comply with 307.4.

Advisory 1002.4.4 Clearances Exception 3. This exception for protruding objects applies to the ride devices, not to circulation areas or accessible routes in the queue lines or the load and unload areas.

1002.4.4.1 Width and Length. *Wheelchair spaces* shall provide a clear width of 30 inches (760 mm) minimum and a clear length of 48 inches (1220 mm) minimum measured to 9 inches (230 mm) minimum above the floor surface.

1002.4.4.2 Side Entry. Where *wheelchair spaces* are entered only from the side, *amusement rides* shall be designed to permit sufficient maneuvering clearance for individuals using a wheelchair or mobility aid to enter and exit the ride.

Advisory 1002.4.4.2 Side Entry. The amount of clear space needed within the ride, and the size and position of the opening are interrelated. A 32 inch (815 mm) clear opening will not provide sufficient width when entered through a turn into an amusement ride. Additional space for maneuvering and a wider door will be needed where a side opening is centered on the ride. For example, where a 42 inch (1065 mm) opening is provided, a minimum clear space of 60 inches (1525 mm) in length and 36 inches (915mm) in depth is needed to ensure adequate space for maneuvering.

1002.4.4.3 Permitted Protrusions in Wheelchair Spaces. Objects are permitted to protrude a distance of 6 inches (150 mm) maximum along the front of the *wheelchair space*, where located 9 inches (230 mm) minimum and 27 inches (685 mm) maximum above the floor or ground surface of the *wheelchair space*. Objects are permitted to protrude a distance of 25 inches (635 mm) maximum along the front of the *wheelchair space*, where located more than 27 inches (685 mm) above the floor or ground surface of the *wheelchair space*.




Figure 1002.4.4.3
Protrusions in Wheelchair Spaces in Amusement Rides

1002.4.5 Ride Entry. Openings providing entry to *wheelchair spaces* on *amusement rides* shall be 32 inches (815 mm) minimum clear.

1002.4.6 Approach. One side of the *wheelchair space* shall adjoin an *accessible* route when in the load and unload position.

1002.4.7 Companion Seats. Where the interior width of the *amusement ride* is greater than 53 inches (1345 mm), seating is provided for more than one rider, and the wheelchair is not required to be centered within the *amusement ride*, a companion seat shall be provided for each *wheelchair space*.

1002.4.7.1 Shoulder-to-Shoulder Seating. Where an *amusement ride* provides shoulder-to-shoulder seating, companion seats shall be shoulder-to-shoulder with the adjacent *wheelchair space*.

EXCEPTION: Where shoulder-to-shoulder companion seating is not operationally or structurally feasible, compliance with this requirement shall be required to the maximum extent practicable.

1002.5 Amusement Ride Seats Designed for Transfer. *Amusement ride seats* designed for transfer shall comply with 1002.5 when positioned for loading and unloading.

Advisory 1002.5 Amusement Ride Seats Designed for Transfer. The proximity of the clear floor or ground space next to an element and the height of the element one is transferring to are both critical for a safe and independent transfer. Providing additional clear floor or ground space both in front of and diagonal to the element will provide flexibility and will increase usability for a more diverse population of individuals with disabilities. Ride seats designed for transfer should involve only one transfer. Where possible, designers are encouraged to locate the ride seat no higher than 17 to 19 inches (430 to 485 mm) above the load and unload surface. Where greater distances are required for transfers, providing gripping surfaces, seat padding, and avoiding sharp objects in the path of transfer will facilitate the transfer.

1002.5.1 Clear Floor or Ground Space. A clear floor or ground *space* complying with 305 shall be provided in the load and unload area adjacent to the *amusement ride seats* designed for transfer.

1002.5.2 Transfer Height. The height of *amusement ride seats* designed for transfer shall be 14 inches (355 mm) minimum and 24 inches (610 mm) maximum measured from the surface of the load and unload area.

1002.5.3 Transfer Entry. Where openings are provided for transfer to *amusement ride seats*, the openings shall provide clearance for transfer from a wheelchair or mobility aid to the *amusement ride seat*.

1002.5.4 Wheelchair Storage Space. Wheelchair storage *spaces* complying with 305 shall be provided in or adjacent to unload areas for each required *amusement ride seat* designed for transfer and shall not overlap any required means of egress or *accessible* route.

1002.6 Transfer Devices for Use with Amusement Rides. *Transfer devices* for use with *amusement rides* shall comply with 1002.6 when positioned for loading and unloading.

Advisory 1002.6 Transfer Devices for Use with Amusement Rides. Transfer devices for use with amusement rides should permit individuals to make independent transfers to and from their wheelchairs or mobility devices. There are a variety of transfer devices available that could be adapted to provide access onto an amusement ride. Examples of devices that may provide for transfers include, but are not limited to, transfer systems, lifts, mechanized seats, and custom designed systems. Operators and designers have flexibility in developing designs that will facilitate individuals to transfer onto amusement rides. These systems or devices should be designed to be reliable and sturdy.

Designs that limit the number of transfers required from a wheelchair or mobility device to the ride seat are encouraged. When using a transfer device to access an amusement ride, the least number of transfers and the shortest distance is most usable. Where possible, designers are encouraged to locate the transfer device seat no higher than 17 to 19 inches (430 to 485 mm) above the load and unload surface. Where greater distances are required for transfers, providing gripping surfaces, seat padding, and avoiding sharp objects in the path of transfer will facilitate the transfer. Where a series of transfers are required to reach the amusement ride seat, each vertical transfer should not exceed 8 inches (205 mm).

1002.6.1 Clear Floor or Ground Space. A clear floor or ground *space* complying with 305 shall be provided in the load and unload area adjacent to the *transfer device*.

1002.6.2 Transfer Height. The height of *transfer device* seats shall be 14 inches (355 mm) minimum and 24 inches (610 mm) maximum measured from the load and unload surface.

1002.6.3 Wheelchair Storage Space. Wheelchair storage *spaces* complying with 305 shall be provided in or adjacent to unload areas for each required *transfer device* and shall not overlap any required means of egress or *accessible* route.

1003 Recreational Boating Facilities

1003.1 General. Recreational boating *facilities* shall comply with 1003.

1003.2 Accessible Routes. *Accessible* routes serving recreational boating *facilities*, including *gangways* and floating piers, shall comply with Chapter 4 except as modified by the exceptions in 1003.2.

1003.2.1 Boat Slips. *Accessible* routes serving *boat slips* shall be permitted to use the exceptions in 1003.2.1.

EXCEPTIONS: 1. Where an existing *gangway* or series of *gangways* is replaced or *altered*, an increase in the length of the *gangway* shall not be required to comply with 1003.2 unless required by 202.4.

2. *Gangways* shall not be required to comply with the maximum rise specified in 405.6.

3. Where the total length of a *gangway* or series of *gangways* serving as part of a required *accessible* route is 80 feet (24 m) minimum, *gangways* shall not be required to comply with 405.2.

4. Where *facilities* contain fewer than 25 *boat slips* and the total length of the *gangway* or series of *gangways* serving as part of a required *accessible* route is 30 feet (9145 mm) minimum, *gangways* shall not be required to comply with 405.2.

5. Where *gangways* connect to *transition plates*, landings specified by 405.7 shall not be required.

6. Where *gangways* and *transition plates* connect and are required to have handrails, handrail extensions shall not be required. Where handrail extensions are provided on *gangways* or *transition plates*, the handrail extensions shall not be required to be parallel with the ground or floor surface.

7. The *cross slope* specified in 403.3 and 405.3 for *gangways*, *transition plates*, and floating piers that are part of *accessible* routes shall be measured in the static position.

8. Changes in level complying with 303.3 and 303.4 shall be permitted on the surfaces of *gangways* and *boat launch ramps*.

Advisory 1003.2.1 Boat Slips Exception 3. The following example shows how exception 3 would be applied: A gangway is provided to a floating pier which is required to be on an accessible route. The vertical distance is 10 feet (3050 mm) between the elevation where the gangway departs the landside connection and the elevation of the pier surface at the lowest water level. Exception 3 permits the gangway to be 80 feet (24 m) long. Another design solution would be to have two 40 foot (12 m) plus continuous gangways joined together at a float, where the float (as the water level falls) will stop dropping at an elevation five feet below the landside connection. The length of transition plates would not be included in determining if the gangway(s) meet the requirements of the exception.

1003.2.2 Boarding Piers at Boat Launch Ramps. Accessible routes serving *boarding piers* at *boat launch ramps* shall be permitted to use the exceptions in 1003.2.2.

EXCEPTIONS: 1. Accessible routes serving floating *boarding piers* shall be permitted to use Exceptions 1, 2, 5, 6, 7 and 8 in 1003.2.1.

2. Where the total length of the *gangway* or series of *gangways* serving as part of a required accessible route is 30 feet (9145 mm) minimum, *gangways* shall not be required to comply with 405.2.

3. Where the accessible route serving a floating *boarding pier* or skid pier is located within a *boat launch ramp*, the portion of the accessible route located within the *boat launch ramp* shall not be required to comply with 405.

1003.3 Clearances. Clearances at *boat slips* and on *boarding piers* at *boat launch ramps* shall comply with 1003.3.

Advisory 1003.3 Clearances. Although the minimum width of the clear pier space is 60 inches (1525 mm), it is recommended that piers be wider than 60 inches (1525 mm) to improve the safety for persons with disabilities, particularly on floating piers.

1003.3.1 Boat Slip Clearance. *Boat slips* shall provide clear pier *space* 60 inches (1525 mm) wide minimum and at least as long as the *boat slips*. Each 10 feet (3050 mm) maximum of linear pier edge serving *boat slips* shall contain at least one continuous clear opening 60 inches (1525 mm) wide minimum.

EXCEPTIONS: 1. Clear pier *space* shall be permitted to be 36 inches (915 mm) wide minimum for a length of 24 inches (610 mm) maximum, provided that multiple 36 inch (915 mm) wide segments are separated by segments that are 60 inches (1525 mm) wide minimum and 60 inches (1525 mm) long minimum.

2. Edge protection shall be permitted at the continuous clear openings, provided that it is 4 inches (100 mm) high maximum and 2 inches (51 mm) wide maximum.

3. In existing piers, clear pier *space* shall be permitted to be located perpendicular to the *boat slip* and shall extend the width of the *boat slip*, where the *facility* has at least one *boat slip* complying with 1003.3, and further compliance with 1003.3 would result in a reduction in the number of *boat slips* available or result in a reduction of the widths of existing slips.

Advisory 1003.3.1 Boat Slip Clearance Exception 3. Where the conditions in exception 3 are satisfied, existing facilities are only required to have one accessible boat slip with a pier clearance which runs the length of the slip. All other accessible slips are allowed to have the required pier clearance at the head of the slip. Under this exception, at piers with perpendicular boat slips, the width of most "finger piers" will remain unchanged. However, where mooring systems for floating piers are replaced as part of pier alteration projects, an opportunity may exist for increasing accessibility. Piers may be reconfigured to allow an increase in the number of wider finger piers, and serve as accessible boat slips.




Figure 1003.3.1
Boat Slip Clearance




Figure 1003.3.1 (Exception 1)
Clear Pier Space Reduction at Boat Slips




Figure 1003.3.1 (Exception 2)
Edge Protection at Boat Slips

1003.3.2 Boarding Pier Clearances. *Boarding piers at boat launch ramps* shall provide clear pier space 60 inches (1525 mm) wide minimum and shall extend the full length of the *boarding pier*. Every 10 feet (3050 mm) maximum of linear pier edge shall contain at least one continuous clear opening 60 inches (1525 mm) wide minimum.

EXCEPTIONS: 1. The clear pier space shall be permitted to be 36 inches (915 mm) wide minimum for a length of 24 inches (610 mm) maximum provided that multiple 36 inch (915 mm) wide segments are separated by segments that are 60 inches (1525 mm) wide minimum and 60 inches (1525 mm) long minimum.

2. Edge protection shall be permitted at the continuous clear openings provided that it is 4 inches (100 mm) high maximum and 2 inches (51 mm) wide maximum.

Advisory 1003.3.2 Boarding Pier Clearances. These requirements do not establish a minimum length for accessible boarding piers at boat launch ramps. The accessible boarding pier should have a length at least equal to that of other boarding piers provided at the facility. If no other boarding pier is provided, the pier would have a length equal to what would have been provided if no access requirements applied. The entire length of accessible boarding piers would be required to comply with the same technical provisions that apply to accessible boat slips. For example, at a launch ramp, if a 20 foot (6100 mm) long accessible boarding pier is provided, the entire 20 feet (6100 mm) must comply with the pier clearance requirements in 1003.3. Likewise, if a 60 foot (18 m) long accessible boarding pier is provided, the pier clearance requirements in 1003.3 would apply to the entire 60 feet (18 m).

The following example applies to a boat launch ramp boarding pier: A chain of floats is provided on a launch ramp to be used as a boarding pier which is required to be accessible by 1003.3.2. At high water, the entire chain is floating and a transition plate connects the first float to the surface of the launch ramp. As the water level decreases, segments of the chain end up resting on the launch ramp surface, matching the slope of the launch ramp.




Figure 1003.3.2
Boarding Pier Clearance




Figure 1003.3.2 (Exception 1)
Clear Pier Space Reduction at Boarding Piers




Figure 1003.3.2 (Exception 2)
Edge Protection at Boarding Piers

1004 Exercise Machines and Equipment

1004.1 Clear Floor Space. Exercise machines and equipment shall have a clear floor space complying with 305 positioned for transfer or for use by an individual seated in a wheelchair. Clear floor or ground spaces required at exercise machines and equipment shall be permitted to overlap.

Advisory 1004.1 Clear Floor Space. One clear floor or ground space is permitted to be shared between two pieces of exercise equipment. To optimize space use, designers should carefully consider layout options such as connecting ends of the row and center aisle spaces. The position of the clear floor space may vary greatly depending on the use of the equipment or machine. For example, to provide access to a shoulder press machine, clear floor space next to the seat would be appropriate to allow for transfer. Clear floor space for a bench press machine designed for use by an individual seated in a wheelchair, however, will most likely be centered on the operating mechanisms.

1005 Fishing Piers and Platforms

1005.1 Accessible Routes. *Accessible* routes serving fishing piers and platforms, including *gangways* and floating piers, shall comply with Chapter 4.

EXCEPTIONS: 1. *Accessible* routes serving floating fishing piers and platforms shall be permitted to use Exceptions 1, 2, 5, 6, 7 and 8 in 1003.2.1.

2. Where the total length of the *gangway* or series of *gangways* serving as part of a required *accessible* route is 30 feet (9145 mm) minimum, *gangways* shall not be required to comply with 405.2.

1005.2 Railings. Where provided, railings, guards, or handrails shall comply with 1005.2.

1005.2.1 Height. At least 25 percent of the railings, guards, or handrails shall be 34 inches (865 mm) maximum above the ground or deck surface.

EXCEPTION: Where a guard complying with sections 1003.2.12.1 and 1003.2.12.2 of the International Building Code (2000 edition) or sections 1012.2 and 1012.3 of the International Building Code (2003 edition) (incorporated by reference, see "Referenced Standards" in Chapter 1) is provided, the guard shall not be required to comply with 1005.2.1.

1005.2.1.1 Dispersion. Railings, guards, or handrails required to comply with 1005.2.1 shall be dispersed throughout the fishing pier or platform.

Advisory 1005.2.1.1 Dispersion. Portions of the railings that are lowered to provide fishing opportunities for persons with disabilities must be located in a variety of locations on the fishing pier or platform to give people a variety of locations to fish. Different fishing locations may provide varying water depths, shade (at certain times of the day), vegetation, and proximity to the shoreline or bank.

1005.3 Edge Protection. Where railings, guards, or handrails complying with 1005.2 are provided, edge protection complying with 1005.3.1 or 1005.3.2 shall be provided.

Advisory 1005.3 Edge Protection. Edge protection is required only where railings, guards, or handrails are provided on a fishing pier or platform. Edge protection will prevent wheelchairs or other mobility devices from slipping off the fishing pier or platform. Extending the deck of the fishing pier or platform 12 inches (305 mm) where the 34 inch (865 mm) high railing is provided is an alternative design, permitting individuals using wheelchairs or other mobility devices to pull into a clear space and move beyond the face of the railing. In such a design, curbs or barriers are not required.

1005.3.1 Curb or Barrier. Curbs or barriers shall extend 2 inches (51 mm) minimum above the surface of the fishing pier or platform.

1005.3.2 Extended Ground or Deck Surface. The ground or deck surface shall extend 12 inches (305 mm) minimum beyond the inside face of the railing. Toe clearance shall be provided and shall

be 30 inches (760 mm) wide minimum and 9 inches (230 mm) minimum above the ground or deck surface beyond the railing.




Figure 1005.3.2
Extended Ground or Deck Surface at Fishing Piers and Platforms

1005.4 Clear Floor or Ground Space. At each location where there are railings, guards, or handrails complying with 1005.2.1, a clear floor or ground *space* complying with 305 shall be provided. Where there are no railings, guards, or handrails, at least one clear floor or ground *space* complying with 305 shall be provided on the fishing pier or platform.

1005.5 Turning Space. At least one turning *space* complying with 304.3 shall be provided on fishing piers and platforms.

1006 Golf Facilities

1006.1 General. Golf *facilities* shall comply with 1006.

1006.2 Accessible Routes. *Accessible* routes serving *teeing grounds*, practice *teeing grounds*, putting greens, practice putting greens, teeing stations at driving ranges, course weather shelters, golf car rental areas, bag drop areas, and course toilet rooms shall comply with Chapter 4 and shall be 48 inches (1220 mm) wide minimum. Where handrails are provided, *accessible* routes shall be 60 inches (1525 mm) wide minimum.

EXCEPTION: Handrails shall not be required on golf courses. Where handrails are provided on golf courses, the handrails shall not be required to comply with 505.

Advisory 1006.2 Accessible Routes. The 48 inch (1220 mm) minimum width for the accessible route is necessary to ensure passage of a golf car on either the accessible route or the golf car passage. This is important where the accessible route is used to connect the golf car rental area, bag drop areas, practice putting greens, practice teeing grounds, course toilet rooms, and course weather shelters. These are areas outside the boundary of the golf course, but are areas where an individual using an adapted golf car may travel. A golf car passage may not be substituted for other accessible routes to be located outside the boundary of the course. For example, an accessible route connecting an accessible parking space to the entrance of a golf course clubhouse is not covered by this provision.

Providing a golf car passage will permit a person that uses a golf car to practice driving a golf ball from the same position and stance used when playing the game. Additionally, the space required for a person using a golf car to enter and maneuver within the teeing stations required to be accessible should be considered.

1006.3 Golf Car Passages. *Golf car passages* shall comply with 1006.3.

1006.3.1 Clear Width. The clear width of *golf car passages* shall be 48 inches (1220 mm) minimum.

1006.3.2 Barriers. Where curbs or other constructed barriers prevent golf cars from entering a fairway, openings 60 inches (1525 mm) wide minimum shall be provided at intervals not to exceed 75 yards (69 m).

1006.4 Weather Shelters. A clear floor or ground space 60 inches (1525 mm) minimum by 96 inches (2440 mm) minimum shall be provided within weather shelters.

1007 Miniature Golf Facilities

1007.1 General. Miniature golf *facilities* shall comply with 1007.

1007.2 Accessible Routes. *Accessible* routes serving holes on miniature golf courses shall comply with Chapter 4. *Accessible* routes located on playing surfaces of miniature golf holes shall be permitted to use the exceptions in 1007.2.

EXCEPTIONS: 1. Playing surfaces shall not be required to comply with 302.2.

2. Where *accessible* routes intersect playing surfaces of holes, a 1 inch (25 mm) maximum curb shall be permitted for a width of 32 inches (815 mm) minimum.

3. A slope not steeper than 1:4 for a 4 inch (100 mm) maximum rise shall be permitted.

4. *Ramp* landing slopes specified by 405.7.1 shall be permitted to be 1:20 maximum.

5. *Ramp* landing length specified by 405.7.3 shall be permitted to be 48 inches (1220 mm) long minimum.

6. *Ramp* landing size specified by 405.7.4 shall be permitted to be 48 inches (1220 mm) minimum by 60 inches (1525 mm) minimum.


7. Handrails shall not be required on holes. Where handrails are provided on holes, the handrails shall not be required to comply with 505.

1007.3 Miniature Golf Holes. Miniature golf holes shall comply with 1007.3.

1007.3.1 Start of Play. A clear floor or ground *space* 48 inches (1220 mm) minimum by 60 inches (1525 mm) minimum with slopes not steeper than 1:48 shall be provided at the start of play.

1007.3.2 Golf Club Reach Range Area. All areas within holes where golf balls rest shall be within 36 inches (915 mm) maximum of a clear floor or ground *space* 36 inches (915 mm) wide minimum and 48 inches (1220 mm) long minimum having a *running slope* not steeper than 1:20. The clear floor or ground *space* shall be served by an *accessible route*.

Advisory 1007.3.2 Golf Club Reach Range Area. The golf club reach range applies to all holes required to be accessible. This includes accessible routes provided adjacent to or, where provided, on the playing surface of the hole.



Note: Running Slope of Clear Floor or Ground Space Not Steeper Than 1:20

Figure 1007.3.2
Golf Club Reach Range Area

1008 Play Areas

1008.1 General. *Play areas* shall comply with 1008.

1008.2 Accessible Routes. *Accessible* routes serving *play areas* shall comply with Chapter 4 and 1008.2 and shall be permitted to use the exceptions in 1008.2.1 through 1008.2.3. Where *accessible* routes serve *ground level play components*, the vertical clearance shall be 80 inches high (2030 mm) minimum.

1008.2.1 Ground Level and Elevated Play Components. *Accessible* routes serving *ground level play components* and *elevated play components* shall be permitted to use the exceptions in 1008.2.1.

EXCEPTIONS: 1. Transfer systems complying with 1008.3 shall be permitted to connect *elevated play components* except where 20 or more *elevated play components* are provided no more than 25 percent of the *elevated play components* shall be permitted to be connected by transfer systems.

2. Where transfer systems are provided, an *elevated play component* shall be permitted to connect to another *elevated play component* as part of an *accessible route*.

1008.2.2 Soft Contained Play Structures. *Accessible routes serving soft contained play structures* shall be permitted to use the exception in 1008.2.2.

EXCEPTION: Transfer systems complying with 1008.3 shall be permitted to be used as part of an *accessible route*.

1008.2.3 Water Play Components. *Accessible routes serving water play components* shall be permitted to use the exceptions in 1008.2.3.

EXCEPTIONS: 1. Where the surface of the *accessible route*, clear floor or ground spaces, or turning spaces serving water play components is submerged, compliance with 302, 403.3, 405.2, 405.3, and 1008.2.6 shall not be required.

2. Transfer systems complying with 1008.3 shall be permitted to connect *elevated play components* in water.

Advisory 1008.2.3 Water Play Components. Personal wheelchairs and mobility devices may not be appropriate for submerging in water when using play components in water. Some may have batteries, motors, and electrical systems that when submerged in water may cause damage to the personal mobility device or wheelchair or may contaminate the water. Providing an aquatic wheelchair made of non-corrosive materials and designed for access into the water will protect the water from contamination and avoid damage to personal wheelchairs.

1008.2.4 Clear Width. *Accessible routes connecting play components* shall provide a clear width complying with 1008.2.4.

1008.2.4.1 Ground Level. At ground level, the clear width of *accessible routes* shall be 60 inches (1525 mm) minimum.

EXCEPTIONS: 1. In *play areas* less than 1000 square feet (93 m²), the clear width of *accessible routes* shall be permitted to be 44 inches (1120 mm) minimum, if at least one turning space complying with 304.3 is provided where the restricted *accessible route* exceeds 30 feet (9145 mm) in length.

2. The clear width of *accessible routes* shall be permitted to be 36 inches (915 mm) minimum for a distance of 60 inches (1525 mm) maximum provided that multiple reduced width segments are separated by segments that are 60 inches (1525 mm) wide minimum and 60 inches (1525 mm) long minimum.

1008.2.4.2 Elevated. The clear width of *accessible routes* connecting *elevated play components* shall be 36 inches (915 mm) minimum.

- EXCEPTIONS:** 1. The clear width of *accessible* routes connecting *elevated play components* shall be permitted to be reduced to 32 inches (815 mm) minimum for a distance of 24 inches (610 mm) maximum provided that reduced width segments are separated by segments that are 48 inches (1220 mm) long minimum and 36 inches (915 mm) wide minimum.
2. The clear width of transfer systems connecting *elevated play components* shall be permitted to be 24 inches (610 mm) minimum.

1008.2.5 Ramps. Within *play areas*, *ramps* connecting *ground level play components* and *ramps* connecting *elevated play components* shall comply with 1008.2.5.

1008.2.5.1 Ground Level. *Ramp* runs connecting *ground level play components* shall have a *running slope* not steeper than 1:16.

1008.2.5.2 Elevated. The rise for any *ramp* run connecting *elevated play components* shall be 12 inches (305 mm) maximum.

1008.2.5.3 Handrails. Where required on *ramps* serving *play components*, the handrails shall comply with 505 except as modified by 1008.2.5.3.

- EXCEPTIONS:** 1. Handrails shall not be required on *ramps* located within *ground level use zones*.
2. Handrail extensions shall not be required.

1008.2.5.3.1 Handrail Gripping Surfaces. Handrail gripping surfaces with a circular cross section shall have an outside diameter of 0.95 inch (24 mm) minimum and 1.55 inches (39 mm) maximum. Where the shape of the gripping surface is non-circular, the handrail shall provide an equivalent gripping surface.

1008.2.5.3.2 Handrail Height. The top of handrail gripping surfaces shall be 20 inches (510 mm) minimum and 28 inches (710 mm) maximum above the *ramp* surface.

1008.2.6 Ground Surfaces. Ground surfaces on *accessible* routes, clear floor or ground *spaces*, and turning *spaces* shall comply with 1008.2.6.

Advisory 1008.2.6 Ground Surfaces. Ground surfaces must be inspected and maintained regularly to ensure continued compliance with the ASTM F 1951 standard. The type of surface material selected and play area use levels will determine the frequency of inspection and maintenance activities.

1008.2.6.1 Accessibility. Ground surfaces shall comply with ASTM F 1951 (incorporated by reference, see "Referenced Standards" in Chapter 1). Ground surfaces shall be inspected and maintained regularly and frequently to ensure continued compliance with ASTM F 1951.

1008.2.6.2 Use Zones. Ground surfaces located within *use zones* shall comply with ASTM F 1292 (1999 edition or 2004 edition) (incorporated by reference, see "Referenced Standards" in Chapter 1).

1008.3 Transfer Systems. Where transfer systems are provided to connect to *elevated play components*, transfer systems shall comply with 1008.3.

Advisory 1008.3 Transfer Systems. Where transfer systems are provided, consideration should be given to the distance between the transfer system and the elevated play components. Moving between a transfer platform and a series of transfer steps requires extensive exertion for some children. Designers should minimize the distance between the points where a child transfers from a wheelchair or mobility device and where the elevated play components are located. Where elevated play components are used to connect to another elevated play component instead of an accessible route, careful consideration should be used in the selection of the play components used for this purpose.

1008.3.1 Transfer Platforms. Transfer platforms shall be provided where transfer is intended from wheelchairs or other mobility aids. Transfer platforms shall comply with 1008.3.1.

1008.3.1.1 Size. Transfer platforms shall have level surfaces 14 inches (355 mm) deep minimum and 24 inches (610 mm) wide minimum.

1008.3.1.2 Height. The height of transfer platforms shall be 11 inches (280 mm) minimum and 18 inches (455 mm) maximum measured to the top of the surface from the ground or floor surface.

1008.3.1.3 Transfer Space. A transfer *space* complying with 305.2 and 305.3 shall be provided adjacent to the transfer platform. The 48 inch (1220 mm) long minimum dimension of the transfer *space* shall be centered on and parallel to the 24 inch (610 mm) long minimum side of the transfer platform. The side of the transfer platform serving the transfer *space* shall be unobstructed.

1008.3.1.4 Transfer Supports. At least one means of support for transferring shall be provided.




Figure 1008.3.1
Transfer Platforms

1008.3.2 Transfer Steps. Transfer steps shall be provided where movement is intended from transfer platforms to levels with *elevated play components* required to be on *accessible* routes. Transfer steps shall comply with 1008.3.2.

1008.3.2.1 Size. Transfer steps shall have level surfaces 14 inches (355 mm) deep minimum and 24 inches (610 mm) wide minimum.

1008.3.2.2 Height. Each transfer step shall be 8 inches (205 mm) high maximum.

1008.3.2.3 Transfer Supports. At least one means of support for transferring shall be provided.

Advisory 1008.3.2.3 Transfer Supports. Transfer supports are required on transfer platforms and transfer steps to assist children when transferring. Some examples of supports include a rope loop, a loop type handle, a slot in the edge of a flat horizontal or vertical member, poles or bars, or D rings on the corner posts.




Figure 1008.3.2
Transfer Steps

1008.4 Play Components. *Ground level play components* on *accessible* routes and *elevated play components* connected by *ramps* shall comply with 1008.4.

1008.4.1 Turning Space. At least one turning *space* complying with 304 shall be provided on the same level as *play components*. Where swings are provided, the turning *space* shall be located immediately adjacent to the swing.

1008.4.2 Clear Floor or Ground Space. Clear floor or ground *space* complying with 305.2 and 305.3 shall be provided at *play components*.

Advisory 1008.4.2 Clear Floor or Ground Space. Clear floor or ground spaces, turning spaces, and accessible routes are permitted to overlap within play areas. A specific location has not been designated for the clear floor or ground spaces or turning spaces, except swings, because each play component may require that the spaces be placed in a unique location. Where play components include a seat or entry point, designs that provide for an unobstructed transfer from a wheelchair or other mobility device are recommended. This will enhance the ability of children with disabilities to independently use the play component.

When designing play components with manipulative or interactive features, consider appropriate reach ranges for children seated in wheelchairs. The following table provides guidance on reach ranges for children seated in wheelchairs. These dimensions apply to either forward or side reaches. The reach ranges are appropriate for use with those play components that children seated in wheelchairs may access and reach. Where transfer systems provide access to elevated play components, the reach ranges are not appropriate.

Children's Reach Ranges			
Forward or Side Reach	Ages 3 and 4	Ages 5 through 8	Ages 9 through 12
High (maximum)	36 in (915 mm)	40 in (1015 mm)	44 in (1120 mm)
Low (minimum)	20 in (510 mm)	18 in (455 mm)	16 in (405 mm)

1008.4.3 Play Tables. Where play tables are provided, knee clearance 24 inches (610 mm) high minimum, 17 inches deep (430 mm) minimum, and 30 inches (760 mm) wide minimum shall be provided. The tops of rims, curbs, or other obstructions shall be 31 inches (785 mm) high maximum.

EXCEPTION: Play tables designed and constructed primarily for children 5 years and younger shall not be required to provide knee clearance where the clear floor or ground space required by 1008.4.2 is arranged for a parallel approach.

1008.4.4 Entry Points and Seats. Where *play components* require transfer to entry points or seats, the entry points or seats shall be 11 inches (280 mm) minimum and 24 inches (610 mm) maximum from the clear floor or ground space.

EXCEPTION: Entry points of slides shall not be required to comply with 1008.4.4.

1008.4.5 Transfer Supports. Where *play components* require transfer to entry points or seats, at least one means of support for transferring shall be provided.

1009 Swimming Pools, Wading Pools, and Spas

1009.1 General. Where provided, pool lifts, sloped entries, transfer walls, transfer systems, and pool stairs shall comply with 1009.

1009.2 Pool Lifts. Pool lifts shall comply with 1009.2.

Advisory 1009.2 Pool Lifts. There are a variety of seats available on pool lifts ranging from sling seats to those that are preformed or molded. Pool lift seats with backs will enable a larger population of persons with disabilities to use the lift. Pool lift seats that consist of materials that resist corrosion and provide a firm base to transfer will be usable by a wider range of people with disabilities. Additional options such as armrests, head rests, seat belts, and leg support will enhance accessibility and better accommodate people with a wide range of disabilities.

1009.2.1 Pool Lift Location. Pool lifts shall be located where the water level does not exceed 48 inches (1220 mm).

EXCEPTIONS: 1. Where the entire pool depth is greater than 48 inches (1220 mm), compliance with 1009.2.1 shall not be required.

2. Where multiple pool lift locations are provided, no more than one pool lift shall be required to be located in an area where the water level is 48 inches (1220 mm) maximum.

1009.2.2 Seat Location. In the raised position, the centerline of the seat shall be located over the deck and 16 inches (405 mm) minimum from the edge of the pool. The deck surface between the centerline of the seat and the pool edge shall have a slope not steeper than 1:48.




Figure 1009.2.2
Pool Lift Seat Location

1009.2.3 Clear Deck Space. On the side of the seat opposite the water, a clear deck space shall be provided parallel with the seat. The space shall be 36 inches (915 mm) wide minimum and shall extend forward 48 inches (1220 mm) minimum from a line located 12 inches (305 mm) behind the rear edge of the seat. The clear deck space shall have a slope not steeper than 1:48.




Figure 1009.2.3
Clear Deck Space at Pool Lifts

1009.2.4 Seat Height. The height of the lift seat shall be designed to allow a stop at 16 inches (405 mm) minimum to 19 inches (485 mm) maximum measured from the deck to the top of the seat surface when in the raised (load) position.




Figure 1009.2.4
Pool Lift Seat Height

1009.2.5 Seat Width. The seat shall be 16 inches (405 mm) wide minimum.

1009.2.6 Footrests and Armrests. Footrests shall be provided and shall move with the seat. If provided, the armrest positioned opposite the water shall be removable or shall fold clear of the seat when the seat is in the raised (load) position.

EXCEPTION: Footrests shall not be required on pool lifts provided in spas.

1009.2.7 Operation. The lift shall be capable of unassisted operation from both the deck and water levels. Controls and operating mechanisms shall be unobstructed when the lift is in use and shall comply with 309.4.

Advisory 1009.2.7 Operation. Pool lifts must be capable of unassisted operation from both the deck and water levels. This will permit a person to call the pool lift when the pool lift is in the opposite position. It is extremely important for a person who is swimming alone to be able to call the pool lift when it is in the up position so he or she will not be stranded in the water for extended periods of time awaiting assistance. The requirement for a pool lift to be independently operable does not preclude assistance from being provided.

1009.2.8 Submerged Depth. The lift shall be designed so that the seat will submerge to a water depth of 18 inches (455 mm) minimum below the stationary water level.




Figure 1009.2.8
Pool Lift Submerged Depth

1009.2.9 Lifting Capacity. Single person pool lifts shall have a weight capacity of 300 pounds. (136 kg) minimum and be capable of sustaining a static load of at least one and a half times the rated load.

Advisory 1009.2.9 Lifting Capacity. Single person pool lifts must be capable of supporting a minimum weight of 300 pounds (136 kg) and sustaining a static load of at least one and a half times the rated load. Pool lifts should be provided that meet the needs of the population they serve. Providing a pool lift with a weight capacity greater than 300 pounds (136 kg) may be advisable.

1009.3 Sloped Entries. Sloped entries shall comply with 1009.3.

Advisory 1009.3 Sloped Entries. Personal wheelchairs and mobility devices may not be appropriate for submerging in water. Some may have batteries, motors, and electrical systems that when submerged in water may cause damage to the personal mobility device or wheelchair or may contaminate the pool water. Providing an aquatic wheelchair made of non-corrosive materials and designed for access into the water will protect the water from contamination and avoid damage to personal wheelchairs or other mobility aids.

1009.3.1 Sloped Entries. Sloped entries shall comply with Chapter 4 except as modified in 1109.3.1 through 1109.3.3.

EXCEPTION: Where sloped entries are provided, the surfaces shall not be required to be slip resistant.

1009.3.2 Submerged Depth. Sloped entries shall extend to a depth of 24 inches (610 mm) minimum and 30 inches (760 mm) maximum below the stationary water level. Where landings are required by 405.7, at least one landing shall be located 24 inches (610 mm) minimum and 30 inches (760 mm) maximum below the stationary water level.

EXCEPTION: In wading pools, the sloped entry and landings, if provided, shall extend to the deepest part of the wading pool.




Figure 1009.3.2
Sloped Entry Submerged Depth

1009.3.3 Handrails. At least two handrails complying with 505 shall be provided on the sloped entry. The clear width between required handrails shall be 33 inches (840 mm) minimum and 38 inches (965 mm) maximum.

EXCEPTIONS: 1. Handrail extensions specified by 505.10.1 shall not be required at the bottom landing serving a sloped entry.

2. Where a sloped entry is provided for wave action pools, leisure rivers, sand bottom pools, and other pools where user access is limited to one area, the handrails shall not be required to comply with the clear width requirements of 1009.3.3.

3. Sloped entries in wading pools shall not be required to provide handrails complying with 1009.3.3. If provided, handrails on sloped entries in wading pools shall not be required to comply with 505.




Figure 1009.3.3
Handrails for Sloped Entry

1009.4 Transfer Walls. Transfer walls shall comply with 1009.4.

1009.4.1 Clear Deck Space. A clear deck *space* of 60 inches (1525 mm) minimum by 60 inches (1525 mm) minimum with a slope not steeper than 1:48 shall be provided at the base of the transfer wall. Where one grab bar is provided, the clear deck *space* shall be centered on the grab bar. Where two grab bars are provided, the clear deck *space* shall be centered on the clearance between the grab bars.




Figure 1009.4.1
Clear Deck Space at Transfer Walls

1009.4.2 Height. The height of the transfer wall shall be 16 inches (405 mm) minimum and 19 inches (485 mm) maximum measured from the deck.




Figure 1009.4.2
Transfer Wall Height

1009.4.3 Wall Depth and Length. The depth of the transfer wall shall be 12 inches (305 mm) minimum and 16 inches (405 mm) maximum. The length of the transfer wall shall be 60 inches (1525 mm) minimum and shall be centered on the clear deck *space*.




Figure 1009.4.3
Depth and Length of Transfer Walls

1009.4.4 Surface. Surfaces of transfer walls shall not be sharp and shall have rounded edges.

1009.4.5 Grab Bars. At least one grab bar complying with 609 shall be provided on the transfer wall. Grab bars shall be perpendicular to the pool wall and shall extend the full depth of the transfer wall. The top of the gripping surface shall be 4 inches (100 mm) minimum and 6 inches (150 mm) maximum above transfer walls. Where one grab bar is provided, clearance shall be 24 inches (610 mm) minimum on both sides of the grab bar. Where two grab bars are provided, clearance between grab bars shall be 24 inches (610 mm) minimum.

EXCEPTION: Grab bars on transfer walls shall not be required to comply with 609.4.




Figure 1009.4.5
Grab Bars for Transfer Walls

1009.5 Transfer Systems. Transfer systems shall comply with 1009.5.

1009.5.1 Transfer Platform. A transfer platform shall be provided at the head of each transfer system. Transfer platforms shall provide 19 inches (485 mm) minimum clear depth and 24 inches (610 mm) minimum clear width.




Figure 1009.5.1
Size of Transfer Platform

1009.5.2 Transfer Space. A transfer *space* of 60 inches (1525 mm) minimum by 60 inches (1525 mm) minimum with a slope not steeper than 1:48 shall be provided at the base of the transfer platform surface and shall be centered along a 24 inch (610 mm) minimum side of the transfer platform. The side of the transfer platform serving the transfer *space* shall be unobstructed.




Figure 1009.5.2
Clear Deck Space at Transfer Platform

1009.5.3 Height. The height of the transfer platform shall comply with 1009.4.2.

1009.5.4 Transfer Steps. Transfer step height shall be 8 inches (205 mm) maximum. The surface of the bottom tread shall extend to a water depth of 18 inches (455 mm) minimum below the stationary water level.

Advisory 1009.5.4 Transfer Steps. Where possible, the height of the transfer step should be minimized to decrease the distance an individual is required to lift up or move down to reach the next step to gain access.




Figure 1009.5.4
Transfer Steps

1009.5.5 Surface. The surface of the transfer system shall not be sharp and shall have rounded edges.

1009.5.6 Size. Each transfer step shall have a tread clear depth of 14 inches (355 mm) minimum and 17 inches (430 mm) maximum and shall have a tread clear width of 24 inches (610 mm) minimum.




Figure 1009.5.6
Size of Transfer Steps

1009.5.7 Grab Bars. At least one grab bar on each transfer step and the transfer platform or a continuous grab bar serving each transfer step and the transfer platform shall be provided. Where a grab bar is provided on each step, the tops of gripping surfaces shall be 4 inches (100 mm) minimum and 6 inches (150 mm) maximum above each step and transfer platform. Where a continuous grab bar is provided, the top of the gripping surface shall be 4 inches (100 mm) minimum and 6 inches (150 mm) maximum above the step nosing and transfer platform. Grab bars shall comply with 609 and be located on at least one side of the transfer system. The grab bar located at the transfer platform shall not obstruct transfer.

EXCEPTION: Grab bars on transfer systems shall not be required to comply with 609.4.




Figure 1009.5.7
Grab Bars

1009.6 Pool Stairs. Pool stairs shall comply with 1009.6.

1009.6.1 Pool Stairs. Pool stairs shall comply with 504.

EXCEPTION: Pool step riser heights shall not be required to be 4 inches (100 mm) high minimum and 7 inches (180 mm) high maximum provided that riser heights are uniform.

1009.6.2 Handrails. The width between handrails shall be 20 inches (510 mm) minimum and 24 inches (610 mm) maximum. Handrail extensions required by 505.10.3 shall not be required on pool stairs.

1010 Shooting Facilities with Firing Positions

1010.1 Turning Space. A circular turning *space* 60 inches (1525 mm) diameter minimum with slopes not steeper than 1:48 shall be provided at shooting facilities with firing positions.

INDEX TO THE 2010 STANDARDS

**36 CFR part 1191,
appendices B and D**
Application and Scoping
1

1991 Standards
Application and Scoping
8-11, 22, 26-28

2004 ADAAG
Application and Scoping
1, 14, 30

2010 Standards
Application and Scoping
1, 8, 10-14, 22, 26-30

A

Accessibility Standards
Application and Scoping
9, 22, 26

Accessible
Application and Scoping
44

Accessible Bathing Facility
Application and Scoping
28

Accessible Entrances
(see Entrances)

Accessible Features
Application and Scoping
8, 13, 24, 92

Accessible Rooms
Application and Scoping
28, 55, 88

Accessible Route(s)
Application and Scoping
8, 9, 11, 12, 21, 24, 29, 44, 50,
52-64, 66-69, 80, 81, 86, 92, 93,
98, 100-102

Technical
108, 113, 117, 118, 119, 127, 131,
133, 150-152, 162, 203, 212, 213,
215, 224, 226-229, 234-239, 241

Addition(s)
Application and Scoping
37, 44, 50, 57, 93, 99

Airport Passenger Terminal
Application and Scoping
21, 25, 56

Air Traffic Control Towers
Application and Scoping
56

**Aisle Seats (see Designated
Aisle Seats)**

Alteration(s)
Application and Scoping
6-10, 13, 14, 19, 21-28, 37,
44, 48, 50-52, 55, 57, 58,
61, 68, 69, 81-83, 90, 93, 95

Technical
19, 131, 156, 212, 221

Amusement Ride(s)
Application and Scoping
45, 48, 59, 60, 64, 74, 94, 95

Technical
224-227

Index and List of Figures

Animal Containment Areas

Application and Scoping
54

Technical
104, 105

ANSI/BHMA

Application and Scoping
40

Technical
126, 127, 143, 145

Apartments

Application and Scoping
12, 29, 46

Area(s) of Sport Activity

Application and Scoping
45, 54, 64, 79, 80

Technical
104, 105

ASME

Application and Scoping
40, 41

Technical
133, 143, 145, 147, 218

Assembly Area(s)

Application and Scoping
12, 29, 45, 48, 57, 58, 68, 71,
73, 76-80

Technical
127, 154, 156, 197

Assistive Listening System(s)

Application and Scoping
45, 73, 76, 77

Technical
194, 197, 198

ASTM

Application and Scoping
41, 42, 48

Technical
239

ATMs (see Automatic Teller Machines)

Automatic Fare Machines (see Fare Machines)

Automatic Teller Machine(s)

Application and Scoping
77

Technical
198, 199, 201

B

Barrier Removal

Application and Scoping
37

Bathing Facilities

Application and Scoping
11, 29, 69, 70, 73

Technical
172, 177, 181, 210, 211, 213

Bathing Rooms

Application and Scoping
69, 70, 73

Technical
160, 210

Bathtubs

Application and Scoping
70

Technical
171-174, 182

Bathtub Seats (see Seats, Bathtub and Shower)

Beds

Application and Scoping
11, 28, 29, 84, 85, 90

Technical
210, 211

Bench(es) (does not include Judges' Benches)

Technical
185, 206, 211, 219, 220

Boarding Pier(s)

Application and Scoping
45, 60, 97

Technical
229, 231

Boat Launch Ramps

Application and Scoping
45, 60, 97

Technical
228, 229, 231

Boat Slip(s)

Application and Scoping
45, 60, 96

Technical
228, 229

Boating Facilities

Application and Scoping
60, 64, 95

Technical
228

Bowling Lanes

Application and Scoping
60, 79

Boxing or Wrestling Rings

Application and Scoping
54

Bus Shelters

Application and Scoping
76

Technical
215

Bus Signs

Technical
216

Bus Stop(s)

Application and Scoping
67, 68

Technical
214, 215, 216

C

Cafeterias (see Restaurants and Cafeterias)

Carpet

Technical
104

Cells

Application and Scoping
13, 14, 53, 56, 68, 89, 90, 91

Technical
163, 211, 212

Cells with Mobility Features

Application and Scoping
13, 14, 56, 90, 211

Change Machines

Application and Scoping
88

Changes in Level

Technical
105-107, 117, 124, 127-129,
151-153, 202, 228

Index and List of Figures

Check-out Aisles

Application and Scoping
73, 74, 87, 88

Technical
220, 221

Children

Application and Scoping
37, 42, 45, 47, 74, 95, 98-100

Technical
113, 154, 159, 160, 161, 165, 167-
169, 171, 182, 206, 219, 240-242

Clear Floor or Ground Space

Application and Scoping
11, 28, 57, 84, 90

Technical
107-110 114-116, 127, 134, 138,
145, 147, 159, 160, 162, 170,
182, 185, 190, 194, 198, 201, 206,
208-212, 215, 218, 219, 221, 222,
227, 228, 233, 235-239, 241, 242

Clearances

Technical
117, 160-162, 174, 207, 225,
229, 231

Clearances, Maneuvering

Technical
120, 123, 124, 127, 129

Clocks

Application and Scoping
76

Technical
218

Clothes Dryers

Application and Scoping
70, 71

Technical
115, 185

Coat Hooks

Application and Scoping
70, 81

Technical
161, 162, 168, 206

Commercial Facility

Application and Scoping
19, 21, 22

Commercial Facilities Located in a Private Residence

Application and Scoping
19

Common Ownership

Application and Scoping
20, 25

Common Use

Application and Scoping
11, 12, 29, 45, 47, 53, 56, 59, 71

Technical
117, 128, 129, 160, 163, 171, 172,
177, 201

Common Use Area

Application and Scoping
12, 29, 53, 56, 71

Common Use Circulation Paths

Application and Scoping
59

Technical

117, 128, 129

Common Site

Application and Scoping
20, 25, 28, 92, 93

Communication Systems (see Two-Way Communication Systems)

Commuter Rail (see also Rail Platforms)

Application and Scoping
46, 76

Commuter Rail (cont'd)

Technical
217

Companion Seats

Application and Scoping
12, 29, 30, 78-80

Technical
202, 206, 226

Compliance Date

Application and Scoping
9, 10, 26, 27

Construction Sites

Application and Scoping
53

Conventions

Application and Scoping
37

**Correctional Facilities (see Detention
and Correctional Facilities)**

**Counters (see also Dining Surfaces and
Work Surfaces)**

Application and Scoping
59, 89, 91

Technical
207, 208, 219, 222

Counters, Sales and Service

Application and Scoping
86-88

Technical
220, 221

Court Sports

Application and Scoping
60

Courtroom

Application and Scoping
45, 54, 57, 63, 76, 89

Courtroom (con'td)

Technical
217

Cross Slope

Application and Scoping
45, 47

Technical
117, 128, 228

Curb Ramps

Application and Scoping
7, 13, 23, 45

Technical
117, 131-133

D

Definitions

Application and Scoping
44

Depot

Application and Scoping
21, 25, 56

Depositories

Application and Scoping
88

Designated Aisle Seats

Application and Scoping
78, 80

Technical
202, 206

Detectable Warnings

Application and Scoping
46

Technical
196, 197, 216

Index and List of Figures

Detention and Correctional Facilities

Application and Scoping
13, 14, 47, 48, 53, 56, 62, 64,
68, 71, 76, 89

Technical
163

Dimensions (General)

Application and Scoping
37, 38

Dining Surfaces

Application and Scoping
37, 86, 87

Technical
219

Disperse, Dispersion

Application and Scoping
12, 13, 29, 30, 63, 66, 67, 79,
80, 85-88, 94, 96, 99

Technical
234

Disproportionate, Disproportionality

Application and Scoping
7-9, 22-25, 51

Diving Boards and Diving Platforms

Application and Scoping
54

Door Swing

Technical
107, 127, 160, 190, 206

Doors, Doorways, and Gates (General)

Application and Scoping
8, 19, 24, 40, 46, 61-63, 70, 72, 83

Technical
117, 119, 120, 123-127, 129

Dressing, Fitting, and Locker Rooms

Application and Scoping
81

Dressing, Fitting, and Locker Rooms (cont'd)

Technical
206

Drinking Fountains

Application and Scoping
7-9, 22-24, 37, 51, 68, 69

Technical
159, 160

Dryers (see Washing Machines and Clothes Dryers)

E

Edge Protection

Technical
129, 130, 221, 229, 231, 234

Elevators

Application and Scoping
8, 23, 40, 45, 49, 63, 73

Technical
117, 133-138, 140-146, 189, 191

Elevator Exemption

Application and Scoping
9, 10, 20, 21, 25

Existing Elevator

Application and Scoping
63, 73

Technical
134, 135, 137, 138, 140, 141, 143

Employee Work Area

Application and Scoping
23, 46, 49, 54, 59, 71

Technical
117, 128, 129

Entrances

Application and Scoping
7-9, 21-24, 46, 47, 48, 52, 55,
57, 61, 62, 66-69, 73, 76, 83, 98

Technical
152, 201, 214, 217

Public Entrance
Application and Scoping
47, 61

Restricted Entrance
Application and Scoping
47, 62

Service Entrance
Application and Scoping
47, 62

Equivalent Access
Application and Scoping
9, 10, 67, 79, 80, 94

Equivalent Facilitation
Application and Scoping
37

Exercise Machine
Application and Scoping
55, 60, 97

Technical
233

Existing Elevator (see Elevators)

Existing Buildings and Facilities
Application and Scoping
22, 37, 50, 57, 63, 71, 93

Technical
180

Exits (see Means of Egress)

F

**Facilities with Residential Units
and Transient Lodging Units**
Application and Scoping
28

Fare Machines
Application and Scoping
77

Technical
198, 199, 201

Figures
Application and Scoping
11, 28, 38

Fire Alarm Systems
Application and Scoping
43, 71

Technical
186, 213

Fishing Piers and Platforms
Application and Scoping
60, 64, 97

Technical
234, 235

Fixed Guideway Stations
Application and Scoping
76

Floor or Ground Surfaces
Scoping
98, 99

Technical
104-107, 117, 124, 128, 130, 151,
152, 202, 224, 225, 239

Food Service Lines
Application and Scoping
87, 88

Index and List of Figures

Food Service Lines (cont'd)

Technical
222

Forward Reach (see Reach Ranges)

G

Gates (see Doors, Doorways, and Gates)

General Exceptions

Application and Scoping
53

Golf Car Passage

Application and Scoping
46, 60

Technical
236

Golf Facilities

Application and Scoping
60, 97

Technical
235

Grab Bars

Application and Scoping
8, 24

Technical
162-164, 167-169, 172-174, 177,
178, 180-182, 247, 248, 251

Gratings (see Openings)

Ground Level Play Components (see Play Areas)

Ground Surfaces (see Floor or Ground Surfaces)

Group Homes

Application and Scoping
11, 28

Guest Rooms (see Transient Lodging)

H

Halfway Houses

Application and Scoping
11, 28

Handrails

Application and Scoping
68

Technical

111, 112, 119, 128-130, 153-157,
224, 228, 234-236, 239, 246, 252

High Speed Rail

Application and Scoping
76

Historic Buildings and Facilities

Application and Scoping
7, 21, 26, 44, 47, 52, 55, 57, 61, 69

National Historic Preservation Act

Application and Scoping
26

Historic Preservation (see Historic Buildings and Facilities)

Historic Properties (see Historic Buildings and Facilities)

Qualified Historic Building or Facility

Application and Scoping
47, 52, 55, 57, 61, 69

Holding Cells (see Cells)

Hospitals (see Medical Care Facilities)

Hotels (see Transient Lodging)

Housing at a Place of Education

Application and Scoping
11, 29, 82

Housing Cells (see Cells)

I

ICC/IBC

Application and Scoping
42

Intercity Rail

Application and Scoping
61, 62, 76

Intersections

Application and Scoping
13

J

Jails (see Detention and Correctional Facilities)

Judges' Benches

Application and Scoping
57, 63

Technical
212

Judicial Facilities

Application and Scoping
62, 89

K

Kitchens and Kitchenettes

Application and Scoping
11, 29, 46, 55, 69, 93

Technical
206-209, 211, 213

Knee and Toe Clearance (see also Toe Clearance)

Technical
106-110, 159, 167, 170, 171, 208,
209, 219, 234

L

Landlord/Tenant

Application and Scoping
23

Lavatories

Application and Scoping
37, 70

Technical
160, 170, 171

Light Rail

Application and Scoping
46, 76

Limited-Use/Limited-Application

Elevators

Technical
143

Lines of Sight

Application and Scoping
79

Technical
203-205

Lockers (see also Storage)

Application and Scoping
85

Locker Rooms (see Dressing, Fitting, and Locker Rooms)

Long-Term Care Facilities

Application and Scoping
14, 47, 48, 68, 81, 82

Technical
180, 209

M

Machinery Spaces

Application and Scoping
53

Mail Boxes

Application and Scoping
46, 88

Technical
221

Index and List of Figures

March 15, 2011

Application and Scoping
9

March 15, 2012

Application and Scoping
8, 10, 26, 27

Maximum Extent Feasible

Application and Scoping
6, 7, 14, 21, 22, 26, 50, 51

Means of Egress

Application and Scoping
44, 46, 64, 68, 72

Technical
127, 212, 227, 228

Medical Care Facilities

Application and Scoping
13, 30, 48, 81, 90

Technical
180, 186

Mezzanine

Application and Scoping
46, 48, 56-58, 80

Technical
217

Miniature Golf Facilities

Application and Scoping
60, 98

Technical
236

Mirrors

Application and Scoping
70

Technical
160

Motels (see Transient Lodging)

Multi-bedroom Housing Units

Application and Scoping
11, 29

Multi-Story Buildings and Facilities

Application and Scoping
56, 57

N

NFPA

Application and Scoping
43

Technical
186, 213

National Historic Preservation Act (see Historic Buildings and Facilities)

New Construction

Application and Scoping
6, 9, 10, 13, 19, 26, 27, 50,
51, 63, 82, 83, 92

Normal Maintenance

Application and Scoping
21, 44

O

Openings

Application and Scoping
88

Technical
105, 119, 140, 218, 226, 227,
229, 231, 236

Operable Parts

Application and Scoping
55

Technical
115, 116, 125, 146, 147, 159,
185, 195, 199, 209, 218

P

Parking

Application and Scoping
7-9, 23, 24, 48, 55, 61, 65-68, 72

Technical
132, 149-152

Passenger Loading Zones

Application and Scoping
55, 65, 67, 68

Technical
152

Passing Spaces

Technical
119

Path of Travel

Application and Scoping
6-9, 22-25, 51

Percentages, Calculation of

Application and Scoping
38

Performance Areas

Application and Scoping
12, 30, 58, 63, 80

Technical
203

Place of Public Accommodation

Application and Scoping
20-22, 25, 26, 47

Places of Lodging

Application and Scoping
28, 82

Platform Lifts

Application and Scoping
40, 41, 45, 63, 64

Technical
117, 147, 212

Play Areas

Application and Scoping
54, 60, 64, 98, 99

Technical
237-239

Player Seating (see Team and Player Seating)

Plumbing Fixtures

Application and Scoping
70

Technical
165, 171

Pools (see Swimming Pools or Wading Pools)

Post-Mounted Objects

Technical
112

Press Boxes

Application and Scoping
58

Primary Function Areas

Application and Scoping
7-9, 22, 23, 25, 50, 51

Prisons (see Detention and Correctional Facilities)

Private Residences (see Commercial Facilities Located in Private Residences)

Private Residence Elevators

Technical
145

Professional Office of a Health Care Provider

Application and Scoping
20, 21, 25, 56

Index and List of Figures

Protruding Objects

Application and Scoping
54

Technical
111, 113

Psychiatric Facilities (see Medical Care Facilities)

Public Address Systems

Application and Scoping
76

Technical
218

Public Entrance (see Entrances)

Public Use

Application and Scoping
12, 29, 42, 45, 47, 54, 56, 63, 68, 71, 75

Technical
160, 163, 171, 172, 177, 197, 201, 216

Public Transportation

Application and Scoping
21, 25, 55, 56, 67

Putting Greens

Application and Scoping
60, 98

Technical
235

Q

Queues (see also Waiting Lines)

Application and Scoping
74, 87, 88

R

Rail Platforms

Technical
216

Raised Areas

Application and Scoping
53

Ramp(s)

Application and Scoping
8, 23, 24, 45, 47, 63, 67, 100

Technical

106, 112, 117, 127-130, 154, 156, 212,
224, 225, 236, 239, 241

Ramp, Pedestrian

Application and Scoping
8, 23

Rapid Rail

Application and Scoping
76

Reach Ranges

Technical
113, 116, 134, 140, 161, 168, 206, 218,
237, 242

Recreation Facilities (see Amusement Rides, Boating Facilities, Exercise Machines, Fishing Piers and Platforms, Golf, Miniature Golf, Saunas and Steam Rooms, Shooting Facilities, Swimming Pools, Wading Pools, or Spas)

Recreational Boating Facilities (see Boating Facilities)

Referenced Standards

Application and Scoping
40-44, 48, 64, 72

Technical

127, 133, 143, 145, 147, 186, 213, 218,
234, 239

Rehabilitation (of buildings and facilities)

Application and Scoping
21, 44

Rehabilitation Facilities
(see Medical Care Facilities)

Remodeling
Application and Scoping
21, 23, 44

Renovation
Application and Scoping
21, 44

**Rental Establishments (see Sales
or Rental Establishments)**

Residential Dwelling Unit
Application and Scoping
11, 13, 28, 29, 47, 48, 51, 53, 56,
62-64, 66, 67, 71, 72, 88, 91-94

Technical
145, 162, 163, 171, 172, 177,
178, 180, 201, 208, 212-214

Residential Facilities
Application and Scoping
11-13, 28, 29, 53, 56, 66, 67, 71,
72, 88, 91

Restaurants and Cafeterias
Application and Scoping
58

Restricted Entrance (see Entrances)

Roll-in Showers (see Showers)

Running Slope
Application and Scoping
45, 47

Technical
117, 119, 127, 128, 133, 237, 239

S

Safe Harbor
Application and Scoping
8

Sales and Service
Application and Scoping
87

Technical
220, 221

Sales or Rental Establishments
Application and Scoping
20, 21, 25, 26

Saunas and Steam Rooms
Application and Scoping
102

Technical
185

Scope of Coverage
Application and Scoping
11, 27

Seats, Bathub and Shower
Technical
172, 174, 175, 181-183

Section 35.151 of 28 CFR part 35
Application and Scoping
6

Security Barriers
Application and Scoping
64

Self-Service Storage (Facilities)
Application and Scoping
47, 62, 86

September 15, 2010
Application and Scoping
9, 10, 26, 27

Series of Smaller Alterations
Application and Scoping
9, 24

Service Entrance (see Entrances)

Index and List of Figures

Shelters

Application and Scoping
11, 28

Shelves

Application and Scoping
70, 76, 81, 86, 88

Technical
161, 162, 168, 206, 222

Shooting Facilities

Application and Scoping
103

Technical
252

Shopping Center or Shopping Mall

Application and Scoping
20, 21, 25, 26, 56

Showers

Application and Scoping
11, 29, 62, 70, 83, 84

Technical
174, 175-182, 210, 211

Roll-in Showers

Application and Scoping
11, 29, 84

Technical
175-180, 183, 210

Shower Compartments

Technical
174-182, 210

Transfer-type Showers

Application and Scoping
11, 29

Technical
174, 177, 178, 180, 183

Signs

Application and Scoping
71-74

Signs (cont'd)

Technical
136, 143, 151, 186, 189, 190,
216, 217, 218

Sinks

Application and Scoping
37, 55, 69

Technical
170, 171, 209

Site Arrival Points

Application and Scoping
55

Sleeping Rooms

Application and Scoping
11, 28, 29, 81, 82

Technical
209, 210

Slope (see Running Slope or Cross Slope)

Soft Contained Play Structures (see Play Areas)

Social Service Center Establishments

Application and Scoping
11, 28

Spas

Application and Scoping
102, 103

Technical
125, 242, 244

Stadiums, Arenas, Grandstands

Application and Scoping
12, 29, 45, 78

Stadium-Style Movie Theaters

Application and Scoping
12, 30

Stairs and Escalators in Existing Buildings

Application and Scoping
57

Stairways

Application and Scoping
45, 68, 72

Technical
139, 153

Start of Physical Construction or Alterations

Application and Scoping
26, 27

Storage (see also Self-Storage)

Application and Scoping
7, 9, 22, 24, 47, 48, 53, 62, 85, 86

Technical
209, 218, 227, 228

Streets, Roads, Highways

Application and Scoping
7, 13, 23, 55

Technical
131, 215

Structural Impracticability

Application and Scoping
6, 19

Structural Parts or Elements

Application and Scoping
21, 44

Swimming Pools

Application and Scoping
102

Technical
242

T

Team or Player Seating

Application and Scoping
64, 79, 80

Technically Infeasible

Application and Scoping
14, 48, 50, 69, 81, 93

Teeing Ground(s)

Application and Scoping
48, 60, 97, 98

Technical
235

Telephones

Application and Scoping
7-9, 22-24, 45, 48, 51, 73-76, 90

Technical
146, 193-196, 199, 201, 211,
212, 222

Temporary Facilities

Application and Scoping
11, 28, 50

Tenant Spaces

Application and Scoping
23, 62

Terminal

Application and Scoping
21, 25, 56, 76

Thresholds

Technical
124, 127, 140, 180

Toe Clearance (see also Knee and Toe Clearance)

Technical
106-110, 159, 167, 170, 171,
208, 209, 219, 234

Index and List of Figures

Toilet Compartments

Application and Scoping
37, 70

Technical
161, 165, 166, 168, 169

Toilet Facilities

Application and Scoping
52, 69

Technical
181, 211, 213

Tolerances, Construction and Manufacturing

Application and Scoping
38

Townhouses

Application and Scoping
12, 29

Transient Lodging

Application and Scoping
11, 12, 28, 29, 47, 48, 56, 62, 64, 71, 82-84

Technical
178, 180, 210

Transportation Facilities

Application and Scoping
51, 61, 76

Technical
214

TTY

Application and Scoping
8, 24, 48, 73-76

Technical
193, 196, 201, 211

Turning Space

Application and Scoping
11, 29

Technical
106, 107, 109, 138, 160, 162, 185, 206, 209, 211-213, 224, 235, 238, 239, 241, 252

Two-Way Communication Systems

Application and Scoping
88

Technical
142, 146, 201

U

Uniform Federal Accessibility Standards (UFAS)

Application and Scoping
8, 9, 10

Unisex Toilet Room

Application and Scoping
69, 70

Urinals

Application and Scoping
70

Technical
170

V

Van Parking Spaces

Application and Scoping
66, 67

Technical
149-151

Vending Machines

Application and Scoping
88

Vertical Clearance

Application and Scoping
54

Technical
113, 151, 152, 196, 237

Vertical Viewing Angle

Application and Scoping
12, 30

Visiting Areas

Application and Scoping
89-91

W

Wading Pools

Application and Scoping
102

Technical
242, 246

Waiting Lines (see also Queues)

Application and Scoping
74, 87, 88

Walk

Application and Scoping
7, 13, 23, 45, 46, 49, 61

Technical
131

Walking Surfaces

Application and Scoping
46-48

Technical
117, 119, 154, 155, 196, 220, 224

Washing Machines

Application and Scoping
70

Technical
115, 185

Water Closets

Application and Scoping
37, 70

Technical
161-169, 182, 210, 211 202-206,
212, 224-226

Water Slides

Application and Scoping
45, 54

Weather Shelters

Application and Scoping
60, 98

Technical
235, 236

Wheelchair Space(s)

Application and Scoping
12, 29, 30, 49, 57, 60, 63,
78, 79, 80, 95

Windows

Application and Scoping
7, 23, 73, 88

Technical
222

Work Surfaces

Application and Scoping
11, 29, 37, 86, 87

Technical
208, 209, 219

Index and List of Figures

LIST OF FIGURES FOR THE 2010 STANDARDS

Figure 104	Graphic Convention for Figures	39
Figure 302.2	Carpet Pile Height	104
Figure 302.3	Elongated Openings in Floor or Ground Surfaces	105
Figure 303.2	Vertical Change in Level	105
Figure 303.3	Beveled Change in Level	106
Figure 304.3.2	T-Shaped Turning Space	107
Figure 305.3	Clear Floor or Ground Space	108
Figure 305.5	Position of Clear Floor or Ground Space	108
Figure 305.7.1	Maneuvering Clearance in an Alcove, Forward Approach	109
Figure 305.7.2	Maneuvering Clearance in an Alcove, Parallel Approach	109
Figure 306.2	Toe Clearance	110
Figure 306.3	Knee Clearance	111
Figure 307.2	Limits of Protruding Objects	112
Figure 307.3	Post-Mounted Protruding Objects	112
Figure 307.4	Vertical Clearance	113
Figure 308.2.1	Unobstructed Forward Reach	114
Figure 308.2.2	Obstructed High Forward Reach	114
Figure 308.3.1	Unobstructed Side Reach	115
Figure 308.3.2	Obstructed High Side Reach	116
Figure 403.5.1	Clear Width of an Accessible Route	118
Figure 403.5.2	Clear Width at Turn	118
Figure 404.2.3	Clear Width of Doorways	120
Figure 404.2.4.1	Maneuvering Clearances at Manual Swinging Doors and Gates	121

Index and List of Figures

Figure 404.2.4.2	Maneuvering Clearances at Doorways without Doors, Sliding Doors, Gates, and Folding Doors	123
Figure 404.2.4.3	Maneuvering Clearances at Recessed Doors and Gates	124
Figure 404.2.6	Doors in Series and Gates in Series	125
Figure 405.7	Ramp Landings	129
Figure 405.9.1	Extended Floor or Ground Surface Edge Protection	130
Figure 405.9.2	Curb or Barrier Edge Protection	130
Figure 406.2	Counter Slope of Surfaces Adjacent to Curb Ramps	131
Figure 406.3	Sides of Curb Ramps	131
Figure 406.4	Landings at the Top of Curb Ramps	132
Figure 406.6	Diagonal or Corner Type Curb Ramps	132
Figure 406.7	Islands in Crossings	133
Figure 407.2.2.2	Visible Hall Signals	135
Figure 407.2.3.1	Floor Designations on Jambs of Elevator Hoistway Entrances	136
Figure 407.2.3.2	Car Designations on Jambs of Destination-Oriented Elevator Hoistway Entrances	136
Figure 407.4.1	Elevator Car Dimensions	138
Figure 408.4.1	Limited-Use/Limited-Application (LULA) Elevator Car Dimensions	144
Figure 409.4.6.2	Location of Private Residence Elevator Control Panel	146
Figure 410.6	Platform Lift Doors and Gates	148
Figure 502.2	Vehicle Parking Spaces	149
Figure 502.3	Parking Space Access Aisle	150
Figure 503.3	Passenger Loading Zone Access Aisle	152
Figure 504.5	Stair Nosings	153
Figure 505.4	Handrail Height	154

Index and List of Figures

Figure 505.5	Handrail Clearance	155
Figure 505.6	Horizontal Projections Below Gripping Surface	155
Figure 505.7.2	Handrail Non-Circular Cross Section	156
Figure 505.10.1	Top and Bottom Handrail Extension at Ramps	157
Figure 505.10.2	Top Handrail Extension at Stairs	157
Figure 505.10.3	Bottom Handrail Extension at Stairs	158
Figure 602.5	Drinking Fountain Spout Location	159
Figure 604.2	Water Closet Location	161
Figure 604.3.1	Size of Clearance at Water Closets	162
Figure 604.3.2	(Exception) Overlap of Water Closet Clearance in Residential Dwelling Units	162
Figure 604.5.1	Side Wall Grab Bar at Water Closets	163
Figure 604.5.2	Rear Wall Grab Bar at Water Closets	164
Figure 604.7	Dispenser Outlet Location	165
Figure 604.8.1.1	Size of Wheelchair Accessible Toilet Compartment	166
Figure 604.8.1.2	Wheelchair Accessible Toilet Compartment Doors	166
Figure 604.8.1.4	Wheelchair Accessible Toilet Compartment Toe Clearance	167
Figure 604.8.2	Ambulatory Accessible Toilet Compartment	168
Figure 605.2	Height and Depth of Urinals	170
Figure 607.2	Clearance for Bathtubs	172
Figure 607.4.1	Grab Bars for Bathtubs with Permanent Seats	173
Figure 607.4.2	Grab Bars for Bathtubs with Removable In-Tub Seats	173
Figure 607.5	Bathtub Control Location	174
Figure 608.2.1	Transfer Type Shower Compartment Size and Clearance	175
Figure 608.2.2	Standard Roll-In Type Shower Compartment Size and Clearance	176

Index and List of Figures

Figure 608.2.3	Alternate Roll-In Type Shower Compartment Size and Clearance	176
Figure 608.3.1	Grab Bars for Transfer Type Showers	177
Figure 608.3.2	Grab Bars for Standard Roll-In Type Showers	177
Figure 608.3.3	Grab Bars for Alternate Roll-In Type Showers	178
Figure 608.5.1	Transfer Type Shower Compartment Control Location	178
Figure 608.5.2	Standard Roll-In Type Shower Compartment Control Location	179
Figure 608.5.3	Alternate Roll-In Type Shower Compartment Control Location	180
Figure 609.2.2	Grab Bar Non-Circular Cross Section	181
Figure 609.3	Spacing of Grab Bars	182
Figure 610.2	Bathtub Seats	183
Figure 610.3	Extent of Seat	183
Figure 610.3.1	Rectangular Shower Seat	184
Figure 610.3.2	L-Shaped Shower Seat	184
Figure 611.4	Height of Laundry Compartment Opening	185
Figure 703.2.5	Height of Raised Characters	187
Figure 703.3.1	Braille Measurement	188
Figure 703.3.2	Position of Braille	189
Figure 703.4.1	Height of Tactile Characters Above Finish Floor or Ground	189
Figure 703.4.2	Location of Tactile Signs at Doors	190
Figure 703.6.1	Pictogram Field	192
Figure 703.7.2.1	International Symbol of Accessibility	193
Figure 703.7.2.2	International Symbol of TTY	193
Figure 703.7.2.3	Volume Control Telephone	193
Figure 703.7.2.4	International Symbol of Access for Hearing Loss	194

Index and List of Figures

Figure 704.2.1.1	Parallel Approach to Telephone	194
Figure 704.2.1.2	Forward Approach to Telephone	195
Figure 705.1	Size and Spacing of Truncated Domes	197
Figure 707.6.2	Numeric Key Layout	200
Figure 802.1.2	Width of Wheelchair Spaces	202
Figure 802.1.3	Depth of Wheelchair Spaces	203
Figure 802.2.1.1	Lines of Sight Over the Heads of Seated Spectators	204
Figure 802.2.1.2	Lines of Sight Between the Heads of Seated Spectators	204
Figure 802.2.2.1	Lines of Sight Over the Heads of Standing Spectators	205
Figure 802.2.2.2	Lines of Sight Between the Heads of Standing Spectators	205
Figure 804.2.1	Pass-Through Kitchens	207
Figure 804.2.2	U-Shaped Kitchens	208
Figure 810.2.2	Dimensions of Bus Boarding and Alighting Areas	215
Figure 810.3	Bus Shelters	216
Figure 810.10	(Exception) Track Crossings	218
Figure 903.4	Bench Back Support	220
Figure 904.3.2	Check-Out Aisle Counters	221
Figure 904.4	(Exception) Alteration of Sales and Service Counters	222
Figure 1002.4.4.3	Protrusions in Wheelchair Spaces in Amusement Rides	226
Figure 1003.3.1	Boat Slip Clearance	230
Figure 1003.3.1	(Exception 1) Clear Pier Space Reduction at Boat Slips	231
Figure 1003.3.1	(Exception 2) Edge Protection at Boat Slips	231
Figure 1003.3.2	Boarding Pier Clearance	232
Figure 1003.3.2	(Exception 1) Clear Pier Space Reduction at Boarding Piers	233
Figure 1003.3.2	(Exception 2) Edge Protection at Boarding Piers	233

Index and List of Figures

Figure 1005.3.2	Extended Ground or Deck Surface at Fishing Piers and Platforms	235
Figure 1007.3.2	Golf Club Reach Range Area	237
Figure 1008.3.1	Transfer Platforms	240
Figure 1008.3.2	Transfer Steps	241
Figure 1009.2.2	Pool Lift Seat Location	243
Figure 1009.2.3	Clear Deck Space at Pool Lifts	244
Figure 1009.2.4	Pool Lift Seat Height	244
Figure 1009.2.8	Pool Lift Submerged Depth	245
Figure 1009.3.2	Sloped Entry Submerged Depth	246
Figure 1009.3.3	Handrails for Sloped Entry	247
Figure 1009.4.1	Clear Deck Space at Transfer Walls	247
Figure 1009.4.2	Transfer Wall Height	248
Figure 1009.4.3	Depth and Length of Transfer Walls	248
Figure 1009.4.5	Grab Bars for Transfer Walls	249
Figure 1009.5.1	Size of Transfer Platform	249
Figure 1009.5.2	Clear Deck Space at Transfer Platform	250
Figure 1009.5.4	Transfer Steps	250
Figure 1009.5.6	Size of Transfer Steps	251
Figure 1009.5.7	Grab Bars	251



TRANSITION PLAN

APPENDIX I

WEB CONTENT ACCESSIBILITY GUIDELINES 2.0



[\[contents\]](#)



Web Content Accessibility Guidelines (WCAG) 2.0

W3C Recommendation 11 December 2008

This version:

<http://www.w3.org/TR/2008/REC-WCAG20-20081211/>

Latest version:

<http://www.w3.org/TR/WCAG20/>

Previous version:

<http://www.w3.org/TR/2008/PR-WCAG20-20081103/>

Editors:

Ben Caldwell, Trace R&D Center, University of Wisconsin-Madison

Michael Cooper, W3C

Loretta Guarino Reid, Google, Inc.

Gregg Vanderheiden, Trace R&D Center, University of Wisconsin-Madison

Previous Editors:

Wendy Chisholm (until July 2006 while at W3C)

John Slatin (until June 2006 while at Accessibility Institute, University of Texas at Austin)

Jason White (until June 2005 while at University of Melbourne)

Please refer to the [errata](#) for this document, which may include normative corrections.

See also [translations](#).

This document is also available in non-normative formats, available from [Alternate Versions of Web Content Accessibility Guidelines 2.0](#).

Copyright © 2008 W3C® (MIT, ERCIM, Keio), All Rights Reserved. W3C [liability](#), [trademark](#) and [document use](#) rules apply.

Abstract

Web Content Accessibility Guidelines (WCAG) 2.0 covers a wide range of recommendations for making Web content more accessible. Following these guidelines will make content accessible to a wider range of people with disabilities, including blindness and low vision, deafness and hearing loss, learning disabilities, cognitive limitations, limited movement, speech disabilities, photosensitivity and combinations of these. Following these guidelines will also often make your Web content more usable to users in general.

WCAG 2.0 success criteria are written as testable statements that are not technology-specific. Guidance about satisfying the success criteria in specific technologies, as well as general information about interpreting the success criteria, is provided in separate documents. See [Web Content Accessibility Guidelines \(WCAG\) Overview](#) for an introduction and links to WCAG technical and educational material.

WCAG 2.0 succeeds [Web Content Accessibility Guidelines 1.0 \[WCAG10\]](#), which was published as a W3C Recommendation May 1999. Although it is possible to conform either to WCAG 1.0 or to WCAG 2.0 (or both), the W3C recommends that new and updated content use WCAG 2.0. The W3C also recommends that Web accessibility policies reference WCAG 2.0.

Status of this Document

This section describes the status of this document at the time of its publication. Other documents may supersede this document. A list of current W3C publications and the latest revision of this technical report can be found in the [W3C technical reports index](#) at <http://www.w3.org/TR/>.

This is the Web Content Accessibility Guidelines (WCAG) 2.0 [W3C Recommendation](#) from the [Web Content Accessibility Guidelines Working Group](#).

This document has been reviewed by W3C Members, by software developers, and by other W3C groups and interested parties, and is endorsed by the Director as a W3C Recommendation. It is a stable document and may be used as reference material or cited from another document. W3C's role in making the Recommendation is to draw attention to the specification and to promote its widespread deployment. This enhances the functionality and interoperability of the Web.

WCAG 2.0 is supported by the associated non-normative documents, [Understanding WCAG 2.0](#) and [Techniques for WCAG 2.0](#). Although those documents do not have the formal status that WCAG 2.0 itself has, they provide information important to understanding and implementing WCAG.

The Working Group requests that any comments be made using the provided [online comment form](#). If this is not possible, comments can also be sent to public-comments-wcag20@w3.org. The [archives for the public comments list](#) are publicly available. Comments received on the WCAG 2.0 Recommendation cannot result in changes to this version of the guidelines, but may be addressed in errata or future versions of WCAG. The Working Group does not plan to make formal responses to comments. Archives of the [WCAG WG mailing list discussions](#) are publicly available, and future work undertaken by the Working Group may address comments received on this document.

This document has been produced as part of the W3C [Web Accessibility Initiative](#) (WAI). The goals of the WCAG Working Group are discussed in the [WCAG Working Group charter](#). The WCAG Working Group is part of the [WAI Technical Activity](#).

This document was produced by a group operating under the [5 February 2004 W3C Patent](#)

[Policy](#). W3C maintains a [public list of any patent disclosures](#) made in connection with the deliverables of the group; that page also includes instructions for disclosing a patent. An individual who has actual knowledge of a patent which the individual believes contains [Essential Claim\(s\)](#) must disclose the information in accordance with [section 6 of the W3C Patent Policy](#).

Table of Contents

[Introduction](#)

[WCAG 2.0 Layers of Guidance](#)

[WCAG 2.0 Supporting Documents](#)

[Important Terms in WCAG 2.0](#)

[WCAG 2.0 Guidelines](#)

[1 Perceivable](#)

[1.1 Provide text alternatives for any non-text content so that it can be changed into other forms people need, such as large print, braille, speech, symbols or simpler language.](#)

[1.2 Provide alternatives for time-based media.](#)

[1.3 Create content that can be presented in different ways \(for example simpler layout\) without losing information or structure.](#)

[1.4 Make it easier for users to see and hear content including separating foreground from background.](#)

[2 Operable](#)

[2.1 Make all functionality available from a keyboard.](#)

[2.2 Provide users enough time to read and use content.](#)

[2.3 Do not design content in a way that is known to cause seizures.](#)

[2.4 Provide ways to help users navigate, find content, and determine where they are.](#)

[3 Understandable](#)

[3.1 Make text content readable and understandable.](#)

[3.2 Make Web pages appear and operate in predictable ways.](#)

[3.3 Help users avoid and correct mistakes.](#)

[4 Robust](#)

[4.1 Maximize compatibility with current and future user agents, including assistive technologies.](#)

[Conformance](#)

[Conformance Requirements](#)

[Conformance Claims \(Optional\)](#)

[Statement of Partial Conformance - Third Party Content](#)

[Statement of Partial Conformance - Language](#)

Appendices

Appendix A: [Glossary](#) (Normative)

Appendix B: [Acknowledgments](#)

Appendix C: [References](#)

Introduction

This section is informative.

Web Content Accessibility Guidelines (WCAG) 2.0 defines how to make Web content more accessible to people with disabilities. Accessibility involves a wide range of disabilities, including visual, auditory, physical, speech, cognitive, language, learning, and neurological disabilities. Although these guidelines cover a wide range of issues, they are not able to address the needs of people with all types, degrees, and combinations of disability. These guidelines also make Web content more usable by older individuals with changing abilities due to aging and often improve usability for users in general.

WCAG 2.0 is developed through the [W3C process](#) in cooperation with individuals and organizations around the world, with a goal of providing a shared standard for Web content accessibility that meets the needs of individuals, organizations, and governments internationally. WCAG 2.0 builds on WCAG 1.0 [\[WCAG10\]](#) and is designed to apply broadly to different Web technologies now and in the future, and to be testable with a combination of automated testing and human evaluation. For an introduction to WCAG, see the [Web Content Accessibility Guidelines \(WCAG\) Overview](#).

Web accessibility depends not only on accessible content but also on accessible Web browsers and other user agents. Authoring tools also have an important role in Web accessibility. For an overview of how these components of Web development and interaction work together, see:

- [Essential Components of Web Accessibility](#)
- [User Agent Accessibility Guidelines \(UAAG\) Overview](#)
- [Authoring Tool Accessibility Guidelines \(ATAG\) Overview](#)

WCAG 2.0 Layers of Guidance

The individuals and organizations that use WCAG vary widely and include Web designers and developers, policy makers, purchasing agents, teachers, and students. In order to meet the varying needs of this audience, several layers of guidance are provided including overall *principles*, general *guidelines*, testable *success criteria* and a rich collection of *sufficient techniques*, *advisory techniques*, and *documented common failures* with examples, resource links and code.

- Principles - At the top are four principles that provide the foundation for Web accessibility: *perceivable*, *operable*, *understandable*, and *robust*. See also [Understanding the Four Principles of Accessibility](#).
- Guidelines - Under the principles are guidelines. The 12 guidelines provide the basic goals that authors should work toward in order to make content more accessible to users with different disabilities. The guidelines are not testable, but provide the framework and overall objectives to help authors understand the success criteria and better implement the techniques.
- Success Criteria - For each guideline, testable success criteria are provided to

allow WCAG 2.0 to be used where requirements and conformance testing are necessary such as in design specification, purchasing, regulation, and contractual agreements. In order to meet the needs of different groups and different situations, three levels of conformance are defined: A (lowest), AA, and AAA (highest). Additional information on WCAG levels can be found in [Understanding Levels of Conformance](#).

- Sufficient and Advisory Techniques - For each of the *guidelines* and *success criteria* in the WCAG 2.0 document itself, the working group has also documented a wide variety of *techniques*. The techniques are informative and fall into two categories: those that are *sufficient* for meeting the success criteria and those that are *advisory*. The advisory techniques go beyond what is required by the individual success criteria and allow authors to better address the guidelines. Some advisory techniques address accessibility barriers that are not covered by the testable success criteria. Where common failures are known, these are also documented. See also [Sufficient and Advisory Techniques in Understanding WCAG 2.0](#).

All of these layers of guidance (principles, guidelines, success criteria, and sufficient and advisory techniques) work together to provide guidance on how to make content more accessible. Authors are encouraged to view and apply all layers that they are able to, including the advisory techniques, in order to best address the needs of the widest possible range of users.

Note that even content that conforms at the highest level (AAA) will not be accessible to individuals with all types, degrees, or combinations of disability, particularly in the cognitive language and learning areas. Authors are encouraged to consider the full range of techniques, including the advisory techniques, as well as to seek relevant advice about current best practice to ensure that Web content is accessible, as far as possible, to this community. [Metadata](#) may assist users in finding content most suitable for their needs.

WCAG 2.0 Supporting Documents

The WCAG 2.0 document is designed to meet the needs of those who need a stable, referenceable technical standard. Other documents, called supporting documents, are based on the WCAG 2.0 document and address other important purposes, including the ability to be updated to describe how WCAG would be applied with new technologies. Supporting documents include:

1. [How to Meet WCAG 2.0](#) - A customizable quick reference to WCAG 2.0 that includes all of the guidelines, success criteria, and techniques for authors to use as they are developing and evaluating Web content.
2. [Understanding WCAG 2.0](#) - A guide to understanding and implementing WCAG 2.0. There is a short "Understanding" document for each guideline and success criterion in WCAG 2.0 as well as key topics.
3. [Techniques for WCAG 2.0](#) - A collection of techniques and common failures, each in a separate document that includes a description, examples, code and tests.
4. [The WCAG 2.0 Documents](#) - A diagram and description of how the technical documents are related and linked.

See [Web Content Accessibility Guidelines \(WCAG\) Overview](#) for a description of the WCAG 2.0 supporting material, including education resources related to WCAG 2.0. Additional resources covering topics such as the business case for Web accessibility, planning implementation to improve the accessibility of Web sites, and accessibility policies are listed in [WAI Resources](#).

Important Terms in WCAG 2.0

WCAG 2.0 includes three important terms that are different from WCAG 1.0. Each of these is introduced briefly below and defined more fully in the glossary.

Web Page

It is important to note that, in this standard, the term "[Web page](#)" includes much more than static HTML pages. It also includes the increasingly dynamic Web pages that are emerging on the Web, including "pages" that can present entire virtual interactive communities. For example, the term "Web page" includes an immersive, interactive movie-like experience found at a single URI. For more information, see [Understanding "Web Page"](#).

Programmatically Determined

Several success criteria require that content (or certain aspects of content) can be "[programmatically determined](#)." This means that the content is delivered in such a way that [user agents](#), including [assistive technologies](#), can extract and present this information to users in different modalities. For more information, see [Understanding Programmatically Determined](#).

Accessibility Supported

Using a technology in a way that is accessibility supported means that it works with assistive technologies (AT) and the accessibility features of operating systems, browsers, and other user agents. Technology features can only be [relied upon](#) to conform to WCAG 2.0 success criteria if they are used in a way that is "[accessibility supported](#)". Technology features can be used in ways that are not accessibility supported (do not work with assistive technologies, etc.) as long as they are not relied upon to conform to any success criterion (i.e., the same information or functionality is also available another way that is supported).

The definition of "accessibility supported" is provided in the [Appendix A: Glossary](#) section of these guidelines. For more information, see [Understanding Accessibility Support](#).

WCAG 2.0 Guidelines

This section is [normative](#).

Principle 1: Perceivable - Information and user interface components must be presentable to users in ways they can perceive.

Guideline 1.1 Text Alternatives: Provide text alternatives for any non-text content so that it can be changed into other forms people need, such as large print, braille, speech, symbols or simpler language.

[Understanding Guideline 1.1](#)

1.1.1 Non-text Content: All non-text content that is presented to the user has a text alternative that serves the equivalent purpose, except for the situations listed below.
(Level A)

[How to Meet 1.1.1](#)
[Understanding 1.1.1](#)

- Controls, Input: If non-text content is a control or accepts user input, then it has a name that describes its purpose. (Refer to [Guideline 4.1](#) for additional requirements for controls and content that accepts user input.)
- Time-Based Media: If non-text content is time-based media, then text alternatives at least provide descriptive identification of the non-text content. (Refer to [Guideline 1.2](#) for additional requirements for media.)
- Test: If non-text content is a test or exercise that would be invalid if presented in text, then text alternatives at least provide descriptive identification of the non-text content.
- Sensory: If non-text content is primarily intended to create a specific sensory experience, then text alternatives at least provide descriptive identification of the non-text content.
- CAPTCHA: If the purpose of non-text content is to confirm that content is being accessed by a person rather than a computer, then text alternatives that identify and describe the purpose of the non-text content are provided, and alternative forms of CAPTCHA using output modes for different types of sensory perception are provided to accommodate different disabilities.
- Decoration, Formatting, Invisible: If non-text content is pure decoration, is used only for visual formatting, or is not presented to users, then it is implemented in a way that it can be ignored by assistive technology.

Guideline 1.2 Time-based Media: Provide alternatives for time-based media.

[Understanding Guideline 1.2](#)

1.2.1 Audio-only and Video-only (Prerecorded): For prerecorded audio-only and prerecorded video-only media, the following are true, except when the audio or video is a media alternative for text and is clearly labeled as such: (Level A)

- Prerecorded Audio-only: An alternative for time-based media is provided that presents equivalent information for prerecorded audio-only content.
- Prerecorded Video-only: Either an alternative for time-based media or an audio track is provided that presents equivalent information for prerecorded video-only content.

[How to Meet 1.2.1](#)
[Understanding 1.2.1](#)

1.2.2 Captions (Prerecorded): Captions are provided for all prerecorded audio content in synchronized media, except when the media is a media alternative for text and is clearly labeled as such. (Level A)

[How to Meet 1.2.2](#)
[Understanding 1.2.2](#)

1.2.3 Audio Description or Media Alternative (Prerecorded): An alternative for time-based media or audio description of the prerecorded video content is provided for synchronized media, except when the media is a media alternative for text and is clearly labeled as such. (Level A)

[How to Meet 1.2.3](#)
[Understanding 1.2.3](#)

1.2.4 Captions (Live): Captions are provided for all live audio content in synchronized media. (Level AA)

[How to Meet 1.2.4](#)
[Understanding 1.2.4](#)

1.2.5 Audio Description (Prerecorded): Audio description is provided for all prerecorded video content in synchronized media. (Level AA)

[How to Meet 1.2.5](#)
[Understanding 1.2.5](#)

1.2.6 Sign Language (Prerecorded): Sign language interpretation is provided for all prerecorded audio content in synchronized media. (Level AAA)

[How to Meet 1.2.6](#)
[Understanding 1.2.6](#)

1.2.7 Extended Audio Description (Prerecorded): Where pauses in foreground audio are insufficient to allow audio descriptions to convey the sense of the video, extended audio description is provided for all prerecorded video content in synchronized media. (Level AAA)

[How to Meet 1.2.7](#)
[Understanding 1.2.7](#)

1.2.8 Media Alternative (Prerecorded): An alternative for time-based media is provided for all prerecorded synchronized media and for all prerecorded video-only media. (Level AAA)

[How to Meet 1.2.8](#)
[Understanding 1.2.8](#)

1.2.9 Audio-only (Live): An alternative for time-based media that presents equivalent information for live audio-only content is provided. (Level AAA)

[How to Meet 1.2.9](#)
[Understanding 1.2.9](#)

Guideline 1.3 Adaptable: Create content that can be presented in different ways (for example simpler layout) without losing information or structure.

[Understanding Guideline 1.3](#)

1.3.1 Info and Relationships: Information, structure, and relationships conveyed through presentation can be programmatically determined or are available in text. (Level A)

[How to Meet 1.3.1](#)
[Understanding 1.3.1](#)

1.3.2 Meaningful Sequence: When the sequence in which content is presented affects its meaning, a correct reading sequence can be programmatically determined. (Level A)

[How to Meet 1.3.2](#)
[Understanding 1.3.2](#)

1.3.3 Sensory Characteristics: Instructions provided for understanding and operating content do not rely solely on sensory characteristics of components such as shape, size, visual location, orientation, or sound. (Level A)

[How to Meet 1.3.3](#)
[Understanding 1.3.3](#)

Note: For requirements related to color, refer to [Guideline 1.4](#).

Guideline 1.4 Distinguishable: Make it easier for users to see and hear content including separating foreground from background.

[Understanding Guideline 1.4](#)

1.4.1 Use of Color: Color is not used as the only visual means of conveying information, indicating an action, prompting a response, or distinguishing a visual element.

[How to Meet 1.4.1](#)
[Understanding 1.4.1](#)

(Level A)

Note: This success criterion addresses color perception specifically. Other forms of perception are covered in [Guideline 1.3](#) including programmatic access to color and other visual presentation coding.

1.4.2 Audio Control: If any audio on a Web page plays automatically for more than 3 seconds, either a mechanism is available to pause or stop the audio, or a mechanism is available to control audio volume independently from the overall system volume level. (Level A)

[How to Meet 1.4.2](#)
[Understanding 1.4.2](#)

Note: Since any content that does not meet this success criterion can interfere with a user's ability to use the whole page, all content on the Web page (whether or not it is used to meet other success criteria) must meet this success criterion. See [Conformance Requirement 5: Non-Interference](#).

1.4.3 Contrast (Minimum): The visual presentation of text and images of text has a contrast ratio of at least 4.5:1, except for the following: (Level AA)

[How to Meet 1.4.3](#)
[Understanding 1.4.3](#)

- Large Text: Large-scale text and images of large-scale text have a contrast ratio of at least 3:1;
- Incidental: Text or images of text that are part of an inactive user interface component, that are pure decoration, that are not visible to anyone, or that are part of a picture that contains significant other visual content, have no contrast requirement.
- Logotypes: Text that is part of a logo or brand name has no minimum contrast requirement.

1.4.4 Resize text: Except for captions and images of text, text can be resized without assistive technology up to 200 percent without loss of content or functionality. (Level AA)

[How to Meet 1.4.4](#)
[Understanding 1.4.4](#)

1.4.5 Images of Text: If the technologies being used can achieve the visual presentation, text is used to convey information rather than images of text except for the following: (Level AA)

[How to Meet 1.4.5](#)
[Understanding 1.4.5](#)

- Customizable: The image of text can be visually customized to the user's requirements;
- Essential: A particular presentation of text is essential to the information being conveyed.

Note: Logotypes (text that is part of a logo or brand name)

are considered essential.

1.4.6 Contrast (Enhanced): The visual presentation of text and images of text has a contrast ratio of at least 7:1, except for the following: (Level AAA)

[How to Meet 1.4.6](#)
[Understanding 1.4.6](#)

- Large Text: Large-scale text and images of large-scale text have a contrast ratio of at least 4.5:1;
- Incidental: Text or images of text that are part of an inactive user interface component, that are pure decoration, that are not visible to anyone, or that are part of a picture that contains significant other visual content, have no contrast requirement.
- Logotypes: Text that is part of a logo or brand name has no minimum contrast requirement.

1.4.7 Low or No Background Audio: For prerecorded audio-only content that (1) contains primarily speech in the foreground, (2) is not an audio CAPTCHA or audio logo, and (3) is not vocalization intended to be primarily musical expression such as singing or rapping, at least one of the following is true: (Level AAA)

[How to Meet 1.4.7](#)
[Understanding 1.4.7](#)

- No Background: The audio does not contain background sounds.
- Turn Off: The background sounds can be turned off.
- 20 dB: The background sounds are at least 20 decibels lower than the foreground speech content, with the exception of occasional sounds that last for only one or two seconds.

Note: Per the definition of "decibel," background sound that meets this requirement will be approximately four times quieter than the foreground speech content.

1.4.8 Visual Presentation: For the visual presentation of blocks of text, a mechanism is available to achieve the following: (Level AAA)

[How to Meet 1.4.8](#)
[Understanding 1.4.8](#)

1. Foreground and background colors can be selected by the user.
2. Width is no more than 80 characters or glyphs (40 if CJK).
3. Text is not justified (aligned to both the left and the right margins).
4. Line spacing (leading) is at least space-and-a-half within paragraphs, and paragraph spacing is at least 1.5 times larger than the line spacing.
5. Text can be resized without assistive technology up to

200 percent in a way that does not require the user to scroll horizontally to read a line of text on a full-screen window.

1.4.9 Images of Text (No Exception): Images of text are only used for pure decoration or where a particular presentation of text is essential to the information being conveyed. (Level AAA)

Note: Logotypes (text that is part of a logo or brand name) are considered essential.

[How to Meet 1.4.9](#)
[Understanding 1.4.9](#)

Principle 2: Operable - User interface components and navigation must be operable.

Guideline 2.1 Keyboard Accessible: Make all functionality available from a keyboard.

[Understanding Guideline 2.1](#)

2.1.1 Keyboard: All functionality of the content is operable through a keyboard interface without requiring specific timings for individual keystrokes, except where the underlying function requires input that depends on the path of the user's movement and not just the endpoints. (Level A)

Note 1: This exception relates to the underlying function, not the input technique. For example, if using handwriting to enter text, the input technique (handwriting) requires path-dependent input but the underlying function (text input) does not.

Note 2: This does not forbid and should not discourage providing mouse input or other input methods in addition to keyboard operation.

[How to Meet 2.1.1](#)
[Understanding 2.1.1](#)

2.1.2 No Keyboard Trap: If keyboard focus can be moved to a component of the page using a keyboard interface, then focus can be moved away from that component using only a keyboard interface, and, if it requires more than unmodified arrow or tab keys or other standard exit methods, the user is advised of the method for moving focus away. (Level A)

Note: Since any content that does not meet this success criterion can interfere with a user's ability to use the whole page, all content on the Web page (whether it is used to

[How to Meet 2.1.2](#)
[Understanding 2.1.2](#)

meet other success criteria or not) must meet this success criterion. See [Conformance Requirement 5: Non-Interference](#).

2.1.3 Keyboard (No Exception): All functionality of the content is operable through a keyboard interface without requiring specific timings for individual keystrokes. (Level AAA)

[How to Meet 2.1.3](#)
[Understanding 2.1.3](#)

Guideline 2.2 Enough Time: Provide users enough time to read and use content.

[Understanding Guideline 2.2](#)

2.2.1 Timing Adjustable: For each time limit that is set by the content, at least one of the following is true: (Level A)

[How to Meet 2.2.1](#)
[Understanding 2.2.1](#)

- Turn off: The user is allowed to turn off the time limit before encountering it; or
- Adjust: The user is allowed to adjust the time limit before encountering it over a wide range that is at least ten times the length of the default setting; or
- Extend: The user is warned before time expires and given at least 20 seconds to extend the time limit with a simple action (for example, "press the space bar"), and the user is allowed to extend the time limit at least ten times; or
- Real-time Exception: The time limit is a required part of a real-time event (for example, an auction), and no alternative to the time limit is possible; or
- Essential Exception: The time limit is essential and extending it would invalidate the activity; or
- 20 Hour Exception: The time limit is longer than 20 hours.

Note: This success criterion helps ensure that users can complete tasks without unexpected changes in content or context that are a result of a time limit. This success criterion should be considered in conjunction with [Success Criterion 3.2.1](#), which puts limits on changes of content or context as a result of user action.

2.2.2 Pause, Stop, Hide: For moving, blinking, scrolling, or auto-updating information, all of the following are true: (Level A)

[How to Meet 2.2.2](#)
[Understanding 2.2.2](#)

- Moving, blinking, scrolling: For any moving,

blinking or scrolling information that (1) starts automatically, (2) lasts more than five seconds, and (3) is presented in parallel with other content, there is a mechanism for the user to pause, stop, or hide it unless the movement, blinking, or scrolling is part of an activity where it is essential; and

- Auto-updating: For any auto-updating information that (1) starts automatically and (2) is presented in parallel with other content, there is a mechanism for the user to pause, stop, or hide it or to control the frequency of the update unless the auto-updating is part of an activity where it is essential.

Note 1: For requirements related to flickering or flashing content, refer to [Guideline 2.3](#).

Note 2: Since any content that does not meet this success criterion can interfere with a user's ability to use the whole page, all content on the Web page (whether it is used to meet other success criteria or not) must meet this success criterion. See [Conformance Requirement 5: Non-Interference](#).

Note 3: Content that is updated periodically by software or that is streamed to the user agent is not required to preserve or present information that is generated or received between the initiation of the pause and resuming presentation, as this may not be technically possible, and in many situations could be misleading to do so.

Note 4: An animation that occurs as part of a preload phase or similar situation can be considered essential if interaction cannot occur during that phase for all users and if not indicating progress could confuse users or cause them to think that content was frozen or broken.

2.2.3 No Timing: Timing is not an essential part of the event or activity presented by the content, except for non-interactive synchronized media and real-time events. (Level AAA)

[How to Meet 2.2.3](#)
[Understanding 2.2.3](#)

2.2.4 Interruptions: Interruptions can be postponed or suppressed by the user, except interruptions involving an emergency. (Level AAA)

[How to Meet 2.2.4](#)
[Understanding 2.2.4](#)

2.2.5 Re-authenticating: When an authenticated session expires, the user can continue the activity without loss of data after re-authenticating. (Level AAA)

[How to Meet 2.2.5](#)
[Understanding 2.2.5](#)

Guideline 2.3 Seizures: Do not design content in a way that is known to cause seizures.

[Understanding Guideline 2.3](#)

2.3.1 Three Flashes or Below Threshold: Web pages do not contain anything that flashes more than three times in any one second period, or the flash is below the general flash and red flash thresholds. (Level A)

[How to Meet 2.3.1](#)
[Understanding 2.3.1](#)

Note: Since any content that does not meet this success criterion can interfere with a user's ability to use the whole page, all content on the Web page (whether it is used to meet other success criteria or not) must meet this success criterion. See [Conformance Requirement 5: Non-Interference](#).

2.3.2 Three Flashes: Web pages do not contain anything that flashes more than three times in any one second period. (Level AAA)

[How to Meet 2.3.2](#)
[Understanding 2.3.2](#)

Guideline 2.4 Navigable: Provide ways to help users navigate, find content, and determine where they are.

[Understanding Guideline 2.4](#)

2.4.1 Bypass Blocks: A mechanism is available to bypass blocks of content that are repeated on multiple Web pages. (Level A)

[How to Meet 2.4.1](#)
[Understanding 2.4.1](#)

2.4.2 Page Titled: Web pages have titles that describe topic or purpose. (Level A)

[How to Meet 2.4.2](#)
[Understanding 2.4.2](#)

2.4.3 Focus Order: If a Web page can be navigated sequentially and the navigation sequences affect meaning or operation, focusable components receive focus in an order that preserves meaning and operability. (Level A)

[How to Meet 2.4.3](#)
[Understanding 2.4.3](#)

2.4.4 Link Purpose (In Context): The purpose of each link can be determined from the link text alone or from the link

[How to Meet 2.4.4](#)
[Understanding 2.4.4](#)

text together with its programmatically determined link context, except where the purpose of the link would be ambiguous to users in general. (Level A)

2.4.5 Multiple Ways: More than one way is available to locate a Web page within a set of Web pages except where the Web Page is the result of, or a step in, a process. (Level AA)

[How to Meet 2.4.5](#)
[Understanding 2.4.5](#)

2.4.6 Headings and Labels: Headings and labels describe topic or purpose. (Level AA)

[How to Meet 2.4.6](#)
[Understanding 2.4.6](#)

2.4.7 Focus Visible: Any keyboard operable user interface has a mode of operation where the keyboard focus indicator is visible. (Level AA)

[How to Meet 2.4.7](#)
[Understanding 2.4.7](#)

2.4.8 Location: Information about the user's location within a set of Web pages is available. (Level AAA)

[How to Meet 2.4.8](#)
[Understanding 2.4.8](#)

2.4.9 Link Purpose (Link Only): A mechanism is available to allow the purpose of each link to be identified from link text alone, except where the purpose of the link would be ambiguous to users in general. (Level AAA)

[How to Meet 2.4.9](#)
[Understanding 2.4.9](#)

2.4.10 Section Headings: Section headings are used to organize the content. (Level AAA)

[How to Meet 2.4.10](#)
[Understanding 2.4.10](#)

Note 1: "Heading" is used in its general sense and includes titles and other ways to add a heading to different types of content.

Note 2: This success criterion covers sections within writing, not user interface components. User Interface components are covered under [Success Criterion 4.1.2](#).

Principle 3: Understandable - Information and the operation of user interface must be understandable.

Guideline 3.1 Readable: Make text content readable and understandable.

[Understanding Guideline 3.1](#)

3.1.1 Language of Page: The default human language of each Web page can be programmatically determined. (Level A)

[How to Meet 3.1.1](#)
[Understanding 3.1.1](#)

3.1.2 Language of Parts: The human language of each passage or phrase in the content can be programmatically determined except for proper names, technical terms, words of indeterminate language, and words or phrases that have become part of the vernacular of the immediately surrounding text. (Level AA)

[How to Meet 3.1.2](#)
[Understanding 3.1.2](#)

3.1.3 Unusual Words: A mechanism is available for identifying specific definitions of words or phrases used in an unusual or restricted way, including idioms and jargon. (Level AAA)

[How to Meet 3.1.3](#)
[Understanding 3.1.3](#)

3.1.4 Abbreviations: A mechanism for identifying the expanded form or meaning of abbreviations is available. (Level AAA)

[How to Meet 3.1.4](#)
[Understanding 3.1.4](#)

3.1.5 Reading Level: When text requires reading ability more advanced than the lower secondary education level after removal of proper names and titles, supplemental content, or a version that does not require reading ability more advanced than the lower secondary education level, is available. (Level AAA)

[How to Meet 3.1.5](#)
[Understanding 3.1.5](#)

3.1.6 Pronunciation: A mechanism is available for identifying specific pronunciation of words where meaning of the words, in context, is ambiguous without knowing the pronunciation. (Level AAA)

[How to Meet 3.1.6](#)
[Understanding 3.1.6](#)

Guideline 3.2 Predictable: Make Web pages appear and operate in predictable ways.

[Understanding Guideline 3.2](#)

3.2.1 On Focus: When any component receives focus, it does not initiate a change of context. (Level A)

[How to Meet 3.2.1](#)
[Understanding 3.2.1](#)

3.2.2 On Input: Changing the setting of any user interface

[How to Meet 3.2.2](#)

component does not automatically cause a change of context unless the user has been advised of the behavior before using the component. (Level A)

[Understanding 3.2.2](#)

3.2.3 Consistent Navigation: Navigational mechanisms that are repeated on multiple Web pages within a set of Web pages occur in the same relative order each time they are repeated, unless a change is initiated by the user. (Level AA)

[How to Meet 3.2.3](#)
[Understanding 3.2.3](#)

3.2.4 Consistent Identification: Components that have the same functionality within a set of Web pages are identified consistently. (Level AA)

[How to Meet 3.2.4](#)
[Understanding 3.2.4](#)

3.2.5 Change on Request: Changes of context are initiated only by user request or a mechanism is available to turn off such changes. (Level AAA)

[How to Meet 3.2.5](#)
[Understanding 3.2.5](#)

Guideline 3.3 Input Assistance: Help users avoid and correct mistakes.

[Understanding Guideline 3.3](#)

3.3.1 Error Identification: If an input error is automatically detected, the item that is in error is identified and the error is described to the user in text. (Level A)

[How to Meet 3.3.1](#)
[Understanding 3.3.1](#)

3.3.2 Labels or Instructions: Labels or instructions are provided when content requires user input. (Level A)

[How to Meet 3.3.2](#)
[Understanding 3.3.2](#)

3.3.3 Error Suggestion: If an input error is automatically detected and suggestions for correction are known, then the suggestions are provided to the user, unless it would jeopardize the security or purpose of the content. (Level AA)

[How to Meet 3.3.3](#)
[Understanding 3.3.3](#)

3.3.4 Error Prevention (Legal, Financial, Data): For Web pages that cause legal commitments or financial transactions for the user to occur, that modify or delete user-controllable data in data storage systems, or that submit user test responses, at least one of the following is true: (Level AA)

[How to Meet 3.3.4](#)
[Understanding 3.3.4](#)

1. Reversible: Submissions are reversible.

2. Checked: Data entered by the user is checked for input errors and the user is provided an opportunity to correct them.
3. Confirmed: A mechanism is available for reviewing, confirming, and correcting information before finalizing the submission.

3.3.5 Help: Context-sensitive help is available. (Level AAA)

[How to Meet 3.3.5](#)
[Understanding 3.3.5](#)

3.3.6 Error Prevention (All): For Web pages that require the user to submit information, at least one of the following is true: (Level AAA)

[How to Meet 3.3.6](#)
[Understanding 3.3.6](#)

1. Reversible: Submissions are reversible.
2. Checked: Data entered by the user is checked for input errors and the user is provided an opportunity to correct them.
3. Confirmed: A mechanism is available for reviewing, confirming, and correcting information before finalizing the submission.

Principle 4: Robust - Content must be robust enough that it can be interpreted reliably by a wide variety of user agents, including assistive technologies.

Guideline 4.1 Compatible: Maximize compatibility with current and future user agents, including assistive technologies.

[Understanding Guideline 4.1](#)

4.1.1 Parsing: In content implemented using markup languages, elements have complete start and end tags, elements are nested according to their specifications, elements do not contain duplicate attributes, and any IDs are unique, except where the specifications allow these features. (Level A)

[How to Meet 4.1.1](#)
[Understanding 4.1.1](#)

Note: Start and end tags that are missing a critical character in their formation, such as a closing angle bracket or a mismatched attribute value quotation mark are not complete.

4.1.2 Name, Role, Value: For all user interface components (including but not limited to: form elements, links

[How to Meet 4.1.2](#)
[Understanding 4.1.2](#)

and components generated by scripts), the name and role can be programmatically determined; states, properties, and values that can be set by the user can be programmatically set; and notification of changes to these items is available to user agents, including assistive technologies. (Level A)

Note: This success criterion is primarily for Web authors who develop or script their own user interface components. For example, standard HTML controls already meet this success criterion when used according to specification.

Conformance

This section is normative.

This section lists requirements for conformance to WCAG 2.0. It also gives information about how to make conformance claims, which are optional. Finally, it describes what it means to be accessibility supported, since only accessibility-supported ways of using technologies can be relied upon for conformance. [Understanding Conformance](#) includes further explanation of the accessibility-supported concept.

Conformance Requirements

In order for a Web page to conform to WCAG 2.0, all of the following conformance requirements must be satisfied:

1. **Conformance Level:** One of the following levels of conformance is met in full.
 - **Level A:** For Level A conformance (the minimum level of conformance), the Web page satisfies all the Level A Success Criteria, or a conforming alternate version is provided.
 - **Level AA:** For Level AA conformance, the Web page satisfies all the Level A and Level AA Success Criteria, or a Level AA conforming alternate version is provided.
 - **Level AAA:** For Level AAA conformance, the Web page satisfies all the Level A, Level AA and Level AAA Success Criteria, or a Level AAA conforming alternate version is provided.

Note 1: Although conformance can only be achieved at the stated levels, authors are encouraged to report (in their claim) any progress toward meeting success criteria from all levels beyond the achieved level of conformance.

Note 2: It is not recommended that Level AAA conformance be required as a general policy for entire sites because it is not possible to satisfy all Level AAA Success Criteria for some content.

2. **Full pages:** Conformance (and conformance level) is for full Web page(s) only, and cannot be achieved if part of a Web page is excluded.

Note 1: For the purpose of determining conformance, alternatives to part of a page's content are considered part of the page when the alternatives can be obtained directly

from the page, e.g., a long description or an alternative presentation of a video.

Note 2: Authors of Web pages that cannot conform due to content outside of the author's control may consider a [Statement of Partial Conformance](#).

3. Complete processes: When a Web page is one of a series of Web pages presenting a process (i.e., a sequence of steps that need to be completed in order to accomplish an activity), all Web pages in the process conform at the specified level or better.

(Conformance is not possible at a particular level if any page in the process does not conform at that level or better.)

Example: An online store has a series of pages that are used to select and purchase products. All pages in the series from start to finish (checkout) conform in order for any page that is part of the process to conform.

4. Only Accessibility-Supported Ways of Using Technologies: Only accessibility-supported ways of using technologies are relied upon to satisfy the success criteria. Any information or functionality that is provided in a way that is not accessibility supported is also available in a way that is accessibility supported. (See [Understanding accessibility support](#).)

5. Non-Interference: If technologies are used in a way that is not accessibility supported, or if they are used in a non-conforming way, then they do not block the ability of users to access the rest of the page. In addition, the Web page as a whole continues to meet the conformance requirements under each of the following conditions:

1. when any technology that is not relied upon is turned on in a user agent,
2. when any technology that is not relied upon is turned off in a user agent, and
3. when any technology that is not relied upon is not supported by a user agent

In addition, the following success criteria apply to all content on the page, including content that is not otherwise relied upon to meet conformance, because failure to meet them could interfere with any use of the page:

- 1.4.2 - Audio Control,
- 2.1.2 - No Keyboard Trap,
- 2.3.1 - Three Flashes or Below Threshold, and
- 2.2.2 - Pause, Stop, Hide.

Note: If a page cannot conform (for example, a conformance test page or an example page), it cannot be included in the scope of conformance or in a conformance claim.

For more information, including examples, see [Understanding Conformance Requirements](#).

Conformance Claims (Optional)

Conformance is defined only for Web pages. However, a conformance claim may be made to cover one page, a series of pages, or multiple related Web pages.

Required Components of a Conformance Claim

Conformance claims are not required. Authors can conform to WCAG 2.0 without making a claim. However, if a conformance claim is made, then the conformance claim

must include the following information:

1. Date of the claim
2. Guidelines title, version and URI "Web Content Accessibility Guidelines 2.0 at <http://www.w3.org/TR/2008/REC-WCAG20-20081211/>"
3. Conformance level satisfied: (Level A, AA or AAA)
4. A concise description of the Web pages, such as a list of URIs for which the claim is made, including whether subdomains are included in the claim.

Note 1: The Web pages may be described by list or by an expression that describes all of the URIs included in the claim.

Note 2: Web-based products that do not have a URI prior to installation on the customer's Web site may have a statement that the product would conform when installed.

5. A list of the Web content technologies relied upon.

Note: If a conformance logo is used, it would constitute a claim and must be accompanied by the required components of a conformance claim listed above.

Optional Components of a Conformance Claim

In addition to the required components of a conformance claim above, consider providing additional information to assist users. Recommended additional information includes:

- A list of success criteria beyond the level of conformance claimed that have been met. This information should be provided in a form that users can use, preferably machine-readable metadata.
- A list of the specific technologies that are "*used but not relied upon*."
- A list of user agents, including assistive technologies that were used to test the content.
- Information about any additional steps taken that go beyond the success criteria to enhance accessibility.
- A machine-readable metadata version of the list of specific technologies that are relied upon.
- A machine-readable metadata version of the conformance claim.

Note 1: Refer to [Understanding Conformance Claims](#) for more information and example conformance claims.

Note 2: Refer to [Understanding Metadata](#) for more information about the use of metadata in conformance claims.

Statement of Partial Conformance - Third Party Content

Sometimes, Web pages are created that will later have additional content added to them. For example, an email program, a blog, an article that allows users to add comments, or applications supporting user-contributed content. Another example would be a page, such as a portal or news site, composed of content aggregated from multiple contributors, or sites that automatically insert content from other sources over time, such as when advertisements are inserted dynamically.

In these cases, it is not possible to know at the time of original posting what the uncontrolled content of the pages will be. It is important to note that the uncontrolled content can affect the accessibility of the controlled content as well. Two options are available:

1. A determination of conformance can be made based on best knowledge. If a page of this type is monitored and repaired (non-conforming content is removed or brought into conformance) within two business days, then a determination or claim of conformance can be made since, except for errors in externally contributed content which are corrected or removed when encountered, the page conforms. No conformance claim can be made if it is not possible to monitor or correct non-conforming content;
OR
2. A "statement of partial conformance" may be made that the page does not conform, but could conform if certain parts were removed. The form of that statement would be, "This page does not conform, but would conform to WCAG 2.0 at level X if the following parts from uncontrolled sources were removed." In addition, the following would also be true of uncontrolled content that is described in the statement of partial conformance:
 - a. It is not content that is under the author's control.
 - b. It is described in a way that users can identify (e.g., they cannot be described as "all parts that we do not control" unless they are clearly marked as such.)

Statement of Partial Conformance - Language

A "statement of partial conformance due to language" may be made when the page does not conform, but would conform if accessibility support existed for (all of) the language(s) used on the page. The form of that statement would be, "This page does not conform, but would conform to WCAG 2.0 at level X if accessibility support existed for the following language(s):"

Appendix A: Glossary

This section is normative.

abbreviation

shortened form of a word, phrase, or name where the abbreviation has not become part of the language

Note 1: This includes initialisms and acronyms where:

1. initialisms are shortened forms of a name or phrase made from the initial letters of words or syllables contained in that name or phrase

Note 1: Not defined in all languages.

Example 1: SNCF is a French initialism that contains the initial letters of the Société Nationale des Chemins de Fer, the French national railroad.

Example 2: ESP is an initialism for extrasensory perception.

2. acronyms are abbreviated forms made from the initial letters or parts of other words (in a name or phrase) which may be pronounced as a word

Example: NOAA is an acronym made from the initial letters of the National Oceanic and Atmospheric Administration in the United States.

Note 2: Some companies have adopted what used to be an initialism as their company name. In these cases, the new name of the company is the letters (for example, Ecma) and the word is no longer considered an abbreviation.

accessibility supported

supported by users' assistive technologies as well as the accessibility features in browsers and other user agents.

To qualify as an accessibility-supported use of a Web content technology (or feature of a technology), both 1 and 2 must be satisfied for a Web content technology (or feature):

1. The way that the Web content technology is used must be supported by users' assistive technology (AT). This means that the way that the technology is used has been tested for interoperability with users' assistive technology in the human language(s) of the content,
AND
2. The Web content technology must have accessibility-supported user agents that are available to users. This means that at least one of the following four statements is true:
 - a. The technology is supported natively in widely-distributed user agents that are also accessibility supported (such as HTML and CSS);
OR
 - b. The technology is supported in a widely-distributed plug-in that is also accessibility supported;
OR
 - c. The content is available in a closed environment, such as a university or corporate network, where the user agent required by the technology and used by the organization is also accessibility supported;
OR
 - d. The user agent(s) that support the technology are accessibility supported and are available for download or purchase in a way that:
 - does not cost a person with a disability any more than a person without a disability and
 - is as easy to find and obtain for a person with a disability as it is for a person without disabilities.

Note 1: The WCAG Working group and the W3C do not specify which or how much support by assistive technologies there must be for a particular use of a Web technology in order for it to be classified as accessibility supported. (See [Level of Assistive Technology Support Needed for "Accessibility Support"](#).)

Note 2: Web technologies can be used in ways that are not accessibility supported as long as they are not relied upon and the page as a whole meets the conformance requirements, including [Conformance Requirement 4: Only Accessibility-Supported Ways of Using Technologies](#) and [Conformance Requirement 5: Non-Interference](#), are

met.

Note 3: When a Web Technology is used in a way that is "accessibility supported," it does not imply that the entire technology or all uses of the technology are supported. Most technologies, including HTML, lack support for at least one feature or use. Pages conform to WCAG only if the uses of the technology that are accessibility supported can be relied upon to meet WCAG requirements.

Note 4: When citing Web content technologies that have multiple versions, the version(s) supported should be specified.

Note 5: One way for authors to locate uses of a technology that are accessibility supported would be to consult compilations of uses that are documented to be accessibility supported. (See [Understanding Accessibility-Supported Web Technology Uses](#).) Authors, companies, technology vendors, or others may document accessibility-supported ways of using Web content technologies. However, all ways of using technologies in the documentation would need to meet the definition of accessibility-supported Web content technologies above.

alternative for time-based media

document including correctly sequenced text descriptions of time-based visual and auditory information and providing a means for achieving the outcomes of any time-based interaction

Note: A screenplay used to create the synchronized media content would meet this definition only if it was corrected to accurately represent the final synchronized media after editing.

ambiguous to users in general

the purpose cannot be determined from the link and all information of the Web page presented to the user simultaneously with the link (i.e., readers without disabilities would not know what a link would do until they activated it)

Example: The word guava in the following sentence "One of the notable exports is guava" is a link. The link could lead to a definition of guava, a chart listing the quantity of guava exported or a photograph of people harvesting guava. Until the link is activated, all readers are unsure and the person with a disability is not at any disadvantage.

ASCII art

picture created by a spatial arrangement of characters or glyphs (typically from the 95 printable characters defined by ASCII).

assistive technology (as used in this document)

hardware and/or software that acts as a user agent, or along with a mainstream user agent, to provide functionality to meet the requirements of users with disabilities that go beyond those offered by mainstream user agents

Note 1: functionality provided by assistive technology includes alternative presentations (e.g., as synthesized speech or magnified content), alternative input methods (e.g., voice), additional navigation or orientation mechanisms, and content transformations (e.g., to make tables more accessible).

Note 2: Assistive technologies often communicate data and messages with

mainstream user agents by using and monitoring APIs.

Note 3: The distinction between mainstream user agents and assistive technologies is not absolute. Many mainstream user agents provide some features to assist individuals with disabilities. The basic difference is that mainstream user agents target broad and diverse audiences that usually include people with and without disabilities. Assistive technologies target narrowly defined populations of users with specific disabilities. The assistance provided by an assistive technology is more specific and appropriate to the needs of its target users. The mainstream user agent may provide important functionality to assistive technologies like retrieving Web content from program objects or parsing markup into identifiable bundles.

Example: Assistive technologies that are important in the context of this document include the following:

- screen magnifiers, and other visual reading assistants, which are used by people with visual, perceptual and physical print disabilities to change text font, size, spacing, color, synchronization with speech, etc. in order to improve the visual readability of rendered text and images;
- screen readers, which are used by people who are blind to read textual information through synthesized speech or braille;
- text-to-speech software, which is used by some people with cognitive, language, and learning disabilities to convert text into synthetic speech;
- speech recognition software, which may be used by people who have some physical disabilities;
- alternative keyboards, which are used by people with certain physical disabilities to simulate the keyboard (including alternate keyboards that use head pointers, single switches, sip/puff and other special input devices.);
- alternative pointing devices, which are used by people with certain physical disabilities to simulate mouse pointing and button activations.

audio

the technology of sound reproduction

Note: Audio can be created synthetically (including speech synthesis), recorded from real world sounds, or both.

audio description

narration added to the soundtrack to describe important visual details that cannot be understood from the main soundtrack alone

Note 1: Audio description of video provides information about actions, characters, scene changes, on-screen text, and other visual content.

Note 2: In standard audio description, narration is added during existing pauses in dialogue. (See also extended audio description.)

Note 3: Where all of the video information is already provided in existing audio, no additional audio description is necessary.

Note 4: Also called "video description" and "descriptive narration."

audio-only

a time-based presentation that contains only audio (no video and no interaction)

blinking

switch back and forth between two visual states in a way that is meant to draw attention

Note: See also flash. It is possible for something to be large enough and blink brightly enough at the right frequency to be also classified as a flash.

blocks of text

more than one sentence of text

CAPTCHA

initialism for "Completely Automated Public Turing test to tell Computers and Humans Apart"

Note 1: CAPTCHA tests often involve asking the user to type in text that is displayed in an obscured image or audio file.

Note 2: A Turing test is any system of tests designed to differentiate a human from a computer. It is named after famed computer scientist Alan Turing. The term was coined by researchers at Carnegie Mellon University. [\[CAPTCHA\]](#)

captions

synchronized visual and/or text alternative for both speech and non-speech audio information needed to understand the media content

Note 1: Captions are similar to dialogue-only subtitles except captions convey not only the content of spoken dialogue, but also equivalents for non-dialogue audio information needed to understand the program content, including sound effects, music, laughter, speaker identification and location.

Note 2: Closed Captions are equivalents that can be turned on and off with some players.

Note 3: Open Captions are any captions that cannot be turned off. For example, if the captions are visual equivalent images of text embedded in video.

Note 4: Captions should not obscure or obstruct relevant information in the video.

Note 5: In some countries, captions are called subtitles.

Note 6: Audio descriptions can be, but do not need to be, captioned since they are descriptions of information that is already presented visually.

changes of context

major changes in the content of the Web page that, if made without user awareness, can disorient users who are not able to view the entire page simultaneously

Changes in context include changes of:

1. user agent;
2. viewport;
3. focus;
4. content that changes the meaning of the Web page.

Note: A change of content is not always a change of context. Changes in content, such as an expanding outline, dynamic menu, or a tab control do not necessarily

change the context, unless they also change one of the above (e.g., focus).

Example: Opening a new window, moving focus to a different component, going to a new page (including anything that would look to a user as if they had moved to a new page) or significantly re-arranging the content of a page are examples of changes of context.

conformance

satisfying all the requirements of a given standard, guideline or specification

conforming alternate version

version that

1. conforms at the designated level, and
2. provides all of the same information and functionality in the same human language, and
3. is as up to date as the non-conforming content, and
4. for which at least one of the following is true:
 - a. the conforming version can be reached from the non-conforming page via an accessibility-supported mechanism, or
 - b. the non-conforming version can only be reached from the conforming version, or
 - c. the non-conforming version can only be reached from a conforming page that also provides a mechanism to reach the conforming version

Note 1: In this definition, "can only be reached" means that there is some mechanism, such as a conditional redirect, that prevents a user from "reaching" (loading) the non-conforming page unless the user had just come from the conforming version.

Note 2: The alternate version does not need to be matched page for page with the original (e.g., the conforming alternate version may consist of multiple pages).

Note 3: If multiple language versions are available, then conforming alternate versions are required for each language offered.

Note 4: Alternate versions may be provided to accommodate different technology environments or user groups. Each version should be as conformant as possible. One version would need to be fully conformant in order to meet [conformance requirement 1](#).

Note 5: The conforming alternative version does not need to reside within the scope of conformance, or even on the same Web site, as long as it is as freely available as the non-conforming version.

Note 6: Alternate versions should not be confused with supplementary content, which support the original page and enhance comprehension.

Note 7: Setting user preferences within the content to produce a conforming version is an acceptable mechanism for reaching another version as long as the method used to set the preferences is accessibility supported.

See [Understanding Conforming Alternate Versions](#)

content (Web content)

information and sensory experience to be communicated to the user by means of a user agent, including code or markup that defines the content's structure, presentation, and interactions

context-sensitive help

help text that provides information related to the function currently being performed

Note: Clear labels can act as context-sensitive help.

contrast ratio

$(L1 + 0.05) / (L2 + 0.05)$, where

- L1 is the relative luminance of the lighter of the colors, and
- L2 is the relative luminance of the darker of the colors.

Note 1: Contrast ratios can range from 1 to 21 (commonly written 1:1 to 21:1).

Note 2: Because authors do not have control over user settings as to how text is rendered (for example font smoothing or anti-aliasing), the contrast ratio for text can be evaluated with anti-aliasing turned off.

Note 3: For the purpose of Success Criteria 1.4.3 and 1.4.6, contrast is measured with respect to the specified background over which the text is rendered in normal usage. If no background color is specified, then white is assumed.

Note 4: Background color is the specified color of content over which the text is to be rendered in normal usage. It is a failure if no background color is specified when the text color is specified, because the user's default background color is unknown and cannot be evaluated for sufficient contrast. For the same reason, it is a failure if no text color is specified when a background color is specified.

Note 5: When there is a border around the letter, the border can add contrast and would be used in calculating the contrast between the letter and its background. A narrow border around the letter would be used as the letter. A wide border around the letter that fills in the inner details of the letters acts as a halo and would be considered background.

Note 6: WCAG conformance should be evaluated for color pairs specified in the content that an author would expect to appear adjacent in typical presentation. Authors need not consider unusual presentations, such as color changes made by the user agent, except where caused by authors' code.

correct reading sequence

any sequence where words and paragraphs are presented in an order that does not change the meaning of the content

emergency

a sudden, unexpected situation or occurrence that requires immediate action to preserve health, safety, or property

essential

if removed, would fundamentally change the information or functionality of the content, and information and functionality cannot be achieved in another way that would conform

extended audio description

audio description that is added to an audiovisual presentation by pausing the video so that there is time to add additional description

Note: This technique is only used when the sense of the video would be lost without the additional audio description and the pauses between dialogue/narration are too short.

flash

a pair of opposing changes in relative luminance that can cause seizures in some people if it is large enough and in the right frequency range

Note 1: See general flash and red flash thresholds for information about types of flash that are not allowed.

Note 2: See also blinking.

functionality

processes and outcomes achievable through user action

general flash and red flash thresholds

a flash or rapidly changing image sequence is below the threshold (i.e., content passes) if any of the following are true:

1. there are no more than three general flashes and / or no more than three red flashes within any one-second period; or
2. the combined area of flashes occurring concurrently occupies no more than a total of .006 steradians within any 10 degree visual field on the screen (25% of any 10 degree visual field on the screen) at typical viewing distance

where:

- A general flash is defined as a pair of opposing changes in relative luminance of 10% or more of the maximum relative luminance where the relative luminance of the darker image is below 0.80; and where "a pair of opposing changes" is an increase followed by a decrease, or a decrease followed by an increase, and
- A red flash is defined as any pair of opposing transitions involving a saturated red.

Exception: Flashing that is a fine, balanced, pattern such as white noise or an alternating checkerboard pattern with "squares" smaller than 0.1 degree (of visual field at typical viewing distance) on a side does not violate the thresholds.

Note 1: For general software or Web content, using a 341 x 256 pixel rectangle anywhere on the displayed screen area when the content is viewed at 1024 x 768 pixels will provide a good estimate of a 10 degree visual field for standard screen sizes and viewing distances (e.g., 15-17 inch screen at 22-26 inches). (Higher resolutions displays showing the same rendering of the content yield smaller and safer images so it is lower resolutions that are used to define the thresholds.)

Note 2: A transition is the change in relative luminance (or relative luminance/color for red flashing) between adjacent peaks and valleys in a plot of relative luminance (or relative luminance/color for red flashing) measurement against time. A flash consists of two opposing transitions.

Note 3: The current working definition in the field for "pair of opposing transitions involving a saturated red" is where, for either or both states involved in each transition, $R/(R + G + B) \geq 0.8$, and the change in the value of $(R - G - B) \times 320$ is > 20 (negative values of $(R - G - B) \times 320$ are set to zero) for both transitions. R, G, B values range from 0-1 as specified in "relative luminance" definition.

[\[HARDING-BINNIE\]](#)

Note 4: Tools are available that will carry out analysis from video screen capture. However, no tool is necessary to evaluate for this condition if flashing is less than or equal to 3 flashes in any one second. Content automatically passes (see #1 and #2 above).

human language

language that is spoken, written or signed (through visual or tactile means) to communicate with humans

Note: See also sign language.

idiom

phrase whose meaning cannot be deduced from the meaning of the individual words and the specific words cannot be changed without losing the meaning

Note: idioms cannot be translated directly, word for word, without losing their (cultural or language-dependent) meaning.

Example 1: In English, "spilling the beans" means "revealing a secret." However, "knocking over the beans" or "spilling the vegetables" does not mean the same thing.

Example 2: In Japanese, the phrase "さじを投げる" literally translates into "he throws a spoon," but it means that there is nothing he can do and finally he gives up.

Example 3: In Dutch, "Hij ging met de kippen op stok" literally translates into "He went to roost with the chickens," but it means that he went to bed early.

image of text

text that has been rendered in a non-text form (e.g., an image) in order to achieve a particular visual effect

Note: This does not include text that is part of a picture that contains significant other visual content.

Example: A person's name on a nametag in a photograph.

informative

for information purposes and not required for conformance

Note: Content required for conformance is referred to as "normative."

input error

information provided by the user that is not accepted

Note: This includes:

1. Information that is required by the Web page but omitted by the user
2. Information that is provided by the user but that falls outside the required data format or values

jargon

words used in a particular way by people in a particular field

Example: The word StickyKeys is jargon from the field of assistive technology/accessibility.

keyboard interface

interface used by software to obtain keystroke input

Note 1: A keyboard interface allows users to provide keystroke input to programs even if the native technology does not contain a keyboard.

Example: A touchscreen PDA has a keyboard interface built into its operating system as well as a connector for external keyboards. Applications on the PDA can use the interface to obtain keyboard input either from an external keyboard or from other applications that provide simulated keyboard output, such as handwriting interpreters or speech-to-text applications with "keyboard emulation" functionality.

Note 2: Operation of the application (or parts of the application) through a keyboard-operated mouse emulator, such as MouseKeys, does not qualify as operation through a keyboard interface because operation of the program is through its pointing device interface, not through its keyboard interface.

label

text or other component with a text alternative that is presented to a user to identify a component within Web content

Note 1: A label is presented to all users whereas the name may be hidden and only exposed by assistive technology. In many (but not all) cases the name and the label are the same.

Note 2: The term label is not limited to the label element in HTML.

large scale (text)

with at least 18 point or 14 point bold or font size that would yield equivalent size for Chinese, Japanese and Korean (CJK) fonts

Note 1: Fonts with extraordinarily thin strokes or unusual features and characteristics that reduce the familiarity of their letter forms are harder to read, especially at lower contrast levels.

Note 2: Font size is the size when the content is delivered. It does not include resizing that may be done by a user.

Note 3: The actual size of the character that a user sees is dependent both on the author-defined size and the user's display or user-agent settings. For many mainstream body text fonts, 14 and 18 point is roughly equivalent to 1.2 and 1.5 em or to 120% or 150% of the default size for body text (assuming that the body font is 100%), but authors would need to check this for the particular fonts in use. When fonts are defined in relative units, the actual point size is calculated by the user agent for display. The point size should be obtained from the user agent, or calculated based on font metrics as the user agent does, when evaluating this success criterion. Users who have low vision would be responsible for choosing appropriate settings.

Note 4: When using text without specifying the font size, the smallest font size used

on major browsers for unspecified text would be a reasonable size to assume for the font. If a level 1 heading is rendered in 14pt bold or higher on major browsers, then it would be reasonable to assume it is large text. Relative scaling can be calculated from the default sizes in a similar fashion.

Note 5: The 18 and 14 point sizes for roman texts are taken from the minimum size for large print (14pt) and the larger standard font size (18pt). For other fonts such as CJK languages, the "equivalent" sizes would be the minimum large print size used for those languages and the next larger standard large print size.

legal commitments

transactions where the person incurs a legally binding obligation or benefit

Example: A marriage license, a stock trade (financial and legal), a will, a loan, adoption, signing up for the army, a contract of any type, etc.

link purpose

nature of the result obtained by activating a hyperlink

live

information captured from a real-world event and transmitted to the receiver with no more than a broadcast delay

Note 1: A broadcast delay is a short (usually automated) delay, for example used in order to give the broadcaster time to queue or censor the audio (or video) feed, but not sufficient to allow significant editing.

Note 2: If information is completely computer generated, it is not live.

lower secondary education level

the two or three year period of education that begins after completion of six years of school and ends nine years after the beginning of primary education

Note: This definition is based on the International Standard Classification of Education [\[UNESCO\]](#).

mechanism

process or technique for achieving a result

Note 1: The mechanism may be explicitly provided in the content, or may be relied upon to be provided by either the platform or by user agents, including assistive technologies.

Note 2: The mechanism needs to meet all success criteria for the conformance level claimed.

media alternative for text

media that presents no more information than is already presented in text (directly or via text alternatives)

Note: A media alternative for text is provided for those who benefit from alternate representations of text. Media alternatives for text may be audio-only, video-only (including sign-language video), or audio-video.

name

text by which software can identify a component within Web content to the user

Note 1: The name may be hidden and only exposed by assistive technology, whereas a label is presented to all users. In many (but not all) cases, the label and the name are the same.

Note 2: This is unrelated to the name attribute in HTML.

navigated sequentially

navigated in the order defined for advancing focus (from one element to the next) using a keyboard interface

non-text content

any content that is not a sequence of characters that can be programmatically determined or where the sequence is not expressing something in human language

Note: This includes ASCII Art (which is a pattern of characters), emoticons, leetspeak (which uses character substitution), and images representing text

normative

required for conformance

Note 1: One may conform in a variety of well-defined ways to this document.

Note 2: Content identified as "informative" or "non-normative" is never required for conformance.

on a full-screen window

on the most common sized desktop/laptop display with the viewport maximized

Note: Since people generally keep their computers for several years, it is best not to rely on the latest desktop/laptop display resolutions but to consider the common desktop/laptop display resolutions over the course of several years when making this evaluation.

paused

stopped by user request and not resumed until requested by user

prerecorded

information that is not live

presentation

rendering of the content in a form to be perceived by users

primary education level

six year time period that begins between the ages of five and seven, possibly without any previous education

Note: This definition is based on the International Standard Classification of Education [\[UNESCO\]](#).

process

series of user actions where each action is required in order to complete an activity

Example 1: Successful use of a series of Web pages on a shopping site requires users to view alternative products, prices and offers, select products, submit an order, provide shipping information and provide payment information.

Example 2: An account registration page requires successful completion of a Turing test before the registration form can be accessed.

programmatically determined (programmatically determinable)

determined by software from author-supplied data provided in a way that different user agents, including assistive technologies, can extract and present this information to users in different modalities

Example 1: Determined in a markup language from elements and attributes that are accessed directly by commonly available assistive technology.

Example 2: Determined from technology-specific data structures in a non-markup language and exposed to assistive technology via an accessibility API that is supported by commonly available assistive technology.

programmatically determined link context

additional information that can be programmatically determined from relationships with a link, combined with the link text, and presented to users in different modalities

Example: In HTML, information that is programmatically determinable from a link in English includes text that is in the same paragraph, list, or table cell as the link or in a table header cell that is associated with the table cell that contains the link.

Note: Since screen readers interpret punctuation, they can also provide the context from the current sentence, when the focus is on a link in that sentence.

programmatically set

set by software using methods that are supported by user agents, including assistive technologies

pure decoration

serving only an aesthetic purpose, providing no information, and having no functionality

Note: Text is only purely decorative if the words can be rearranged or substituted without changing their purpose.

Example: The cover page of a dictionary has random words in very light text in the background.

real-time event

event that a) occurs at the same time as the viewing and b) is not completely generated by the content

Example 1: A Webcast of a live performance (occurs at the same time as the viewing and is not prerecorded).

Example 2: An on-line auction with people bidding (occurs at the same time as the viewing).

Example 3: Live humans interacting in a virtual world using avatars (is not completely generated by the content and occurs at the same time as the viewing).

relationships

meaningful associations between distinct pieces of content

relative luminance

the relative brightness of any point in a colorspace, normalized to 0 for darkest black and 1 for lightest white

Note 1: For the sRGB colorspace, the relative luminance of a color is defined as $L =$

$0.2126 * R + 0.7152 * G + 0.0722 * B$ where R, G and B are defined as:

- if $R_{sRGB} \leq 0.03928$ then $R = R_{sRGB}/12.92$ else $R = ((R_{sRGB}+0.055)/1.055) ^{2.4}$
- if $G_{sRGB} \leq 0.03928$ then $G = G_{sRGB}/12.92$ else $G = ((G_{sRGB}+0.055)/1.055) ^{2.4}$
- if $B_{sRGB} \leq 0.03928$ then $B = B_{sRGB}/12.92$ else $B = ((B_{sRGB}+0.055)/1.055) ^{2.4}$

and R_{sRGB} , G_{sRGB} , and B_{sRGB} are defined as:

- $R_{sRGB} = R_{8bit}/255$
- $G_{sRGB} = G_{8bit}/255$
- $B_{sRGB} = B_{8bit}/255$

The "^" character is the exponentiation operator. (Formula taken from [\[sRGB\]](#) and [\[IEC-4WD\]](#)).

Note 2: Almost all systems used today to view Web content assume sRGB encoding. Unless it is known that another color space will be used to process and display the content, authors should evaluate using sRGB colorspace. If using other color spaces, see [Understanding Success Criterion 1.4.3](#).

Note 3: If dithering occurs after delivery, then the source color value is used. For colors that are dithered at the source, the average values of the colors that are dithered should be used (average R, average G, and average B).

Note 4: Tools are available that automatically do the calculations when testing contrast and flash.

Note 5: A [MathML version of the relative luminance definition](#) is available.

relied upon (technologies that are)

the content would not conform if that technology is turned off or is not supported

role

text or number by which software can identify the function of a component within Web content

Example: A number that indicates whether an image functions as a hyperlink, command button, or check box.

same functionality

same result when used

Example: A submit "search" button on one Web page and a "find" button on another Web page may both have a field to enter a term and list topics in the Web site related to the term submitted. In this case, they would have the same functionality but would not be labeled consistently.

same relative order

same position relative to other items

Note: Items are considered to be in the same relative order even if other items are inserted or removed from the original order. For example, expanding navigation menus may insert an additional level of detail or a secondary navigation section may be inserted into the reading order.

satisfies a success criterion

the success criterion does not evaluate to 'false' when applied to the page

section

A self-contained portion of written content that deals with one or more related topics or thoughts

Note: A section may consist of one or more paragraphs and include graphics, tables, lists and sub-sections.

set of Web pages

collection of Web pages that share a common purpose and that are created by the same author, group or organization

Note: Different language versions would be considered different sets of Web pages.

sign language

a language using combinations of movements of the hands and arms, facial expressions, or body positions to convey meaning

sign language interpretation

translation of one language, generally a spoken language, into a sign language

Note: True sign languages are independent languages that are unrelated to the spoken language(s) of the same country or region.

specific sensory experience

a sensory experience that is not purely decorative and does not primarily convey important information or perform a function

Example: Examples include a performance of a flute solo, works of visual art etc.

structure

1. The way the parts of a Web page are organized in relation to each other; and
2. The way a collection of Web pages is organized

supplemental content

additional content that illustrates or clarifies the primary content

Example 1: An audio version of a Web page.

Example 2: An illustration of a complex process.

Example 3: A paragraph summarizing the major outcomes and recommendations made in a research study.

synchronized media

audio or video synchronized with another format for presenting information and/or with time-based interactive components, unless the media is a media alternative for text that is clearly labeled as such

technology (Web content)

mechanism for encoding instructions to be rendered, played or executed by user agents

Note 1: As used in these guidelines "Web Technology" and the word "technology" (when used alone) both refer to Web Content Technologies.

Note 2: Web content technologies may include markup languages, data formats, or programming languages that authors may use alone or in combination to create end-user experiences that range from static Web pages to synchronized media presentations to dynamic Web applications.

Example: Some common examples of Web content technologies include HTML, CSS, SVG, PNG, PDF, Flash, and JavaScript.

text

sequence of characters that can be programmatically determined, where the sequence is expressing something in human language

text alternative

Text that is programmatically associated with non-text content or referred to from text that is programmatically associated with non-text content. Programmatically associated text is text whose location can be programmatically determined from the non-text content.

Example: An image of a chart is described in text in the paragraph after the chart. The short text alternative for the chart indicates that a description follows.

Note: Refer to [Understanding Text Alternatives](#) for more information.

used in an unusual or restricted way

words used in such a way that requires users to know exactly which definition to apply in order to understand the content correctly

Example: The term "gig" means something different if it occurs in a discussion of music concerts than it does in article about computer hard drive space, but the appropriate definition can be determined from context. By contrast, the word "text" is used in a very specific way in WCAG 2.0, so a definition is supplied in the glossary.

user agent

any software that retrieves and presents Web content for users

Example: Web browsers, media players, plug-ins, and other programs — including assistive technologies — that help in retrieving, rendering, and interacting with Web content.

user-controllable

data that is intended to be accessed by users

Note: This does not refer to such things as Internet logs and search engine monitoring data.

Example: Name and address fields for a user's account.

user interface component

a part of the content that is perceived by users as a single control for a distinct function

Note 1: Multiple user interface components may be implemented as a single

programmatic element. Components here is not tied to programming techniques, but rather to what the user perceives as separate controls.

Note 2: User interface components include form elements and links as well as components generated by scripts.

Example: An applet has a "control" that can be used to move through content by line or page or random access. Since each of these would need to have a name and be settable independently, they would each be a "user interface component."

video

the technology of moving or sequenced pictures or images

Note: Video can be made up of animated or photographic images, or both.

video-only

a time-based presentation that contains only video (no audio and no interaction)

viewport

object in which the user agent presents content

Note 1: The user agent presents content through one or more viewports. Viewports include windows, frames, loudspeakers, and virtual magnifying glasses. A viewport may contain another viewport (e.g., nested frames). Interface components created by the user agent such as prompts, menus, and alerts are not viewports.

Note 2: This definition is based on [User Agent Accessibility Guidelines 1.0 Glossary](#).

visually customized

the font, size, color, and background can be set

Web page

a non-embedded resource obtained from a single URI using HTTP plus any other resources that are used in the rendering or intended to be rendered together with it by a user agent

Note 1: Although any "other resources" would be rendered together with the primary resource, they would not necessarily be rendered simultaneously with each other.

Note 2: For the purposes of conformance with these guidelines, a resource must be "non-embedded" within the scope of conformance to be considered a Web page.

Example 1: A Web resource including all embedded images and media.

Example 2: A Web mail program built using Asynchronous JavaScript and XML (AJAX). The program lives entirely at <http://example.com/mail>, but includes an inbox, a contacts area and a calendar. Links or buttons are provided that cause the inbox, contacts, or calendar to display, but do not change the URI of the page as a whole.

Example 3: A customizable portal site, where users can choose content to display from a set of different content modules.

Example 4: When you enter "<http://shopping.example.com/>" in your browser, you enter a movie-like interactive shopping environment where you visually move around in a store dragging products off of the shelves around you and into a visual shopping cart in front of you. Clicking on a product causes it to be demonstrated with a specification sheet floating alongside. This might be a single-page Web site or just

one page within a Web site.

Appendix B: Acknowledgments

This section is informative.

This publication has been funded in part with Federal funds from the U.S. Department of Education, National Institute on Disability and Rehabilitation Research (NIDRR) under contract number ED05CO0039. The content of this publication does not necessarily reflect the views or policies of the U.S. Department of Education, nor does mention of trade names, commercial products, or organizations imply endorsement by the U.S. Government.

Additional information about participation in the Web Content Accessibility Guidelines Working Group (WCAG WG) can be found on the [Working Group home page](#).

Participants active in the WCAG WG at the time of publication

- Bruce Bailey (U.S. Access Board)
- Frederick Boland (NIST)
- Ben Caldwell (Trace R&D Center, University of Wisconsin)
- Sofia Celic (W3C Invited Expert)
- Michael Cooper (W3C)
- Roberto Ellero (International Webmasters Association / HTML Writers Guild)
- Bengt Farre (Rigab)
- Loretta Guarino Reid (Google)
- Katie Haritos-Shea
- Andrew Kirkpatrick (Adobe)
- Drew LaHart (IBM)
- Alex Li (SAP AG)
- David MacDonald (E-Ramp Inc.)
- Roberto Scano (International Webmasters Association / HTML Writers Guild)
- Cynthia Shelly (Microsoft)
- Andi Snow-Weaver (IBM)
- Christophe Strobbe (DocArch, K.U.Leuven)
- Gregg Vanderheiden (Trace R&D Center, University of Wisconsin)

Other previously active WCAG WG participants and other contributors to WCAG 2.0

Shadi Abou-Zahra, Jim Allan, Jenae Andershonis, Avi Arditti, Aries Arditi, Mike Barta, Sandy Bartell, Kynn Bartlett, Marco Bertoni, Harvey Bingham, Chris Blouch, Paul Bohman, Patrice Bourlon, Judy Brewer, Andy Brown, Dick Brown, Doyle Burnett, Raven Calais, Tomas Caspers, Roberto Castaldo, Sambhavi Chandrashekar, Mike Cherim, Jonathan Chetwynd, Wendy Chisholm, Alan Chuter, David M Clark, Joe Clark, James Coltham,

James Craig, Tom Croucher, Nir Dagan, Daniel Dardailler, Geoff Deering, Pete DeVasto, Don Evans, Neal Ewers, Steve Faulkner, Lainey Feingold, Alan J. Flavell, Nikolaos Floratos, Kentarou Fukuda, Miguel Garcia, P.J. Gardner, Greg Gay, Becky Gibson, Al Gilman, Kerstin Goldsmith, Michael Grade, Jon Gunderson, Emmanuelle Gutiérrez y Restrepo, Brian Hardy, Eric Hansen, Sean Hayes, Shawn Henry, Hans Hillen, Donovan Hipke, Bjoern Hoehrmann, Chris Hofstadter, Yvette Hoitink, Carlos Iglesias, Ian Jacobs, Phill Jenkins, Jyotsna Kaki, Leonard R. Kasday, Kazuhito Kidachi, Ken Kipness, Marja-Riitta Koivunen, Preeti Kumar, Gez Lemon, Chuck Letourneau, Scott Luebking, Tim Lacy, Jim Ley, William Loughborough, Greg Lowney, Luca Mascaro, Liam McGee, Jens Meiert, Niqui Merret, Alessandro Miele, Mathew J Mirabella, Charles McCathieNeville, Matt May, Marti McCuller, Sorch Moore, Charles F. Munat, Robert Neff, Bruno von Niman, Tim Noonan, Sebastiano Nutarelli, Graham Oliver, Sean B. Palmer, Sailesh Panchang, Nigel Peck, Anne Pemberton, David Poehlman, Adam Victor Reed, Chris Ridpath, Lee Roberts, Gregory J. Rosmaita, Matthew Ross, Sharron Rush, Gian Sampson-Wild, Joel Sanda, Gordon Schantz, Lisa Seeman, John Slatin, Becky Smith, Jared Smith, Neil Soiffer, Jeanne Spellman, Mike Squillace, Michael Stenitzer, Jim Thatcher, Terry Thompson, Justin Thorp, Makoto Ueki, Eric Velleman, Dena Wainwright, Paul Walsch, Takayuki Watanabe, Jason White.

Appendix C: References

This section is informative.

CAPTCHA

The CAPTCHA Project, Carnegie Mellon University. The project is online at <http://www.captcha.net>.

HARDING-BINNIE

Harding G. F. A. and Binnie, C.D., Independent Analysis of the ITC Photosensitive Epilepsy Calibration Test Tape. 2002.

IEC-4WD

IEC/4WD 61966-2-1: Colour Measurement and Management in Multimedia Systems and Equipment - Part 2.1: Default Colour Space - sRGB. May 5, 1998.

sRGB

"A Standard Default Color Space for the Internet - sRGB," M. Stokes, M. Anderson, S. Chandrasekar, R. Motta, eds., Version 1.10, November 5, 1996. A copy of this paper is available at <http://www.w3.org/Graphics/Color/sRGB.html>.

UNESCO

International Standard Classification of Education, 1997. A copy of the standard is available at http://www.unesco.org/education/information/nfsunesco/doc/isced_1997.htm.

WCAG10

Web Content Accessibility Guidelines 1.0, G. Vanderheiden, W. Chisholm, I. Jacobs, Editors, W3C Recommendation, 5 May 1999, <http://www.w3.org/TR/1999/WAI-WEBCONTENT-19990505/>. The latest version of WCAG 1.0 is available at <http://www.w3.org/TR/WAI-WEBCONTENT/>.




TRANSITION PLAN

APPENDIX J

ADA REQUESTS FOR ACCOMMODATION








TRANSITION PLAN

APPENDIX K

ADA GRIEVANCES







TRANSITION PLAN

APPENDIX L

ADA BARRIER REMOVAL SUMMARY





ADA BARRIER REMOVAL SUMMARY

2017 ANNUAL REPORT

[illegible]



TRANSITION PLAN

APPENDIX M

ANNUAL PROGRAM MONITORING REPORTS



Appendix N:
Barrier Removal Update (2017–2025)



This appendix serves as an updated summary of the City of New Albany's efforts to remove physical barriers and improve accessibility since the adoption of its ADA Transition Plan in 2017. It replaces the previous Appendix L (Barrier Removal Summary).

1. Summary of Systematic Barrier Removal Practices

The City of New Albany maintains an active policy of integrating ADA barrier removal into its capital and maintenance programs. In particular:

- **Annual Street Resurfacing Program**

The City systematically reconstructs non-compliant curb ramps in accordance with ADA standards during each paving season. Where feasible, adjacent sidewalk panels are also improved. This ensures that resurfacing projects result in tangible accessibility gains over time. Improvements are coordinated using both internal ADA knowledge and current design standards.

- **Community Development Block Grant (CDBG) Projects**

The City has prioritized sidewalk and ramp reconstruction projects in historically underserved neighborhoods through federal CDBG funds. These projects often include full sidewalk replacements, curb ramps, and other pedestrian enhancements to improve accessibility and safety for all residents.

2. CDBG-Funded Sidewalk & Ramp Projects (2017–2025)

The following CDBG-funded projects have been implemented to directly address sidewalk and ramp barriers in disadvantaged areas:

- **Thomas St** (Beeler St to Market St)
- **Oak St** (North side from Vincennes St to Silver St)
- **Elm St** (Vincennes St to Silver St)
- **Union St** (State St to Bono Rd)
- **Green St** (State St to Bono Rd)
- **Olive Ave** (State St to Bono Rd)
- **Beechwood Ave** (Lopp St to CSX railroad tracks)
- **Lopp St** (Beechwood Ave to Roosevelt Ave)

Each of these projects addressed longstanding deficiencies and added ADA-compliant pedestrian infrastructure in areas with high concentrations of low- to moderate-income residents.

3. Annual Street Paving Program and Associated Ramp Upgrades

The City's resurfacing program—funded by local and state allocations such as MVH and Community Crossings—has included widespread ADA upgrades from 2017 through 2025. Typical improvements have included:

- Installation or reconstruction of ADA curb ramps at intersections along paved routes.
- Replacement of broken or non-compliant sidewalk segments when feasible.
- Attention to sidewalk continuity and landing areas where pedestrian conflicts may arise.

Although a comprehensive list of all street segments resurfaced and upgraded is maintained internally by the Engineering Department, the following statement outlines the standard process:

“The City systematically reconstructs non-compliant curb ramps during its annual resurfacing program. Work is performed citywide and coordinated with ADA design standards.”

4. Segment-Level Paving Record

A detailed paving history by street segment is available from the City's GIS and Engineering records. This segment-level data provides insight into where ADA upgrades likely occurred in conjunction with resurfacing.

A full segment-by-segment paving record is maintained by the City Engineer and is available upon request.

Appendix O:

Sidewalk and Ramp Inventory Update (2023)



In 2023, the City of New Albany contracted with **Clark Dietz, Inc.** to perform a comprehensive citywide inventory of curb ramps and sidewalks. This effort builds upon the original conditions survey conducted as part of the 2017 ADA Transition Plan and reflects the City's continued commitment to proactive barrier identification and removal.

Scope and Methodology

The inventory includes:

- Field assessment of **sidewalk conditions**, including slope, surface integrity, width, and obstructions.
- Detailed evaluation of **curb ramps**, including detectable warnings, cross slope, orientation, and landing areas.
- Geospatial mapping of each feature using the City's GIS system for integration with ongoing planning and capital budgeting.

The 2023 inventory is being updated in 2025 to incorporate:

- **New construction and reconstructed infrastructure** since the initial 2023 assessment.
- **Corrections and refinements** identified through field verification and project implementation.

Integration with Transition Planning

This dataset forms the foundation for prioritizing barrier removal in upcoming capital projects. It also serves as a tracking mechanism to document ADA improvements over time.

A select portion of the sidewalk inventory is included in this appendix.

Street Prefix	Street Name	Street Suffix	From Street Prefix	From Street Name	From Street Suffix	To Street Prefix	To Street Name	To Street Suffix	Surface Type	Condition	Condition Description	Max Long Slope (%)	Max Cross Slope (%)	Width Min (ft)	Width Max (ft)	Curb Ramp From St	Curb Ramp From St ADA	Curb Ramp To St	Curb Ramp To St ADA	ADA Compliant	Comments
E	10TH	ST	E	OAK	ST	E	ELM	ST	Concrete	4	Fair	0.25	3.05	4	5	Yes	No	Yes	No	No	
E	10TH	ST	E	SPRING	ST	E	MARKET	ST	Concrete	4	Fair	1.10	6.20	4	15	Yes	No	Yes	No	No	
E	10TH	ST	E	MARKET	ST	E	MAIN	ST	Concrete	3	Poor	2.00	2.35	4	5	Yes	No	Yes	No	No	
E	10TH	ST	E	SPRING	ST	E	MARKET	ST	Concrete	3	Poor	1.10	3.40	4	5	Yes	No	Yes	Yes	No	
E	10TH	ST		CULBERTSON	AVE	E	OAK	ST	Concrete	3	Poor	1.10	2.50	4	10	Yes	Yes	Yes	No	No	
E	10TH	ST	E	ELM	ST	E	SPRING	ST	Concrete	3	Poor	1.35	2.30	5	6	Yes	No	Yes	No	No	
E	10TH	ST	E	MAIN	ST		DEAD END		Brick	3	Poor	5.10	2.30	6	8	Yes	Yes	No		No	
E	10TH	ST	E	OAK	ST	E	ELM	ST	Concrete	2	Very Poor	2.50	2.50	4	5	Yes	No	Yes	No	No	
E	10TH	ST		CULBERTSON	AVE	E	OAK	ST	Concrete	2	Very Poor	0.85	0.50	8	16	Yes	No	Yes	No	Yes	
E	10TH	ST	E	MARKET	ST	E	MAIN	ST	Concrete	1	PastServiceLife	4.45	4.25	4	5	Yes	Yes	Yes	Yes	No	
E	10TH	ST	E	ELM	ST	E	SPRING	ST	Concrete	1	PastServiceLife	0.40	2.35	5	6	Yes	No	Yes	No	No	
E	11TH	ST		BEELER	ST		CULBERTSON	AVE	Concrete	TBD	Good	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	Yes	
E	11TH	ST		EKIN	AVE		CULBERTSON	AVE	Concrete	TBD	Good	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	Yes	
E	11TH	ST		GREENWAY	PL		EKIN	AVE	Concrete	TBD	Good	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	Yes	
E	11TH	ST	E	OAK	ST	E	ELM	ST	Concrete	TBD	Good	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	Yes	
E	11TH	ST	E	OAK	ST	E	ELM	ST	Concrete	TBD	Good	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	Yes	
E	11TH	ST		BEELER	ST		GREENWAY	PL	Concrete	TBD	Good	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	Yes	
E	11TH	ST	E	ELM	ST	E	SPRING	ST	Concrete	TBD	Good	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	Yes	
E	11TH	ST	E	ELM	ST	E	SPRING	ST	Concrete	TBD	Good	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	Yes	
E	11TH	ST	E	MAIN	ST		DEWEY	ST	Concrete	3	Poor	1.40	0.50	4	4	Yes	Yes	No		Yes	there is a 400 set section brick sidewalk midblock
E	11TH	ST	E	MARKET	ST	E	MAIN	ST	Concrete	3	Poor	1.60	2.40	4	6	Yes	No	Yes	Yes	No	
E	11TH	ST	E	MARKET	ST	E	MAIN	ST	Concrete	3	Poor	0.30	3.50	4	6	Yes	Yes	Yes	Yes	No	
E	11TH	ST	E	SPRING	ST	E	MARKET	ST	Concrete	3	Poor	0.50	2.80	4	6	Yes	Yes	Yes	No	No	
E	11TH	ST	E	SPRING	ST	E	MARKET	ST	Concrete	3	Poor	1.20	1.40	4	8	Yes	Yes	Yes	Yes	Yes	
E	11TH	ST	E	MAIN	ST		DEWEY	ST	Brick	2	Very Poor	1.60	9.50	8	8	Yes	Yes	No		No	
E	12TH	ST	E	MARKET	ST	E	MAIN	ST	Concrete	3	Poor	1.20	0.70	4	5	Yes	No	Yes	Yes	Yes	
E	12TH	ST	E	MARKET	ST	E	MAIN	ST	Concrete	3	Poor	3.30	1.40	4	5	Yes	No	Yes	Yes	Yes	
E	12TH	ST	E	MAIN	ST		DEAD END		Concrete	2	Very Poor	2.40	1.20	4	4	Yes	Yes	No		Yes	
E	12TH	ST		DEAD END			DEAD END		Concrete	2	Very Poor	1.40	4.20	4	4	No		No		No	
E	12TH	ST		DEAD END			DEAD END		Concrete	2	Very Poor	0.50	3.10	4	4	No		No		No	
E	13TH	ST	E	ELM	ST	E	SPRING	ST	Concrete	5	Good	1.30	1.35	5	9	Yes	No	Yes	No	Yes	
E	13TH	ST		EKIN	AVE		CULBERTSON	AVE	Concrete	4	Fair	2.40	3.05	4	5	Yes	No	Yes	No	No	
E	13TH	ST		EKIN	AVE		CULBERTSON	AVE	Concrete	4	Fair	0.40	2.70	4	5	Yes	No	Yes	No	No	Pearl St to Alley is rated 5
E	13TH	ST	E	OAK	ST	E	ELM	ST	Concrete	4	Fair	0.65	2.15	4	5	Yes	Yes	Yes	No	No	
E	13TH	ST	E	MARKET	ST	E	MAIN	ST	Concrete	4	Fair	0.50	2.10	5	6	Yes	Yes	Yes	Yes	No	
E	13TH	ST	E	SPRING	ST	E	MARKET	ST	Concrete	4	Fair	1.60	1.60	4	6	Yes	No	Yes	No	Yes	
E	13TH	ST		CULBERTSON	AVE	E	OAK	ST	Concrete	4	Fair	0.85	0.95	4	6	Yes	No	Yes	No	Yes	
E	13TH	ST	E	OAK	ST	E	ELM	ST	Concrete	3	Poor	0.30	1.65	4	8	Yes	No	Yes	No	Yes	brick sidewalk on south end
E	13TH	ST	E	MARKET	ST	E	MAIN	ST	Concrete	3	Poor	1.00	2.30	4	10	Yes	Yes	Yes	Yes	No	
E	13TH	ST	E	SPRING	ST	E	MARKET	ST	Concrete	3	Poor	1.20	1.40	5	10	Yes	No	Yes	No	Yes	
E	13TH	ST		CULBERTSON	AVE	E	OAK	ST	Asphalt	3	Poor	1.80	2.35	8	20	Yes	No	Yes	No	No	
E	13TH	ST	E	ELM	ST	E	SPRING	ST	Concrete	3	Poor	0.65	4.45	7	8	Yes	No	Yes	No	No	
E	13TH	ST	E	MAIN	ST		DEWEY	ST	Concrete	2	Very Poor	2.40	4.20	6	6	Yes	Yes	No		No	
E	13TH	ST	E	MAIN	ST		DEWEY	ST	Concrete	2	Very Poor	2.40	0.20	6	6	Yes	Yes	No		Yes	
E	14TH	ST	E	MAIN	ST		DEAD END		Concrete	5	Good	1.00	3.00	5	6	Yes	Yes	No		No	
E	14TH	ST	E	MAIN	ST		DEAD END		Concrete	4	Fair	0.20	2.60	4	5	Yes	Yes	No		No	
E	14TH	ST		MARKET	ST	E	MAIN	ST	Concrete	3	Poor	0.70	0.10	5	5	Yes	No	Yes	Yes	Yes	
E	14TH	ST	E	MARKET	ST	E	MAIN	ST	Concrete	1	PastServiceLife	0.50	2.40	4	4	Yes	No	Yes	Yes	No	
E	15TH	ST	E	MAIN	ST		DEWEY	ST	Concrete	5	Good	1.00	0.30	5	15	Yes	Yes	No		Yes	
E	15TH	ST		BEELER	ST		EKIN	AVE	Concrete	5	Good	1.30	0.65	5	5	No		Yes	No	Yes	
E	15TH	ST	E	MARKET	ST	E	MAIN	ST	Concrete	5	Good	2.10	0.30	4	5	Yes	No	Yes	Yes	Yes	
E	15TH	ST		EKIN	AVE		CULBERTSON	AVE	Concrete	4	Fair	0.50	0.75	4	4	Yes	No	Yes	No	Yes	
E	15TH	ST		EKIN	AVE		CULBERTSON	AVE	Concrete	4	Fair	1.00	2.15	4	4	Yes	No	Yes	No	No	
E	15TH	ST		SHELBY	PL		EKIN	AVE	Concrete	4	Fair	0.25	3.65	4	4	Yes	Yes	Yes	No	No	
E	15TH	ST	E	OAK	ST	E	ELM	ST	Concrete	4	Fair	1.55	1.70	4	4	Yes	No	Yes	No	Yes	
E	15TH	ST	E	OAK	ST	E	ELM	ST	Concrete	4	Fair	1.00	0.60	5	5	Yes	No	Yes	No	Yes	
E	15TH	ST		CULBERTSON	AVE	E	OAK	ST	Concrete	4	Fair	0.85	2.05	4	4	Yes	No	Yes	No	No	
E	15TH	ST		CULBERTSON	AVE	E	OAK	ST	Concrete	4	Fair	0.15	2.05	5	5	Yes	No	Yes	No	No	
E	15TH	ST		DEAD END			SHELBY	PL	Concrete	4	Fair	0.40	2.75	4	12	No		Yes	Yes	No	
E	15TH	ST		GRANT	ST	E	MARKET	ST	Concrete	3	Poor	1.70	4.90	5	5	Yes	No	Yes	No	No	
E	15TH	ST	E	SPRING	ST		GRANT	ST	Concrete	2	Very Poor	0.50	4.70	5	15	Yes	No	Yes	No	No	
E	15TH	ST	E	MARKET	ST	E	MAIN	ST	Concrete	2	Very Poor	1.20	2.60	5	6	Yes	No	Yes	Yes	No	
E	15TH	ST	E	MAIN	ST		DEWEY	ST	Brick	1	PastServiceLife	1.20	5.10	10	12	Yes	Yes	No		No	
E	15TH	ST	E	SPRING	ST	E	MARKET	ST	Concrete	1	PastServiceLife	3.10	0.50	5	5	Yes	No	Yes	No	Yes	
E	15TH	ST	E	ELM	ST	E	SPRING	ST	Concrete	1	PastServiceLife	1.05	5.05	5	5	Yes	No	Yes	No	No	
E	15TH	ST	E	ELM	ST	E	SPRING	ST	Concrete	1	PastServiceLife	0.30	3.55	5	5	Yes	No	Yes	No	No	
E	16TH	ST	E	MAIN	ST		DEWEY	ST	Concrete	3	Poor	4.70	2.10	4	4	Yes	Yes	Yes	No	No	
E	16TH	ST	E	MAIN	ST		DEWEY	ST	Concrete	2	Very Poor	6.00	4.00	3	3	Yes	Yes	Yes	No	No	
E	18TH	ST	E	MAIN	ST		DEWEY	ST	Concrete	5	Good	2.30	1.00	4	4	Yes	No	Yes	Yes	Yes	
E	18TH	ST	E	MAIN	ST		DEWEY	ST	Concrete	5	Good	2.10	2.40	4	4	Yes	No	Yes	Yes	No	
E	18TH	ST	E	SPRING	ST		DIVISION	ST	Concrete	5	Good	0.30	1.20	4	4	Yes	Yes	Yes	Yes	Yes	From E 6th St to Ally is stone
E	18TH	ST		DEWEY	ST		TROY	ST	Concrete	5	Good	0.50	2.30	5	5	Yes	Yes	No		No	
E	18TH	ST		DIVISION	ST		CONSERVATIVE	ST	Concrete	3	Poor	2.80	1.00	4	4	Yes	Yes	Yes	Yes	Yes	
E	18TH	ST		DEWEY	ST		TROY	ST	Concrete	2	Very Poor	0.20	1.00	4	4	Yes	Yes	No		Yes	
W	1ST	ST	W	MAIN	ST		DEAD END		Concrete	5	Good	12.00	9.00	5	11	No		No		No	
W	1ST	ST	W	MAIN	ST		DEAD END		Concrete	5	Good	6.00	2.00	5	5	Yes	Yes	No		Yes	
W	1ST	ST	W	OAK	ST	W	ELM	ST	Concrete	4	Fair	2.00	3.10	2.5	4	Yes	No	Yes	Yes	No	
W	1ST	ST	W	MARKET	ST	W	MAIN	ST	Concrete	4	Fair	3.00	3.10	6	11	Yes	No			Yes	
W	1ST	ST	W	SPRING	ST	W	MARKET	ST	Concrete	4	Fair	2.00	3.00	12	12	No		Yes	Yes	No	
W	1ST	ST	W	ELM	ST	W	SPRING	ST	Concrete	4	Fair	3.80	1.50	5	6	No		No		Yes	
W	1ST	ST	W	OAK	ST	W	ELM	ST	Concrete	3	Poor	2.50	5.50	5	5	Yes	Yes	Yes	No	No	First half from Pearl St to Ally is rated 5

Street Prefix	Street Name	Street Suffix	From Street Prefix	From Street Name	From Street Suffix	To Street Prefix	To Street Name	To Street Suffix	Surface Type	Condition	Condition Description	Max Long Slope (%)	Max Cross Slope (%)	Width Min (ft)	Width Max (ft)	Curb Ramp From St	Curb Ramp From St ADA	Curb Ramp To St	Curb Ramp To St ADA	ADA Compliant	Comments
W	1ST	ST	W	MARKET	ST	W	MAIN	ST	Concrete	3	Poor	2.00	2.50	6	10	Yes	Yes	Yes	Yes	No	
W	1ST	ST	W	SPRING	ST	W	MARKET	ST	Concrete	3	Poor	3.20	0.70	6	10	Yes	No	Yes	Yes	Yes	
W	1ST	ST	W	ELM	ST	W	SPRING	ST	Brick	3	Poor	3.80	1.00	5	5	Yes	No	No		Yes	
W	1ST	ST	W	ELM	ST	W	SPRING	ST	Concrete	2	Very Poor	4.20	4.50	5	11	Yes	No	No		No	
E	3RD	ST	E	SPRING	ST	E	MARKET	ST	Concrete	4	Fair	1.70	2.05	6	12	Yes	Yes	Yes	Yes	No	
E	3RD	ST	E	ELM	ST	E	SPRING	ST	Concrete	4	Fair	1.20	4.10	4	10	Yes	No	Yes	Yes	No	
E	3RD	ST	E	SPRING	ST	E	MARKET	ST	Concrete	3	Poor	0.15	4.00	6	12	Yes	No	Yes	Yes	No	
E	3RD	ST	E	ELM	ST	E	SPRING	ST	Concrete	3	Poor	1.55	5.05	7	8	Yes	No	Yes	No	No	
E	3RD	ST	E	OAK	ST	E	ELM	ST	Concrete	2	Very Poor	4.15	2.25	4	4	No		Yes	No	No	
E	3RD	ST	E	OAK	ST	E	ELM	ST	Concrete	2	Very Poor	2.35	4.60	5	8	No		Yes	No	No	
E	3RD	ST	E	MARKET	ST	E	MAIN	ST	Concrete	2	Very Poor	4.45	5.55	6	10	Yes	Yes			No	
E	3RD	ST	E	MARKET	ST	E	MAIN	ST	Concrete	1	PastServiceLife	3.55	12.60	4	10	Yes	No			No	
E	3RD	ST	E	MAIN	ST		DEAD END		Brick	1	PastServiceLife	11.00	3.05	5	12	Yes	Yes	No		No	
E	4TH	ST	E	ELM	ST	E	SPRING	ST	Concrete	5	Good	0.50	2.15	5	5	Yes	No	Yes	No	No	
W	4TH	ST	W	MARKET	ST	W	MAIN	ST	Concrete	4	Fair	0.05	3.75	4	4	Yes	Yes	Yes	No	No	
E	4TH	ST	E	SPRING	ST	E	MARKET	ST	Concrete	4	Fair	0.60	1.90	4	5	Yes	No	Yes	Yes	Yes	
E	4TH	ST	E	ELM	ST	E	SPRING	ST	Concrete	4	Fair	0.85	3.10	4	5	Yes	No	Yes	No	No	
E	4TH	ST	E	MAIN	ST		DEAD END		Concrete	4	Fair	9.00	4.00	4	5	Yes	Yes	No		No	
E	4TH	ST	E	SPRING	ST	E	MARKET	ST	Concrete	3	Poor	1.00	2.35	7	12	Yes	Yes	Yes	Yes	No	
W	4TH	ST	W	SPRING	ST	W	MARKET	ST	Concrete	3	Poor	1.55	1.00	4	4	Yes	No	Yes	Yes	Yes	
E	4TH	ST		CULBERTSON	AVE	E	OAK	ST	Concrete	3	Poor	0.75	0.60	6	10	Yes	Yes	Yes	No	Yes	
E	4TH	ST	E	MARKET	ST	E	MAIN	ST	Concrete	2	Very Poor	0.25	2.70	5	8	Yes	Yes			No	
W	4TH	ST	W	MARKET	ST	W	MAIN	ST	Concrete	2	Very Poor	0.30	2.85	4	7	Yes	Yes	Yes	No	No	
W	4TH	ST	W	SPRING	ST	W	MARKET	ST	Concrete	2	Very Poor	1.35	1.20	4	4	No		Yes	Yes	Yes	
E	4TH	ST		CULBERTSON	AVE	E	OAK	ST	Concrete	2	Very Poor	1.45	3.05	4	6	Yes	Yes	Yes	No	No	
E	4TH	ST	E	OAK	ST	E	ELM	ST	Concrete	1	PastServiceLife	0.65	1.30	4	5	Yes	No	Yes	No	Yes	
E	4TH	ST	E	OAK	ST	E	ELM	ST	Concrete	1	PastServiceLife	0.65	4.85	3	5	Yes	No	Yes	No	No	
E	4TH	ST	E	MARKET	ST	E	MAIN	ST	Concrete	1	PastServiceLife	1.10	4.15	4	20	Yes	Yes			No	
E	4TH	ST	E	MAIN	ST		DEAD END		Concrete	1	PastServiceLife	11.90	5.65	4	5	Yes	Yes	No		No	
E	5TH	ST	E	MARKET	ST	E	MAIN	ST	Concrete	5	Good	0.25	2.25	4	5	Yes	Yes	Yes	Yes	No	
E	5TH	ST	E	MARKET	ST	E	MAIN	ST	Concrete	5	Good	2.60	4.10	4	14	Yes	Yes			No	One panel is popping up
E	5TH	ST	E	SPRING	ST	E	MARKET	ST	Concrete	5	Good	0.45	0.65	4	5	Yes	Yes	Yes	No	Yes	
E	5TH	ST	E	ELM	ST	E	SPRING	ST	Concrete	5	Good	0.65	1.20	4	4	Yes	No	Yes	Yes	Yes	
E	5TH	ST	E	ELM	ST	E	SPRING	ST	Concrete	5	Good	0.85	1.60	4	5	Yes	No	Yes	Yes	Yes	
W	5TH	ST	W	MARKET	ST	W	MAIN	ST	Concrete	4	Fair	0.75	1.55	4	4	Yes	No	Yes	No	Yes	
E	5TH	ST	E	SPRING	ST	E	MARKET	ST	Concrete	4	Fair	4.90	1.25	4	5	Yes	No	Yes	Yes	Yes	
E	5TH	ST	E	OAK	ST	E	ELM	ST	Concrete	3	Poor	1.60	2.05	4	5	Yes	No	Yes	No	No	
E	5TH	ST	E	OAK	ST	E	ELM	ST	Concrete	3	Poor	1.80	2.05	4	5	Yes	No	Yes	No	No	
W	5TH	ST	E	MARKET	ST	W	MAIN	ST	Concrete	3	Poor	0.65	2.50	4	4	Yes	Yes	Yes	No	No	
E	5TH	ST		CULBERTSON	AVE	E	OAK	ST	Concrete	3	Poor	0.75	3.10	4	5	Yes	No	Yes	No	No	
E	5TH	ST		CULBERTSON	AVE	E	OAK	ST	Concrete	3	Poor	1.35	3.10	4	5	Yes	Yes	Yes	No	No	
W	5TH	ST	W	SPRING	ST	W	MARKET	ST	Concrete	2	Very Poor	7.05	8.65	4	4	Yes	No	Yes	Yes	No	
W	5TH	ST	W	SPRING	ST	W	MARKET	ST	Concrete	2	Very Poor	5.20	1.30	4	8	Yes	No	Yes	No	Yes	Drive is cracked
E	5TH	ST	E	MAIN	ST		DEAD END		Concrete	1	PastServiceLife	8.65	4.95	4	4	Yes	Yes	No		No	
E	5TH	ST	E	MAIN	ST		DEAD END		Concrete	1	PastServiceLife	15.90	5.90	4	5	Yes	No	No		No	
W	6TH	ST	W	MARKET	ST	W	MAIN	ST	Concrete	TBD	Good	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	Yes	
W	6TH	ST	W	MARKET	ST	W	MAIN	ST	Concrete	TBD	Good	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	Yes	
W	6TH	ST	W	SPRING	ST	W	MARKET	ST	Concrete	TBD	Good	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	Yes	
W	6TH	ST		ELM	ST	W	SPRING	ST	Concrete	TBD	Good	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	Yes	
E	6TH	ST	E	ELM	ST	E	SPRING	ST	Concrete	5	Good	0.95	1.20	4	5	No		Yes	No	Yes	
E	6TH	ST	E	ELM	ST	E	SPRING	ST	Concrete	3	Poor	1.90	1.80	4	5	No		Yes	Yes	Yes	
E	6TH	ST	E	SPRING	ST		DEAD END		Concrete	3	Poor	1.80	3.65	3	4	Yes	Yes	No		No	
E	6TH	ST	E	MAIN	ST		DEAD END		Concrete	2	Very Poor	3.50	3.00	4	4	Yes	Yes	No		No	
W	7TH	ST	W	MARKET	ST	W	MAIN	ST	Concrete	4	Fair	1.20	5.05	4	4	Yes	Yes	Yes	No	No	
W	7TH	ST	W	SPRING	ST	W	MARKET	ST	Concrete	4	Fair	1.20	3.55	4	4	Yes	Yes	Yes	No	No	
E	7TH	ST	E	ELM	ST	E	SPRING	ST	Concrete	4	Fair	0.25	0.60	4	5	Yes	No	Yes	No	Yes	
W	7TH	ST		OHIO	ST		COMMERCE	ST	Concrete	3	Poor	0.50	2.50	5	6	No		Yes	No	No	
E	7TH	ST	E	OAK	ST	E	ELM	ST	Concrete	3	Poor	1.00	1.70	4	5	Yes	No	Yes	No	Yes	
E	7TH	ST	E	MARKET	ST	E	MAIN	ST	Concrete	3	Poor	1.80	1.30	4	4	Yes	No	Yes	No	Yes	
W	7TH	ST	W	MARKET	ST	W	MAIN	ST	Concrete	3	Poor	8.30	0.85	4	5	Yes	Yes	Yes	No	No	
W	7TH	ST	W	SPRING	ST	W	MARKET	ST	Concrete	3	Poor	0.75	3.05	4	5	Yes	Yes	Yes	Yes	No	
E	7TH	ST		CULBERTSON	AVE	E	OAK	ST	Concrete	3	Poor	1.90	2.40	3	4	Yes	No	Yes	No	No	
W	7TH	ST		ELM	ST	W	SPRING	ST	Concrete	3	Poor	0.30	1.40	4	4	Yes	No	Yes	No	Yes	
W	7TH	ST		OHIO	ST		COMMERCE	ST	Concrete	2	Very Poor	1.60	1.60	5	6	Yes	No	Yes	No	Yes	
W	7TH	ST		COMMERCE	ST		ELM	ST	Concrete	2	Very Poor	0.40	4.80	4	6			Yes	Yes	No	
W	7TH	ST		COMMERCE	ST		ELM	ST	Concrete	2	Very Poor	1.35	2.85	4	6	Yes	No	Yes	Yes	No	
E	7TH	ST	E	MARKET	ST	E	MAIN	ST	Concrete	2	Very Poor	4.00	4.50	4	4	Yes	No	Yes	No	No	
E	7TH	ST	E	SPRING	ST	E	MARKET	ST	Concrete	2	Very Poor	0.85	3.55	4	5	Yes	No	Yes	No	No	
W	7TH	ST		CHERRY	ST		OHIO	ST	Concrete	2	Very Poor	1.00	2.00	4	5	Yes	No	No		Yes	
W	7TH	ST		CHERRY	ST		OHIO	ST	Concrete	2	Very Poor	2.00	1.70	4	5	Yes	No	No		Yes	
E	7TH	ST	E	ELM	ST	E	SPRING	ST	Concrete	2	Very Poor	0.45	4.95	4	5	Yes	No	Yes	No	No	
W	7TH	ST		ELM	ST	W	SPRING	ST	Concrete	2	Very Poor	4.60	2.35	4	6	Yes	Yes	No		No	
E	7TH	ST	E	OAK	ST	E	ELM	ST	Concrete	1	PastServiceLife	0.75	2.70	4	4	Yes	No	Yes	No	No	
E	7TH	ST	E	SPRING	ST	E	MARKET	ST	Concrete	1	PastServiceLife	2.85	2.25	4	5	Yes	No	Yes	No	No	
E	7TH	ST		CULBERTSON	AVE	E	OAK	ST	Concrete	1	PastServiceLife	4.85	7.85	3	4	Yes	No	Yes	No	No	
W	8TH	ST	W	MARKET	ST	W	MAIN	ST	Concrete	4	Fair	0.95	2.15	4	5	Yes	No	Yes	No	No	
W	8TH	ST	W	MARKET	ST	W	MAIN	ST	Concrete	4	Fair	2.25	2.25	5	5	Yes	No	Yes	No	No	
E	8TH	ST	E	ELM	ST	E	SPRING	ST	Concrete	4	Fair	3.25	3.75	4	8	Yes	No	Yes	No	No	
E	8TH	ST	E	OAK	ST	E	ELM	ST	Concrete	3	Poor	2.70	4.60	4	6	Yes	No	Yes	No	No	
E	8TH	ST		DEAD END			JACKSON	ST	Concrete	3	Poor	0.10	2.50	4	4	No		Yes	No	No	

Street Prefix	Street Name	Street Suffix	From Street Prefix	From Street Name	From Street Suffix	To Street Prefix	To Street Name	To Street Suffix	Surface Type	Condition	Condition Description	Max Long Slope (%)	Max Cross Slope (%)	Width Min (ft)	Width Max (ft)	Curb Ramp From St	Curb Ramp From St ADA	Curb Ramp To St	Curb Ramp To St ADA	ADA Compliant	Comments
W	8TH	ST	W	SPRING	ST	W	MARKET	ST	Concrete	3	Poor	3.90	4.45	4	5	Yes	Yes	Yes	No	No	
W	8TH	ST	W	SPRING	ST	W	MARKET	ST	Concrete	3	Poor	0.15	2.60	4	10	Yes	No	Yes	No	No	
E	8TH	ST		CULBERTSON	AVE	E	OAK	ST	Concrete	3	Poor	2.50	1.65	5	8	Yes	No	Yes	No	Yes	
E	8TH	ST		CULBERTSON	AVE	E	OAK	ST	Concrete	3	Poor	0.30	2.40	4	5	Yes	No	Yes	No	No	
E	8TH	ST	E	ELM	ST	E	SPRING	ST	Concrete	3	Poor	2.50	3.45	8	10	Yes	Yes	Yes	No	No	
E	8TH	ST		JACKSON	ST		BEELER	ST	Concrete	2	Very Poor	0.60	3.40	4	5	No		Yes	No	No	
E	8TH	ST		BEELER	ST		CULBERTSON	AVE	Concrete	2	Very Poor	0.70	2.30	4	12	No		No		No	
E	8TH	ST	E	OAK	ST	E	ELM	ST	Concrete	2	Very Poor	2.70	3.10	4	5	Yes	No	Yes	No	No	
E	8TH	ST		SHELBY	ST		CULBERTSON	AVE	Concrete	1	PastServiceLife	1.80	4.00	6	8	No		No		No	
E	9TH	ST	E	MAIN	ST		DEAD END		Concrete	5	Good	5.20	1.20	4	4	Yes	Yes	No		Yes	
E	9TH	ST	E	MARKET	ST	E	MAIN	ST	Concrete	4	Fair	1.80	1.80	4	9	Yes	No	Yes	Yes	Yes	
E	9TH	ST	E	OAK	ST	E	ELM	ST	Concrete	3	Poor	0.30	1.80	4	5	Yes	Yes	Yes	No	Yes	
E	9TH	ST	E	OAK	ST	E	ELM	ST	Concrete	3	Poor	0.15	2.25	3	5	Yes	No	Yes	No	No	
W	9TH	ST	W	10TH	ST	W	MAIN	ST	Concrete	3	Poor	2.40	0.95	4	6	No		Yes	No	Yes	
E	9TH	ST	E	MARKET	ST	E	MAIN	ST	Concrete	3	Poor	2.05	2.30	4	5	Yes	No	Yes	Yes	No	
W	9TH	ST	W	MARKET	ST	W	MAIN	ST	Concrete	3	Poor	0.60	0.95	4	6	Yes	No	Yes	No	Yes	
E	9TH	ST	E	SPRING	ST	E	MARKET	ST	Concrete	3	Poor	0.50	2.00	4	5	Yes	No	Yes	Yes	Yes	
E	9TH	ST	E	SPRING	ST	E	MARKET	ST	Concrete	3	Poor	2.70	2.05	4	5	Yes	No	Yes	No	No	
E	9TH	ST		CULBERTSON	AVE	E	OAK	ST	Concrete	3	Poor	0.25	1.65	4	4	Yes	No	Yes	No	Yes	
E	9TH	ST		CULBERTSON	AVE	E	OAK	ST	Concrete	3	Poor	5.65	3.70	4	4	Yes	No	Yes	No	No	
E	9TH	ST	E	ELM	ST	E	SPRING	ST	Concrete	3	Poor	0.95	1.90	4	5	Yes	No	Yes	No	Yes	
E	9TH	ST	E	ELM	ST	E	SPRING	ST	Concrete	3	Poor	2.60	2.40	3	5	Yes	No	Yes	No	No	
	ACADEMY	DR		DEAD END			GRANT LINE	RD	Concrete	4	Fair	6.00	3.70	4	4	No		Yes	No	No	
	ADAMS	ST		WEST	ST		STATE	ST	Concrete	2	Very Poor	1.00	4.35	4	4	Yes	No	Yes	No	No	
	ADAMS	ST		DEAD END			STATE	ST	Concrete	2	Very Poor	4.45	4.15	4	4			Yes	No	No	
	AEBERSOLD	DR		SILVER	ST		AEBERSOLD	CT	Concrete	3	Poor	1.40	4.40	4	4	Yes	No	Yes	No	No	
	AEBERSOLD	DR		SILVER	ST		AEBERSOLD	CT	Concrete	2	Very Poor	2.80	8.90	4	4	Yes	No	No		No	
	ALPINE	CT		SUMMIT	AVE		DEAD END		Concrete	2	Very Poor	1.20	3.40	4	4	No		No		No	Last approx. 200 ft is brick and in bad shape
	ALYSON	CT		GREEN VALLEY	RD		GREEN VALLEY	RD	Concrete	4	Fair	1.35	4.70	4	4	No		No		No	
	AMY	CT		MT TABOR	RD		MT TABOR	RD	Concrete	3	Poor	0.20	2.30	4	4	No		No		No	
	ASHLEY	CT		FARRINGTON	DR		FARRINGTON	DR	Concrete	3	Poor	2.70	1.00	4	4	No		No		Yes	Tile replaced with gravel
	ASHWOOD	DR		BRENTWOOD	CT		OAKWOOD	CT	Concrete	4	Fair	0.70	1.80	4	5	Yes	Yes	Yes	Yes	Yes	
	ASHWOOD	DR		BRENTWOOD	CT		CASTLEWOOD	DR	Concrete	3	Poor	1.90	5.15	4	5	No		No		No	
	ASHWOOD	DR		OAKWOOD	CT		CASTLEWOOD	DR	Concrete	3	Poor	1.80	5.65	4	5	No		No		No	
	ASPEN	CT		HICKORYVALE	DR		HICKORYVALE	DR	Concrete	3	Poor	2.40	2.60	4	4	Yes	No	Yes	No	No	
	BANK	ST	E	MARKET	ST	E	MAIN	ST	Concrete	5	Good	0.85	2.60	4	10	Yes	No			No	
	BANK	ST	E	MAIN	ST		PEARL	ST	Concrete	5	Good	10.55	2.75	5	10	Yes	Yes	No		No	
	BANK	ST	E	SPRING	ST	E	MARKET	ST	Concrete	4	Fair	1.30	0.95	7	9	Yes	Yes	Yes	No	Yes	
	BANK	ST	E	MAIN	ST		DEAD END		Concrete	4	Fair	12.10	13.50	5	8	Yes	Yes	No		No	
	BANK	ST	E	MARKET	ST	E	MAIN	ST	Concrete	3	Poor	1.35	3.20	4	10	Yes	No			No	
	BANK	ST	E	SPRING	ST	E	MARKET	ST	Concrete	3	Poor	2.05	1.30	4	10	Yes	Yes	Yes	No	Yes	
	BANK	ST	E	ELM	ST	E	SPRING	ST	Concrete	3	Poor	0.50	1.65	6	8	Yes	Yes	Yes	Yes	Yes	
	BANK	ST	E	ELM	ST	E	SPRING	ST	Concrete	3	Poor	1.00	3.75	7	10	Yes	No	Yes	No	No	
	BANK	ST	E	OAK	ST	E	ELM	ST	Concrete	2	Very Poor	1.65	2.05	4	10	Yes	No	Yes	No	No	
	BANK	ST	E	OAK	ST	E	ELM	ST	Concrete	2	Very Poor	1.00	0.15	4	7	Yes	No	No		Yes	
	BANK	ST		CULBERTSON	AVE	E	OAK	ST	Concrete	1	PastServiceLife	8.30	6.55	4	4	Yes	No	No		No	
	BARACK OBAMA WAY			DURGEE RD			GRANT LINE RD		Asphalt	4	Fair	6.60	1.90	10	10	Yes	Yes	Yes	Yes	Yes	Sidewalk from Market St to ally is rated 3
	BARRINGTON	CT		CITY LIMITS			GLENMILL	RD	Concrete	5	Good	3.10	2.60	4	4	No		No		No	
	BARRINGTON	CT		CITY LIMITS			GLENMILL	RD	Concrete	5	Good	2.10	1.50	4	4	No		No		Yes	
	BARRINGTON	CT		CITY LIMITS			GLENMILL	RD	Concrete	5	Good	3.80	0.60	4	4	No		No		Yes	
	BARRINGTON	CT		CITY LIMITS			GLENMILL	RD	Concrete	5	Good	4.30	3.20	4	4	No		No		No	
	BEECHGROVE	AVE			ST		DEAD END		Concrete	2	Very Poor	0.50	2.10	4	4	No		No		No	
	BEECHGROVE	AVE		DEAD END			DEAD END		Concrete	2	Very Poor	0.30	2.50	4	4	No		No		No	
	BEECHGROVE	AVE		DEAD END			DEAD END		Concrete	1	PastServiceLife	2.10	3.80	4	4	No		No		No	
	BEECHWOOD	AVE		LOPP	AVE		CHARLESTOWN	RD	Concrete	3	Poor	8.70	1.70	4	4	Yes	No	Yes	No	No	
	BEECHWOOD	AVE		LOPP	AVE		CHARLESTOWN	RD	Concrete	3	Poor	1.90	2.90	4	4	Yes	No	Yes	No	No	
	BEECHWOOD	AVE		LOGAN	ST		HAND	AVE	Concrete	3	Poor	3.10	3.20	4	6	Yes	No	Yes	No	No	
	BEECHWOOD	AVE		GRANT LINE	RD		LOGAN	ST	Concrete	3	Poor	2.30	1.70	4	8	Yes	No	Yes	No	Yes	
	BEECHWOOD	AVE		GRANT LINE	RD		LOGAN	ST	Concrete	3	Poor	1.10	0.10	4	8	Yes	No	Yes	No	Yes	
	BEECHWOOD	AVE		HAND	AVE		MONON	AVE	Concrete	3	Poor	0.20	0.30	4	6	Yes	No	Yes	No	Yes	
	BEECHWOOD	AVE		LOGAN	ST		MONON	AVE	Concrete	3	Poor	1.20	1.20	4	6	Yes	No	No		Yes	
	BEECHWOOD	AVE		MONON	AVE		WEST	ST	Concrete	3	Poor	1.90	2.30	4	4	No		Yes	No	No	
	BEECHWOOD	AVE		CHARLESTOWN	RD		DEPAUW	AVE	Concrete	2	Very Poor	4.40	1.60	4	5	Yes	No	Yes	No	Yes	
	BEECHWOOD	AVE		WEST	ST		LOPP	AVE	Concrete	2	Very Poor	7.90	1.20	4	4	Yes	No	Yes	No	Yes	
	BEECHWOOD	AVE		CHARLESTOWN	RD		DEPAUW	AVE	Concrete	3	Poor	3.50	0.20	4	5	Yes	No	Yes	No	Yes	
	BEELER	ST		CHARLES	ST		CLARK	ST	Concrete	4	Fair	0.95	1.80	4	4	Yes	No	Yes	No	Yes	Ground is starting to wash out from under sidewalk
	BEELER	ST		THOMAS	AVE		HAZELWOOD	AVE	Concrete	4	Fair	0.30	2.75	4	6	Yes	Yes	No		No	
	BEELER	ST		JAY	ST		SILVER	ST	Concrete	4	Fair	0.60	3.65	5	5	Yes	No	No		No	
	BEELER	ST		CHARTRES	ST		JACKSON	ST	Concrete	3	Poor	0.60	1.00	3	4	Yes	No	Yes	Yes	Yes	
	BEELER	ST		THOMAS	AVE		JAY	ST	Concrete	3	Poor	4.35	2.85	4	4	Yes	No	Yes	No	No	
	BEELER	ST	E	15TH	ST		VINCENNES	ST	Concrete	3	Poor	3.50	4.85	5	12	No		Yes	No	No	
	BEELER	ST		CLARK	ST		VINCENNES	ST	Concrete	3	Poor	1.10	2.15	4	4	Yes	No	Yes	No	No	
	BEELER	ST	E	8TH	ST	E	11TH	ST	Concrete	2	Very Poor	1.30	2.60	5	5	No		Yes	No	No	
	BEELER	ST		LOCUST	ST		CHARLES	ST	Concrete	2	Very Poor	2.15	2.95	4	4	No		Yes	No	No	
	BEELER	ST	E	8TH	ST		CHARTRES	ST	Concrete	2	Very Poor	1.65	2.50	4	4	Yes	No	Yes	No	No	
	BEELER	ST		MCDONALD	AVE		KORB	AVE	Concrete	2	Very Poor	1.20	2.40	4	4	Yes	No	Yes	No	No	
	BEELER	ST		INDIANA	AVE		MCDONALD	AVE	Concrete	2	Very Poor	1.85	2.65	4	4	Yes	No	Yes	No	No	
	BEELER	ST		SILVER	ST		INDIANA	AVE	Concrete	1	PastServiceLife	2.85	3.55	4	4	Yes	No	Yes	No	No	
	BEELER	ST		SILVER	ST		INDIANA	AVE	Concrete	1	PastServiceLife	4.15	1.10	4	4	Yes	No	Yes	No	Yes	
	BEELER	ST		MCDONALD	AVE		KORB	AVE	Concrete	1	PastServiceLife	1.30	2.95	4	4	Yes	No	Yes	No	No	
	BEELER	ST		INDIANA	AVE		MCDONALD	AVE	Concrete	1	PastServiceLife	2.85	3.55	4	4	Yes	No	Yes	No	No	

Street Prefix	Street Name	Street Suffix	From Street Prefix	From Street Name	From Street Suffix	To Street Prefix	To Street Name	To Street Suffix	Surface Type	Condition	Condition Description	Max Long Slope (%)	Max Cross Slope (%)	Width Min (ft)	Width Max (ft)	Curb Ramp From St	Curb Ramp From St ADA	Curb Ramp To St	Curb Ramp To St ADA	ADA Compliant	Comments
	BEELER	ST	E	11TH	ST	E	15TH	ST	Concrete	3	Poor	3.45	1.35	5	6	No		No		Yes	
	BEHARRELL	AVE	E	ELM	ST		SPRING	AVE	Concrete	4	Fair	0.20	1.10	4	4	Yes		Yes	No	Yes	
	BEHARRELL	AVE	E	OAK	ST	E	ELM	ST	Concrete	3	Poor	0.50	2.10	4	4	Yes	No	Yes	No	No	
	BEHARRELL	AVE	E	ELM	ST		SPRING	AVE	Concrete	3	Poor	0.50	3.20	4	4	Yes	No	Yes	Yes	No	
	BEHARRELL	AVE		GLENWOOD	PK	E	SPRING	ST	Concrete	3	Poor	0.40	0.20	4	5	Yes	Yes	Yes	No	Yes	
	BEHARRELL	AVE		SPRING	AVE	E	SPRING	ST	Concrete	3	Poor	3.00	0.80	4	4	Yes	No	Yes	No	Yes	
	BEHARRELL	AVE		SLATE RUN	RD	E	ELM	ST	Concrete	2	Very Poor	0.50	0.50	5	5	Yes	No	Yes	Yes	Yes	
	BEHARRELL	AVE		GLENWOOD	CT		GLENWOOD	PK	Concrete	2	Very Poor	2.10	2.40	4	4	Yes	No	Yes	Yes	No	
	BEHARRELL	AVE		SPRING	AVE		GLENWOOD	CT	Concrete	2	Very Poor	1.40	1.10	4	4	Yes	Yes	Yes	No	Yes	
	BEHARRELL	AVE	E	SPRING	ST	E	MARKET	ST	Concrete	2	Very Poor	0.60	1.30	4	4	Yes	No	Yes	No	Yes	
	BEHARRELL	AVE	E	SPRING	ST	E	MARKET	ST	Concrete	2	Very Poor	0.40	1.90	4	4	Yes	Yes	No		Yes	
	BEHARRELL	AVE		SLATE RUN	RD	E	OAK	ST	Concrete	2	Very Poor	0.30	2.70	4	4	No		Yes	No	No	
	BELLEMEADE	DR		MILL	LN		MILLER	LN	Concrete	3	Poor	1.50	1.50	4	4	No		No		Yes	
	BELLEMEADE	DR		MILL	LN		MILLER	LN	Concrete	3	Poor	0.70	2.00	4	4	No		No		Yes	
	BENTBROOK	DR		SCHELL	LN		DRAWBROOK	CIR	Concrete	3	Poor	6.20	0.40	4	4	Yes	Yes	No		Yes	
	BENTBROOK	DR		SCHELL	LN		DRAWBROOK	CIR	Concrete	3	Poor	0.10	0.20	4	4	Yes	Yes	No		Yes	
	BENTBROOK	DR		DRAWBROOK	CIR		DRAWBROOK	CIR	Concrete	2	Very Poor	2.30	3.80	4	4	No		No		No	
	BEST	AVE	E	SPRING	ST		RENO	AVE	Concrete	3	Poor	1.20	0.20	4	4	Yes	No	Yes	Yes	Yes	
	BEST	AVE		RENO	AVE		ALLY		Concrete	1	PastServiceLife	0.50	1.80	4	4	Yes	No	No		Yes	
	BLACKISTON BLVD			BLACKISTON MILL RD			BLACKISTON BLVD		Concrete	4	Fair	8.70	4.70	5	5	Yes	Yes	Yes	Yes	No	
	BLACKISTON BLVD			PAYNE KOEHLER RD			BLACKISTON BLVD		Concrete	4	Fair	4.40	0.90	5	5			Yes	Yes	Yes	
	BLACKISTON BLVD			BLACKISTON BLVD			DEAD END		Concrete	4	Fair	0.90	2.10	5	5	Yes	Yes			No	
	BLACKISTON BLVD			BLACKISTON MILL RD			BLACKISTON BLVD		Concrete	3	Poor	4.20	4.90	4	5	Yes	Yes	Yes	Yes	No	
	BLACKISTON MILL RD			DEAD END			BLACKISTON BLVD		Concrete	3	Poor	3.10	1.70	4	4			Yes	Yes	Yes	
	BONNIE SLOAN	DR		ERNI	AVE		ERNI	AVE	Concrete	3	Poor	1.50	6.40	4	4	No		No		No	
	BONO	RD		MARTIN	DR	E	COTTOM	AVE	Concrete	4	Fair	3.40	1.60	4	4	Yes	No	Yes	No	Yes	
	BONO	RD		GARY	DR		COUNTRY CLUB	DR	Concrete	4	Fair	1.20	2.00	4	4	Yes	No	Yes	No	Yes	
	BONO	RD		COUNTRY CLUB	DR		ERNI	AVE	Concrete	4	Fair	7.40	0.50	4	4	Yes	No	Yes	No	Yes	
	BONO	RD		GREEN VALLEY	RD		MARTIN	DR	Concrete	4	Fair	1.20	1.30	4	4	Yes	No	Yes	No	Yes	
	BONO	RD		CLAY	ST		UNION	ST	Concrete	4	Fair	0.80	2.70	5	7	Yes	Yes	No		No	
	BONO	RD		ERNI	AVE		CARDINAL	DR	Concrete	3	Poor	0.80	1.20	4	4	Yes	No	Yes	No	Yes	
	BONO	RD		GREEN	ST		CLAY	ST	Concrete	3	Poor	1.50	0.60	4	4	Yes	No	Yes	No	Yes	
	BONO	RD		OLIVE	AVE		CONNER	ST	Concrete	3	Poor	0.20	1.40	4	4	Yes	No	Yes	No	Yes	
	BONO	RD		GREEN VALLEY	DR		GARY	DR	Concrete	3	Poor	1.20	1.90	4	4	Yes	No	Yes	No	Yes	
	BONO	RD		CARDINAL	DR		GRAYBROOK	LN	Concrete	3	Poor	1.60	1.50	4	4	Yes	No	Yes	No	Yes	
	BONO	RD		SLOEMER	AVE		GREEN	ST	Concrete	3	Poor	0.30	0.80	4	4	Yes	No	Yes	No	Yes	
	BONO	RD		CONNER	ST	E	LEWIS	ST	Concrete	3	Poor	1.10	1.80	4	4	Yes	No	Yes	No	Yes	
	BONO	RD	E	COTTOM	AVE		OLIVE	AVE	Concrete	3	Poor	0.20	0.10	4	4	Yes	No	Yes	No	Yes	
	BONO	RD	E	LEWIS	ST		SLOEMER	AVE	Concrete	3	Poor	1.50	0.90	4	4	Yes	No	Yes	No	Yes	
	BRENTWOOD	CT		PENNWOOD	DR		ASHWOOD	DR	Concrete	4	Fair	0.50	0.30	4	5	Yes	Yes	Yes	Yes	Yes	
	BRENTWOOD	CT		ASHWOOD	DR		DEERWOOD	DR	Concrete	3	Poor	5.75	0.85	4	4	No		No		Yes	
	BRENTWOOD	CT		PENNWOOD	DR		DEERWOOD	DR	Concrete	2	Very Poor	2.35	2.75	4	5	No		No		No	
	BULTER	ST		DEAD END			DEWEY	ST	Concrete	1	PastServiceLife	4.00	3.00	3	3	No		Yes	No	No	
	BURTON	AVE		DEPAUW	AVE		LOCUST	ST	Concrete	3	Poor	0.20	3.10	4	6	Yes	No	Yes	No	No	
	BURTON	AVE		DEPAUW	AVE		LOCUST	ST	Concrete	2	Very Poor	0.50	1.80	4	6	Yes	No	Yes	No	Yes	
	BUTLER	ST	E	MAIN	ST		DEWEY	ST	Concrete	1	PastServiceLife	9.00	6.80	3	3	Yes	Yes	Yes	No	No	
	CARDINAL	DR		BONO	RD		ERNI	AVE	Concrete	3	Poor	3.30	1.70	4	4	Yes	No	No		Yes	
	CARDINAL	DR		BONO	RD		ERNI	AVE	Concrete	3	Poor	0.80	3.00	4	4	Yes	No	No		No	
	CASTLEWOOD	DR		PENNWOOD	DR		ASHWOOD	DR	Concrete	4	Fair	3.70	2.80	4	4	Yes	Yes	No		No	
	CASTLEWOOD	DR		ASHWOOD	DR		DEERWOOD	DR	Concrete	3	Poor	2.15	3.40	4	5	Yes	Yes	No		No	
	CASTLEWOOD	DR		DEERWOOD	DR		KLERNER	LN	Concrete	3	Poor	3.80	1.45	4	4	No		Yes	Yes	Yes	
	CASTLEWOOD	DR		DEAD END			KLERNER	LN	Concrete	3	Poor	7.05	3.55	4	5	No		Yes	Yes	No	
	CATHERINE	PL		BEELER	ST		EKIN	AVE	Concrete	4	Fair	4.50	1.60	4	4	No		Yes	No	Yes	
	CATHERINE	PL		BEELER	ST		EKIN	AVE	Concrete	4	Fair	3.90	1.80	4	4	No		Yes	No	Yes	
	CAVEL	ST	E	MARKET	ST	E	MAIN	ST	Concrete	3	Poor	1.40	0.50	4	4	Yes	No	Yes	Yes	Yes	
	CAVEL	ST	E	MARKET	ST	E	MAIN	ST	Concrete	2	Very Poor	0.70	4.40	4	4	Yes	No	Yes	Yes	No	
	CEDAR RIDGE	DR		DEAD END			WEST	ST	Concrete	3	Poor	2.35	2.35	4	4	No		No		No	
	CEDARBOUGH	PL		BEELER	ST		EKIN	AVE	Concrete	1	PastServiceLife	3.40	1.80	4	5	No		Yes	No	Yes	
	CEDARBOUGH	PL		BEELER	ST		EKIN	AVE	Concrete	1	PastServiceLife	7.60	1.80	4	6	No		Yes	No	Yes	
	CENTER	ST		THOMAS	AVE		JAY	ST	Concrete	2	Very Poor	1.10	1.70	4	4	Yes	No	No		Yes	
	CENTER	ST		THOMAS	AVE		JAY	ST	Concrete	2	Very Poor	2.50	5.50	4	4	No		Yes	No	No	
	CENTER	ST		DEAD END			THOMAS	AVE	Concrete	2	Very Poor	2.80	1.00	4	4	No		Yes	No	Yes	
	CENTER	ST		DEAD END			THOMAS	AVE	Concrete	2	Very Poor	0.40	2.20	4	4	No		Yes	Yes	No	
	CHADWOOD	DR		DEAD END			EDGEWOOD	DR	Concrete	5	Good	6.30	2.70	4	4	No		No		No	
	CHADWOOD	DR		EDGE MONT	DR		SPICKERT KNOB	DR	Concrete	3	Poor	3.90	3.10	4	4	No		Yes	No	No	
	CHARLESTOWN	RD		LINCOLN	AVE		BEECHWOOD	AVE	Concrete	5	Good	0.40	1.30	5	6	Yes	No	Yes	Yes	Yes	
	CHARLESTOWN	RD		VINCENNES	ST		CLARK	ST	Concrete	5	Good	0.30	0.40	4	5	Yes	No	Yes	No	Yes	
	CHARLESTOWN	RD		WOODLAWN	DR		COES	LN	Concrete	5	Good	1.30	2.40	4	4	No		Yes	No	No	
	CHARLESTOWN	RD		VANCE	AVE		SOUTH	ST	Concrete	5	Good	0.80	1.00	4	5	Yes	No	Yes	No	Yes	
	CHARLESTOWN	RD		SOUTH	ST		VINCENNES	ST	Concrete	5	Good	0.30	0.70	4	6	Yes	No	Yes	No	Yes	
	CHARLESTOWN	RD		MCDONALD	LN	N	AUDUBON	DR	Concrete	4	Fair	0.10	1.50	6	6	Yes	Yes	Yes	No	Yes	
	CHARLESTOWN	RD		SILVER	ST		BEEHWOOD	AVE	Concrete	4	Fair	0.90	1.30	4	5	Yes	No	Yes	No	Yes	
	CHARLESTOWN	RD		VINCENNES	ST		CLARK	ST	Concrete	4	Fair	0.10	0.80	4	4	Yes	No	Yes	No	Yes	
	CHARLESTOWN	RD		HEDDEN	CT		HEDDEN	PK	Concrete	4	Fair	0.50	2.30	4	5	Yes	No	Yes	No	No	
	CHARLESTOWN	RD		HEDDEN	PK		INDIANA	AVE	Concrete	4	Fair	0.70	1.40	4	5	Yes	No	Yes	No	Yes	
	CHARLESTOWN	RD		ROOSEVELT	AVE		LINCOLN	AVE	Concrete	4	Fair	0.20	0.60	4	5	Yes	No	Yes	No	Yes	
	CHARLESTOWN	RD		SCHELLER	LN		MCDONALD	LN	Concrete	4	Fair	1.70	1.40	6	6	Yes	No	Yes	Yes	Yes	
	CHARLESTOWN	RD		CITY LIMITS			RAINBOW	DR	Concrete	4	Fair	1.60	1.70	4	4	No		Yes	No	Yes	
	CHARLESTOWN	RD		SILVER	ST		ROOSEVELT	AVE	Concrete	4	Fair	1.60	1.20	4	5	Yes	No	Yes	No	Yes	
	CHARLESTOWN	RD		LYNNWOOD	DR		SCHELLER	LN	Concrete	4	Fair	0.10	1.10	4	6	Yes	Yes	Yes	Yes	Yes	
	CHARLESTOWN	RD		LAFAYETTE	DR		SERENITY SPRINGS	DR	Concrete	4	Fair	3.10	3.00	4	4	Yes	No	Yes	No	No	

Street Prefix	Street Name	Street Suffix	From Street Prefix	From Street Name	From Street Suffix	To Street Prefix	To Street Name	To Street Suffix	Surface Type	Condition	Condition Description	Max Long Slope (%)	Max Cross Slope (%)	Width Min (ft)	Width Max (ft)	Curb Ramp From St	Curb Ramp From St ADA	Curb Ramp To St	Curb Ramp To St ADA	ADA Compliant	Comments
	CHARLESTOWN	RD		INDIANA	AVE		SILVER	ST	Concrete	4	Fair	0.10	0.80	4	4	Yes	No	Yes	No	Yes	
	CHARLESTOWN	RD		BEECHWOOD	AVE		VANCE	AVE	Concrete	4	Fair	0.50	1.80	5	6	Yes	No	Yes	No	Yes	
	CHARLESTOWN	RD		VANCE	AVE		VINCENNES	ST	Concrete	4	Fair	0.80	1.00	4	6	Yes	No	Yes	No	Yes	
	CHARLESTOWN	RD		COES	LN		DEAD END		Concrete	4	Fair	0.60	0.40	4	4	Yes	No	Yes	No	Yes	
	CHARLESTOWN	RD		DEAD END			DEAD END		Concrete	4	Fair	0.30	1.60	4	5	No		No		Yes	
	CHARLESTOWN	RD		PAYNE KOEHLER	RD		BLACKISTON	RD	Concrete	3	Poor	0.90	1.50	4	4	Yes	No	Yes	No	Yes	
	CHARLESTOWN	RD		BLACKISTON MILL	RD		COLONIAL VILLAGE	DR	Concrete	3	Poor	1.40	1.90	4	4	Yes	No	Yes	No	Yes	
	CHARLESTOWN	RD		SLATE RUN	RD		GARRETSON	LN	Concrete	3	Poor	0.10	2.90	4	5	Yes	Yes	Yes	No	No	
	CHARLESTOWN	RD	N	AUDUBON	DR		GENUNG	DR	Concrete	3	Poor	1.60	1.10	6	6	Yes	No	Yes	No	Yes	
	CHARLESTOWN	RD		CLARK	ST		GRANT LINE	RD	Concrete	3	Poor	1.00	1.40	4	5	Yes	No	No		Yes	
	CHARLESTOWN	RD		MCDONALD	AVE		INDIANA	AVE	Concrete	3	Poor	0.70	1.40	4	4	Yes	Yes	Yes	No	Yes	
	CHARLESTOWN	RD		COLONIAL VILLAGE	DR		KLERNER	LN	Concrete	3	Poor	1.00	1.20	4	4	Yes	No	Yes	No	Yes	
	CHARLESTOWN	RD		SERENITY SPRINGS	DR		KLERNER	LN	Concrete	3	Poor	0.30	3.50	4	4	Yes	No	Yes	No	No	
	CHARLESTOWN	RD		MT TABOR	RD		LAFAYETTE	DR	Concrete	3	Poor	1.30	2.10	4	4	Yes	No	Yes	No	No	
	CHARLESTOWN	RD		KLERNER	LN		LILY	LN	Concrete	3	Poor	2.00	0.20	6	6	Yes	No	Yes	No	Yes	
	CHARLESTOWN	RD		MILLERWOOD	DR		LYNNWOOD	DR	Concrete	3	Poor	3.30	2.00	4	4	Yes	No	Yes	Yes	Yes	
	CHARLESTOWN	RD		ABBIE DELL	AVE		MCDONALD	AVE	Concrete	3	Poor	0.30	1.60	4	4	No		Yes	Yes	Yes	
	CHARLESTOWN	RD		LILY	LN		MILLERWOOD	DR	Concrete	3	Poor	1.20	0.80	4	4	Yes	No	Yes	No	Yes	
	CHARLESTOWN	RD		RAINBOW	DR		MT TABOR	RD	Concrete	3	Poor	5.50	3.80	4	4	Yes	No	Yes	No	No	
	CHARLESTOWN	RD		GARRETSON	LN		ROSELAWN	AVE	Concrete	3	Poor	0.90	3.30	6	6	Yes	No	Yes	No	No	
	CHARLESTOWN	RD		INDIANA	AVE		SILVER	ST	Concrete	3	Poor	0.90	2.00	4	4	Yes	No	Yes	No	Yes	
	CHARLESTOWN	RD		BRYN MAWR	CT		SLATE RUN	RD	Concrete	3	Poor	0.50	0.20	4	4	Yes	No	Yes	No	Yes	
	CHARLESTOWN	RD		BEECHWOOD	AVE		VANCE	AVE	Concrete	3	Poor	0.10	1.00	4	5	Yes	Yes	Yes	No	Yes	
	CHARLESTOWN	RD		CLARK	ST		DEAD END		Concrete	3	Poor	2.70	1.70	4	4	Yes	No	No		Yes	
	CHARLESTOWN	RD		ROSELAWN	AVE		DEAD END		Concrete	3	Poor	0.90	2.20	6	6	Yes	No	No		No	
	CHARLESTOWN	RD		OLD FORD	RD		BRYN MAWR	CT	Concrete	3	Poor	0.30	5.20	4	4	Yes	No	Yes	No	No	
	CHARLESTOWN CROSSING			KAMER MILLER RD			CHARLESTOWN CROSSING WAY	CT	Concrete	4	Fair	2.40	1.90	5	5	Yes	Yes	No	No	Yes	
	CHARLESTOWN CROSSING			KAMER MILLER RD			CHARLESTOWN CROSSING WAY		Concrete	4	Fair	0.90	2.40	4	4	Yes	Yes	No	No	No	
	CHARLESTOWN CROSSING			CHARLESTOWN CROSSING WAY			CHARLESTOWN RD		Concrete	3	Poor	2.10	3.30	4	4	Yes	Yes	Yes	Yes	No	
	CHARLESTOWN CROSSING			CHARLESTOWN CROSSING WAY			CHARLESTOWN RD		Concrete	3	Poor	3.00	6.30	4	5	No		Yes	Yes	No	
	CHARLESTOWN CROSSING WAY			CHARLESTOWN CROSSING			NORTHSIDE DR		Concrete	3	Poor	3.30	1.60	4	4	No		Yes	Yes	Yes	
	CHARLESTOWN RD			SUNSET DR			CITY LIMITS		Concrete	4	Fair	1.60	1.40	4	4	Yes	Yes			Yes	
	CHARLESTOWN RD			KAMER MILLER RD			CHARLESTOWN CROSSING		Concrete	3	Poor	2.60	2.50	4		Yes	Yes	Yes	Yes	No	
	CHARLESTOWN RD			KAMER MILLER RD			CHARLESTOWN CROSSING		Concrete	3	Poor	1.70	2.80	4	4	Yes	No	Yes	No	No	
	CHARLESTOWN RD			CHARLESTOWN CROSSING			NORTHSIDE DR		Concrete	3	Poor	4.20	4.00	4	5	Yes	Yes	Yes	No	No	
	CHARLESTOWN RD			CHARLESTOWN CROSSING			NORTHSIDE DR		Concrete	3	Poor	1.90	3.70	4	4	Yes	Yes	Yes	No	No	
	CHARLESTOWN RD			PROFESSIONAL CT			PROFESSIONAL CT		Concrete	3	Poor	2.60	4.00	4	4	Yes	No	Yes	No	No	
	CHARLESTOWN RD			NORTHSIDE DR			SUNSET DR		Concrete	3	Poor	3.50	1.40	5	5	Yes	No	Yes	Yes	Yes	
	CHARLESTOWN STATION	CT		LYNNWOOD	DR		LYNNWOOD	DR	Concrete	3	Poor	9.50	5.60	4	4	No		No		No	
	CHARTERES	ST		JACKSON	ST		BEELER	ST	Concrete	2	Very Poor	1.80	2.30	5	7	Yes	Yes	No		No	
	CHARTRES	ST		CHARLES	ST		JACKSON	ST	Concrete	3	Poor	1.50	1.20	6	8	Yes	Yes	No		Yes	
	CHARTRES	ST		JACKSON	ST		BEELER	ST	Concrete	2	Very Poor	0.40	1.30	5	7	Yes	Yes	Yes		Yes	
	CHARTRES	ST		CLARK	ST		CHARLES	ST	Concrete	2	Very Poor	0.30	0.10	5	6	No		Yes	No	Yes	
	CHARTRES	ST		VINCENNES	ST		CLARK	ST	Concrete	2	Very Poor	1.50	0.50	5	8	No		Yes	No	Yes	
	CHARTRES	ST		CHARLES	ST		JACKSON	ST	Concrete	2	Very Poor	2.00	2.00	5	7	Yes	Yes	No		Yes	
	CHARTRES	ST		CLARK	ST		CHARLES	ST	Concrete	1	PastServiceLife	5.70	6.20	5	6	No		Yes	No	No	
	CHARTRES	ST		VINCENNES	ST		CLARK	ST	Concrete	1	PastServiceLife	1.10	3.00	4	6	Yes	No	Yes	No	No	
	CHERRY	SY		GRIFFIN	ST		HILDRETH	ST	Concrete	4	Fair	1.00	1.00	5	7	Yes	No	Yes	No	Yes	
	CHERRY	ST		HILDRETH	ST		STATE	ST	Concrete	4	Fair	0.90	0.40	3	8	Yes	No	Yes	No	Yes	
	CHERRY	ST	W	8TH	ST	W	7TH	ST	Concrete	3	Poor	0.50	1.70	4	5	Yes	No	Yes	Yes	Yes	
	CHERRY	ST		OLD VINCENNES	RD	W	8TH	ST	Concrete	3	Poor	0.20	0.80	8	10	Yes	Yes	No		Yes	
	CHERRY	ST	W	7TH	ST		ALLY		Concrete	3	Poor	2.30	2.20	4	5	Yes	Yes	No		No	
	CHERRY	ST		HILDRETH	ST		SCRIBNER	DR	Concrete	3	Poor	0.20	0.10	4	6	Yes	No	Yes	No	Yes	
	CHERRY	ST		SCRIBNER	DR		STATE	ST	Concrete	3	Poor	0.50	0.60	4	6	Yes	No	Yes	No	Yes	
	CHERRY	ST		VALLEY VIEW	RD		WEST	ST	Concrete	3	Poor	1.30	1.00	4	6	Yes	Yes	No		Yes	
	CHERRY	ST	W	9TH	ST	W	8TH	ST	Concrete	2	Very Poor	0.50	0.20	4	5	Yes	Yes	No		Yes	
	CHERRY	ST	W	10TH	ST	W	9TH	ST	Concrete	2	Very Poor	2.00	0.60	4	6	No		No		Yes	
	CHERRY	ST		WEST	ST		GRIFFIN	ST	Concrete	2	Very Poor	0.20	0.40	5	6	Yes	No	Yes	No	Yes	
	CHERRY	ST		GRIFFIN	ST		HILDRETH	ST	Concrete	2	Very Poor	3.40	3.60	5	6	No		No		No	
	CHERRY	ST	W	8TH	ST		VALLEY VIEW	RD	Concrete	2	Very Poor	4.20	2.40	4	10	No	Yes	Yes		No	
	CHERRY	ST		STATE	ST		PEARL	ST	Concrete	3	Poor	1.40	0.10	4	6	Yes	No	Yes	No	Yes	
	CHERRY	ST		STATE	ST		PEARL	ST	Concrete	3	Poor	1.00	3.70	4	5	Yes	No	Yes	No	No	
	CLARA LEE	CT		ELHANAN	CT		SHELL	LN	Concrete	5	Good	0.80	2.10	4	4	Yes	No	No		No	
	CLARA LEE	CT		ELHANAN	CT		SHELL	LN	Concrete	5	Good	0.50	0.90	4	4	No		Yes	No	Yes	
	CLARK	ST		CHARLESTOWN	RD	E	8TH	ST	Concrete	3	Poor	6.30	5.40	4	4	Yes	No	Yes	No	No	
	CLARK	ST		LOCUST	ST		BEELER	ST	Concrete	3	Poor	0.70	0.40	6	12	Yes	No	Yes	No	Yes	
	CLARK	ST		LOCUST	ST		BEELER	ST	Concrete	3	Poor	0.10	0.30	4	6	Yes	No	Yes	No	Yes	
	CLARK	ST		DEAD END			CHARLESTOWN	RD	Concrete	3	Poor	0.20	0.70	3	3	No		Yes	No	Yes	
	CLARK	ST	E	8TH	ST		CHARTRES	ST	Concrete	3	Poor	4.50	3.10	4	4	Yes	No	Yes	No	No	
	CLARK	ST		CHARLESTOWN	RD		CHARTRES	ST	Concrete	3	Poor	4.00	6.10	4	4	Yes	No	Yes	No	No	
	CLARK	ST		CHARTRES	ST		LOCUST	ST	Concrete	3	Poor	1.00	0.70	5	7	Yes	No	Yes	No	Yes	
	CLARK	ST		CHARTRES	ST		LOCUST	ST	Concrete	3	Poor	0.70	0.60	5	8	Yes	No	No		Yes	
	CLARK	ST		DEAD END			CHARLESTOWN	RD	Concrete	2	Very Poor	2.40	5.20	4	10	No		Yes	No	No	
	CLAY	ST		STATE	ST		BONO	RD	Concrete	2	Very Poor	1.40	1.20	4	8	No		No		Yes	
	CLAY	ST		VINE	ST		BONO	RD	Concrete	2	Very Poor	0.30	2.10	4	6	Yes	No	No		No	
	CLAY	ST		STATE	ST		VINE	ST	Concrete	2	Very Poor	1.20	1.50	4	6	Yes	No	Yes	No	Yes	
	CLIFFWOOD	CT		CLIFFWOOD	DR		CLIFFWOOD	DR	Concrete	4	Fair	0.60	0.90	4	5	No		No		Yes	
	CLIFFWOOD	DR		CLIFWOOD	CT		KLERNER	LN	Concrete	3	Poor	2.70	2.75	4	4	No		No		No	
	CLIFFWOOD	DR		DEERWOOD	DR		KLERNER	LN	Concrete	3	Poor	2.15	0.60	4	5	No		No		Yes	
	CLIFFWOOD	DR		PENNWOOD	DR		CLIFFWOOD	CT	Concrete	2	Very Poor	0.25	2.95	4	4	No		No		No	
	CLIFFWOOD	DR		DEERWOOD	DR		PENNWOOD	DR	Concrete	2	Very Poor	2.05	7.40	4	4	No		No		No	

Street Prefix	Street Name	Street Suffix	From Street Prefix	From Street Name	From Street Suffix	To Street Prefix	To Street Name	To Street Suffix	Surface Type	Condition	Condition Description	Max Long Slope (%)	Max Cross Slope (%)	Width Min (ft)	Width Max (ft)	Curb Ramp From St	Curb Ramp From St ADA	Curb Ramp To St	Curb Ramp To St ADA	ADA Compliant	Comments
	CLOVER	AVE		VALLEY VIEW	CT		ALLY		Concrete	3	Poor	0.50	0.80	4	4	No		No		Yes	
	CLOVER	AVE		VALLEY VIEW	CT		ALLY		Concrete	3	Poor	2.20	0.30	4	4	No		No		Yes	
	CONNOR	ST		STATE	ST		DEAD END		Concrete	3	Poor	5.10	0.10	4	4	Yes	No	No		Yes	
	CONSERVATIVE	ST		GREEN	ST	E	18TH	ST	Concrete	3	Poor	1.60	1.80	4	4	Yes	Yes	Yes	Yes	Yes	
	CONSERVATIVE	ST	E	18TH	ST		DEAD END		Concrete	1	PastServiceLife	1.10	1.70	4	4	Yes	Yes	Yes	No	Yes	
	CONSERVATIVE	ST		GREEN	ST		DEAD END		Concrete	1	PastServiceLife	0.20	2.20	4	4	Yes	Yes	Yes	No	No	
	CORYDON PIKE			CAMP	AVE	W	MAIN	ST	Concrete	1	PastServiceLife	0.90	2.10	4	4	No		No		No	
	COST	AVE		SPRING	AVE	E	SPRING	ST	Concrete	3	Poor	4.00	2.20	4	5	Yes	No	Yes	No	No	
	COST	AVE		SPRING	AVE	E	SPRING	ST	Concrete	3	Poor	3.50	1.50	4	5	No		Yes	No	Yes	
	COST	AVE	E	SPRING	ST		ALLY		Concrete	2	Very Poor	1.10	3.20	4	4	Yes	Yes	No		No	
	COST	AVE	E	SPRING	ST		RENO	AVE	Concrete	2	Very Poor	0.50	0.60	4	4	Yes	No	Yes	No	Yes	
E	COTTOM	AVE	N	PEARL	ST		BONO	RD	Concrete	4	Fair	2.20	0.90	5	5	Yes	No	Yes	No	Yes	
E	COTTOM	AVE	N	PEARL	ST		BONO	RD	Concrete	2	Very Poor	0.40	1.00	4	4	Yes	No	Yes	No	Yes	
E	COTTOM	AVE		STATE	ST	N	PEARL	ST	Concrete	2	Very Poor	0.20	2.60	4	4	Yes	No	Yes	No	No	
W	COTTOM	AVE		WEST	ST		STATE	ST	Concrete	2	Very Poor	1.00	1.10	4	4	No		Yes	No	Yes	
W	COTTOM	AVE		WEST	ST		STATE	ST	Concrete	2	Very Poor	1.20	3.05	4	4	No		Yes	No	No	
	COUNTRY CLUB	DR		BONO	RD		FAIRWAY	CT	Concrete	3	Poor	3.30	0.40	4	5	Yes	Yes	Yes	No	Yes	
	COUNTRY CLUB	DR		HORNUNG	DR		GRAYBROOK	LN	Concrete	3	Poor	3.40	0.40	4	4	Yes	No	Yes	No	Yes	
	COUNTRY CLUB	DR		PLAYER	PL		HORNUNG HILL	DR	Concrete	3	Poor	2.60	0.60	4	4	Yes	No	Yes	No	Yes	
	COUNTRY CLUB	DR		BONO	RD		PLAYER	PL	Concrete	3	Poor	0.20	0.50	4	5	Yes	No	Yes	No	Yes	
	COUNTRY CLUB	DR		PALMER	CT	W	VILLAGE	DR	Concrete	3	Poor	0.50	2.00	3	4	Yes	No	Yes	No	Yes	
	COUNTRY CLUB	DR	W	VILLAGE	DR	E	VILLAGE	DR	Concrete	2	Very Poor	2.00	0.80	4	4	Yes	No	Yes	No	Yes	
	COUNTRY CLUB	DR		FAIRWAY	CT		PALMER	DT	Concrete	3	Poor	0.70	3.00	4	4	Yes	No	Yes	No	No	
	CREEKVIEW	CIR		DOEBROOK	DR		DOEBROOK	DR	Concrete	4	Fair	0.50	1.70	4	4	No		No		Yes	
	CREEKVIEW	CIR		WOODFIELD	DR		DOEBROOK	DR	Concrete	4	Fair	0.80	1.70	4	4	No		No		Yes	
	CREEKVIEW	CIR		DOEBROOK	DR		WOODFIELD	DR	Concrete	4	Fair	1.20	0.90	4	4	No		No		Yes	
	CREEKVIEW	CIR		DOEBROOK	DR		WOODFIELD	DR	Concrete	4	Fair	0.90	1.30	4	4	No		No		Yes	
	CREEKVIEW	CIR		DOEBROOK	DR		WOODFIELD	DR	Concrete	4	Fair	0.90	1.20	4	4	No		No		Yes	
	CREEKWOOD	CT		ROLLING CREEK	DR		ROLLING CREEK	DR	Concrete	3	Poor	0.50	1.70	4	4	Yes	No	Yes	No	Yes	
	CROWN	CT		DEAD END			GREEN VALLEY	RD	Concrete	5	Good	0.40	1.80	4	4	No		Yes	No	Yes	
	CROWN	CT		DEAD END			GREEN VALLEY	RD	Concrete	5	Good	0.50	1.70	4	4	No		Yes	No	Yes	
	CRYSTAL	AVE		SHERLEY	ST		EALY	ST	Concrete	2	Very Poor	5.30	1.30	4	4	Yes	No	Yes	No	Yes	
	CULBERTSON	AVE	E	11TH	ST	E	13TH	ST	Concrete	4	Fair	1.45	2.15	6	10	Yes	No	Yes	No	No	
	CULBERTSON	AVE	E	13TH	ST	E	15TH	ST	Concrete	4	Fair	0.25	2.35	5	5	Yes	No	Yes	No	No	
	CULBERTSON	AVE	E	13TH	ST	E	15TH	ST	Concrete	4	Fair	1.20	4.10	5	5	Yes	No	Yes	No	No	
	CULBERTSON	AVE	E	5TH	ST	E	7TH	ST	Concrete	4	Fair	0.60	1.80	3	5	Yes	No	Yes	No	Yes	
	CULBERTSON	AVE	E	6TH	ST	E	7TH	ST	Concrete	4	Fair	1.55	2.70	4	4	Yes	No	Yes	No	No	
	CULBERTSON	AVE	E	7TH	ST	E	8TH	ST	Concrete	4	Fair	1.00	2.15	5	5	Yes	No	Yes	No	No	Couple sections of brick
	CULBERTSON	AVE		PEARL	ST		BANK	ST	Concrete	4	Fair	8.10	1.20	4	4	Yes	No	No		No	
	CULBERTSON	AVE		THOMAS	AVE		JAY	ST	Concrete	4	Fair	1.45	0.75	5	5	Yes	No	Yes	No	Yes	
	CULBERTSON	AVE		JAY	ST		SILVER	ST	Concrete	4	Fair	0.05	1.00	5	5	Yes	No	Yes	No	Yes	
	CULBERTSON	AVE		JAY	ST		SILVER	ST	Concrete	4	Fair	0.05	0.95	5	5	Yes	No	Yes	No	Yes	
	CULBERTSON	AVE		VINCENNES	ST		THOMAS	AVE	Concrete	4	Fair	1.10	1.65	5	5	Yes	No	Yes	No	Yes	
	CULBERTSON	AVE		VINCENNES	ST		THOMAS	AVE	Concrete	4	Fair	2.70	2.40	5	5	Yes	No	Yes	No	No	
	CULBERTSON	AVE	E	9TH	ST	E	10TH	ST	Concrete	3	Poor	1.80	6.55	4	5	Yes	No	Yes	Yes	No	
	CULBERTSON	AVE	E	9TH	ST	E	10TH	ST	Concrete	3	Poor	0.95	1.30	4	5	Yes	Yes	Yes	Yes	Yes	
	CULBERTSON	AVE	E	10TH	ST	E	13TH	ST	Asphalt	3	Poor	2.15	0.95	8	20	Yes	No	Yes	No	Yes	
	CULBERTSON	AVE	E	4TH	ST	E	6TH	ST	Concrete	3	Poor	0.50	3.75	4	4	Yes	Yes	Yes	No	No	
	CULBERTSON	AVE	E	7TH	ST	E	8TH	ST	Concrete	3	Poor	1.10	0.95	4	5	Yes	No	Yes	No	Yes	
	CULBERTSON	AVE	E	8TH	ST	E	9TH	ST	Concrete	3	Poor	0.65	1.70	4	5	Yes	No	Yes	No	Yes	
	CULBERTSON	AVE	E	8TH	ST	E	9TH	ST	Concrete	3	Poor	1.45	2.95	4	5	Yes	No	Yes	Yes	No	
	CULBERTSON	AVE		SILVER	ST		INDIANA	AVE	Concrete	3	Poor	0.25	1.90	4	5	Yes	No	Yes	No	Yes	
	CULBERTSON	AVE		THOMAS	AVE		JAY	ST	Concrete	3	Poor	0.05	1.00	5	5	Yes	No	Yes	No	Yes	
	CULBERTSON	AVE	E	15TH	ST		VINCENNES	ST	Concrete	3	Poor	2.85	2.50	5	6	Yes	No	Yes	No	No	
	CULBERTSON	AVE	E	15TH	ST		VINCENNES	ST	Concrete	3	Poor	1.45	1.00	5	5	Yes	No	Yes	No	Yes	
	CULBERTSON	AVE		BANK	ST	E	4TH	ST	Concrete	2	Very Poor	2.60	3.30	6	8	No		Yes	No	No	
	CULBERTSON	AVE		SILVER	ST		INDIANA	AVE	Concrete	2	Very Poor	0.40	1.55	4	4	Yes	No	Yes	No	Yes	
	CULBERTSON	AVE		BANK	ST	E	4TH	ST	Concrete	1	PastServiceLife	2.40	2.75	6	7	No		Yes	No	No	
	CULBERTSON	AVE	E	4TH	ST	E	5TH	ST	Concrete	1	PastServiceLife	1.70	3.90	6	8	Yes	Yes	Yes	No	No	
	CULBERTSON	AVE		PEARL	ST		BANK	ST	Concrete	1	PastServiceLife	7.85	1.90	4	4	Yes	No	No		Yes	
W	DAISY	LN		STATE	ST		COYLE	DR	Concrete	4	Fair	0.90	1.80	4	4	Yes	No	Yes	No	Yes	
	DAISY	SUMMIT		STATE	ST		END		Concrete	4	Fair	6.30	0.90	4	4	Yes	No	No		Yes	
	DAISY	SUMMIT		STATE	ST		END		Concrete	4	Fair	6.50	1.10	4	4	Yes	No	No		Yes	
W	DAISY	LN		FRANKLIN	DR		HARRIS	CT	Concrete	4	Fair	0.80	1.50	4	4	Yes	No	Yes	No	Yes	
W	DAISY	LN		STATE	ST		FRANKLIN	DR	Concrete	3	Poor	3.50	0.40	4	4	Yes	No	Yes	No	Yes	
E	DAISY	LN		GRAYBROOK	LN		GRANT LINE	RD	Concrete	3	Poor	1.30	3.70	4	4	Yes	No	Yes	No	No	
E	DAISY	LN		ROSEVIEW	TER		GRANT LINE	RD	Concrete	3	Poor	4.60	2.10	4	4	Yes	No	Yes	No	No	
E	DAISY	LN		LYNN	RD		GRAYBROOK	LN	Concrete	3	Poor	3.40	1.30	4	4	Yes	No	Yes	No	Yes	
W	DAISY	LN		TRINITY RUN	CT		GREEN VALLEY	RD	Concrete	3	Poor	0.60	0.30	4	4	Yes	No	Yes	No	Yes	
W	DAISY	LN		COYLE	DR		GREEN VALLEY	RD	Concrete	3	Poor	1.10	0.70	4	4	Yes	No	Yes	No	Yes	
E	DAISY	LN		ZURSHMEIDE	DR		JACOBS	DR	Concrete	3	Poor	2.20	0.20	4	4	Yes	No	Yes	No	Yes	
E	DAISY	LN		GREEN VALLEY	RD		LYNN	RD	Concrete	3	Poor	4.60	2.10	4	4	Yes	No	Yes	No	No	
E	DAISY	LN		SHELL	LN		ROSEVIEW	TER	Concrete	3	Poor	2.90	1.90	4	4	Yes	No	Yes	Yes	Yes	
E	DAISY	LN		STOVER	DR		SHELL	LN	Concrete	3	Poor	3.30	1.20	4	4	Yes	No	Yes	No	Yes	
E	DAISY	LN		JACOBS	DR		STOVER	DR	Concrete	3	Poor	2.40	1.60	4	4	Yes	No	Yes	No	Yes	
W	DAISY	LN		HARRIS	CT		TRINITY RUN	CT	Concrete	3	Poor	1.20	0.30	4	4	Yes	No	Yes	No	Yes	
E	DAISY	LN		GREEN VALLEY	RD		ZURSCHMEIDE	DR	Concrete	3	Poor	3.70	1.20	4	4	Yes	No	Yes	No	Yes	
E	DAISY	LN		ROSEVIEW	TER		ROSEVIEW	TER	Concrete	2	Very Poor	0.70	0.80	4	4	Yes	Yes	Yes	No	Yes	
	DALE	CT		GREENDALE	DR		GREENDALE	DR	Concrete	TBD	Good	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	Yes	
	DEERWOOD	DR		CLIFFWOOD	DR		CASTLEWOOD	DR	Concrete	3	Poor	1.70	0.70	4	5	No		Yes	No	Yes	
	DEERWOOD	DR		PENNWOOD	DR		CLIFFWOOD	DR	Concrete	3	Poor	4.35	1.90	4	4	No		No		Yes	

Street Prefix	Street Name	Street Suffix	From Street Prefix	From Street Name	From Street Suffix	To Street Prefix	To Street Name	To Street Suffix	Surface Type	Condition	Condition Description	Max Long Slope (%)	Max Cross Slope (%)	Width Min (ft)	Width Max (ft)	Curb Ramp From St	Curb Ramp From St ADA	Curb Ramp To St	Curb Ramp To St ADA	ADA Compliant	Comments
	DEERWOOD	DR		PENNWOOD	DR		BRENTWOOD	CT	Concrete	2	Very Poor	0.60	3.10	4	5	Yes	Yes	No	No	No	
	DEERWOOD	DR		BRENTWOOD	CT		CASTLEWOOD	DR	Concrete	2	Very Poor	4.50	1.90	4	4	No		No		Yes	Patch of brick sidewalk
	DENNISON	AVE	W	LEWIS	ST		DEAD END		Concrete	2	Very Poor	5.65	4.25	4	6	No		No		No	
	DENNY	DR		PAMELA	DR		PAMELA	DR	Concrete	4	Fair	0.70	2.50	4	4	Yes	Yes	Yes	Yes	No	
	DENNY	DR		PAMELA	DR		LINDA	DR	Concrete	3	Poor	0.30	1.50	4	4	Yes	Yes	Yes	Yes	Yes	
	DENNY	DR		PAMELA	DR		LINDA	DR	Concrete	3	Poor	0.30	2.50	4	4	Yes	Yes	Yes	Yes	No	
	DEOBROOK	DR		DOEBROOK	CT		CREEKVIEW	CIR	Concrete	4	Fair	0.50	1.30	4	4	No		Yes	No	Yes	
	DEPAUW	AVE		VANCE	AVE		BEECHWOOD	AVE	Concrete	4	Fair	0.30	0.60	6	6	Yes	No	Yes	No	Yes	
	DEPAUW	AVE		DEPAUW	AVE		BURTON	AVE	Concrete	4	Fair	0.30	0.20	4	5	Yes	No	Yes	No	Yes	
	DEPAUW	AVE		VINCENNES	ST		VANCE	AVE	Concrete	4	Fair	0.80	0.60	6	6	Yes	No	Yes	Yes	Yes	
	DEPAUW	AVE		MYRTLE	AVE		BURTON	AVE	Concrete	3	Poor	2.50	0.90	4	5	Yes	No	Yes	No	Yes	
	DEPAUW	AVE		MYRTLE	AVE		DEPAUW	AVE	Concrete	3	Poor	0.80	0.10	4	8	Yes	No	Yes	No	Yes	
	DEPAUW	AVE		BEECHWOOD	AVE		MYRTLE	AVE	Concrete	3	Poor	0.50	1.20	4	6	Yes	No	Yes	No	Yes	
	DEPAUW	AVE		VINCENNES	ST		MYRTLE	AVE	Concrete	3	Poor	0.60	0.30	4	6	Yes	No	Yes	No	Yes	
	DEWEY	ST		DEAD END		E	16TH	ST	Concrete	3	Poor	0.20	9.60	3	4	No		Yes	No	No	
	DEWEY	ST	E	13TH	ST	E	14TH	ST	Concrete	1	PastServiceLife	0.70	1.90	4	4	No		No		Yes	
	DEWEY	ST	E	14TH	ST	E	16TH	ST	Brick	1	PastServiceLife	0.50	4.00	10	12	Yes	No	Yes	No	No	
	DEWEY	ST	E	16TH	ST		BUTLER	ST	Concrete	1	PastServiceLife	1.00	0.50	4	4	Yes	No	Yes	No	Yes	
	DEWEY	ST	E	16THH	ST		DEAD END		Concrete	5	Good	2.60	0.70	4	5	Yes	Yes	No		Yes	
	DIEHLMAN	DR		HORNUNG HILL	DR		DEAD END		Concrete	3	Poor	3.10	3.10	4	4	No		No		No	Partially brick sidewalk
	DIEHLMAN	DR		DEAD END			DEAD END		Concrete	3	Poor	3.10	0.70	4	4	No		No		Yes	
	DISCOVERY CT			DEAD END			CHARLESTOWN CROSSING WAY		Concrete	3	Poor	3.70	4.20	4	4	No		Yes	Yes	No	
	DIVISION	ST		GREEN	ST	E	18TH	ST	Concrete	5	Good	0.90	0.10	4	4	Yes	Yes	Yes	No	Yes	
	DOEBROOK	DR		FARMGATE	LN		CREEKVIEW	CIR	Concrete	4	Fair	0.60	2.40	4	4	Yes	No	Yes	No	No	
	DOEBROOK	DR		CREEKVIEW	CIR		DOEBROOK	CT	Concrete	4	Fair	1.30	1.30	4	4	Yes	No	No		Yes	
	DOEBROOK	CT		DOEBROOK	DR		DOEBROOK	DR	Concrete	4	Fair	0.50	1.70	4	4	No		No		Yes	
	DOEBROOK	DR		CREEKVIEW	CIR		FARMGATE	LN	Concrete	4	Fair	1.00	1.10	4	4	Yes	No	Yes	No	Yes	
	DRAWBROOK	CIR		BRETBROOK	DR		BENTBROOK	DR	Concrete	3	Poor	4.90	0.80	4	4	No		No		Yes	
	DRAWBROOK	CIR		BENTBOOK	DR		DEAD END		Concrete	3	Poor	4.60	0.90	4	4	No		No		Yes	
	DRAWBROOK	CIR		BENTBROOK	DR		DEAD END		Concrete	3	Poor	2.10	1.30	4	4	No		No		Yes	
	EAGLE	LN		EAGLE RIDGE	CT		DEAD END		Concrete	4	Fair	1.30	3.45	4	4	No		No		No	
	EAGLE RIDGE	CT		EAGLE	LN		EAGLE	LN	Concrete	4	Fair	5.05	3.30	4	4	No		No		No	
	EALY	ST		DENNISON	AVE		GRIFFIN	ST	Concrete	3	Poor	0.50	1.70	4	4	No		Yes	No	Yes	
	EALY	ST		WEST	ST		GRIFFIN	ST	Concrete	3	Poor	1.30	2.35	4	4	Yes	No	Yes	No	No	
	EALY	ST		HILDRETH	ST		STATE	ST	Concrete	3	Poor	5.20	1.55	4	4	Yes	No	Yes	No	Yes	
	EALY	ST		WEST	ST		CRYSTAL	AVE	Concrete	2	Very Poor	0.50	0.50	4	4	Yes	No	Yes	No	Yes	
	EALY	ST		CRYSTAL	AVE		DENNISON	AVE	Concrete	2	Very Poor	1.70	0.40	2	4	Yes	No	No	No	Yes	
	EALY	ST		GRIFFIN	ST		HILDRETH	ST	Concrete	2	Very Poor	2.85	0.40	1	4	Yes	No	Yes	No	Yes	
	EALY	ST		GRIFFIN	ST		HILDRETH	ST	Concrete	2	Very Poor	3.65	0.30	4	4	Yes	No	No		Yes	
	EALY	ST		HILDRETH	ST		STATE	ST	Concrete	2	Very Poor	4.60	1.70	4	4	Yes	No	Yes	No	Yes	Overall in good shape other than patch pictures
	EASTRIDGE	DR		KLERNER	LN		DEAD END		Concrete	4	Fair	1.50	1.50	4	5	Yes	No	Yes	No	Yes	
	EASTRIDGE	DR		DEAD END			DEAD END		Concrete	4	Fair	1.50	1.20	4	5	Yes	No	Yes	No	Yes	
	EDGEMONT	DR		CHADWOOD	DR		GREENVIEW	DR	Concrete	4	Fair	1.60	0.80	4	4	No		Yes	No	Yes	
	EDGEMONT	DR		CHADWOOD	DR		SPICKERT KNOB	RD	Concrete	3	Poor	1.20	1.00	4	4	No		Yes	No	Yes	Approx. 200 East of Thomas St is concrete sidewalk and rated 3
	EDGEMONT	DR		GREENVIEW	DR		SPICKERT KNOB	RD	Concrete	3	Poor	3.20	2.90	4	4	Yes	No	No		No	
	EDGEWOOD STATION	RD		DEAD END			KNOW VIEW	AVE	Concrete	4	Fair	3.70	2.60	4	4	No		No		No	
	EKIN	AVE		MCDONALD	AVE		SLATE RUN	RD	Concrete	5	Good	0.30	1.55	4	4	No		No		Yes	
	EKIN	AVE		JAY	ST		SILVER	ST	Concrete	4	Fair	3.45	6.25	5	5	No		Yes	No	No	
	EKIN	AVE		JAY	ST		SILVER	ST	Concrete	4	Fair	1.00	4.45	8	8	Yes	Yes	Yes	No	No	
	EKIN	AVE	E	11TH	ST	E	13TH	ST	Concrete	3	Poor	4.60	1.30	4	5	Yes	No	Yes	No	Yes	
	EKIN	AVE	E	13TH	ST	E	15TH	ST	Concrete	3	Poor	2.05	1.70	5	5	Yes	No	Yes	No	Yes	
	EKIN	AVE		CATHERINE	PL	E	15TH	ST	Concrete	3	Poor	1.30	2.05	6	6	Yes	No	Yes	No	No	
	EKIN	AVE		CEDAR BOUGH	PL		CATHERINE	PL	Concrete	3	Poor	1.45	1.90	4	4	Yes	No	Yes	No	Yes	
	EKIN	AVE	E	11TH	ST		CEDAR BOUGH	PL	Concrete	3	Poor	3.30	2.10	4	5	Yes	No	Yes	No	No	
	EKIN	AVE		THOMAS	AVE		JAY	ST	Concrete	3	Poor	0.15	2.95	5	5	Yes	No	No		No	
	EKIN	AVE		INDIANA	AVE		MCDONALD	AVE	Concrete	3	Poor	1.10	2.40	4	4	No		Yes	No	No	
	EKIN	AVE		VINCENNES	ST		THOMAS	AVE	Concrete	3	Poor	1.35	1.90	6	6	Yes	No	Yes	Yes	Yes	
	EKIN	AVE	E	15TH	ST		VINCENNES	ST	Concrete	3	Poor	1.10	1.45	4	5	Yes	No	Yes	No	Yes	
	EKIN	AVE		SILVER	ST		INDIANA	AVE	Concrete	2	Very Poor	1.70	1.45	4	4	Yes	No	Yes	No	Yes	
	EKIN	AVE		SILVER	ST		INDIANA	AVE	Concrete	2	Very Poor	0.15	2.00	4	4	Yes	No	Yes	No	Yes	
	EKIN	AVE		INDIANA	AVE		MCDONALD	AVE	Concrete	2	Very Poor	2.00	1.30	4	4	No		Yes	No	Yes	Part between Green St and Alley is new
	EKIN	AVE	E	15TH	ST		VINCENNES	ST	Concrete	2	Very Poor	1.55	1.30	4	5	Yes	No	Yes	No	Yes	
	EKIN	AVE		THOMAS	AVE		JAY	ST	Brick	1	PastServiceLife	1.35	3.45	4	5	Yes	No	Yes	No	No	
	EKIN	AVE		VINCENNES	ST		THOMAS	AVE	Concrete	1	PastServiceLife	2.05	2.60	6	6	Yes	No	Yes	No	No	
	ELHANAN	CT		CLARA LEE	CT		CLARA LEE	CT	Concrete	5	Good	0.90	1.70	4	4	No		No		Yes	
	ELLEN	CT		DEAD END			GREEN VALLEY	RD	Concrete	4	Fair	1.00	2.35	4	4	No		No		No	
	ELLEN	CT		DEAD END			GREEN VALLEY	RD	Concrete	4	Fair	1.55	1.55	4	4	Yes	No	No		Yes	
E	ELM	ST		VINCENNES	ST	E	18TH	ST	Concrete	5	Good	0.60	1.20	4	5	Yes	No	Yes	No	Yes	
E	ELM	ST	E	4TH	ST	E	5TH	ST	Concrete	5	Good	4.35	1.20	5	5	Yes	No	Yes	No	Yes	
E	ELM	ST		THOMAS	AVE		JAY	ST	Concrete	5	Good	1.00	0.75	4	5	Yes	No	Yes	Yes	Yes	
E	ELM	ST		JAY	ST		SILVER	ST	Concrete	5	Good	0.50	1.35	5	5	Yes	No	Yes	Yes	Yes	
E	ELM	ST		JAY	ST		SILVER	ST	Concrete	5	Good	0.85	1.30	5	5	Yes	Yes	Yes	Yes	Yes	
E	ELM	ST	E	18TH	ST		THOMAS	AVE	Concrete	5	Good	0.75	1.70	4	5	Yes	Yes	Yes	No	Yes	
E	ELM	ST	E	18TH	ST		THOMAS	AVE	Concrete	5	Good	0.60	0.50	4	5	Yes	Yes	Yes	No	Yes	
E	ELM	ST	E	9TH	ST	E	10TH	ST	Concrete	4	Fair	1.65	1.65	3	5	Yes	No	Yes	No	Yes	
E	ELM	ST	E	10TH	ST	E	11TH	ST	Concrete	4	Fair	0.15	2.05	4	6	Yes	No	Yes	No	No	
E	ELM	ST	E	11TH	ST	E	13TH	ST	Concrete	4	Fair	0.65	3.10	4	5	Yes	No	Yes	No	No	
E	ELM	ST	E	11TH	ST	E	13TH	ST	Concrete	4	Fair	1.20	2.75	4	5	Yes	No	Yes	No	No	
E	ELM	ST	E	13TH	ST	E	15TH	ST	Concrete	4	Fair	0.50	2.15	4	5	Yes	No	Yes	No	No	
E	ELM	ST		VINCENNES	ST	E	18TH	ST	Concrete	4	Fair	0.40	2.25	4	5	Yes	No	Yes	No	No	
E	ELM	ST	E	3RD	ST	E	4TH	ST	Concrete	4	Fair	2.05	1.45	4	6	Yes	No	Yes	No	Yes	

Street Prefix	Street Name	Street Suffix	From Street Prefix	From Street Name	From Street Suffix	To Street Prefix	To Street Name	To Street Suffix	Surface Type	Condition	Condition Description	Max Long Slope (%)	Max Cross Slope (%)	Width Min (ft)	Width Max (ft)	Curb Ramp From St	Curb Ramp From St ADA	Curb Ramp To St	Curb Ramp To St ADA	ADA Compliant	Comments
E	ELM	ST		PEARL	ST		BANK	ST	Concrete	4	Fair	2.00	1.80	8	14	Yes	Yes	Yes	No	Yes	
E	ELM	ST		PEARL	ST		BANK	ST	Concrete	4	Fair	0.30	1.00	5	8	Yes	No	Yes	No	Yes	
E	ELM	ST		THOMAS	AVE		JAY	ST	Concrete	4	Fair	0.50	3.55	4	5	Yes	No	Yes	Yes	No	
E	ELM	ST	E	15TH	ST		VINCENNES	ST	Concrete	4	Fair	0.15	1.00	4	5	Yes	No	Yes	No	Yes	
E	ELM	ST	E	15TH	ST		VINCENNES	ST	Concrete	4	Fair	3.40	4.25	4	5	Yes	No	Yes	No	No	
E	ELM	ST	E	9TH	ST	E	10TH	ST	Concrete	3	Poor	0.30	4.45	4	5	Yes	No	Yes	No	No	
E	ELM	ST	E	10TH	ST	E	11TH	ST	Concrete	3	Poor	1.10	2.60	4	8	Yes	No	Yes	No	No	
E	ELM	ST	E	13TH	ST	E	15TH	ST	Concrete	3	Poor	0.40	3.55	4	8	Yes	No	Yes	No	No	
W	ELM	ST		SCRIBNER	DR	W	1ST	ST	Concrete	3	Poor	6.10	4.80	4	8	Yes	No	Yes	No	No	
W	ELM	ST		SCRIBNER	DR	W	1ST	ST	Concrete	3	Poor	1.30	5.55	4	5	Yes	No	Yes	Yes	No	
E	ELM	ST		BANK	ST	E	3RD	ST	Concrete	3	Poor	1.90	3.05	5	8	Yes	No	Yes	No	No	
E	ELM	ST	E	3RD	ST	E	4TH	ST	Concrete	3	Poor	1.90	2.75	5	6	Yes	No	Yes	No	No	
E	ELM	ST	E	4TH	ST	E	5TH	ST	Concrete	3	Poor	1.90	2.50	5	6	Yes	No	Yes	No	No	
E	ELM	ST	E	5TH	ST	E	6TH	ST	Concrete	3	Poor	3.40	4.10	4	5	Yes	No	Yes	No	No	
E	ELM	ST	E	5TH	ST	E	7TH	ST	Concrete	3	Poor	6.25	3.75	4	5	Yes	No	Yes	No	No	
E	ELM	ST	E	6TH	ST	E	7TH	ST	Concrete	3	Poor	0.75	4.15	4	5	Yes	No	Yes	No	No	
E	ELM	ST	E	7TH	ST	E	8TH	ST	Concrete	3	Poor	2.25	3.80	4	5	Yes	No	Yes	No	No	
E	ELM	ST	E	7TH	ST	E	8TH	ST	Concrete	3	Poor	2.35	3.20	8	10	Yes	No	Yes	No	No	
E	ELM	ST	E	8TH	ST	E	9TH	ST	Concrete	3	Poor	0.15	1.20	3	5	Yes	No	Yes	No	Yes	
E	ELM	ST	E	8TH	ST	E	9TH	ST	Concrete	3	Poor	4.95	6.25	5	10	Yes	Yes	Yes	No	No	
E	ELM	ST		WOODROW	AVE		BEHARRELL	AVE	Concrete	3	Poor	0.75	1.90	4	5	No		Yes	Yes	Yes	No
W	ELM	ST	W	1ST	ST		STATE	ST	Concrete	3	Poor	4.10	1.30	4	10	Yes	No	Yes	No	Yes	
W	ELM	ST	W	1ST	ST		STATE	ST	Concrete	3	Poor	2.85	5.20	5	7	Yes	No	Yes	No	No	
E	ELM	ST		WOODROW	AVE		TERRACE	CT	Concrete	3	Poor	1.55	1.10	4	5	No		No		Yes	
E	ELM	ST		BANK	ST	E	3RD	ST	Concrete	2	Very Poor	2.70	0.75	4	5	Yes	No	Yes	No	Yes	
E	ELM	ST		SILVER	ST		INDIANA	AVE	Concrete	2	Very Poor	0.25	1.10	4	4	Yes	No	No		Yes	
E	ELM	ST		STATE	ST		PEARL	ST	Concrete	2	Very Poor	1.45	1.00	6	9	Yes	No	Yes	No	Yes	
E	ELM	ST		STATE	ST		PEARL	ST	Concrete	2	Very Poor	1.55	3.75	6	8	Yes	Yes	Yes	No	No	
E	ELM	ST		INDIANA	AVE		WOODROW	AVE	Concrete	2	Very Poor	0.15	5.20	4	5	No		No		No	
E	ELM	ST		SILVER	ST		WOODROW	AVE	Concrete	2	Very Poor	0.40	1.20	4	4	Yes	No	No		Yes	
E	ELM	ST		TERRACE	CT		BEHARRELL	AVE	Concrete	1	PastServiceLife	0.65	4.35	4	5	Yes	No	Yes	Yes	No	
	ERNI	AVE		BONO	AVE		BONNIE SLOAN	DR	Concrete	3	Poor	2.20	3.10	4	4	Yes	No	No		No	
	ERNI	AVE		MORGAN	AVE		BONNIE SLOAN	DR	Concrete	3	Poor	0.10	2.70	4	4	No		Yes	No	No	
	ERNI	AVE		BONO	RD		CARDINAL	DR	Concrete	3	Poor	0.30	2.50	4	4	Yes	No	Yes	No	No	
	ERNI	AVE		CARDINAL	DR		MORGAN	AVE	Concrete	3	Poor	3.30	1.70	4	4	No		No		Yes	
	FAIRWAY	CT		COUNTRY CLUB	DR		COUNTRY CLUB	DR	Concrete	3	Poor	3.50	0.90	4	4	Yes	No	Yes	No	Yes	
	FALL RUN	CT		HICKORYVALE	DR		HICKORYVALE	DR	Concrete	4	Fair	2.80	2.60	4	4	Yes	No	Yes	No	No	
	FARMGATE	LN		PLAINFIELD	DR		KLERNER	LN	Concrete	4	Fair	1.40	1.50	4	4	Yes	No	Yes	No	Yes	
	FARMGATE	LN		DOEBROOK	DR		WOODFIELD	DR	Concrete	4	Fair	0.40	0.60	4	4	Yes	No	Yes	No	Yes	
	FARMGATE	LN		DOEBROOK	DR		WOODFIELD	DR	Concrete	4	Fair	0.80	1.40	4	4	Yes	No	Yes	No	Yes	
	FARMGATE	LN		WOODFIELD	DR		KLERNER	LN	Concrete	3	Poor	1.70	2.10	4	4	Yes	No	Yes	No	No	
	FARMGATE	LN		WOODFIELD	DR		MEADOWVIEW	DR	Concrete	3	Poor	0.50	0.40	4	4	Yes	No	Yes	No	Yes	
	FARMGATE	LN		MEADOWVIEW	DR		PLAINFIELD	DR	Concrete	3	Poor	2.30	2.10	4	4	Yes	No	Yes	No	No	
	FARRINGTON	DR		GREENVIEW	DR		ASHLEY	CT	Concrete	4	Fair	0.50	1.50	4	4	Yes	No	No		Yes	
	FARRINGTON	DR		GREENVIEW	DR		JAFFERY	DR	Concrete	4	Fair	3.20	0.60	4	4	Yes	No	Yes	No	Yes	
	FARRINGTON	DR		ASHLEY	CT		GREEN VALLEY	RD	Concrete	3	Poor	0.90	1.20	4	4	No		Yes	No	Yes	
	FARRINGTON	DR		JAFFERY	DR		GREEN VALLEY	RD	Concrete	3	Poor	1.20	1.10	4	4	Yes	No	Yes	No	Yes	
	FIELDSTONE	CT		GREEN VALLEY	RD		GREEN VALLEY	RD	Concrete	3	Poor	4.00	6.70	4	4	No		No		No	
	FLORENCE	AVE		VINCENNES	ST		VANCE	AVE	Concrete	2	Very Poor	0.70	1.40	4	4	Yes	No	Yes	No	Yes	
	FLORENCE	AVE		VINCENNES	ST		VANCE	AVE	Concrete	1	PastServiceLife	2.30	8.70	4	4	Yes	No	Yes	No	No	
	GALT	ST		STONE	ST	E	MAIN	ST	Concrete	4	Fair	3.30	3.50	4	4	Yes	Yes	Yes	Yes	No	
	GALT	ST		STONE	ST	E	MAIN	ST	Concrete	3	Poor	2.60	2.60	4	4	Yes	No	Yes	Yes	No	
	GALT	ST		DEAD END		E	MARKET	ST	Concrete	3	Poor	1.00	1.70	4	5	No		Yes	Yes	Yes	
	GALT	ST		DEAD END		E	MARKET	ST	Concrete	3	Poor	0.80	0.80	4	4	No		Yes	Yes	Yes	
	GALT	ST	E	MAIN	ST		DEWEY	ST	Concrete	2	Very Poor	2.10	2.70	4	4	Yes	No	No		No	
	GALT	ST	E	MAIN	ST		DEWEY	ST	Concrete	2	Very Poor	1.40	3.00	4	4	Yes	No	No		No	
	GALT	ST	E	MARKET	ST		STONE	ST	Concrete	2	Very Poor	1.30	1.40	4	4	Yes	Yes	Yes	Yes	Yes	
	GALT	ST	E	MARKET	ST		STONE	ST	Concrete	2	Very Poor	0.40	3.50	4	4	Yes	Yes	Yes	No	No	
	GARRETSON	LN		HOOVER	AVE		SLATE RUN	RD	Concrete	5	Good	1.70	1.20	4	4	No		No		Yes	
	GARRETSON	LN		ALICE	AVE		HOOVER	AVE	Concrete	3	Poor	0.90	2.00	4	4	No		No		Yes	
	GARRETSON	LN		CHARLESTOWN	RD		SLATE RUN	RD	Concrete	2	Very Poor	2.30	0.50	3	4	No		No		Yes	
	GORDON	DR		PAMELA	DR		LINDA	DR	Concrete	3	Poor	0.20	1.10	4	4	Yes	Yes	No		Yes	
	GORDON	DR		DEAD END			LINDA	DR	Concrete	2	Very Poor	0.90	0.80	4	4	No		No		Yes	
	GORDON	DR		DEAD END			PAMELA	DR	Concrete	2	Very Poor	1.00	0.20	4	4	No		Yes	Yes	Yes	
	GRABLE	CT		MILLER	LN		MILLER	LN	Concrete	3	Poor	0.90	2.30	4	4	No		No		No	
	GRANT	ST	E	14TH	ST	E	15TH	ST	Concrete	2	Very Poor	1.40	2.80	4	4	Yes	No	Yes	No	No	
	GRANT	ST	E	14TH	ST	E	15TH	ST	Concrete	1	PastServiceLife	1.60	1.90	4	4	Yes	No	Yes	No	Yes	
	GRANT LINE	RD		SLEEPY	LN		CHEROKEE	ST	Concrete	4	Fair	3.00	0.70	8	8	Yes	No	Yes	No	Yes	
	GRANT LINE	RD		ELMWOOD	AVE		JOLLISAIN	AVE	Concrete	4	Fair	0.10	0.80	4	4	Yes	No	Yes	No	Yes	
	GRANT LINE	RD		UNIVERSITY WOODS	DR		PLAZA	DR	Concrete	4	Fair	0.90	0.10	4	4	Yes	No	Yes	No	Yes	
	GRANT LINE	RD		JACQUES	LN		SLEEPY	LN	Concrete	4	Fair	3.90	0.50	8	8	Yes	No	Yes	No	Yes	
	GRANT LINE	RD		LOGAN	ST		SOUTH	ST	Concrete	3	Poor	0.20	1.90	4	5	No		Yes	No	Yes	
	GRANT LINE	RD		SOUTH	ST		VINCENNES	ST	Concrete	3	Poor	0.40	1.00	4	5	Yes	No	Yes	No	Yes	
	GRANT LINE	RD		DEAD END			DEAD END		Concrete	3	Poor	0.30	1.50	4	5	No		No		Yes	
	GRANT LINE	RD		NAVAJO	DR		KNOB HILL	RD	Concrete	5	Good	0.40	0.30	8	8	Yes	No	Yes	Yes	Yes	
	GRANT LINE	RD		KNOB HILL	RD		NELSON	AVE	Concrete	5	Good	0.10	0.70	8	8	Yes	Yes	Yes	Yes	Yes	
	GRANT LINE	RD		JOLLISAIN	AVE		BEECHWOOD	AVE	Concrete	4	Fair	1.20	1.60	4	4	Yes	No	Yes	No	Yes	
	GRANT LINE	RD		NELSON	AVE	E	DAISY	LN	Concrete	4	Fair	0.90	0.90	4	8	Yes	Yes	Yes	No	Yes	
	GRANT LINE	RD		MC DONALD	LN		ELMWOOD	AVE	Concrete	4	Fair	7.00	1.00	4	4	Yes	No	Yes	No	Yes	
	GRANT LINE	RD		ROLLING CREEK	DR		JACQUES	LN	Concrete	4	Fair	0.40	0.40	6	6	Yes	No	Yes	No	Yes	
	GRANT LINE	RD		PLAZA	DR		MC DONALD	LN	Concrete	4	Fair	2.30	0.90	4	4	Yes	No	Yes	No	Yes	

Street Prefix	Street Name	Street Suffix	From Street Prefix	From Street Name	From Street Suffix	To Street Prefix	To Street Name	To Street Suffix	Surface Type	Condition	Condition Description	Max Long Slope (%)	Max Cross Slope (%)	Width Min (ft)	Width Max (ft)	Curb Ramp From St	Curb Ramp From St ADA	Curb Ramp To St	Curb Ramp To St ADA	ADA Compliant	Comments
	GRANT LINE	RD		CHEROKEE	DR		NAVAJO	DR	Concrete	4	Fair	2.50	1.30	8	8	Yes	No	Yes	No	Yes	
	GRANT LINE	RD		MT TABOR	RD		PILLSBURY	LN	Concrete	4	Fair	0.90	0.40	6	6	Yes	No	Yes	No	Yes	
	GRANT LINE	RD		PILLSBURY	LN		ROLLING CREEK	DR	Concrete	4	Fair	0.60	1.20	6	6	Yes	No	Yes	No	Yes	
	GRANT LINE	RD		MT TABOR	RD		UNIVERSITY WOODS	DR	Concrete	4	Fair	2.10	0.20	4	4	Yes	No	Yes	No	Yes	
	GRANT LINE	RD		BEECHWOOD	AVE		DEAD END		Concrete	4	Fair	1.40	0.80	4	4	Yes	No	No		Yes	
	GRAYBROOK	LN		WOLFE	TRCE		COUNTRY CLUB	DR	Concrete	3	Poor	3.10	0.30	4	5	Yes	Yes	Yes	No	Yes	
	GRAYBROOK	LN		COUNTRY CLUB	DR		MORGAN	AVE	Concrete	3	Poor	2.40	7.10	4	4	Yes	No	Yes	No	No	
	GRAYBROOK	LN	E	DAISY	LN		WOLFE	TRCE	Concrete	3	Poor	1.30	1.00	4	4	Yes	No	Yes	Yes	Yes	
	GRAYBROOK	LN		BONO	RD		MINTON	DR	Concrete	2	Very Poor	0.50	1.50	4	4	Yes	No	Yes	No	Yes	
	GRAYBROOK	LN		WOODLAND	DR		MINTON	DR	Concrete	2	Very Poor	1.10	2.40	4	4	Yes	No	Yes	No	No	
	GRAYBROOK	LN		MORGAN	AVE		WOODLAND	DR	Concrete	2	Very Poor	2.20	1.20	4	4	Yes	No	Yes	No	Yes	
	GREEN	ST		VINE	ST		BONO	RD	Concrete	4	Fair	0.30	0.70	4	5	Yes	No	Yes	No	Yes	
	GREEN	ST		STATE	ST		VINE	ST	Concrete	4	Fair	0.60	0.10	4	5	Yes	No	Yes	No	Yes	
	GREEN	ST		STATE	ST		VINE	ST	Concrete	4	Fair	1.20	1.50	4	5	Yes	No	Yes	No	Yes	
	GREEN	ST		DIVISION	ST		CONSERVATIVE	ST	Concrete	3	Poor	0.50	1.60	4	4	Yes	Yes	Yes	Yes	Yes	
	GREEN	ST		VINE	ST		BONO	RD	Concrete	4	Fair	1.70	0.70	4	5	Yes	No	Yes	No	Yes	
	GREEN VALLEY	RD		GENVIEW	HTS		ALYSON	CT	Concrete	4	Fair	2.10	0.30	4	4	Yes	Yes	Yes	No	Yes	
	GREEN VALLEY	RD		ROYAL	CT		CROWN	CT	Concrete	4	Fair	0.20	1.30	4	4	Yes	No	Yes	No	Yes	
	GREEN VALLEY	RD	W	DAISY	LN		ELLEN	CT	Concrete	4	Fair	0.60	0.70	4	5	Yes	No	Yes	No	Yes	
	GREEN VALLEY	RD		MILLS	LN		FIELDSTONE	CT	Concrete	4	Fair	0.20	1.20	4	4	Yes	No	Yes	No	Yes	
	GREEN VALLEY	RD		WELLINGTON	DR		GLENMILL	RD	Concrete	4	Fair	1.70	1.20	4	4	Yes	No	Yes	Yes	Yes	
	GREEN VALLEY	RD		ALYSON	CT		GREENBRIAR	DR	Concrete	4	Fair	0.50	0.80	4	4	Yes	No	Yes	No	Yes	
	GREEN VALLEY	RD		HOLY TRINITY	CEM		HOLY TRINITY	CEM	Concrete	4	Fair	0.30	0.90	4	5	No		Yes	No	Yes	
	GREEN VALLEY	RD		CROWN	CT		MILLS	LN	Concrete	4	Fair	0.40	2.90	4	4	Yes	No	Yes	No	No	
	GREEN VALLEY	RD		GLENMILL	RD		ROYAL	CT	Concrete	4	Fair	2.50	0.90	4	4	Yes	Yes	Yes	No	Yes	
	GREEN VALLEY	DR		4-H	LN		4-H	RD	Concrete	3	Poor	0.20	0.90	4	4	No		No		Yes	
	GREEN VALLEY	RD		GREENLAWN	DR		4-H	LN	Concrete	3	Poor	1.60	1.10	4	4	Yes	No	No		Yes	
	GREEN VALLEY	RD		WATKINS PRAIRIE	LN		BALDWIN	DR	Concrete	3	Poor	2.80	0.80	4	4	Yes	No	Yes	No	Yes	
	GREEN VALLEY	RD		GORDON	DR	N	BOHANNON	LN	Concrete	3	Poor	1.90	2.30	4	4	Yes	No	Yes	No	No	Curb is rated 2 rest of sidewalk is 5
	GREEN VALLEY	RD		FENWICK	DR		BONO	RD	Concrete	3	Poor	1.30	1.00	4	5	Yes	No	Yes	No	Yes	
	GREEN VALLEY	RD		FIELDSTONE	CT		GLENVIEW	HTS	Concrete	3	Poor	0.50	1.10	4	4	Yes	No	Yes	Yes	Yes	
	GREEN VALLEY	RD		BALDWIN	DR		GREENDALE	DR	Concrete	3	Poor	1.40	1.00	4	4	Yes	No	Yes	No	Yes	
	GREEN VALLEY	RD		HOLY TRINITY	CEM		HOLY TRINITY	CEM	Concrete	3	Poor	2.00	2.70	4	4	No		No		No	
	GREEN VALLEY	RD		MT TABOR	RD		WATKINS PRAIRIE	LN	Concrete	3	Poor	0.30	0.10	4	4	Yes	No	Yes	No	Yes	
	GREEN VALLEY	RD		FARRINGTON	DR		WELLINGTON	DR	Concrete	3	Poor	1.50	4.80	4	4	Yes	Yes	Yes	No	No	
	GREEN VALLEY	RD		MARTIN	DR		STATE	ST	Concrete	5	Good	1.40	0.80	4	6	Yes	No	Yes	No	Yes	
	GREEN VALLEY	RD	S	BOHANNON	LN	E	DAISY	LN	Concrete	4	Fair	1.50	1.70	4	5	Yes	No	Yes	No	Yes	
	GREEN VALLEY	RD	E	DAISY	LN		FENWICK	DR	Concrete	4	Fair	1.10	2.80	4	5	Yes	No	Yes	No	No	
	GREEN VALLEY	RD		4-H	RD		GORDON	DR	Concrete	4	Fair	1.60	0.90	4	4	No		Yes	No	Yes	
	GREEN VALLEY	DR		ELLEN	CT		KNABLE	LN	Concrete	4	Fair	0.40	0.80	4	5	Yes	No	Yes	No	Yes	
	GREEN VALLEY	RD	N	BOHANNON	LN	S	BOHANNON	LN	Concrete	3	Poor	1.50	1.90	3	4	Yes	No	Yes	No	Yes	
	GREEN VALLEY	RD		HOLY TRINITY	CEM	W	DAISY	LN	Concrete	3	Poor	1.20	0.60	4	5	No		Yes	No	Yes	
	GREEN VALLEY	RD		MT TABOR	RD		FARRINGTON	DR	Concrete	3	Poor	1.90	1.30	4	4	No		Yes	No	Yes	
	GREEN VALLEY	RD		GREENDALE	DR		GREENLAWN	DR	Concrete	3	Poor	0.10	0.20	4	4	Yes	No	Yes	No	Yes	
	GREEN VALLEY	RD		GREENBRIAR	DR		HOLY TRINITY	CEM	Concrete	3	Poor	0.20	2.40	4	4	Yes	No	No		No	
	GREEN VALLEY	RD		BONO	RD		MARTIN	DR	Concrete	3	Poor	0.50	3.70	4	5	Yes	No	Yes	No	No	
	GREENDALE	DR		GREEN VALLEY	RD		DALE	CT	Concrete	TBD	Good	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	Yes	
	GREENDALE	DR		DALE	CT		GREENLAWN	DR	Concrete	TBD	Good	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	Yes	
	GREENDALE	DR		GREENLAWN	DR		GREENLAWN	DR	Concrete	TBD	Good	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	Yes	
	GREENDALE	DR		GREEN VALLEY	RD		LAWN	CT	Concrete	TBD	Good	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	Yes	
	GREENLAWN	DR		GREEN VALLEY	RD		LINDA	DR	Concrete	3	Poor	1.20	2.50	4	4	Yes	No	Yes	No	No	
	GREENLAWN	DR		GREENDALE	DR		LINDA	DR	Concrete	3	Poor	0.70	1.00	4	4	Yes	No	Yes	No	Yes	
	GREENLAWN	DR		GREEN VALLEY	RD		GREENDALE	DR	Concrete	2	Very Poor	1.70	2.20	4	4	Yes	No	Yes	No	No	
	GREENVIEW	DR		WELLINGTON	DR		EDGE MONT	DR	Concrete	4	Fair	2.20	0.90	4	4	Yes	Yes	Yes	No	Yes	
	GREENVIEW	DR		WELLINGTON	DR		FARRINGTON	DR	Concrete	3	Poor	0.50	2.50	4	4	Yes	No	Yes	No	No	
	GREENVIEW	DR		EDGE MONT	DR		JAFFERY	DR	Concrete	3	Poor	3.80	2.90	4	4	Yes	No	Yes	No	No	
	GREENVIEW	DR		FARRINGTON	DR		JAFFERY	DR	Concrete	3	Poor	4.80	2.60	4	4	Yes	No	Yes	No	No	
	GREENWAY	PL	E	11TH	ST		DEAD END		Concrete	1	PastServiceLife	1.65	10.30	4	4	Yes	No	No		No	
	GREENWAY	PL	E	11TH	ST		DEAD END		Concrete	1	PastServiceLife	0.15	3.50	4	4	Yes	No	No		No	
	GREENWOOD	CT		OAKWOOD	CT		DEAD END		Concrete	3	Poor	0.70	1.80	2	4	No		No		Yes	
	GRIFFIN	ST		EALY	ST		JACKSON	ST	Concrete	TBD	Good	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	Yes	
	GRIFFIN	ST		JACKSON	ST		DEAD END		Concrete	TBD	Good	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	Yes	
	GRIFFIN	ST		DEAD END			DEAD END		Concrete	TBD	Good	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	Yes	
	GRIFFIN	ST		DEAD END			EALY	ST	Concrete	3	Poor					No		Yes	No	Yes	
	HARBROOK	CT		MURR	LN		MURR	LN	Concrete	4	Fair	2.30	0.30	4	4	No		No		Yes	
	HARBROOK	DR		MURR	LN		WOODBOURNE	DR	Concrete	3	Poor	1.00	0.50	4	4	No		Yes	Yes	Yes	
	HARBROOK	DR		MURR	LN		WOODBOURNE	DR	Concrete	3	Poor	4.40	3.80	4	4	No		Yes	Yes	No	
	HARRIET	CT		SLATE RUN	RD		SLATE RUN	RD	Concrete	2	Very Poor	0.80	6.60	4	4	No		No		No	
	HAUSFELDT	LN		PARKEAST	BLVD		SOUTHERN	DR	Concrete	4	Fair	3.20	0.30	4	4	Yes	No	Yes	No	Yes	
	HAUSFELDT	LN		EARNINGS	WAY		CITY LIMITS		Concrete	3	Poor	0.90	2.40	4	4	Yes	No	No		No	
	HAUSFELDT	LN		GREEN VALLEY	RD		EARNINGS	WAY	Concrete	3	Poor	4.50	2.50	4	4	Yes	No	Yes	No	No	
	HAUSFELDT	LN		HAUSFELDT	LN		DEAD END		Concrete	3	Poor	0.40	0.10	4	4	No		No		Yes	
	HAUSFELDT	LN		SOUTHERN	DR		GRANT LINE	RD	Concrete	2	Very Poor	0.10	0.90	4	4	Yes	No	Yes	No	Yes	
	HAUSFELDT	LN		REAS	LN		PARKEAST	BLVD	Concrete	3	Poor	0.40	1.20	4	4	Yes	No	Yes	No	Yes	
	HAUSFELDT	LN		CITY	LIMITS		REAS	LN	Concrete	3	Poor	2.30	0.80	4	4	No		Yes	No	Yes	
	HAZELWOOD	AVE		LOCUST	ST		BEELER	ST	Concrete	4	Fair	0.10	0.60	6	6	Yes	No	Yes	No	Yes	
	HAZELWOOD	AVE		LINDBERG	CT		BEELER	ST	Concrete	3	Poor	0.60	0.60	4	4	Yes	No	Yes	No	Yes	
	HAZELWOOD	AVE		LOCUST	ST		LINDBERG	CT	Concrete	3	Poor	0.10	0.20	4	4	Yes	No	Yes	No	Yes	
	HICKORYVALE	DR		SCOTT	RD		OLD HICKORY	CT	Concrete	4	Fair	1.20	0.70	4	4	No		Yes	No	Yes	
	HICKORYVALE	DR		MCDONALD	DR		DEAD END		Concrete	4	Fair	3.80	1.50	4	4	No		No		Yes	
	HICKORYVALE	DR		FALL RUN	CT		ASPEN	CT	Concrete	3	Poor	2.60	1.50	4	4	Yes	No	Yes	No	Yes	

Street Prefix	Street Name	Street Suffix	From Street Prefix	From Street Name	From Street Suffix	To Street Prefix	To Street Name	To Street Suffix	Surface Type	Condition	Condition Description	Max Long Slope (%)	Max Cross Slope (%)	Width Min (ft)	Width Max (ft)	Curb Ramp From St	Curb Ramp From St ADA	Curb Ramp To St	Curb Ramp To St ADA	ADA Compliant	Comments
	HICKORYVALE	DR		VALE	CT		FALL RUN	CT	Concrete	3	Poor	0.20	0.10	4	4	Yes	No	Yes	No	Yes	
	HICKORYVALE	DR		OLD HICKORY	CT		VALE	CT	Concrete	3	Poor	0.90	0.20	4	4	Yes	No	Yes	No	Yes	
	HICKORYVALE	DR		ASPEN	CT		DEAD END		Concrete	3	Poor	0.60	0.60	4	4	Yes	No	No		Yes	
	HICKORYVALE	DR		MCDONALD	LN		DEAD END		Concrete	3	Poor	0.80	1.90	4	4	Yes	No	No		Yes	
	HIGH PARK	DR		DEAD END			PARKLINE	DR	Concrete	5	Good	3.10	0.90	4	4			Yes	Yes	Yes	
	HIGHLAND	AVE		DEAD END			MAIN STREET HILL	RD	Stone	4	Fair	4.40	4.15	4	4	No		No		No	
	HIGHLAND	AVE		ALLY			RIDGEWAY	AVE	Concrete	4	Fair	2.75	1.20	4	4	No		No		Yes	
	HIGHLAND	AVE		RIDGEWAY	AVE		DENT	AVE	Concrete	3	Poor	3.30	0.05	3	4	No		No		Yes	
	HIGHLAND	AVE		MAIN STREET HILL	RD		DEAD END		Concrete	3	Poor	2.35	3.20	4	4	Yes	No	No		No	
	HILDRETH	ST		JACKSON	ST		CHERRY	ST	Concrete	2	Very Poor	2.60	2.50	4	4	Yes	No	Yes	No	No	
	HILDRETH	ST		EALY	ST		JACKSON	ST	Concrete	2	Very Poor	4.45	3.90	4	4	Yes	No			Yes	
	HOFFMAN	DR		HOLLARY	DR		HOFFMAN	DR	Concrete	4	Fair	2.90	4.50	4	4	No		No		No	
	HOFFMAN	DR		HOFFMAN	DR		HOLLARY	DR	Concrete	4	Fair	2.80	2.40	4	4	No		No		No	
	HOLLARY	DR		HORNUNG HILL	DR		HOFFMAN	DR	Concrete	3	Poor	1.70	5.40	4	4	Yes	No	No		No	
	HORNUNG HILL	DR		COUNTRY CLUB	DR		DIELMAN	DR	Concrete	3	Poor	4.50	4.00	4	4	Yes	No	No		No	
	HORNUNG HILL	DR		COUNTRY CLUB	DR		DEAD END		Concrete	3	Poor	4.40	2.70	4	4	Yes	No	No		No	
	HORNUNG HILL	DR		DEAD END			DEAD END		Concrete	3	Poor	5.30	2.50	4	4	No		Yes	No	No	
	HORNUNG HILL	DR		DEAD END			HOLLARY	DR	Concrete	1	PastServiceLife	6.80	2.10	4	4	No		Yes	No	No	
	INDIANA	AVE		ALLY			LAKE	ST	Concrete	5	Good	0.30	0.70	4	4	No		No		Yes	
	INDIANA	AVE		LAKE	ST		WILLARD	AVE	Concrete	5	Good	1.40	1.00	4	4	Yes	Yes	Yes	Yes	Yes	
	INDIANA	AVE		EKIN	AVE		CULBERTSON	AVE	Concrete	4	Fair	1.30	0.90	4	5	Yes	No	Yes	No	Yes	
	INDIANA	AVE		SHELBY	ST		EKIN	AVE	Concrete	4	Fair	0.50	0.40	4	4	No		Yes	No	Yes	
	INDIANA	AVE		MORTON	AVE		MCLEAN	AVE	Concrete	4	Fair	1.30	1.50	4	4	Yes	No	Yes	No	Yes	
	INDIANA	AVE		ROANOKE	AVE		ALLY		Concrete	3	Poor	0.90	1.30	4	5	Yes	No	Yes	No	Yes	
	INDIANA	AVE		MORTON	AVE		MCLEAN	AVE	Concrete	3	Poor	0.60	1.40	4	4	Yes	No	Yes	No	Yes	
	INDIANA	AVE		WILLARD	AVE		MORTON	AVE	Concrete	3	Poor	0.80	0.30	4	4	Yes	Yes	Yes	No	Yes	
	INDIANA	AVE		DEAD END			ROANOKE	AVE	Concrete	3	Poor	1.30	0.40	4	6	No		Yes	No	Yes	
	INDIANA	AVE		BEELER	ST		SHELBY	ST	Concrete	3	Poor	0.40	0.70	4	4	No		No		Yes	Condition varies throughout
	INDIANA	AVE		CHARLESTOWN	RD		WOOD	AVE	Concrete	3	Poor	1.70	3.80	4	4	Yes	No	Yes	No	No	
	INDIANA	AVE		ROANOKE	AVE		ALLY		Concrete	2	Very Poor	0.20	0.30	4	5	Yes	No	Yes	No	Yes	
	INDIANA	AVE		SHRADER	AVE		ALLY		Concrete	2	Very Poor	2.20	1.20	4	5	Yes	No	No		Yes	
	INDIANA	AVE		MCLEAN	AVE		BEELER	ST	Concrete	2	Very Poor	0.80	1.70	4	4	Yes	Yes	No		Yes	
	INDIANA	AVE		EKIN	AVE		CULBERTSON	AVE	Concrete	2	Very Poor	0.30	1.60	4	4	Yes	No	No		Yes	
	INDIANA	AVE		SHELBY	ST		EKIN	AVE	Concrete	2	Very Poor	0.20	0.60	4	4	No		No		Yes	
	INDIANA	AVE		HUMPHREY	ST		ROANOKE	AVE	Concrete	2	Very Poor	1.00	0.60	4	5	No		Yes	No	Yes	
	INDIANA	AVE		BEELER	ST		SHELBY	ST	Concrete	2	Very Poor	0.30	0.20	4	4	No		Yes	No	Yes	
	INDIANA	AVE		FAIRMONT	AVE		SHRADER	AVE	Concrete	2	Very Poor	0.30	2.30	4	5	Yes	No	Yes	No	No	
	INDIANA	AVE		FAIRMONT	AVE		SHRADER	AVE	Concrete	2	Very Poor	0.20	2.10	4	5	Yes	No	Yes	No	No	
	INDIANA	AVE		CHARLESTOWN	RD		WOOD	AVE	Concrete	2	Very Poor	2.40	1.70	4	4	Yes	No	Yes	No	Yes	
	INDIANA	AVE		SHRADER	AVE		ALLY		Concrete	1	PastServiceLife	2.50	3.00	4	5	Yes	No	No		No	
	INDIANA	AVE		MCLEAN	AVE		BEELER	ST	Concrete	1	PastServiceLife	0.30	1.30	4	4	Yes	No	Yes	Yes	Yes	
	INDIANA	AVE		WILLARD	AVE		MORTON	AVE	Concrete	1	PastServiceLife	1.80	1.60	4	4	Yes	Yes	Yes	No	Yes	
	INDIANA	AVE		LAKE	ST		WILLARD	AVE	Concrete	5	Good	0.50	0.80	4	4	No		Yes	Yes	Yes	
	JACKSON	ST	E	8TH	ST		CHARTRES	ST	Concrete	3	Poor	0.40	0.20	4	5	Yes	Yes	Yes	No	Yes	
	JACKSON	ST		WEST	ST		GRIFFIN	ST	Concrete	3	Poor	2.80	4.00	4	4	Yes	No	Yes	No	No	
	JACKSON	ST		GRIFFIN	ST		HILDRETH	ST	Concrete	2	Very Poor	4.50	3.80	4	4	No		Yes	No	No	
	JACKSON	ST		CHARTRES	ST		LOCUST	ST	Concrete	2	Very Poor	0.40	0.50	4	6	No		Yes	Yes	Yes	
	JAFFERY	DR		GREENVIEW	DR		FARRINGTON	DR	Concrete	4	Fair	0.90	0.30	4	4	Yes	No	Yes	No	Yes	
	JAFFERY	DR		FARRINGTON	DR		SIDNEY	CT	Concrete	3	Poor	0.50	3.10	4	4	Yes	No	Yes	No	No	
	JAFFERY	DR		GREENVIEW	DR		SIDNEY	CT	Concrete	3	Poor	6.20	1.30	4	4	Yes	No	Yes	No	Yes	
	JANIE	LN		VENETIAN	WAY		LINDA	DR	Concrete	TBD	Good	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	Yes	
	JANIE	LN		DEAD END			LINDA	DR	Concrete	TBD	Good	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	Yes	
	JANIE	LN		LINDA	DR		DEAD END		Concrete	TBD	Good	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	Yes	
	JASON	DR		DEAD END			RITA	DR	Concrete	3	Poor	4.70	7.00	4	4	No		No		No	
	JASON	DR		RITA	DR		DEAD END		Concrete	3	Poor	1.20	8.70	4	4	No		No		No	
	JASON	DR		DEAD END			DEAD END		Concrete	3	Poor	0.70	1.60	4	4	No		No		Yes	
	JAY	ST		BEELER	ST		EKIN	AVE	Concrete	5	Good	0.75	2.15	4	4	Yes	No	Yes	No	No	
	JAY	ST		EKIN	AVE		CULBERTSON	AVE	Concrete	3	Poor	0.50	2.25	4	5	Yes	No	Yes	Yes	No	
	JAY	ST		EKIN	AVE		CULBERTSON	AVE	Concrete	3	Poor	4.45	2.75	4	4	Yes	No	Yes	Yes	No	
	JAY	ST	E	OAK	ST	E	ELM	ST	Concrete	3	Poor	1.45	2.35	4	4	Yes	No	Yes	Yes	No	
	JAY	ST		CULBERTSON	AVE	E	OAK	ST	Concrete	3	Poor	0.25	4.70	4	4	Yes	Yes	Yes	Yes	No	
	JAY	ST	E	ELM	ST	E	SPRING	ST	Concrete	3	Poor	7.50	3.55	4	4	Yes	Yes	Yes	No	No	
	JAY	ST	E	ELM	ST	E	SPRING	ST	Concrete	3	Poor	7.15	3.30	4	4	Yes	No	Yes	No	No	
	JAY	ST	E	OAK	ST	E	ELM	ST	Concrete	2	Very Poor	1.80	4.60	4	4	Yes	No	Yes	Yes	No	
	JAY	ST		CULBERTSON	AVE	E	OAK	ST	Concrete	2	Very Poor	1.20	2.40	4	4	Yes	No	Yes	No	No	
	JAY CEE	DR		MCDONALD	ST		BROADWAY	ST	Concrete	3	Poor	0.30	4.90	4	4	Yes	Yes	Yes	Yes	No	
	JAY CEE	DR		CANNON	ST		BROOK	ST	Concrete	3	Poor	0.20	3.30	4	4	Yes	Yes	Yes	No	No	
	JAY CEE	DR		BROOK	ST		MCDONALD	ST	Concrete	3	Poor	1.90	2.30	4	4	Yes	Yes	Yes	Yes	No	
	JAY CEE	DR		BROADWAY	ST		ROANOKE	AVE	Concrete	3	Poor	2.80	5.20	4	4	Yes	Yes	Yes	No	No	
	KAYWOOD	DR		WOODBOURNE	DR		WOODBOURNE	DR	Concrete	3	Poor	0.70	0.30	4	4	Yes	Yes	Yes	Yes	Yes	
	KAYWOOD	DR		WOODBOURNE	DR		WOODBOURNE	DR	Concrete	3	Poor	3.10	0.30	4	4	Yes	Yes	Yes	Yes	Yes	
	KING	ST		DEAD END			VINCENNES	ST	Concrete	2	Very Poor	0.90	3.10	4	4	No		Yes	Yes	No	Approx. 200 ft of Brick at McCaffry Dr.
	KLERNER	LN		DEAD END			CHARLESTOWN	RD	Concrete	3	Poor	1.70	1.70	4	6	No		Yes	No	Yes	Curb at to st is brick
	KLERNER	LN		DEAD END			CHARLESTOWN	RD	Concrete	3	Poor	3.50	2.50	4	4	No		Yes	No	No	
	KNOB HILL	RD		PINEHURST	CT		ELLIOT	AVE	Concrete	4	Fair	1.10	3.20	4	4	Yes	No	Yes	No	No	
	KNOB HILL	RD		ELLIOT	AVE		GRANT LINE	RD	Concrete	2	Very Poor	5.80	0.70	3	4	Yes	No	Yes	No	Yes	Curb at from st is brick
	KNOB VIEW	AVE		WOODBOURNE	DR		SCHELLER	LN	Concrete	3	Poor	0.70	1.70	4	4	Yes	Yes	No		Yes	
	KORB	AVE		DEAD END			MARY ANN	DR	Concrete	3	Poor	5.20	3.40	4	4	No		No		No	
	KORB	AVE		MARY ANN	DR		ROSS	DR	Concrete	3	Poor	3.45	0.85	4	4	No		No		Yes	
	KORB	AVE		BEELER	ST		SHELBY	ST	Concrete	1	PastServiceLife	1.45	2.95	4	5	No		Yes	No	No	
	KORB	AVE	BEELER	ST		SHELBY	ST		Concrete	1	PastServiceLife	0.65	1.35	4	5	No		Yes	No	Yes	

Street Prefix	Street Name	Street Suffix	From Street Prefix	From Street Name	From Street Suffix	To Street Prefix	To Street Name	To Street Suffix	Surface Type	Condition	Condition Description	Max Long Slope (%)	Max Cross Slope (%)	Width Min (ft)	Width Max (ft)	Curb Ramp From St	Curb Ramp From St ADA	Curb Ramp To St	Curb Ramp To St ADA	ADA Compliant	Comments
	KYRA	CIR		MUIRFIELD	DR		MUIRFIELD	DR	Concrete	3	Poor	0.90	2.30	4	4	Yes	No	Yes	No	No	
	LAFAYETTE	DR		LEXINGTON	DR		CHARLESTOWN	RD	Concrete	3	Poor	6.10	4.90	4	4	No		Yes	No	No	
	LAFAYETTE	DR		LAFAYETTE	DR		LAFAYETTE	DR	Concrete	3	Poor	1.60	4.40	4	4	No		No		No	
	LAFAYETTE	DR		SAVANNAH	DR		LEXINGTON	DR	Concrete	3	Poor	0.30	2.10	4	4	Yes	Yes	No		No	
	LAFAYETTE	ST	W	MARKET	ST	W	MAIN	ST	Concrete	3	Poor	0.85	0.60	5	6	Yes	Yes	Yes	No	Yes	
	LAFAYETTE	DR		LAFAYETTE	DR		SAVANNAH	DR	Concrete	3	Poor	6.10	2.40	4	4	No		Yes	No	No	
	LAFAYETTE	DR		SAVANNAH	DR		SAVANNAH	DR	Concrete	3	Poor	6.30	4.50	4	4	Yes	Yes	Yes	Yes	No	
	LAFAYETTE	DR		LAFFAYETTE	DR		DEAD END		Concrete	3	Poor	0.30	4.50	4	4	No		Yes	No	No	
	LAKE	ST		SILVER	ST		INDIANA	AVE	Concrete	2	Very Poor	0.30	4.25	4	4	Yes	No	Yes	Yes	No	
	LAKE	ST		SILVER	ST		INDIANA	AVE	Concrete	2	Very Poor	0.85	2.35	4	4	Yes	No	Yes	Yes	No	
	LAURENS	CIR		MUIRFIELD	DR		MUIRFIELD	DR	Concrete	3	Poor	2.00	4.30	4	4	Yes	No	Yes	No	No	
	LAWN	CT		GREENDALE	DR		GREENDALE	DR	Concrete	TBD	Good	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	Yes	
	LAYAYETTE	DR		LAFAYETTE	DR		LEXINGTON	DR	Concrete	3	Poor	4.50	2.10	4	4	No		No		No	
W	LEWIS	ST		WALNUT	ST		STATE	ST	Concrete	3	Poor	2.70	0.30	4	4	Yes	No	Yes	No	Yes	
W	LEWIS	ST		DENNISON	AVE		BEECH	ST	Concrete	2	Very Poor	4.90	0.70	4	4	No		No		Yes	
W	LEWIS	ST		BEECH	ST		WALNUT	ST	Concrete	1	PastServiceLife	2.00	4.90	4	4	Yes	No	Yes	No	No	
	LEXINGTON	DR		LAFAYETTE	DR		LEXINGTON	DR	Concrete	4	Fair	3.80	3.00	4	4	No		No		No	
	LEXINGTON	DR		LAFAYETTE	DR		LEXINGTON	DR	Concrete	3	Poor	0.90	0.50	4	4	No		No		Yes	
	LEXINGTON	DR		LAFAYETTE	DR		LAFAYETTE	DR	Concrete	3	Poor	1.70	9.30	4	4	No		No		No	
	LINCOLN	AVE		LOPP	AVE		CHARLESTOWN	RD	Concrete	4	Fair	2.30	3.10	4	4	No		Yes	No	No	
	LINCOLN	AVE		LOPP	AVE		CHARLESTOWN	RD	Concrete	4	Fair	3.50	0.20	4	4	No		Yes	No	Yes	
	LINDA	DR		VENETIAN	WAY		GREENLAWN	DR	Concrete	TBD	Good	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	Yes	
	LINDA	DR		JANIE	LN		PIMLICO	DR	Concrete	TBD	Good	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	Yes	
	LINDA	DR		JANIE	LN		PIMLICO	DR	Concrete	TBD	Good	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	Yes	
	LINDA	DR		PIMLICO	DR		VENETIAN	WAY	Concrete	TBD	Good	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	Yes	
	LINDA	DR		PIMLICO	DR		DEAD END		Concrete	TBD	Good	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	Yes	
	LINDA	DR		GORDON	DR		DENNY	DR	Concrete	4	Fair	0.10	4.10	4	4	Yes	Yes	Yes	Yes	No	
	LINDA	DR		DEAD END			GORDON	DR	Concrete	4	Fair	0.70	1.50	4	4	No		Yes	Yes	Yes	
	LINDA	DR		DEAD END			DEAD END		Concrete	3	Poor	0.50	0.10	4	4	No		No		Yes	
	LINDA	DR		DENNY	DR		DEAD END		Concrete	1	PastServiceLife	0.80	2.50	3	4	Yes	Yes	No		No	
	LINDBERG	CT		HAZELWOOD	AVE		ALLY		Concrete	2	Very Poor	0.10	2.00	4	4	Yes	No	Yes	No	Yes	
	LINDBERG	CT		HAZELWOOD	AVE		ALLY		Concrete	2	Very Poor	0.30	1.80	4	4	Yes	No	Yes	No	Yes	
	LOCUST	ST		VINCENNES	ST		HAZELWOOD	AVE	Concrete	4	Fair	0.30	0.80	4	4	Yes	No	Yes	No	Yes	
	LOCUST	ST		VINCENNES	ST		MYRTLE	AVE	Concrete	4	Fair	1.20	3.90	4	4	Yes	No	Yes	No	No	
	LOCUST	ST		DEPAUW	AVE		BURTON	AVE	Concrete	3	Poor	1.10	3.20	4	4	Yes	No	Yes	No	No	
	LOCUST	ST		CLARK	ST		CHARLES	ST	Concrete	3	Poor	2.40	1.80	4	6	Yes	No	Yes	No	Yes	
	LOCUST	ST		CLARK	ST		CHARLES	ST	Concrete	3	Poor	2.90	4.20	4	6	Yes	No	Yes	No	No	
	LOCUST	ST		CHARLES	ST		JACKSON	ST	Concrete	3	Poor	0.60	0.60	4	6	Yes	No	Yes	No	Yes	
	LOCUST	ST		CHARLES	ST		JACKSON	ST	Concrete	3	Poor	1.10	2.50	4	6	Yes	No	Yes	No	No	
	LOCUST	ST		MYRTLE	AVE		BURTON	AVE	Concrete	2	Very Poor	0.80	2.60	4	4	Yes	No	Yes	No	No	
	LOCUST	ST		DEPAUW	AVE		SILVER	ST	Concrete	2	Very Poor	1.20	4.70	4	4	Yes	No	Yes	No	No	
	LOCUST	ST		HAZELWOOD	AVE		SILVER	ST	Concrete	2	Very Poor	0.40	0.20	4	4	Yes	No	Yes	No	Yes	
	LOCUST	ST		CLARK	ST		VINCENNES	ST	Concrete	2	Very Poor	2.30	1.40	4	12	Yes	No	Yes	No	Yes	
	LOCUST	ST		CLARK	ST		VINCENNES	ST	Concrete	2	Very Poor	0.10	1.20	4	12	Yes	No	Yes	No	Yes	
	LOLA DELL	CT		RAINBOW	DR		RAINBOW	DR	Concrete	3	Poor	3.40	1.00	4	4	Yes	No	Yes	No	Yes	
	LONG	CT		DEAD END			SHELL	LN	Concrete	3	Poor	2.00	3.30	4	4	No		No		No	
	LONG	CT		DEAD END			SHELL	LN	Concrete	2	Very Poor	1.00	2.30	4	4	No		Yes	Yes	No	
	LOPP	AVE		SOUTH	ST		VINCENNES	ST	Concrete	3	Poor	0.50	4.70	4	4	Yes	No	Yes	No	No	
	LOPP	AVE		SOUTH	ST		VINCENNES	ST	Concrete	2	Very Poor	0.20	3.00	4	4	Yes	No	Yes	Yes	No	
E	MAIN	ST	E	3RD	ST	E	3RD	ST	Concrete	5	Good	2.90	0.20	16	18	Yes	Yes	Yes	Yes	Yes	
E	MAIN	ST		BANK	ST	E	3RD	ST	Concrete	5	Good	1.10	0.70	16	18	Yes	Yes	Yes	Yes	Yes	
E	MAIN	ST		BANK	ST	E	3RD	ST	Concrete	5	Good	2.00	0.40	16	18	Yes	Yes	Yes	Yes	Yes	
E	MAIN	ST	E	3RD	ST	E	4TH	ST	Concrete	5	Good	4.40	1.00	16	18	Yes	Yes	Yes	Yes	Yes	
E	MAIN	ST	E	4TH	ST	E	5TH	ST	Concrete	5	Good					Yes	Yes	Yes	Yes	Yes	
E	MAIN	ST	E	4TH	ST	E	5TH	ST	Concrete	5	Good	2.40	0.20	8	20	Yes	Yes	Yes	Yes	Yes	Sidewalk and Curb have substantially settled
E	MAIN	ST		PEARL	ST		BANK	ST	Concrete	5	Good	0.30	0.70	12	18	Yes	Yes	Yes	Yes	Yes	
E	MAIN	ST		PEARL	ST		BANK	ST	Concrete	5	Good	0.60	0.10	16	18	Yes	Yes	Yes	Yes	Yes	
E	MAIN	ST		STATE	ST		PEARL	ST	Concrete	5	Good	0.00	0.80	16	16	Yes	Yes	Yes	Yes	Yes	
E	MAIN	ST		STATE	ST		PEARL	ST	Concrete	5	Good	0.00	1.20	16	18	Yes	Yes	Yes	Yes	Yes	
W	MAIN	ST	W	1ST	ST		STATE	ST	Concrete	5	Good	2.40	0.50	12	15	Yes	No	Yes	No	Yes	
E	MAIN	ST	E	9TH	ST	E	10TH	ST	Concrete	4	Fair	0.90	0.20	6	8	Yes	Yes			Yes	
E	MAIN	ST	E	10TH	ST	E	11TH	ST	Concrete	4	Fair	0.90	0.70	6	8	Yes	Yes	Yes	Yes	Yes	
E	MAIN	ST	E	10TH	ST	E	11TH	ST	Concrete	4	Fair	0.90	1.90	8	8	Yes	Yes	Yes	Yes	Yes	
E	MAIN	ST	E	11TH	ST	E	12TH	ST	Concrete	4	Fair	0.30	0.70	6	8	Yes	Yes	Yes	Yes	Yes	
E	MAIN	ST	E	11TH	ST	E	12TH	ST	Concrete	4	Fair	1.40	0.90	8	8	Yes	Yes	Yes	Yes	Yes	
E	MAIN	ST	E	12TH	ST	E	13TH	ST	Concrete	4	Fair	0.20	0.30	4	8	Yes	Yes	Yes	Yes	Yes	
E	MAIN	ST	E	12TH	ST	E	13TH	ST	Concrete	4	Fair	0.90	1.20	8	8	Yes	Yes	Yes	Yes	Yes	
E	MAIN	ST	E	13TH	ST	E	14TH	ST	Concrete	4	Fair	0.50	0.50	8	8	Yes	Yes	Yes	Yes	Yes	
E	MAIN	ST	E	13TH	ST	E	14TH	ST	Concrete	4	Fair	0.20	0.50	8	8	Yes	Yes	Yes	Yes	Yes	
E	MAIN	ST	E	14TH	ST	E	15TH	ST	Concrete	4	Fair	0.20	0.20	6	8	Yes	Yes	Yes	Yes	Yes	
E	MAIN	ST	E	14TH	ST	E	15TH	ST	Concrete	4	Fair	0.20	0.20	8	8	Yes	Yes	Yes	Yes	Yes	
E	MAIN	ST	E	15TH	ST	E	16TH	ST	Concrete	4	Fair	1.40	0.30	6	8	Yes	Yes	Yes	Yes	Yes	
E	MAIN	ST		GALT	ST	E	18TH	ST	Concrete	4	Fair	0.70	0.50	5	6	Yes	No	Yes	No	Yes	
E	MAIN	ST		GALT	ST	E	18TH	ST	Concrete	4	Fair	0.30	3.00	6	6	Yes	Yes	Yes	No	No	
W	MAIN	ST		SCRIBNER	DR	W	1ST	ST	Concrete	4	Fair	0.90	0.50	5	15	Yes	No	Yes	Yes	Yes	
W	MAIN	ST		SCRIBNER	DR	W	1ST	ST	Concrete	4	Fair	0.30	2.80	5	10	Yes	No	Yes	No	No	
W	MAIN	ST	W	7TH	ST	W	5TH	ST	Concrete	4	Fair	1.20	0.20	4	4	Yes	No	Yes	No	Yes	
E	MAIN	ST	E	5TH	ST	E	7TH	ST	Concrete	4	Fair	0.20	0.30	8	8	Yes	Yes	Yes	Yes	Yes	
W	MAIN	ST	W	10TH	ST	W	8TH	ST	Concrete	4	Fair	1.20	0.30	4	4	Yes	No	Yes	No	Yes	
E	MAIN	ST	E	6TH	ST	E	9TH	ST	Concrete	4	Fair	0.50	0.30	6	8	Yes	Yes	Yes	Yes	Yes	
E	MAIN	ST	E	7TH	ST	E	9TH	ST	Concrete	4	Fair	0.20	0.30	8	8	Yes	Yes	Yes	Yes	Yes	

Street Prefix	Street Name	Street Suffix	From Street Prefix	From Street Name	From Street Suffix	To Street Prefix	To Street Name	To Street Suffix	Surface Type	Condition	Condition Description	Max Long Slope (%)	Max Cross Slope (%)	Width Min (ft)	Width Max (ft)	Curb Ramp From St	Curb Ramp From St ADA	Curb Ramp To St	Curb Ramp To St ADA	ADA Compliant	Comments
E	MAIN	ST	E	16TH	ST		BUTLER	ST	Concrete	4	Fair	0.20	1.40	6	8	Yes	Yes	Yes	Yes	Yes	
E	MAIN	ST	E	15TH	ST		CAVEL	ST	Concrete	4	Fair	0.50	0.30	8	8	Yes	Yes	Yes	Yes	Yes	
E	MAIN	ST		VINCENNES	ST		GALT	ST	Concrete	4	Fair	0.70	1.40	6	6	Yes	No	Yes	Yes	Yes	
W	MAIN	ST		LAFAYETTE	ST		SCRIBNER	DR	Concrete	4	Fair	0.20	4.00	4	12	Yes	No	Yes	No	No	
E	MAIN	ST		BULTER	ST		VINCENNES	ST	Concrete	4	Fair	1.00	0.50	8	8	Yes	Yes	Yes	Yes	Yes	
E	MAIN	ST		CAVEL	ST		VINCENNES	ST	Concrete	4	Fair	0.90	0.70	8	8	Yes	Yes	Yes	Yes	Yes	
E	MAIN	ST	E	9TH	ST	E	10TH	ST	Brick	3	Poor	0.30	0.20	7	7	Yes	Yes	Yes	Yes	Yes	
E	MAIN	ST	E	9TH	ST	E	10TH	ST	Brick	3	Poor	1.20	1.60	8	12			Yes	Yes	Yes	
W	MAIN	ST		CORYDON PIKE		W	10TH	ST	Concrete	3	Poor	1.00	4.50	4	4	No		Yes	No	No	
W	MAIN	ST	S	SR 111		W	10TH	ST	Concrete	3	Poor	0.20	3.50	4	4	Yes	No	Yes	No	No	
W	MAIN	ST	W	5TH	ST	W	4TH	ST	Concrete	3	Poor	1.60	2.30	3	4	Yes	No	Yes	No	No	
W	MAIN	ST	W	5TH	ST	W	4TH	ST	Concrete	3	Poor	1.00	5.40	4	8	Yes	No	Yes	No	No	
W	MAIN	ST	W	6TH	ST	W	5TH	ST	Concrete	3	Poor	0.50	2.60	4	15	Yes	No	Yes	No	No	
E	MAIN	ST	E	5TH	ST	E	6TH	ST	Brick	3	Poor	0.30	1.70	6	8	Yes	Yes	Yes	Yes	Yes	
W	MAIN	ST	W	7TH	ST	W	6TH	ST	Concrete	3	Poor	1.00	1.20	6	8	Yes	No	Yes	No	Yes	
W	MAIN	ST	W	8TH	ST	W	7TH	ST	Concrete	3	Poor	0.90	3.00	4	4	Yes	No	Yes	No	No	
W	MAIN	ST	W	9TH	ST	W	8TH	ST	Concrete	3	Poor	0.70	6.30	4	4	Yes	No	Yes	No	No	
W	MAIN	ST	W	10TH	ST	W	9TH	ST	Concrete	3	Poor	0.50	1.60	4	5	Yes	No	Yes	No	Yes	
E	MAIN	ST	E	18TH	ST		EAST	ST	Concrete	3	Poor	1.20	2.60	4	4	Yes	No	Yes	No	No	
E	MAIN	ST		VINCENNES	ST		GALT	ST	Concrete	3	Poor	2.40	0.50	4	6	Yes	No	Yes	No	Yes	
W	MAIN	ST	W	4TH	ST		LAFAYETTE	ST	Concrete	3	Poor	4.50	2.60	4	20	Yes	No	Yes	No	No	
W	MAIN	ST	W	4TH	ST		LAFAYETTE	ST	Concrete	3	Poor	3.30	3.50	4	5	Yes	No	Yes	No	No	
E	MAIN	ST	E	18TH	ST		RIVERSIDE	TER	Concrete	3	Poor	0.70	0.30	4	4	No		No		Yes	
W	MAIN	ST		LAFAYETTE	ST		SCRIBNER	DR	Concrete	3	Poor	1.40	0.30	4	12	Yes	No	Yes	No	Yes	
E	MAIN	ST		RIVERSIDE	TER		SILVER	ST	Concrete	3	Poor	5.60	1.40	4	4	No		No		Yes	
W	MAIN	ST	W	1ST	ST		STATE	ST	Concrete	3	Poor	0.50	1.60	4	15	Yes	Yes	Yes	No	Yes	
W	MAIN	ST	W	8TH	ST	W	7TH	ST	Concrete	2	Very Poor	0.20	6.60	12	15	Yes	No	Yes	No	No	
E	MARKET	ST		STATE	ST		PEARL	ST	Concrete	5	Good	0.30	2.00	9	10	Yes	Yes	Yes	No	Yes	
E	MARKET	ST	E	9TH	ST	E	10TH	ST	Concrete	4	Fair	2.25	2.00	8	8	Yes	No	Yes	No	Yes	
E	MARKET	ST	E	12TH	ST	E	13TH	ST	Concrete	4	Fair	0.70	0.90	8	8	Yes	Yes	Yes	No	Yes	
E	MARKET	ST	E	12TH	ST	E	13TH	ST	Concrete	4	Fair	0.70	3.70	8	8	Yes	No	Yes	Yes	No	
E	MARKET	ST	E	15TH	ST	E	16TH	ST	Concrete	4	Fair	0.30	3.50	8	12	Yes	No	Yes	No	No	
W	MARKET	ST		SCRIBNER	DR	W	1ST	ST	Concrete	4	Fair	1.20	1.55	5	9	Yes	No	Yes	Yes	Yes	
E	MARKET	ST		BANK	ST	E	3RD	ST	Concrete	4	Fair	0.50	1.65	6	20	Yes	No	Yes	Yes	Yes	
E	MARKET	ST		BANK	ST	E	3RD	ST	Concrete	4	Fair	2.05	0.40	8	12	Yes	Yes	Yes	No	Yes	
E	MARKET	ST	E	4TH	ST	E	5TH	ST	Concrete	4	Fair	0.75	1.80	8	20	Yes	Yes	Yes	No	Yes	
W	MARKET	ST	W	6TH	ST	W	5TH	ST	Concrete	4	Fair	2.40	2.95	5	6	Yes	No	Yes	No	No	
W	MARKET	ST	W	6TH	ST	W	5TH	ST	Concrete	4	Fair	0.50	2.70	5	5	Yes	No	Yes	No	No	
E	MARKET	ST	E	7TH	ST	E	6TH	ST	Concrete	4	Fair	3.10	0.15	8	8	Yes	No	Yes	No	Yes	
W	MARKET	ST	W	7TH	ST	W	6TH	ST	Concrete	4	Fair	0.50	3.20	5	6	Yes	Yes	Yes	No	No	
W	MARKET	ST	W	7TH	ST	W	6TH	ST	Concrete	4	Fair	1.00	3.55	5	6	Yes	No	Yes	No	No	
E	MARKET	ST	E	5TH	ST	E	7TH	ST	Concrete	4	Fair	2.15	1.35	8	15	Yes	No	Yes	No	Yes	
W	MARKET	ST	W	8TH	ST	W	7TH	ST	Concrete	4	Fair	0.50	1.65	5	6	Yes	No	Yes	No	Yes	
E	MARKET	ST	E	7TH	ST	E	9TH	ST	Concrete	4	Fair	0.95	2.85	8	8	Yes	No	Yes	Yes	No	
E	MARKET	ST	E	7TH	ST	E	9TH	ST	Concrete	4	Fair	1.35	2.15	5	8	Yes	No	Yes	No	No	
W	MARKET	ST	W	1ST	ST		STATE	ST	Concrete	4	Fair	0.15	3.40	10	20	Yes	No	Yes	Yes	No	
E	MARKET	ST	E	16TH	ST		VINCENNES	ST	Concrete	4	Fair	0.50	2.70	8	12	Yes	No	Yes	Yes	No	
W	MARKET	ST	W	4TH	ST		WASHINGTON	PL	Concrete	4	Fair	2.15	2.10	5	5	Yes	Yes	Yes	Yes	No	
E	MARKET	ST	E	9TH	ST	E	10TH	ST	Concrete	3	Poor	1.00	0.25	8	8	Yes	No	Yes	No	Yes	
E	MARKET	ST	E	10TH	ST	E	11TH	ST	Concrete	3	Poor	0.70	3.80	6	8	Yes	No	Yes	No	No	
E	MARKET	ST	E	11TH	ST	E	12TH	ST	Concrete	3	Poor	0.20	1.60	8	8	Yes	Yes	Yes	No	Yes	First 90 ft from McLean Ave is rated 5
E	MARKET	ST	E	13TH	ST	E	14TH	ST	Concrete	3	Poor	1.20	2.40	8	8	Yes	Yes	Yes	No	No	
E	MARKET	ST	E	13TH	ST	E	14TH	ST	Concrete	3	Poor	0.20	4.40	8	12	Yes	Yes	Yes	No	No	
E	MARKET	ST	E	14TH	ST	E	15TH	ST	Concrete	3	Poor	1.20	1.90	8	8	Yes	No	Yes	No	Yes	
E	MARKET	ST	E	14TH	ST	E	15TH	ST	Concrete	3	Poor	1.00	0.50	8	12	Yes	No	Yes	No	Yes	
W	MARKET	ST		SCRIBNER	DR	W	1ST	ST	Concrete	3	Poor	3.40	4.00	5	18	Yes	No	Yes	Yes	No	
E	MARKET	ST	E	3RD	ST	E	4TH	ST	Concrete	3	Poor	1.80	2.60	12	15	Yes	Yes	Yes	Yes	No	
E	MARKET	ST	E	3RD	ST	E	4TH	ST	Concrete	3	Poor	4.45	4.00	12	16	Yes	Yes	Yes	No	No	
W	MARKET	ST	W	5TH	ST	W	4TH	ST	Concrete	3	Poor	2.40	6.00	5	5	Yes	Yes	Yes	Yes	No	
E	MARKET	ST	E	4TH	ST	E	5TH	ST	Concrete	3	Poor	0.60	2.85	8	15	Yes	Yes	Yes	No	No	
W	MARKET	ST	W	8TH	ST	W	7TH	ST	Concrete	3	Poor	0.25	1.80	6	6	Yes	No	Yes	No	Yes	
W	MARKET	ST	W	9TH	ST	W	8TH	ST	Concrete	3	Poor	0.65	3.30	5	6	Yes	No	Yes	No	No	
W	MARKET	ST	W	9TH	ST	W	8TH	ST	Concrete	3	Poor	0.40	2.35	5	6	Yes	No	Yes	No	No	
E	MARKET	ST		PEARL	ST		BANK	ST	Brick	3	Poor	1.90	2.95	8	14	Yes	No	Yes	No	No	
E	MARKET	ST		PEARL	ST		BANK	ST	Brick	3	Poor	1.45	6.20	5	15	Yes	No	Yes	No	No	
E	MARKET	ST		SILVER	ST		BEST	AVE	Concrete	3	Poor	0.20	0.90	4	4	Yes	No	Yes	No	Yes	
E	MARKET	ST	E	15TH	ST		CAVEL	ST	Concrete	3	Poor	1.40	2.90	8	12	Yes	Yes	Yes	No	No	
E	MARKET	ST		BEST	AVE		COST	AVE	Concrete	3	Poor	1.20	2.00	4	4	Yes	No	Yes	No	Yes	
E	MARKET	ST	E	MARKET	ST		EAST	ST	Concrete	3	Poor	0.80	3.40	4	4	No		No		No	
E	MARKET	ST		VINCENNES	ST		GALT	ST	Concrete	3	Poor	0.90	1.80	4	4	Yes	Yes	Yes	Yes	Yes	
E	MARKET	ST		VINCENNES	ST		GALT	ST	Concrete	3	Poor	1.10	1.60	4	10	Yes	Yes	Yes	Yes	Yes	
W	MARKET	ST	W	4TH	ST		LAFAYETTE	ST	Concrete	3	Poor	0.60	1.65	5	20	Yes	Yes	Yes	Yes	Yes	
E	MARKET	ST		STATE	ST		PEARL	ST	Concrete	3	Poor	2.35	3.40	5	10	Yes	No	Yes	No	No	
W	MARKET	ST		LAFAYETTE	ST		SCRIBNER	DR	Concrete	3	Poor	0.10	3.80	5	5			Yes	Yes	No	
W	MARKET	ST		WASHINGTON	PL		SCRIBNER	DR	Concrete	3	Poor	0.60	2.90	5	5	Yes	Yes	Yes	Yes	No	
W	MARKET	ST	W	1ST	ST		STATE	ST	Concrete	3	Poor	1.65	3.05	8	10	Yes	No	Yes	Yes	No	
E	MARKET	ST		CAVEL	ST		VINCENNES	ST	Concrete	3	Poor	1.20	0.90	8	12	Yes	No	Yes	Yes	Yes	
E	MARKET	ST	E	10TH	ST	E	11TH	ST	Concrete	2	Very Poor	1.40	2.80	6	6	Yes	No	Yes	No	No	
E	MARKET	ST	E	11TH	ST	E	12TH	ST	Concrete	2	Very Poor	0.30	3.80	8	8	Yes	No	Yes	No	No	
W	MARKET	ST	W	5TH	ST	W	4TH	ST	Concrete	2	Very Poor	0.50	4.00	3	4	Yes	Yes	Yes	Yes	No	
E	MARKET	ST		SILVER	ST		BEHARREL	AVE	Concrete	2	Very Poor	0.30	0.70	4	4	Yes	No	No		Yes	

Street Prefix	Street Name	Street Suffix	From Street Prefix	From Street Name	From Street Suffix	To Street Prefix	To Street Name	To Street Suffix	Surface Type	Condition	Condition Description	Max Long Slope (%)	Max Cross Slope (%)	Width Min (ft)	Width Max (ft)	Curb Ramp From St	Curb Ramp From St ADA	Curb Ramp To St	Curb Ramp To St ADA	ADA Compliant	Comments
E	MARKET	ST		WOODROW	AVE		BEHARRELL	AVE	Concrete	2	Very Poor	0.40	0.80	4	4	Yes	No	Yes	No	Yes	
E	MARKET	ST		GALT	ST		GREEN	ST	Concrete	2	Very Poor	0.10	1.20	4	4	Yes	Yes	Yes	No	Yes	
E	MARKET	ST		THOMAS	AVE		JAY	ST	Concrete	2	Very Poor	3.30	4.40	4	4	Yes	Yes	Yes	No	No	
E	MARKET	ST	E	18TH	ST	E	MARKET	ST	Concrete	2	Very Poor	1.60	1.40	4	8	No		No		Yes	
E	MARKET	ST		ALLY			SILVER	ST	Concrete	2	Very Poor	3.30	2.80	5	5	No		Yes	No	No	
E	MARKET	ST		JAY	ST		SILVER	ST	Concrete	2	Very Poor	1.70	2.10	5	5	Yes	No	Yes	No	No	
E	MARKET	ST	E	MARKET	ST		THOMAS	AVE	Concrete	2	Very Poor	0.20	0.90	4	4	No		Yes	No	Yes	
E	MARKET	ST		COST	AVE		WOODROW	AVE	Concrete	2	Very Poor	1.80	1.60	4	4	Yes	No	Yes	No	Yes	
E	MARKET	ST		GREEN	ST		DEAD END		Concrete	2	Very Poor	0.40	2.50	4	4	No				No	
E	MARKET	ST		GALT	ST	E	18TH	ST	Concrete	1	PastServiceLife	0.20	2.30	4	8	Yes	Yes	No		No	
	MARY ANN	DR		KORB	AVE		ROSS	DR	Concrete	2	Very Poor	0.30	10.20	3	4	No		No		No	
	MARY ANN	DR		KORB	AVE		ROSS	DR	Concrete	2	Very Poor	4.45	5.50	4	4	No		No		No	
	MARY DELL	CT		RAINBOW	DR		RAINBOW	DR	Concrete	3	Poor	4.30	1.90	4	4	Yes	No	Yes	No	Yes	
	MARYLAND	AVE		DEAD END			DEAD END		Concrete	1	PastServiceLife	0.20	6.10	4	4	No		No		No	
	MC CARTIN	DR		MILL	LN		MILLER	LN	Concrete	3	Poor	1.40	1.40	4	4	Yes	No	Yes	No	Yes	
	MC CARTIN	DR		MILL	LN		MILLER	LN	Concrete	3	Poor	1.40	1.10	4	4	Yes	No	Yes	No	Yes	
	MCDONALD	LN		RITA	DR		HICKORYVALE	DR	Concrete	5	Good	3.20	0.50	4	4	Yes	Yes	No		Yes	
	MCDONALD	LN		UNRUH	CT		BEACON	DR	Concrete	4	Fair	4.20	0.50	4	4	Yes	Yes	Yes	Yes	Yes	
	MCDONALD	LN		ROANOKE	AVE		CHARLESTOWN	RD	Concrete	4	Fair	4.50	3.30	4	5	Yes	No	Yes	No	No	
	MCDONALD	LN		ROANOKE	AVE		CHARLESTOWN	RD	Concrete	4	Fair	0.70	3.30	4	5	Yes	No	Yes	No	No	
	MCDONALD	LN		BEACON	DR		MURR	LN	Concrete	4	Fair	1.30	1.00	4	4	Yes	Yes	Yes	Yes	Yes	
	MCDONALD	LN		OXFORD	DR		NASSAU	LN	Concrete	4	Fair	0.50	0.60	4	4	Yes	Yes	Yes	Yes	Yes	
	MCDONALD	LN		MURR	LN		OXFORD	DR	Concrete	4	Fair	3.70	0.40	4	4	Yes	Yes	Yes	Yes	Yes	
	MCDONALD	LN		HICKORYVALE	DR		ROANOKE	AVE	Concrete	4	Fair	1.20	3.10	5	5	Yes	No	Yes	No	No	
	MCDONALD	LN		KNOB VIEW	AVE		ROANOKE	AVE	Concrete	4	Fair	2.80	5.10	5	5	Yes	No	Yes	No	No	
	MCDONALD	LN		GRANT LINE	RD		UNRUH	CT	Concrete	4	Fair	4.60	0.20	4	4	Yes	Yes	Yes	Yes	Yes	
	MCDONALD	LN		OXFORD	DR		KNOB VIEW	AVE	Concrete	3	Poor	1.20	3.80	4	5	Yes	No	Yes	No	No	
	MCDONALD	LN		NASSAU	LN		OXFORD	DR	Concrete	3	Poor	2.40	0.50	4	4	Yes	No	Yes	No	Yes	
	MCDONALD	LN		GRANT LINE	RD		RITA	DR	Concrete	3	Poor	0.40	2.60	4	4	Yes	Yes	Yes	Yes	No	
	MCDONALD	AVE		SHRADER	AVE		CHARLESTOWN	RD	Concrete	2	Very Poor	1.70	1.30	3	4	Yes	No	No		Yes	
	MCDONALD	AVE		ROANOKE	AVE		FAIRMONT	AVE	Concrete	2	Very Poor	0.30	2.10	4	5	Yes	No	Yes	No	No	
	MCDONALD	AVE		HUMPHREY	ST		ROANOKE	AVE	Concrete	2	Very Poor	1.20	2.40	4	5	No		No		No	
	MCDONALD	AVE		DEAD END			ROANOKE	AVE	Concrete	2	Very Poor	1.80	2.50	4	5	No		No		No	
	MCDONALD	AVE		FAIRMONT	AVE		SHRADER	AVE	Concrete	2	Very Poor	0.50	1.60	4	4	Yes	No	Yes	No	Yes	
	MCLEAN	AVE	SILVER	ST		INDIANA	AVE		Concrete	2	Very Poor	1.00	10.65	4	5	Yes	No	Yes	Yes	No	
	MCLEAN	AVE		SILVER	ST		INDIANA	AVE	Concrete	2	Very Poor	0.30	4.60	4	5	Yes	No	Yes	Yes	No	
	MCLEAN	AVE		INDIANA	AVE		MCDONALD	AVE	Concrete	2	Very Poor	1.10	3.60	4	5	Yes	Yes	No		No	
	MCLEAN	AVE		MCDONALD	AVE		KORB	AVE	Concrete	1	PastServiceLife	0.60	2.40	4	5	Yes	No	No		No	
	MCLEAN	AVE		MCDONALD	AVE		KORB	AVE	Concrete	1	PastServiceLife	0.85	6.25	4	4	No		No		No	
	MCLEAN	AVE		INDIANA	AVE		MCDONALD	AVE	Concrete	1	PastServiceLife	0.50	6.35	4	5	Yes	Yes	Yes	No	No	
	MEADOWVIEW	DR		FARMGATE	LN		KLERNER	LN	Concrete	3	Poor	2.00	0.20			Yes	No	Yes	Yes	Yes	
	MEADOWVIEW	DR		PLAINFIELD	DR		KLERNER	LN	Concrete	3	Poor	2.40	1.80	4	5	Yes	Yes	Yes	No	Yes	
	MEADOWVIEW	DR		FARMGATE	LN		PLAINVIEW	DR	Concrete	3	Poor	0.20	0.90	4	5	Yes	No		Yes	Yes	
	MELLWOOD	DR		WOODSIDE	DR		DEAD END		Concrete	3	Poor	0.20	0.90	4	4	No		No		Yes	
	MELLWOOD	DR		DEAD END			DEAD END		Concrete	3	Poor	0.30	2.30	4	4	No		No		No	
	MELLWOOD	DR		DEAD END			WOODSIDE	DR	Concrete	2	Very Poor	2.60	6.80	4	4	No		No		No	
	MELLWOOD	DR		DEAD END			DEAD END		Concrete	2	Very Poor	1.60	0.20	4	4	No		No		Yes	
	MELLWOOD	DR		DEAD END			DEAD END		Concrete	2	Very Poor	3.50	3.10	4	4	No		No		No	
	MELLWOOD	DR		DEAD END			DEAD END		Concrete	2	Very Poor	4.40	0.90	4	4	No		No		Yes	
	MILL	LN		DEAD END			BELLEMEADE	DR	Concrete	3	Poor	3.90	3.40	4	4	No		No		No	
	MILL	LN		BELLEMEADE	DR		MC CARTIN	DR	Concrete	3	Poor	2.40	1.80	4	4	No		Yes	No	Yes	
	MILL	LN		MC CARTIN	DR		DEAD END		Concrete	3	Poor	0.90	2.40	4	4	Yes	No	No		No	
	MILLER	LN		MC CARTIN	DR		BELLEWOOD CT		Concrete	4	Fair	1.90	1.20	4	4	Yes	No	No		Yes	
	MILLER	LN		GRABLE	CT		BELLEMEADE	DR	Concrete	3	Poor	2.00	0.50	4	4	No		No		Yes	
	MILLER	LN		OLD FORD	RD		GRABLE	CT	Concrete	3	Poor	3.00	1.10	4	4	No		No		Yes	
	MILLER	LN		BELLEMEADE	DR		MC CARTIN	DR	Concrete	3	Poor	1.40	1.40	4	4	No		Yes	No	Yes	
	MILLER	LN		OLD FORD	RD		BELLEWOOD	CT	Concrete	3	Poor	3.20	1.30	4	4	No		No		Yes	
	MILLS	LN		DEAD END			GREEN VALLEY	RD	Concrete	4	Fair	1.50	1.00	4	4	No		Yes	No	Yes	
	MORGAN	AVE		ERNI	AVE		GRAYBROOK	LN	Concrete	3	Poor	0.40	3.20	4	4	Yes	No	Yes	No	No	
	MORGAN	AVE		WOODLAND	DR		GRAYBROOK	LN	Concrete	3	Poor	0.40	2.50	4	4	Yes	No	Yes	No	No	
	MORGAN	AVE		ERNI	AVE		WOODLAND	DR	Concrete	3	Poor	0.50	2.10	4	4	No		No		No	
	MORTON	AVE		MCDONALD	AVE		KORB	AVE	Concrete	5	Good	3.30	1.10	4	5	Yes	Yes	No		Yes	
	MORTON	AVE		MCDONALD	AVE		KORB	AVE	Concrete	3	Poor	3.90	4.85	4	4	Yes	Yes	No		No	
	MORTON	AVE		SILVER	ST		INDIANA	AVE	Concrete	2	Very Poor	0.60	3.10	4	4	Yes	No	Yes	Yes	No	
	MORTON	AVE		SILVER	ST		INDIANA	AVE	Concrete	2	Very Poor	2.60	5.40	4	4	Yes	No	Yes	Yes	No	
	MORTON	AVE		INDIANA	AVE		MCDONALD	AVE	Concrete	2	Very Poor	0.75	2.15	4	4	Yes	Yes	No		No	
	MORTON	AVE		INDIANA	AVE		MCDONALD	AVE	Concrete	2	Very Poor	0.30	3.30	4	4	Yes	Yes	No		No	
	MT TABOR	RD	E	OAKWOOD	DR		DEAD END		Concrete	4	Fair	0.90	0.10	4	5	Yes	No	Yes	No	Yes	
	MT TABOR	RD		PROGRESS	BLVD		INDUSTRIAL	BLVD	Concrete	3	Poor	0.40	1.60	4	4	Yes	No	Yes	No	Yes	
	MT TABOR	RD		GREEN VALLEY	RD		LANCASTER	DR	Concrete	3	Poor	1.30	2.90	4	4	Yes	No	Yes	No	No	
	MT TABOR	RD	W	OAKWOOD	DR	E	OAKWOOD	DR	Concrete	3	Poor	3.70	0.20	4	5	Yes	No	Yes	No	Yes	
	MT TABOR	RD		LANCASTER	DR		WEXFORD	CT	Concrete	3	Poor	0.20	1.10	4	4	Yes	No	Yes	No	Yes	
	MT TABOR	RD		UNNAMED CEMETARY	RD		UNNAMED CEMETARY	RD	Concrete	5	Good	1.50	0.90	4	4	Yes	No	Yes	No	Yes	
	MT TABOR	RD		UNNAMED CEMETARY	RD		DEAD END		Concrete	5	Good	1.50	0.30	4	4	Yes	No	No		Yes	
	MT TABOR	RD		TABOR	CT		GRANT LINE	RD	Concrete	4	Fair	2.00	0.30	4	4	Yes	No	Yes	No	Yes	
	MT TABOR	RD		TIGER	BLVD	W	OAKWOOD	DR	Concrete	4	Fair	4.35	0.30	5	5	Yes	Yes	Yes	No	Yes	
	MT TABOR	RD		BELL	LN		TABOR	CT	Concrete	4	Fair	1.30	0.40	4	4	Yes	No	Yes	No	Yes	
	MT TABOR	RD		GRANT LINE	RD		TIGER	BLVD	Concrete	4	Fair	2.50	1.30	4	4	Yes	No	Yes	No	Yes	
	MT TABOR	RD		GRANT LINE	RD		UNNAMED CEMETARY		Concrete	4	Fair	2.95	0.60	5	6	Yes	No	Yes	No	Yes	
	MT TABOR	RD		WEXFORD	CT		BELL	LN	Concrete	3	Poor	1.60	1.50	4	6	Yes	No	Yes	No	Yes	
	MT TABOR	RD		INDUSTRIAL	BLVD		GRANT LINE	RD	Concrete	3	Poor	0.30	1.20	4	6	Yes	No	Yes	No	Yes	

Street Prefix	Street Name	Street Suffix	From Street Prefix	From Street Name	From Street Suffix	To Street Prefix	To Street Name	To Street Suffix	Surface Type	Condition	Condition Description	Max Long Slope (%)	Max Cross Slope (%)	Width Min (ft)	Width Max (ft)	Curb Ramp From St	Curb Ramp From St ADA	Curb Ramp To St	Curb Ramp To St ADA	ADA Compliant	Comments
	MT TABOR	RD		CITY LIMITS			PROGRESS	BLVD	Concrete	3	Poor	0.90	2.30	4	4	No		Yes	No	No	
	MUIRFIELD	DR		LAURENS	CIR		KYRA	CIR	Concrete	3	Poor	3.60	3.70	4	4	Yes	No	Yes	No	No	
	MUIRFIELD	DR		RAINBOW	DR		KYRA	CIR	Concrete	3	Poor	4.80	1.80	4	4	Yes	No	Yes	No	Yes	
	MUIRFIELD	DR		LAURENS	CIR		RAINBOW	DR	Concrete	3	Poor	3.10	0.80	4	4	Yes	No	Yes	No	Yes	
	MURR	LN		DEAD END			HARBROOK	CT	Concrete	3	Poor	4.50	2.10	4	4	No		No		No	
	MURR	LN		HARBROOK	DR		WOODBOURNE	DR	Concrete	3	Poor	0.50	2.30	4	4	No		Yes	Yes	No	
	MURR	LN		HARBROOK	CT		WOODBOURNE	DR	Concrete	3	Poor	3.70	2.30	4	4	No		Yes	Yes	No	
	MYRTLE	AVE		DEPAUW	AVE		RASMUSSEN	CT	Concrete	3	Poor	1.30	0.60	4	5	Yes	No	Yes	No	Yes	
	MYRTLE	AVE		RASMUSSEN	CT		LOCUST	ST	Concrete	2	Very Poor	1.60	2.20	4	5	Yes	No	Yes	No	No	
	MYRTLE	AVE		DEPAUW	AVE		LOCUST	ST	Concrete	2	Very Poor	1.30	3.60	4	5	Yes	No	Yes	No	No	
	NAGHEL	ST		ALBANY	ST	W	LEWIS	ST	Concrete	3	Poor	4.70	3.10	4	4	Yes	No	Yes	No	No	
	NAGHEL	ST		ALBANY	ST	W	LEWIS	ST	Concrete	2	Very Poor	4.50	3.75	4	4	Yes	No	Yes	No	Yes	
	NELSON	AVE		KNOB HILL	RD		DEAD END		Concrete	4	Fair	1.20	3.00	4	4	Yes	No	No		No	
	NELSON	AVE		PINEHURST	CT		DEAD END		Concrete	4	Fair	1.80	2.10	4	4	No		No		No	
	NORTHSIDE DR			CHARLESTOWN CROSSING WAY			CHARLESTOWN RD		Concrete	3	Poor	8.40	3.00	4	5	Yes	Yes	Yes	No	No	
	NORTHSIDE DR			CHARLESTOWN CROSSING WAY			CHARLESTOWN RD		Concrete	3	Poor	3.00	2.50	4	4	Yes	Yes	No		No	
	NULL			NULL			NULL		Concrete	5	Good	0.60	1.60	4	4	No		No		Yes	
	NULL			NULL			NULL		Concrete	4	Fair	4.10	2.75	6	6	No		No		No	
	NULL			NULL			NULL		Concrete	4	Fair	1.70	2.10	4	4	No		No		No	
	NULL			NULL			NULL		Concrete	4	Fair	0.50	3.30	4	4	Yes	No	Yes	Yes	No	
	NULL			NULL			NULL		Concrete	4	Fair	5.90	6.60	4	4	Yes	No	Yes	No	No	
	NULL			NULL			NULL		Concrete	3	Poor	0.60	1.50	4	4	No		No		Yes	
	NULL			NULL			NULL		Concrete	2	Very Poor	1.40	1.60	4	4	Yes		Yes	No	Yes	
E	OAK	ST	E	5TH	ST	E	7TH	ST	Concrete	5	Good	1.00	2.15	5	6	Yes	No	Yes	No	No	
E	OAK	ST		PEARL	ST		BANK	ST	Concrete	5	Good	0.60	3.10	5	6	Yes	No	Yes	No	No	
E	OAK	ST		THOMAS	AVE		JAY	ST	Concrete	5	Good	0.85	1.45	4	5	Yes	No	Yes	Yes	Yes	
E	OAK	ST	E	9TH	ST	E	10TH	ST	Concrete	4	Fair	1.10	2.95	4	5	Yes	Yes	Yes	No	No	
E	OAK	ST	E	10TH	ST	E	11TH	ST	Concrete	4	Fair	1.20	1.60	10	10	Yes	No	Yes	No	Yes	
E	OAK	ST	E	13TH	ST	E	15TH	ST	Concrete	4	Fair	0.65	0.95	5	6	Yes	No	Yes	No	Yes	
E	OAK	ST		VINCENNES	ST	E	18TH	ST	Concrete	4	Fair	1.65	1.45	5	5	Yes	No	Yes	Yes	Yes	
E	OAK	ST	E	7TH	ST	E	8TH	ST	Concrete	4	Fair	0.75	1.45	5	6	Yes	No	Yes	No	Yes	
E	OAK	ST	E	7TH	ST	E	8TH	ST	Concrete	4	Fair	0.95	1.90	5	6	Yes	No	Yes	No	Yes	
E	OAK	ST		THOMAS	AVE		JAY	ST	Concrete	4	Fair	0.65	0.30	5	5	Yes	No	Yes	No	Yes	
E	OAK	ST		JAY	ST		SILVER	ST	Concrete	4	Fair	0.65	1.70	5	5	Yes	No	Yes	No	Yes	
E	OAK	ST		JAY	ST		SILVER	ST	Concrete	4	Fair	0.50	2.00	4	5	Yes	Yes	Yes	No	Yes	
E	OAK	ST	E	18TH	ST		THOMAS	AVE	Concrete	4	Fair	4.15	2.15	5	5	Yes	Yes	Yes	Yes	No	
E	OAK	ST		VINCENNES	ST		THOMAS	AVE	Concrete	4	Fair	0.75	1.80	5	5	Yes	No	Yes	No	Yes	
E	OAK	ST	E	15TH	ST		VINCENNES	ST	Concrete	4	Fair	0.50	2.70	5	5	Yes	No	Yes	No	No	
E	OAK	ST	E	15TH	ST		VINCENNES	ST	Concrete	4	Fair	0.15	2.70	4	5	Yes	No	Yes	No	No	
E	OAK	ST	E	9TH	ST	E	10TH	ST	Concrete	3	Poor	0.75	0.75	4	6	Yes	Yes	Yes	No	Yes	
E	OAK	ST	E	10TH	ST	E	13TH	ST	Asphalt	3	Poor	1.45	0.95	8	12	Yes	No	Yes	Yes	Yes	
E	OAK	ST	E	11TH	ST	E	13TH	ST	Concrete	3	Poor	2.25	3.10	4	5	Yes	No	Yes	Yes	No	
E	OAK	ST	E	13TH	ST	E	15TH	ST	Concrete	3	Poor	0.15	2.00	5	5	Yes	No	Yes	No	Yes	
E	OAK	ST	E	4TH	ST	E	5TH	ST	Concrete	3	Poor	0.25	4.25	4	5	Yes	No	Yes	No	No	
E	OAK	ST	E	5TH	ST	E	7TH	ST	Concrete	3	Poor	1.10	3.05	4	5	Yes	No	Yes	No	No	
E	OAK	ST		SILVER	ST		INDIANA	AVE	Concrete	3	Poor	10.65	1.80	4	4	Yes	No	No		No	
E	OAK	ST		STATE	ST		PEARL	ST	Concrete	3	Poor	1.45	4.50	4	6	Yes	Yes	Yes	No	No	
W	OAK	ST	W	1ST	ST		STATE	ST	Concrete	3	Poor	1.00	1.65	5	7	Yes	Yes	Yes	No	Yes	
E	OAK	ST		INDIANA	AVE		DEAD END		Concrete	3	Poor	3.90	6.55	4	4	No		No		No	
W	OAK	ST		SCRIBNER	DR	W	1ST	ST	Concrete	2	Very Poor	11.80	2.15	5	6	Yes	No	Yes	Yes	No	
E	OAK	ST		BANK	ST	E	3RD	ST	Concrete	2	Very Poor	1.20	2.80	4	5	Yes	No	No		No	
E	OAK	ST	E	3RD	ST	E	4TH	ST	Concrete	2	Very Poor	0.50	1.70	4	5	No		Yes	No	Yes	
E	OAK	ST	E	4TH	ST	E	5TH	ST	Concrete	2	Very Poor	0.85	4.10	5	6	Yes	No	Yes	No	No	
E	OAK	ST	E	8TH	ST	E	9TH	ST	Concrete	2	Very Poor	3.30	1.90	4	5	Yes	No	Yes	No	Yes	
E	OAK	ST	E	8TH	ST	E	9TH	ST	Concrete	2	Very Poor	0.40	1.35	4	5	Yes	No	Yes	No	Yes	
E	OAK	ST		SILVER	ST		INDIANA	AVE	Concrete	2	Very Poor	9.70	1.00	4	4	Yes	No	No		No	
E	OAK	ST		STATE	ST		PEARL	ST	Concrete	2	Very Poor	0.60	4.50	4	6	Yes	Yes	Yes	No	No	
W	OAK	ST	W	1ST	ST		STATE	ST	Concrete	2	Very Poor	22.95	6.10	4	6	No		Yes	Yes	No	
E	OAK	ST		INDIANA	AVE		DEAD END		Concrete	2	Very Poor	1.70	2.05	4	4	No		No		No	
E	OAK	ST		BANK	ST	E	4TH	ST	Concrete	1	PastServiceLife	2.40	2.50	3	5	Yes	No	Yes	No	No	
E	OAK	ST		PEARL	ST		BANK	ST	Concrete	1	PastServiceLife	9.40	1.80	4	5	Yes	No	Yes	No	No	
	OAKWOOD	CT		GREENWOOD	CT		ASHWOOD	DR	Concrete	4	Fair	0.30	3.50	3	4	No		No		No	
	OAKWOOD	CT		DEAD END			ASHWOOD	DR	Concrete	3	Poor	1.90	1.60	3	5	No		No		Yes	
	OAKWOOD	CT		DEAD END			GREENWOOD	CT	Concrete	3	Poor	0.50	0.20	2	3	No			No	Yes	
E	OAKWOOD	DR		MT TABOR	RD		PENNWOOD	DR	Concrete	3	Poor	0.65	0.30	4	5	No		Yes	Yes	Yes	
W	OAKWOOD	DR		MT TABOR	RD		PENNWOOD	DR	Concrete	2	Very Poor	8.65	5.15	4	5	No		Yes	Yes	No	
W	OAKWOOD	DR		MT TABOR	RD		PENNWOOD	DR	Concrete	2	Very Poor	3.90	0.60	4	5	No		Yes	Yes	Yes	
E	OAKWOOD	DR		MT TABOR	RD		PENNWOOD	DR	Concrete	2	Very Poor	1.30	0.85	4	5	No		Yes	Yes	Yes	
	OLD FORD	RD		CHARLESTOWN	RD		DEAD END		Concrete	3	Poor	1.90	1.60	4	4	Yes	No	No		Yes	
	OLD FORD	RD		DEAD END			DEAD END		Concrete	2	Very Poor	3.90	2.40	4	4	No		No		No	
	OLD HICKORY	CT		HICKORYVALE	DR		HICKORYVALE	DR	Concrete	4	Fair	1.40	0.50	4	4	Yes	No	Yes	No	Yes	
	OLD KLERNER	LN		KLERNER	LN		PINE CREEK	CIR	Concrete	4	Fair	1.10	0.90	4	4	Yes	No	Yes	No	Yes	
	OLD VINCENNES	RD		DEAD END			CHERRY	ST	Concrete	2	Very Poor	1.40	1.40	10	3	No		No		Yes	
	OLIVE	AVE	N	PEARL	ST		BONO	RD	Concrete	5	Good	0.20	0.30	4	4	Yes	Yes	Yes	Yes	Yes	
	OLIVE	AVE	N	PEARL	ST		BONO	RD	Concrete	5	Good	0.20	1.10	4	4	Yes	Yes	Yes	Yes	Yes	
	OLIVE	AVE		STATE	ST	N	PEARL	ST	Concrete	5	Good	0.30	0.40	4	4	Yes	Yes	Yes	Yes	Yes	
	OLIVE	AVE		STATE	ST	N	PEARL	ST	Concrete	5	Good	0.80	0.80	4	4	Yes	Yes	Yes	Yes	Yes	
	OLIVE	ST		CAPTIAN FRANK	RD	VALLEY VIEW	CT		Concrete	3	Poor	2.40	0.40	4	4	Yes	No	Yes	No	Yes	
	OLIVE	ST		VALLEY VIEW	CT		ALLY		Concrete	2	Very Poor	2.60	0.20	4	4	Yes	No	No		Yes	
	PALMER	CT		COUNTRY CLUB	DR		COUNTRY CLUB	DR	Concrete	3	Poor	6.10	2.20	4	4	Yes	No	Yes	No	No	
	PAMELA	DR		GORDON	DR		DENNY	DR	Concrete	4	Fair	0.90	4.10	4	4	Yes	Yes	Yes	Yes	No	

Street Prefix	Street Name	Street Suffix	From Street Prefix	From Street Name	From Street Suffix	To Street Prefix	To Street Name	To Street Suffix	Surface Type	Condition	Description	Max Long Slope (%)	Max Cross Slope (%)	Width Min (ft)	Width Max (ft)	Curb Ramp From St	Curb Ramp From St ADA	Curb Ramp To St	Curb Ramp To St ADA	ADA Compliant	Comments
	PAMELA	DR		GORDON	DR		DENNY	DR	Concrete	3	Poor	0.30	2.00	4	4	Yes	Yes	Yes	Yes	Yes	
	PAMELA	DR		DEAD END	DR		DENNY	DR	Concrete	2	Very Poor	0.10	1.70	4	4	Yes	Yes	No		Yes	
	PARK	AVE		FAIR	ST		ANN	AVE	Concrete	2	Very Poor	0.80	3.10	4	6	Yes	No	No		No	
	PARK	AVE		FAIR	ST		ANN	AVE	Concrete	2	Very Poor	1.40	0.10	4	6	Yes	No	No		Yes	
	PARK	AVE		JOLLISAIN	AVE		FAIR	ST	Concrete	2	Very Poor	2.40	1.40	4	6	Yes	No	No		Yes	
	PARK	AVE		JOLLISAIN	AVE		FAIR	ST	Concrete	2	Very Poor	1.50	0.90	4	6	Yes	No	Yes		Yes	
	PARKEAST	BLVD		REAS	LN		PARKEAST	BLVD	Concrete	4	Fair	1.00	1.30	4	4	Yes	Yes	Yes	No	Yes	
	PARKEAST	BLVD		DEAD END			HAUSFELDT	LN	Concrete	3	Poor	0.50	1.40	4	4	No		Yes	No	Yes	
	PARKLINE	DR		PARKLINE	DR		PARKSIDE	DR	Concrete	3	Poor	0.10	1.70	4	4	No		No		Yes	
	PARKLINE	DR		HIGH PARK	DR		SHELL	LN	Concrete	3	Poor	0.40	4.20	4	4	Yes	Yes	Yes	Yes	No	
	PARKLINE	DR		PARKLINE	DR		SHELL	LN	Concrete	3	Poor	1.30	0.90	4	4	No		Yes	Yes	Yes	
	PARKLINE	DR		PARKSIDE	DR		SHELL	LN	Concrete	3	Poor	2.70	2.30	4	4	No		Yes	Yes	No	
	PARKSIDE	DR		PARKLINE	DR		SHELL	LN	Concrete	3	Poor	3.80	0.30	4	4	No		Yes	Yes	Yes	
	PARKSIDE	DR		PARKLINE	DR		SHELL	LN	Concrete	3	Poor	3.80	1.20	4	4	No		Yes	Yes	Yes	
	PEARL	ST		PEARL	ST		BANK	ST	Concrete	4	Fair	0.05	1.45	6	6	No		No		Yes	
	PEARL	ST	E	MARKET	ST	E	MAIN	ST	Brick	4	Fair	0.60	2.70	5	10	Yes	Yes			No	
	PEARL	ST	E	MARKET	ST	E	MAIN	ST	Brick	4	Fair	1.10	5.75	6	15	Yes	No			No	
	PEARL	ST	E	SPRING	ST		MARKET	ST	Brick	4	Fair	2.40	0.85	5	9	Yes	No	Yes	Yes	Yes	
	PEARL	ST	E	SPRING	ST	E	MARKET	ST	Brick	4	Fair	9.80	4.35	6	20	Yes	Yes	Yes	No	No	
	PEARL	ST	E	ELM	ST	E	SPRING	ST	Concrete	4	Fair	2.50	1.65	10	14	Yes	Yes	Yes	No	Yes	
	PEARL	ST	E	MAIN	ST		DEAD END		Brick	4	Fair	7.60	4.70	5	10	Yes	Yes	Yes	No	No	
	PEARL	ST		CULBERTSON	AVE	E	OAK	ST	Concrete	3	Poor	0.20	2.80	5	8	Yes	No	Yes	No	No	
	PEARL	ST	E	ELM	ST	E	SPRING	ST	Concrete	3	Poor	1.30	3.20	5	10	Yes	Yes	Yes	No	No	
	PEARL	ST		GRAYBROOK	LN		UNION	ST	Concrete	3	Poor	1.70	0.50	4	5	Yes	No	Yes	No	Yes	
	PEARL	ST	E	OAK	ST	E	ELM	ST	Concrete	2	Very Poor	0.95	3.30	5	11	Yes	No	Yes	No	No	
	PEARL	ST		UNION	ST		SUMMIT	AVE	Concrete	2	Very Poor	0.50	1.50	4	8	Yes	No	Yes	No	Yes	
	PEARL	ST	E	OAK	ST	E	ELM	ST	Concrete	1	PastServiceLife	1.30	3.20	6	12	Yes	No	Yes	No	No	
	PEARL	ST		PEARL	ST		BANK	ST	Concrete	4	Fair	1.30	5.05	5	5	No		No		No	
	PEARL	ST	E	MAIN	ST		PEARL	ST	Brick	4	Fair	8.35	3.75	5	12	Yes	Yes	No		No	
	PEARL	ST		CHERRY	ST	E	OAK	ST	Concrete	3	Poor	1.30	1.10	3.5	5	Yes	No	Yes	No	Yes	
	PEARL	ST		MONROE	S7T		CHERRY	ST	Concrete	2	Very Poor	3.90	1.60	4	5	Yes	No	Yes	No	Yes	
	PEARL	ST		SUMMIT	AVE		CULBERTSON	AVE	Concrete	2	Very Poor	8.20	1.10	4	5	Yes	No	Yes	No	No	
	PEARL	ST		UNION	ST		MONROE	ST	Concrete	2	Very Poor	0.20	1.60	3.5	4	Yes	No	Yes	No	Yes	
	PEBBLECREEK	CT		ROLLING CREEK	DR		ROLLING CREEK	DR	Concrete	3	Poor	5.30	0.60	4	4	No		No		Yes	
	PENNWOOD	DR		CASTLEWOOD	DR	W	OAKWOOD	DR	Concrete	4	Fair	0.80	4.40	4	5	No		Yes	No	No	
	PENNWOOD	DR		CASTLEWOOD	DR		BRENTWOOD	CT	Concrete	3	Poor	2.10	0.40	4	5	Yes	Yes	No		Yes	
	PENNWOOD	DR		DEERWOOD	DR		CLIFFWOOD	DR	Concrete	3	Poor	0.50	2.75	4	4	No		No		No	
	PENNWOOD	DR		BRENTWOOD	CT		DEERWOOD	DR	Concrete	3	Poor	8.80	3.20	4	5	No		No		No	
	PENNWOOD	DR	W	OAKWOOD	DR	E	OAKWOOD	DR	Concrete	3	Poor	8.35	0.75	4	4	No		No		No	
	PENNWOOD	DR	E	OAKWOOD	DR		CLIFFWOOD	DR	Concrete	2	Very Poor	4.25	2.05	4	4	No		No		No	
	PICKWICK	DR		SLATE RUN	RD		PICKWICK	DR	Concrete	4	Fair	1.30	2.60	4	4	Yes	Yes	No		No	
	PICKWICK	DR		SLATE RUN	RD		DEAD END		Concrete	4	Fair	0.20	0.60	4	4	Yes	Yes	No		Yes	
	PICKWICK	DR		DEAD END			DEAD END		Concrete	4	Fair	0.70	1.70	4	4	No		No		Yes	
	PIMLICO	DR		VENETIAN	WAY		LINDA	DR	Concrete	TBD	Good	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	Yes	
	PIMLICO	DR		VENETIAN	WAY		LINDA	DR	Concrete	TBD	Good	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	Yes	
	PIMLICO	DR		LINDA	DR		DEAD END		Concrete	TBD	Good	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	Yes	
	PIMLICO	DR		LINDA	DR		DEAD END		Concrete	TBD	Good	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	Yes	
	PINE CREEK	CIR		OLD KLERNER	LN		RAINBOW	DR	Concrete	3	Poor	0.90	0.30	4	4	Yes	No	Yes	No	Yes	
	PINEHURST	CT		NELSON	AV		NOB HILL	RD	Concrete	5	Good	1.60	1.30	4	4	Yes	No	No		Yes	
	PLAINFIELD	DR		FARMGATE	LN		MEADOWVIEW	DR	Concrete	4	Fair	1.40	0.10	4	4	Yes	No	Yes	No	Yes	
	PLAINFIELD	DR		FARMGATE	LN		MEADOWVIEW	DR	Concrete	4	Fair	1.00	0.80			Yes	No	Yes	No	Yes	
	PLAYER	PL		DEAD END			COUNTRY CLUB	DR	Concrete	2	Very Poor	2.70	2.30	4	4	Yes	No	No		No	
	PROFESSIONAL CT			DEAD END			CHARLESTOWN RD		Concrete	4	Fair	4.90	5.10	5	5	Yes	No	Yes	No	No	
	PROFESSIONAL CT			PROFESSIONAL CT			CHARLESTOWN RD		Concrete	4	Fair	5.10	3.50	4	4	Yes	No	Yes	No	No	
	PROFESSIONAL CT			CHARLESTOWN RD			PROFESSIONAL CT		Concrete	4	Fair	5.90	1.40	4	4	Yes	No	Yes	No	Yes	
	RAINBOW	DR		MONTY	DR		CHARLESTOWN	DR	Concrete	4	Fair	0.50	1.20	4	4	Yes	No	Yes	No	Yes	
	RAINBOW	DR		PINE CREEK	CIR		DALE BROOK	DR	Concrete	4	Fair	0.30	0.80	4	4	Yes	No	Yes	No	Yes	
	RAINBOW	DR		MARY DELL	CT		DALEBROOK	DR	Concrete	4	Fair	3.80	0.70	4	4	Yes	No	Yes	No	Yes	
	RAINBOW	DR		DALEBROOK	DR		LOLA DELL	CT	Concrete	4	Fair	2.80	0.80	4	4	Yes	No	Yes	No	Yes	
	RAINBOW	DR		OLD KLERNER	DR		LOLA DELL	CT	Concrete	4	Fair	1.00	0.10	4	4	Yes	No	Yes	No	Yes	
	RAINBOW	DR		LOLA DELL	CT		MARY DELL	CT	Concrete	4	Fair	4.40	0.50	4	4	Yes	No	Yes	No	Yes	
	RAINBOW	DR		DALE BROOK	DR		MONTY	DR	Concrete	4	Fair	1.40	0.30								

Street Prefix	Street Name	Street Suffix	From Street Prefix	From Street Name	From Street Suffix	To Street Prefix	To Street Name	To Street Suffix	Surface Type	Condition	Condition Description	Max Long Slope (%)	Max Cross Slope (%)	Width Min (ft)	Width Max (ft)	Curb Ramp From St	Curb Ramp From St ADA	Curb Ramp To St	Curb Ramp To St ADA	ADA Compliant	Comments
	ROANOKE	AVE		DEAD END			FAIRMONT	AVE	Concrete	2	Very Poor	0.50	0.20	4	5	Yes	No	Yes	No	Yes	
	Roanoke	Ave		McDonald	Lane		Scheller	Lane	Concrete	2	Very Poor	1.70	2.30	4	4	Yes	No	Yes	No	No	
	ROLLING CREEK	DR		PEBBLE CREEK	CT		CREEKWOOD	CT	Concrete	3	Poor	2.30	3.40	4	4	Yes	No	Yes	No	No	
	ROLLING CREEK	DR		DEAD END			GRANT LINE	RD	Concrete	3	Poor	1.60	0.20	4	4	No		Yes	No	Yes	
	ROLLING CREEK	DR		CREEKWOOD	CT		SLATE CREEK	CT	Concrete	3	Poor	1.70	0.30	4	4	Yes	No	Yes	No	Yes	
	ROLLING CREEK	DR		PEBBLE CREEK	CT		DEAD END		Concrete	3	Poor	3.10	4.20	4	4	No		No		No	
	ROOSEVELT	AVE		LOPP	AVE		CHARLESTOWN	RD	Concrete	2	Very Poor	0.60	1.60	4	4	Yes	No	Yes	No	Yes	
	ROOSEVELT	AVE		LOPP	AVE		CHARLESTOWN	RD	Concrete	1	PastServiceLife	0.20	3.70	4	4	Yes	No	Yes	No	No	
	ROSEVIEW	TER	E	DAISY	LN	E	DAISY	LN	Concrete	3	Poor	0.30	2.30	4	4	Yes	No	Yes	No	No	
	ROSEVIEW	TER	E	DAISY	LN		ROSEVIEW	TER	Concrete	3	Poor	8.30	0.30	4	4	Yes	No	No		No	
	ROSEVIEW	TER		ROSEVIEW	TER		DEAD END		Concrete	3	Poor	3.20	1.70	4	4	No		No		Yes	
	ROSEVIEW	TER		ROSEVIEW	TER	E	DAISY	LN	Concrete	2	Very Poor	2.80	0.20	4	4	No		Yes	No	Yes	
	ROSS	DR		KORB	AVE		DEAD END		Concrete	2	Very Poor	8.70	4.70	4	4	No		No		No	
	ROSS	DR		MARY ANN	DR		DEAD END		Concrete	1	PastServiceLife	6.90	2.70	4	4	No		No		No	
	ROSS	DR		KORB	AVE		MARY ANN	DR	Concrete	1	PastServiceLife	7.25	1.30	4	4	No		No		Yes	
	ROYAL	CT		DEAD END			GREEN VALLEY	RD	Concrete	5	Good	0.90	3.40	4	4	No		Yes	No	No	
	ROYAL	CT		DEAD END			GREEN VALLEY	RD	Concrete	5	Good	1.10	3.30	4	4	No		Yes	No	No	
	SADDLEWOOD	CT		WATKINS PRAIRIE	LN		WEBERPAL	CIR	Concrete	3	Poor	1.10	2.00	4	4	Yes	No	Yes	No	Yes	
	SADDLEWOOD	CT		WEBERPAL	CIR		WATKINS PRAIRIE	LN	Concrete	2	Very Poor	0.50	1.70	4	4	No		Yes	No	Yes	
	SAVANNAH	DR		KLERNER	LN		LAFAYETTE	DR	Concrete	2	Very Poor	1.70	6.30	4	5	No		No		No	
	SAVANNAH	DR		LAFAYETTE	LN		LAFAYETTE	DR	Concrete	2	Very Poor	0.20	1.20	4	5	No		No		Yes	
	SAVANNAH	DR		LAFAYETTE	DR		LAFAYETTE	DR	Concrete	2	Very Poor	0.40	1.10	3.5	4.5	Yes	No	No		Yes	
	SCHELL	LN		LONG	CT		BROOKRIDGE	CIR	Concrete	5	Good	3.50	0.50	4	4	Yes	Yes	Yes	Yes	Yes	
	SCHELL	LN		TYLER	DR		CLARA LEE	CT	Concrete	5	Good	1.80	1.70	4	4	Yes	Yes	Yes	Yes	Yes	
	SCHELL	LN		CLARA LEE	CT	E	DAISY	LN	Concrete	5	Good	1.50	1.20	4	4	Yes	Yes	Yes	Yes	Yes	
	SCHELL	LN		DEAD END		E	DAISY	LN	Concrete	5	Good	1.50	0.50	4	4	Yes	Yes	Yes	Yes	Yes	
	SCHELL	LN		ALAN	DR		LONG	CT	Concrete	5	Good	4.20	1.20	4	4	Yes	Yes	Yes	Yes	Yes	
	SCHELL	LN		BROOKRIDGE	CIR		TYLER	DR	Concrete	5	Good	3.70	1.40	4	4	Yes	Yes	Yes	Yes	Yes	
	SCHELL	LN		PARKSIDE	DR		PARKLINE	DR	Concrete	4	Fair	0.70		4	4	Yes	Yes	Yes	Yes	Yes	
	SCHELL	LN		PARKLINE	DR		ALAN	DR	Concrete	3	Poor	3.50	2.10	4	4	Yes	Yes	Yes	Yes	No	
	SCHELL	LN		PARKLINE	DR		PARKSIDE	DR	Concrete	3	Poor	3.90	0.30	4	4	Yes	Yes	Yes	Yes	Yes	
	SCHELLER	LN		KNOB VIEW	AVE		DEAD END		Concrete	4	Fair	2.00	0.80	4	4	No		No		Yes	
	SCHELLER	LN		DEAD END			CHARLESTOWN	RD	Concrete	3	Poor	1.70	1.60	4	4	No		Yes	No	Yes	
	SCHELLER	LN		DEAD END			ROANOKE	AVE	Concrete	2	Very Poor	0.80	3.10	4	4	No		Yes	No	No	
	SCOTT	RD		DEAD END			HICKORYVALE	DR	Concrete	3	Poor	0.70	3.30	4	4	No		No		No	
	SCRIBNER	DR	W	MARKET	ST	W	MAIN	ST	Concrete	4	Fair	1.50	2.50	5	11	Yes	No	Yes	No	No	
	SCRIBNER	DR	W	SPRING	ST	W	MARKET	ST	Concrete	4	Fair	0.65	0.85	11	11	Yes	No	Yes	No	Yes	
	SCRIBNER	DR	W	ELM	ST	W	SPRING	ST	Concrete	4	Fair	2.50	4.25	6	12	Yes	No	No		No	
	SCRIBNER	DR	W	ELM	ST	W	SPRING	ST	Concrete	4	Fair	0.65	3.30	7	12	No		Yes	No	No	
	SCRIBNER	DR	W	OAK	ST	E	ELM	ST	Concrete	3	Poor	1.00	5.15	6	6	No		Yes	No	No	
	SCRIBNER	DR	W	SPRING	ST	W	MARKET	ST	Concrete	3	Poor	2.00	5.55	5	11			Yes	No	No	
	SCRIBNER	DR	W	MARKET	ST	W	1ST	ST	Concrete	2	Very Poor	0.65	2.40	6	12	Yes	No	Yes	No	No	
	SECURITY PKWY			GRANT LINE RD			FOUNDATION BLVD		Concrete	4	Fair	3.10	2.10	4	4	Yes	Yes	Yes	Yes	No	
	SERENITY SPRINGS	DR		CHARLESTOWN	RD		CHARLESTOWN	RD	Concrete	5	Good	3.00	0.20	4	4	No		No		Yes	
	SHELBY	PL	E	15TH	ST		VINCENNES	ST	Concrete	5	Good	2.10	1.80	5	5	Yes	Yes	Yes	Yes	Yes	
	SHELBY	ST		MCDONALD	AVE		KORB	AVE	Concrete	4	Fair	1.00	2.50	4	5	Yes	No	Yes	No	No	
	SHELBY	ST		INDIANA	AVE		MCDONALD	AVE	Concrete	4	Fair	0.05	1.10	4	5	No		Yes	No	Yes	
	SHELBY	PL	E	15TH	ST		DEAD END		Concrete	4	Fair	1.20	1.60	5	5	Yes	No	Yes	No	Yes	
	SHELBY	ST		VINCENNES	ST		NEW ALBANY HS		Concrete	3	Poor	5.50	6.60	6	6	Yes	No	Yes	Yes	No	
	SHELBY	ST		THOMAS	AVE		DEAD END		Concrete	3	Poor	0.95	3.45	3	3	Yes	No	No		No	
	SHELBY	ST		SILVER	ST		INDIANA	AVE	Concrete	2	Very Poor	1.70	5.55	4	5	Yes	No	No		No	
	SHELBY	ST		MCDONALD	AVE		KORB	AVE	Concrete	2	Very Poor	0.50	2.10	4	4	No		Yes	No	No	
	SHELBY	ST		INDIANA	AVE		MCDONALD	AVE	Concrete	2	Very Poor	1.20	1.70	4	5	No		No		Yes	
	SHELBY	ST		VINCENNES	ST		DEAD END		Concrete	2	Very Poor	1.65	1.35	5	6	Yes	No	No		Yes	
	SHELBY	ST		SILVER	ST		INDIANA	AVE	Concrete	1	PastServiceLife	0.85	3.10	4	4	Yes	No	No		No	
	SHELBY	ST		KORB	AVE		SLATE RUN	RD	Concrete	1	PastServiceLife	1.90	1.70	4	4	Yes	Yes	Yes	No	Yes	
	SHELBY	ST		KORB	AVE		SLATE RUN	RD	Concrete	1	PastServiceLife	0.50	3.10	4	4	Yes	No	Yes	No	No	
	SHELBY	ST		NEW ABLANY HS			THOMAS	AVE	Concrete	1	PastServiceLife	3.30	1.55	5	5	Yes	Yes	Yes	No	Yes	
	SHELBY	ST		DEAD END			THOMAS	AVE	Concrete	1	PastServiceLife	2.00	0.40	4	4	No		Yes	No	Yes	
	SHELBY	ST		DEAD END			DEAD END		Concrete	1	PastServiceLife	2.60	6.70	4	4	No		No		No	
	SHERLEY	ST		WEST	ST		CRYSTAL	AVE	Concrete	2	Very Poor	0.40	5.30	3	4	Yes	No	No		No	
	SHERLEY	ST		CRYSTAL	AVE		NAGHEL	ST	Concrete	2	Very Poor	0.60	1.90	4	4	Yes	No	No		Yes	
	SHORT MINTON	DR		MINTON	DR		WOODLAND	DR	Concrete	3	Poor	2.30	2.60	4	4	No		No		No	
	SHRADER	AVE		DEAD END			MCDONALD	AVE	Concrete	1	PastServiceLife	0.20	2.70	3	4	No		Yes	No	No	
	SHRADER	AVE		DEAD END			MCDONALD	AVE	Concrete	1	PastServiceLife	1.10	2.50	5	4	No		No		No	
	SIDNEY	CT		JAFFERY	DR		JAFFERY	DR	Concrete	3	Poor	4.60	3.10	4	4	Yes	No	Yes	No	No	
	SILVER	ST		AEBERSOLD	DR		AEBERSOLD	CT	Concrete	4	Fair	1.10	1.40	4	4	Yes	No	Yes	No	Yes	
	SILVER	ST		LOCUST	ST		BEELER	ST	Concrete	4	Fair	0.30	0.30	4	4	Yes	No	Yes	No	Yes	
	SILVER	ST		MCLEAN	AVE		BEELER	ST	Concrete	4	Fair	0.40	3.30	4	4	Yes	No	Yes	No	No	
	SILVER	ST		EKIN	AVE		CULBERTSON	AVE	Concrete	4	Fair	0.90	1.10	4	4	Yes	No	Yes	No	Yes	
	SILVER	ST		EKIN	AVE		CULBERTSON	AVE	Concrete	4	Fair	2.40	1.20	4	4	Yes	No	Yes	Yes	Yes	
	SILVER	ST		BEELER	ST		EKIN	AVE	Concrete	4	Fair	0.90	2.30	4	6	Yes	No	Yes	No	No	
	SILVER	ST	E	OAK	ST	E	ELM	ST	Concrete	4	Fair	0.70	1.60	4	4	Yes	No	Yes	No	Yes	
	SILVER	ST		AEBERSOLD	CT		LOCUST	ST	Concrete	4	Fair	0.10	2.20	4	4	Yes	No	Yes	No	No	
	SILVER	ST		DIVISION	ST	E	MARKET	ST	Concrete	4	Fair	0.60		6	6	Yes	No	Yes	No	No	
	SILVER	ST		MORTON	AVE		MCLEAN	AVE	Concrete	4	Fair	0.90	2.40	4	4	Yes	No	Yes	No	No	
	SILVER	ST		SLATE RUN	RD	E	OAK	ST	Concrete	4	Fair	0.60	1.80	4	4	Yes	No	Yes	No	Yes	
	SILVER	ST		BEELER	ST		SHELBY	ST	Concrete	4	Fair	0.70	1.80	4	4	Yes	No	Yes	No	Yes	
	SILVER	ST		CULBERTSON	AVE		SLATE RUN	RD	Concrete	4	Fair	0.30	1.10	4	4	Yes	Yes	Yes	No	Yes	
	SILVER	ST		CHARLESTOWN	RD		AEBERSOLD	DR	Concrete	3	Poor	1.60	0.30	4	4	Yes	No	Yes	No	Yes	
	SILVER	ST		SHRADER	AVE		ALLY		Concrete	3	Poor	2.40	2.20	4	6	Yes	No	Yes	No	No	

Street Prefix	Street Name	Street Suffix	From Street Prefix	From Street Name	From Street Suffix	To Street Prefix	To Street Name	To Street Suffix	Surface Type	Condition	Condition Description	Max Long Slope (%)	Max Cross Slope (%)	Width Min (ft)	Width Max (ft)	Curb Ramp From St	Curb Ramp From St ADA	Curb Ramp To St	Curb Ramp To St ADA	ADA Compliant	Comments
	SILVER	ST		SHRADER	AVE		ALLY		Concrete	3	Poor	2.10	2.10	4	6	Yes	No	No		No	
	SILVER	ST	E	MARKET	ST		ALTHEA	AVE	Concrete	3	Poor	2.40	1.90	5	5	Yes	No	Yes	No	Yes	
	SILVER	ST	E	ELM	ST		BEECHWOOD	AVE	Concrete	3	Poor	1.10	3.60	4	4	Yes	No	No		No	
	SILVER	ST		WOOD	AVE		CARLTON	DR	Concrete	3	Poor	5.10	2.30	4	4	Yes	No	Yes	No	No	
	SILVER	ST	E	SPRING	ST		DIVISION	ST	Concrete	3	Poor	1.30	1.90	4	4	Yes	No	Yes	No	Yes	
	SILVER	ST		SHELBY	ST		EKIN	AVE	Concrete	3	Poor	0.60	4.00	4	4	Yes	No	Yes	No	No	
	SILVER	ST	E	OAK	ST	E	ELM	ST	Concrete	3	Poor	1.30	1.20	4	4	Yes	No	Yes	No	Yes	
	SILVER	ST		CARLTON	DR		LAKE	ST	Concrete	3	Poor	2.40	2.10	4	4	Yes	No	Yes	No	No	
	SILVER	ST		ALTHEA	AVE	E	MAIN	ST	Concrete	3	Poor	7.20	2.80	5	5	Yes	No	No		No	
	SILVER	ST		WILLOW	ST	E	MAIN	ST	Concrete	3	Poor	3.00	1.90	5	5	Yes	No	Yes	No	Yes	
	SILVER	ST		RENO	AVE	E	MARKET	ST	Concrete	3	Poor	0.50	1.60	4	4	Yes	No	Yes	No	Yes	
	SILVER	ST		WILLARD	AVE		MORTON	AVE	Concrete	3	Poor	0.20	2.10	4	4	Yes	No	Yes	No	No	
	SILVER	ST		CULBERTSON	AVE	E	OAK	ST	Concrete	3	Poor	0.50	2.10	4	8	Yes	No	Yes	Yes	No	
	SILVER	ST		BEECHWOOD	AVE	E	SPRING	ST	Concrete	3	Poor	1.30	3.20	4	4	No		Yes	Yes	No	
	SILVER	ST	E	ELM	ST	E	SPRING	ST	Concrete	3	Poor	2.20	1.80	4	4	Yes	No	Yes	No	Yes	
	SILVER	ST	E	MARKET	ST		WILLOW	ST	Concrete	3	Poor	2.40	1.60	4	5	Yes	No	Yes	No	Yes	
	SILVER	ST		CHARLESTOWN	RD		WOOD	AVE	Concrete	3	Poor	4.00	0.90	3	4	Yes	No	Yes	No	Yes	
	SILVER	ST		ROANOKE	AVE		FAIRMONT	AVE	Concrete	2	Very Poor	0.90	0.70	4	5	Yes	No	Yes	No	Yes	
	SILVER	ST	E	SPRING	ST		RENO	AVE	Concrete	2	Very Poor	1.40	6.10	4	4	Yes	No	Yes	No	No	
	SILVER	ST		DEAD END			ROANOKE	AVE	Concrete	2	Very Poor	0.50	4.70	4	5	Yes	No	No		No	
	SILVER	ST		DEAD END			ROANOKE	AVE	Concrete	2	Very Poor	0.70	2.30	4	5	Yes	No	No		No	
	SILVER	ST		FAIRMONT	AVE		SHRADER	AVE	Concrete	2	Very Poor	1.70	0.50	4	5	Yes	No	Yes	No	Yes	
	SILVER	ST		FAIRMONT	AVE		SHRADER	AVE	Concrete	2	Very Poor	1.30	0.80	4	5	Yes	No	Yes	No	Yes	
	SILVER	ST		LAKE	ST		WILLARD	AVE	Concrete	4	Fair	0.20	1.50	4	4	Yes	No	Yes	No	Yes	
	SILVER SLATE	DR		SLATE RUN	RD		END		Concrete	3	Poor	0.10	0.10	4	4	Yes	No	No		Yes	
	SILVER SLATE	DR		SLATE RUN	RD		END		Concrete	3	Poor	0.30	1.70	4	4	Yes	No	No		Yes	
	SLATE CREEK	CT		DEAD END			ROLLING CREEK	DR	Concrete	4	Fair	1.30	3.30	4	4	Yes	No	Yes	No	No	
	SLATE RUN	RD		MEADOW	LN		EASTWOOD	AVE	Concrete	5	Good	0.70	0.50	4	4	Yes	Yes	Yes	Yes	Yes	
	SLATE RUN	RD		CHARLESTOWN	RD		GARRETSON	LN	Concrete	5	Good	3.50	1.20	4	4	Yes	Yes	Yes	Yes	Yes	
	SLATE RUN	RD		GARRETSON	LN		LAIB	DR	Concrete	5	Good	1.30	0.10	4	4	Yes	Yes	Yes	Yes	Yes	
	SLATE RUN	RD		PICK WICK	DR		MEADOW	LN	Concrete	5	Good	1.40	0.80	4	4	Yes	Yes	Yes	Yes	Yes	
	SLATE RUN	RD		DEAD END			PICK WICK	DR	Concrete	5	Good	0.40	0.20	4	4	Yes	Yes	Yes	Yes	Yes	
	SLATE RUN	RD		EASTWOOD	AVE		DEAD END		Concrete	5	Good	0.40	0.90	4	6	Yes	Yes	No		Yes	
	SLATE RUN	RD		LAIB	DR		HARRIET	CT	Concrete	4	Fair	0.50	0.70	4	5	Yes	Yes	No		Yes	
	SLATE RUN	RD		HARRIET	CT		SUMMIT	AVE	Concrete	4	Fair	0.40	0.60	4	4	No		No		Yes	
	SLATE RUN	RD		BEELER	ST		SHELBY	ST	Concrete	3	Poor	5.15	2.65	4	5	Yes	No	Yes	No	No	
	SLATE RUN	RD		SILVER SLATE	DR		DEAD END		Concrete	3	Poor	7.70	2.30	4	4	Yes	No	No		No	
	SLOEMER	AVE		VINE	ST		BONO	RD	Concrete	2	Very Poor	0.50	0.10	3.5	4	Yes	No	Yes	No	Yes	
	SLOEMER	AVE		STATE	ST		VINE	ST	Concrete	2	Very Poor	0.40	0.20	3	4	Yes	No	Yes	No	Yes	
	SLOEMER	AVE		VINE	ST		BONO	RD	Concrete	1	PastServiceLife	1.60	2.20	3	4	Yes	No	Yes	No	No	
	SLOEMER	AVE		STATE	ST		VINE	ST	Concrete	1	PastServiceLife	1.00	4.70	3	4	No		Yes	No	No	
	SOUTH	ST		LOPP	AVE		CHARLESTOWN	RD	Concrete	2	Very Poor	1.40	2.60	4	4	Yes	Yes	Yes	No	No	
	SOUTH	ST		LOPP	AVE		CHARLESTOWN	RD	Concrete	2	Very Poor	1.60	1.70	4	4	Yes	Yes	Yes	No	Yes	
	SOUTH	ST		MONON	AVE		LOPP	AVE	Concrete	2	Very Poor	0.50	1.70	4	4	No		Yes	Yes	Yes	
	SOUTH	ST		MONON	AVE		LOPP	AVE	Concrete	2	Very Poor	1.40	2.60	4	4	No		Yes	Yes	No	
	SOUTH	ST		GRANT LINE	RD		DEAD END		Concrete	2	Very Poor	2.10	5.80	4	4	Yes	No	No		No	
	SOUTH	ST		GRANT LINE	RD		DEAD END		Concrete	1	PastServiceLife	0.90	4.20	4	4	Yes	No	No		No	
W	SPRING	ST		WASHINGTON	PL		SCRIBNER	DR	Concrete	TBD	Good	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	Yes	
E	SPRING	ST	E	3RD	ST	E	4TH	ST	Concrete	5	Good	0.65	1.80	6	12	Yes	Yes	Yes	No	Yes	
E	SPRING	ST	E	3RD	ST	E	4TH	ST	Concrete	5	Good	0.95	1.70	8	12	Yes	Yes	Yes	No	Yes	
E	SPRING	ST	E	4TH	ST	E	5TH	ST	Concrete	5	Good	1.80	1.45	4	10	Yes	No	Yes	No	Yes	
E	SPRING	ST	E	5TH	ST	E	6TH	ST	Concrete	5	Good	3.40	0.60	6	10	Yes	Yes	Yes	Yes	Yes	
E	SPRING	ST		STATE	ST		PEARL	ST	Concrete	5	Good	2.15	2.60	8	12	Yes	No	Yes	Yes	No	
E	SPRING	ST		BEHARRELL	AVE		DEAD END		Concrete	5	Good	2.70	1.00	5	5	Yes	Yes	No		Yes	
E	SPRING	ST	E	9TH	ST	E	10TH	ST	Concrete	4	Fair	1.00	5.15	8	12	Yes	No	Yes	No	No	
E	SPRING	ST	E	9TH	ST	E	10TH	ST	Concrete	4	Fair	0.85	1.90	8	8	Yes	No	Yes	No	Yes	
E	SPRING	ST	E	10TH	ST	E	11TH	ST	Concrete	4	Fair	0.10	0.20	8	8	Yes	No	Yes	No	Yes	
E	SPRING	ST		VINCENNES	ST	E	18TH	ST	Concrete	4	Fair	0.10	1.00	8	12	Yes	No	Yes	No	Yes	
W	SPRING	ST		SCRIBNER	DR	W	1ST	ST	Concrete	4	Fair	6.90	5.15	6	10	Yes	No	Yes	No	No	
E	SPRING	ST		BANK	ST	E	3RD	ST	Concrete	4	Fair	1.10	1.10	8	10	Yes	Yes	Yes	No	Yes	
E	SPRING	ST		BANK	ST	E	3RD	ST	Concrete	4	Fair	1.65	2.25	6	10	Yes	Yes	Yes	No	No	
E	SPRING	ST	E	4TH	ST	E	5TH	ST	Concrete	4	Fair	2.40	4.00	8	12	Yes	Yes	Yes	Yes	No	
W	SPRING	ST	W	6TH	ST	W	5TH	ST	Concrete	4	Fair	2.05	1.10	6	7	Yes	No	Yes	No	Yes	
W	SPRING	ST	W	6TH	ST	W	5TH	ST	Concrete	4	Fair	2.70	1.70	8	10	Yes	No	Yes	No	Yes	
E	SPRING	ST		PEARL	ST		BANK	ST	Concrete	4	Fair	0.15	0.95	7	12	Yes	No	Yes	No	Yes	
E	SPRING	ST		PEARL	ST		BANK	ST	Concrete	4	Fair	3.45	2.00	7	12	Yes	No	Yes	Yes	Yes	
E	SPRING	ST		WOODROW	AVE		BEHARRELL	AVE	Concrete	4	Fair	0.80	0.90	4	5	Yes	No	Yes	Yes	Yes	
E	SPRING	ST		WOODROW	AVE		BEHARRELL	AVE	Concrete	4	Fair	1.40	3.00	4	4	Yes	No	Yes	No	No	
E	SPRING	ST		SPRING	AVE		COST	AVE	Concrete	4	Fair	0.70	1.10	4	4	Yes	No	Yes	No	Yes	
E	SPRING	ST		JAY	ST		SILVER	ST	Concrete	4	Fair	1.30	1.40	8	8	Yes	No	Yes	No	Yes	
W	SPRING	ST	W	1ST	ST		STATE	ST	Concrete	4	Fair	11.90	3.10	6	12	Yes	No	Yes	Yes	No	
W	SPRING	ST	W	1ST	ST		STATE	ST	Concrete	4	Fair	1.45	1.70	6	12	Yes	No	Yes	Yes	Yes	
E	SPRING	ST	E	18TH	ST		THOMAS	AVE	Concrete	4	Fair	0.30	1.50	8	8	Yes	Yes	Yes	No	Yes	
E	SPRING	ST		COST	AVE		WOODROW	AVE	Concrete	4	Fair	0.90	1.60	4	4	Yes	No	Yes	No	Yes	
	SPRING	AVE	E	SPRING	ST		WOODROW	AVE	Concrete	4	Fair	2.50	5.00	4	4	Yes	No	Yes	No	No	
E	SPRING	SR	E	10TH	ST	E	11TH	ST	Concrete	3	Poor	1.00	0.50	8	8	Yes	No	Yes	No	Yes	
E	SPRING	ST	E	11TH	ST	E	13TH	ST	Concrete	3	Poor	0.60	0.50	8	12	Yes	No	Yes	No	Yes	
E	SPRING	ST	E	11TH	ST	E	13TH	ST	Concrete	3	Poor	2.40	0.80	8	8	Yes	No	Yes	No	Yes	
E	SPRING	ST	E	13TH	ST	E	15TH	ST	Concrete	3	Poor	0.60	0.20	8	8	Yes	No	Yes	No	Yes	
E	SPRING	ST	E	13TH	ST	E	15TH	ST	Concrete	3	Poor	0.60	0.30	8	12	Yes	No	Yes	No	Yes	
E	SPRING	ST		VINCENNES	ST	E	18TH	ST	Concrete	3	Poor	0.60	1.00	8	8	Yes	Yes	Yes	Yes	Yes	

Street Prefix	Street Name	Street Suffix	From Street Prefix	From Street Name	From Street Suffix	To Street Prefix	To Street Name	To Street Suffix	Surface Type	Condition	Condition Description	Max Long Slope (%)	Max Cross Slope (%)	Width Min (ft)	Width Max (ft)	Curb Ramp From St	Curb Ramp From St ADA	Curb Ramp To St	Curb Ramp To St ADA	ADA Compliant	Comments
W	SPRING	ST		SCRIBNER	DR	W	1ST	ST	Concrete	3	Poor	0.15	7.50	10	14	Yes	No	Yes	No	No	
W	SPRING	ST	W	5TH	ST	W	4TH	ST	Concrete	3	Poor	0.50	3.75	8	8	Yes	No	Yes	No	No	
E	SPRING	ST	E	6TH	ST	E	5TH	ST	Concrete	3	Poor	1.35	3.80	8	12	Yes	No	Yes	No	No	
W	SPRING	ST	W	7TH	ST	W	6TH	ST	Concrete	3	Poor	1.00	5.15	6	7	Yes	Yes	Yes	No	No	
W	SPRING	ST	W	7TH	ST	W	6TH	ST	Concrete	3	Poor	1.45	2.40	8	8	Yes	Yes	Yes	No	No	
E	SPRING	ST	E	6TH	ST	E	7TH	ST	Concrete	3	Poor	2.85	4.10	8	12	Yes	No	Yes	No	No	
W	SPRING	ST	W	8TH	ST	W	7TH	ST	Concrete	3	Poor	1.20	2.60	6	5	Yes	No	Yes	Yes	No	
W	SPRING	ST	W	8TH	ST	W	7TH	ST	Concrete	3	Poor	1.45	0.30	8	8	No		Yes	Yes	Yes	
E	SPRING	ST	E	7TH	ST	E	8TH	ST	Concrete	3	Poor	0.60	1.00	10	12	Yes	No	Yes	No	Yes	
E	SPRING	ST	E	7TH	ST	E	9TH	ST	Concrete	3	Poor	0.95	3.45	8	10	Yes	No	Yes	No	No	
E	SPRING	ST	E	8TH	ST	E	9TH	ST	Concrete	3	Poor	0.15	4.45	8	12	Yes	No	Yes	No	No	
E	SPRING	ST		SILVER	ST		BEST	AVE	Concrete	3	Poor	0.20	0.90	4	5	Yes	No	Yes	No	Yes	
E	SPRING	SR		BEST	AVE		COST	AVE	Concrete	3	Poor	2.50	0.50	4	4	Yes	No	Yes	No	Yes	
	SPRING	AVE	E	SPRING	ST		COST	AVE	Concrete	3	Poor	1.70	2.40	4	4	Yes	No	Yes	No	No	
E	SPRING	ST		THOMAS	AVE		JAY	ST	Concrete	3	Poor	0.50	1.30	8	8	Yes	No	Yes	No	Yes	
E	SPRING	ST		STATE	ST		PEARL	ST	Concrete	3	Poor	0.50	2.40	10	12			Yes	Yes	Yes	
E	SPRING	ST		STATE	ST		PEARL	ST	Concrete	3	Poor	0.65	5.15	6	12			Yes	Yes	No	
E	SPRING	ST		JAY	ST		SILVER	ST	Concrete	3	Poor	0.60	1.30	8	8	Yes	No	Yes	No	Yes	
E	SPRING	ST		SILVER	ST		SPRING	AVE	Concrete	3	Poor	1.00	1.60	5	8	Yes	Yes	Yes	Yes	Yes	
E	SPRING	ST	E	18TH	ST		THOMAS	AVE	Concrete	3	Poor	0.90	0.80	8	8	Yes	Yes	Yes	No	Yes	
E	SPRING	ST	E	15TH	ST		VINCENNES	ST	Concrete	3	Poor	1.90	1.80	8	12	Yes	No	Yes	Yes	Yes	
E	SPRING	ST	E	15TH	ST		VINCENNES	ST	Concrete	3	Poor	0.70	0.20	8	12	Yes	No	Yes	No	Yes	
W	SPRING	ST	W	4TH	ST		WASHINGTON	PL	Concrete	3	Poor	1.10	4.35	6	7	Yes	No	Yes	No	No	
E	SPRING	ST		COST	AVE		WOODROW	AVE	Concrete	3	Poor	0.70	1.10	4	4	Yes	No	Yes	Yes	Yes	
	SPRING	AVE		COST	AVE		WOODROW	AVE	Concrete	3	Poor	1.30	2.10	4	4	No		Yes	No	No	
	SPRING	AVE		WOODROW	AVE		BEHARRELL	AVE	Concrete	2	Very Poor	2.40	0.60	4	5	No		No		Yes	
	SPRING	AVE		WOODROW	AVE		BEHARRELL	AVE	Concrete	2	Very Poor	2.95	4.70	4	5	No		No		No	
E	SPRING	ST	E	7TH	ST	E	6TH	ST	Concrete	1	PastServiceLife	2.40	3.30	8	12	Yes	No	Yes	No	No	
E	SPRING	ST		THOMAS	AVE		JAY	ST	Concrete	1	PastServiceLife	6.40	1.50	8	8	Yes	No	Yes	No	Yes	
	ST JOE	RD		DEAD END			ST JOE	RD	Concrete	4	Fair	3.20	0.80	4	4	No		No		Yes	
	ST JOE	RD		ST JOE	RD		CITY LIMITS		Concrete	4	Fair	1.30	1.30	4	4	No		No		Yes	
	STATE	ST	W	COTTOM	AVE		ALBANY	ST	Concrete	4	Fair	0.30	1.10	5	6	Yes	Yes	Yes	Yes	Yes	
	STATE	ST		OLIVE	AVE		CONNER	ST	Concrete	4	Fair	1.10	0.90	5	6	Yes	Yes	Yes	Yes	Yes	
	STATE	ST		ADAMS	ST	W	COTTOM	AVE	Concrete	4	Fair	0.30	2.00	5	6	Yes	Yes	Yes	Yes	Yes	
	STATE	ST		KNABLE	LN		COYLE	DR	Concrete	4	Fair	0.70	0.50	5	6	Yes	Yes	Yes	Yes	Yes	
	STATE	ST	E	COTTOM	AVE		GREEN VALLEY	RD	Concrete	4	Fair	0.10	0.20	4	6	Yes	Yes	Yes	Yes	Yes	
	STATE	ST		ALBANY	ST	W	LEWIS	ST	Concrete	4	Fair	0.10	0.50	5	6	Yes	Yes	Yes	Yes	Yes	
	STATE	ST		CONNER	ST	E	LEWIS	ST	Concrete	4	Fair	1.30	0.10	5	6	Yes	Yes	Yes	Yes	Yes	
	STATE	ST	W	MARKET	ST	W	MAIN	ST	Concrete	4	Fair	0.25	2.50	5	14	Yes	No	Yes	No	No	
	STATE	ST		SPRING	ST	E	MARKET	ST	Concrete	4	Fair	0.15	3.00	7	10	Yes	Yes	Yes	Yes	No	
	STATE	ST	E	COTTOM	AVE		OLIVE	AVE	Concrete	4	Fair	2.20	1.10	5	6	Yes	Yes	Yes	Yes	Yes	
	STATE	ST	E	LEWIS	ST		SLOEMER	AVE	Concrete	4	Fair	0.50	1.30	5	6	Yes	Yes	Yes	Yes	Yes	
	STATE	ST	W	ELM	ST	W	SPRING	ST	Concrete	4	Fair	1.00	2.05	6	12	Yes	No	Yes	No	No	
	STATE	ST		CLAY	ST		UNION	ST	Concrete	4	Fair	0.70	0.60	4	12	Yes	Yes	Yes	Yes	Yes	
	STATE	ST		ADAMS	ST		WEST	ST	Concrete	4	Fair	1.20	1.10	5	6	Yes	Yes	Yes	Yes	Yes	
	STATE	ST	E	MAIN	ST		DEAD END		Concrete	4	Fair	6.70	0.60		10	Yes	Yes	Yes	Yes	No	
	STATE	ST		EALY	ST		CHERRY	ST	Concrete	3	Poor	0.50	0.20	8	4	Yes	No	Yes	No	Yes	
	STATE	ST		GREEN	ST		CLAY	ST	Concrete	3	Poor	0.90	0.80	6	15	Yes	No	Yes	Yes	Yes	
	STATE	ST		CAPTIAN FRANK	RD		DAISY	SUMMIT	Concrete	3	Poor	0.90	0.40	4	4	Yes	No	Yes	No	Yes	
	STATE	ST	W	LEWIS	ST		EALY	ST	Concrete	3	Poor	1.30	1.60	5	8	Yes	No	Yes	No	Yes	
	STATE	ST	W	OAK	ST	W	ELM	ST	Concrete	3	Poor	0.40	0.85	5	15	Yes	Yes	Yes	No	Yes	
	STATE	ST		SLOEMER	AVE		GREEN	ST	Concrete	3	Poor	0.10	0.90	6	8	Yes	No	Yes	No	Yes	
	STATE	ST		GREEN VALLEY	RD		KNABLE	LN	Concrete	3	Poor	1.60	1.50	4	5	Yes	No	Yes	No	Yes	
	STATE	ST	E	MARKET	ST	E	MAIN	ST	Concrete	3	Poor	2.40	5.60	15	15	Yes	No	Yes	Yes	No	
	STATE	ST	W	SPRING	ST	W	MARKET	ST	Concrete	3	Poor	1.70	6.40	10	14	Yes	Yes	Yes	No	No	
	STATE	ST		CHERRY	ST		MONROE	ST	Concrete	3	Poor	1.70	1.50	6	15	Yes	No	Yes	No	Yes	
	STATE	ST		UNION	ST		MONROE	ST	Concrete	3	Poor	1.90	1.40	5	7	Yes	No	Yes	No	Yes	
	STATE	ST		CHERRY	ST	W	OAK	ST	Concrete	3	Poor	0.20	0.60	4	8	Yes	No	Yes	No	Yes	
	STATE	ST		CHERRY	ST	W	OAK	ST	Concrete	3	Poor	1.70	1.70	4	6	Yes	No	Yes	No	Yes	
	STATE	ST	E	ELM	ST	E	SPRING	ST	Concrete	3	Poor	2.25	5.65	8	12	Yes	No	Yes	Yes	No	
	STATE	ST	E	OAK	ST																

Street Prefix	Street Name	Street Suffix	From Street Prefix	From Street Name	From Street Suffix	To Street Prefix	To Street Name	To Street Suffix	Surface Type	Condition	Condition Description	Max Long Slope (%)	Max Cross Slope (%)	Width Min (ft)	Width Max (ft)	Curb Ramp From St	Curb Ramp From St ADA	Curb Ramp To St	Curb Ramp To St ADA	ADA Compliant	Comments
	THOMAS	AVE		EKIN	AVE		CULBERTSON	AVE	Concrete	4	Fair	6.90	1.20	4	4	Yes	No	Yes	No	Yes	
	THOMAS	AVE		EKIN	AVE		CULBERTSON	AVE	Concrete	4	Fair	5.40	1.35	4	4	Yes	No	Yes	Yes	Yes	
	THOMAS	AVE	E	SPRING	ST		DIVISION	ST	Concrete	4	Fair	1.70	0.80	4	4	Yes	No	Yes	No	Yes	
	THOMAS	AVE		CENTER	ST	E	MARKET	ST	Concrete	4	Fair	0.40	0.60	4	4	Yes	Yes	Yes	No	Yes	
	THOMAS	AVE		CENTER	ST	E	MARKET	ST	Concrete	4	Fair	0.50	1.20	4	4	Yes	No	Yes	No	Yes	
	THOMAS	AVE		CULBERTSON	AVE	E	OAK	ST	Concrete	4	Fair	4.25	4.50	4	4	Yes	No	Yes	No	No	
	THOMAS	AVE		CULBERTSON	AVE	E	OAK	ST	Concrete	4	Fair	0.40	2.35	4	4	Yes	No	Yes	Yes	No	
	THOMAS	AVE	E	SPRING	ST		DIVISION	ST	Concrete	3	Poor	1.90	1.50	4	4	Yes	No	Yes	No	Yes	
	THOMAS	AVE		SHELBY	ST		EKIN	AVE	Concrete	3	Poor	1.10	1.90	4	4	Yes	No	Yes	No	Yes	
	THOMAS	AVE	E	OAK	ST	E	ELM	ST	Concrete	3	Poor	0.65	1.35	4	4	Yes	No	Yes	No	Yes	
	THOMAS	AVE		BEELER	ST		SHELBY	ST	Concrete	3	Poor	0.15	1.20	4	4	Yes	No	Yes	No	Yes	
	THOMAS	AVE	E	ELM	ST	E	SPRING	ST	Concrete	3	Poor	2.50	1.20	4	4	Yes	No	Yes	No	Yes	
	THOMAS	AVE	E	ELM	ST	E	SPRING	ST	Concrete	3	Poor	1.65	2.25	4	4	Yes	No	Yes	No	No	
	THOMAS	AVE		NEW ALBANY HS			SHELBY	ST	Concrete	2	Very Poor	0.60	3.55	4	4	Yes	No	Yes	Yes	No	
	TRINITY RUN	CT	W	DAISY	LN	W	DAISY	LN	Concrete	4	Fair	4.85	3.05	4	4	Yes	No	Yes	No	No	
	UNION	ST		STATE	ST		PEARL	ST	Concrete	4	Fair	1.30	0.60	6	8	Yes	Yes	Yes	Yes	Yes	
	UNION	ST		STATE	ST		PEARL	ST	Concrete	4	Fair	1.50	0.90	6	8	Yes	Yes	Yes	Yes	Yes	
	VALE	CT		HICKORYVALE	DR		HICKORYVALE	DR	Concrete	3	Poor	3.70	0.50	4	4	Yes	No	Yes	No	Yes	
N	VALLEY VIEW	RD	N	VALLEY VIEW	RD		DEAD END		Concrete	4	Fair	1.80	8.10	4	4	No		No		No	
	VALLEY VIEW	TRC		VALLEY VIEW	RD		VALLEY VIEW	RD	Concrete	3	Poor	10.30	22.15	4	4	No		No		No	
	VALLEY VIEW	TRC		VALLEY VIEW	RD		VALLEY VIEW	RD	Concrete	3	Poor	6.55	12.85	4	4	No		No		No	
	VALLEY VIEW	CT		VALLEY VIEW	CT		VALLEY VIEW	CT	Concrete	3	Poor	3.20	0.90	4	4	Yes	No	Yes	No	Yes	
	VALLEY VIEW	CT		CLOVER	AVE		WEST	ST	Concrete	3	Poor	0.10	1.70	4	4	No		Yes	No	Yes	
	VALLEY VIEW	CT		OLIVE	ST		CLOVER	AVE	Concrete	2	Very Poor	2.80	0.30	4	4	Yes	No	No		Yes	
	VALLEY VIEW	CT		OLIVE	ST		VALLEY VIEW	CT	Concrete	1	PastServiceLife	1.30	2.10	4	4	Yes	No	Yes	No	No	
	VALLEY VIEW	CT		VALLEY VIEW	CT		WEST	ST	Concrete	4	Fair	0.30	1.30	4	4	Yes	No	Yes	No	Yes	
	VALLEY VIEW	CT		VALLEY VIEW	CT		VALLEY VIEW	CT	Concrete	2	Very Poor	0.40	7.80	4	4	Yes	No	Yes	No	No	
	VALLEY VIEW	CT		VALLEY VIEW	CT		VALLEY VIEW	CT	Concrete	1	PastServiceLife	1.80	3.50	4	4	Yes	No	Yes	No	No	
	VANCE	AVE		LOPP	AVE		CHARLESTOWN	RD	Concrete	4	Fair	5.40	1.40	4	4	Yes	No	Yes	No	Yes	
	VANCE	AVE		LOPP	AVE		CHARLESTOWN	RD	Concrete	4	Fair	5.20	1.00	4	4	Yes	No	Yes	No	Yes	
	VANCE	AVE		MONON	AVE		LOPP	AVE	Concrete	4	Fair	1.20	1.40	4	4	Yes	No	Yes	No	Yes	
	VANCE	AVE		WEST	ST		LOPP	AVE	Concrete	4	Fair	0.20	1.20	4	4	Yes	No	Yes	No	Yes	
	VANCE	AVE		MONON	AVE		WEST	ST	Concrete	4	Fair	0.20	3.50	4	4	Yes	No	Yes	No	No	
	VANCE	AVE		CHARLESTOWN	RD		DEPAUW	AVE	Concrete	3	Poor	7.70	0.90	4	4	Yes	No	Yes	No	Yes	
	VANCE	AVE		FLORENCE	AVE		DEPAUW	AVE	Concrete	1	PastServiceLife	13.90	1.60	4	4	Yes	No	Yes	No	No	
	VANCE	AVE		CHARLESTOWN	RD		FLORENCE	AVE	Concrete	1	PastServiceLife	7.70	7.00	4	4	Yes	No	Yes	No	No	
	VENETIAN	WAY		JANIE	LN		LINDA	DR	Concrete	TBD	Good	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	Yes	
	VENETIAN	WAY		PIMLICO	DR		LINDA	DR	Concrete	TBD	Good	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	Yes	
	VENETIAN	WAY		JANIE	LN		PIMLICO	DR	Concrete	TBD	Good	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	Yes	
W	VILLAGE	DR		DEAD END			DEAD END		Concrete	4	Fair	0.70	0.40	4	5	No		No		Yes	
W	VILLAGE	DR	E	VILLAGE	DR		COUNTRY CLUB	DR	Concrete	3	Poor	1.40	0.50	5	6	No		No		Yes	
E	VILLAGE	DR	E	VILLAGE	DR		COUNTRY CLUB	DR	Concrete	3	Poor	1.40	0.30	4	5	No		No		Yes	
E	VILLAGE	DR		DEAD END		E	VILLAGE	DR	Concrete	3	Poor	2.80	3.00	5	6	No		No		No	
E	VILLAGE	DR		DEAD END		E	VILLAGE	DR	Concrete	4	Fair	3.50	2.30	5	6	No		No		No	
	VINCENNES	ST		KING	ST	E	MARKET	ST	Concrete	5	Good	0.50	4.40	6	14	Yes	Yes	Yes	Yes	No	
	VINCENNES	ST		EKIN	AVE		CULBERTSON	AVE	Concrete	4	Fair	1.35	3.40	5	9	Yes	Yes	Yes	No	No	
	VINCENNES	ST	E	SPRING	ST		DIVISION	ST	Concrete	4	Fair	0.50	0.20	8	12	Yes	No	Yes	Yes	Yes	
	VINCENNES	ST	E	OAK	ST	E	ELM	ST	Concrete	4	Fair	0.60	1.45	5	7	Yes	Yes	Yes	No	Yes	
	VINCENNES	ST	E	SPRING	ST	E	MARKET	ST	Concrete	4	Fair	0.70	0.70	8	12	Yes	No	Yes	No	Yes	
	VINCENNES	ST		DEPAUW	AVE		RASMUSSEN	CT	Concrete	4	Fair	1.90	0.20	5	5	Yes	No	No		Yes	
	VINCENNES	ST		BEELER	ST		SHELBY	PL	Concrete	4	Fair	0.75	0.95	5	8	Yes	No	Yes	No	Yes	
	VINCENNES	ST	E	ELM	ST	E	SPRING	ST	Concrete	4	Fair	0.25	0.95	5	7	Yes	No	Yes	Yes	Yes	
	VINCENNES	ST		LOCUST	ST		BEELER	ST	Concrete	3	Poor	0.40	0.65	6	12	Yes	No	Yes	No	Yes	
	VINCENNES	ST		LOPP	AVE		CHARLESTOWN	RD	Concrete	3	Poor	1.20	2.80	4	4	Yes	Yes	Yes	No	No	
	VINCENNES	ST		DEAD END			CHARLESTOWN	RD	Concrete	3	Poor	0.90	1.60	5	8	Yes	No	Yes	No	Yes	
	VINCENNES	ST		CHARLESTOWN	RD		CHARTRES	ST	Concrete	3	Poor	4.50	0.50	5	6	Yes	No	Yes	No	Yes	
	VINCENNES	ST		EKIN	AVE		CULBERTSON	AVE	Concrete	3	Poor	1.20	0.95	8	3	Yes	No	Yes	No	Yes	
	VINCENNES	ST		FLORENCE	AVE		DEPAUW	AVE	Concrete	3	Poor	3.00	3.10	5	6	Yes	No	Yes	No	No	
	VINCENNES	ST		SHELBY	ST		EKIN	AVE	Concrete	3	Poor	4.25	2.05	6	10	Yes	No	Yes	No	No	
	VINCENNES	ST		SHELBY	PL		EKIN	AVE	Concrete	3	Poor	1.20	1.45	5	12	Yes	No	Yes	No	Yes	
	VINCENNES	ST	E	OAK	ST	E	ELM	ST	Concrete	3	Poor	0.05	1.90	5	8	Yes	No	Yes	No	Yes	
	VINCENNES	ST		CHARLESTOWN	RD		FLORENCE	AVE	Concrete	3	Poor	4.50	0.20	5	6	Yes	No	Yes	No	Yes	
	VINCENNES	ST		DIVISION	ST		KING	ST	Concrete	3	Poor	1.00	1.90	8	12	Yes	Yes	Yes	No	Yes	
	VINCENNES	ST		CHARTRES	ST		LOCUST	ST	Concrete	3	Poor	1.80	0.50	5	8	Yes	No	Yes	No	Yes	
	VINCENNES	ST		RASMUSSEN	CT		LOCUST	ST	Concrete	3	Poor	3.65	1.10	6	8	No		Yes	No	Yes	
	VINCENNES	ST		MONON	AVE		LOPP	AVE	Concrete	3	Poor	0.30	1.00	4	4	No		Yes	Yes	Yes	
	VINCENNES	ST	E	MARKET	ST	E	MAIN	ST	Concrete	3	Poor	1.20	7.90	4	12	Yes	Yes	Yes	No	No	
	VINCENNES	ST		STONE	ST	E	MAIN	ST	Concrete	3	Poor	0.20	1.60	10	12	Yes	No	Yes	No	Yes	
	VINCENNES	ST		GRANT LINE	RD		MONON	AVE	Concrete	3	Poor	0.90	1.60	5	5	Yes	No	No		Yes	
	VINCENNES	ST		CULBERTSON	AVE	E	OAK	ST	Concrete	3	Poor	0.25	4.25	5	8	Yes	No	Yes	No	No	
	VINCENNES	ST		CULBERTSON	AVE	E	OAK	ST	Concrete	3	Poor	1.30	2.75	5	9	Yes	No	Yes	No	No	
	VINCENNES	ST		LOCUST	ST		SHELBY	ST	Concrete	3	Poor	2.60	0.60	8	13	Yes	No	Yes	No	Yes	
	VINCENNES	ST	E	ELM	ST	E	SPRING	ST	Concrete	3	Poor	1.00	1.90	5	8	Yes	No	Yes	No	Yes	
	VINCENNES	ST	E	MARKET	ST		STONE	ST	Concrete	3	Poor	2.40	1.70	10	12	Yes	No	Yes	No	Yes	
	VINCENNES	ST		GRANT LINE	RD		DEAD END		Concrete	3	Poor	1.00	0.50	5	5	Yes	No	No		Yes	
	VINCENNES	ST	E	MAIN	ST		DEWEY	ST	Concrete	2	Very Poor	1.40	2.70	4	5	Yes	No	No		No	
	VINCENNES	ST	E	MAIN	ST		DEWEY	ST	Concrete	1	PastServiceLife	1.70	0.70	6	6	Yes	Yes	No		Yes	
	VINE	ST		DEAD END			SLOEMER	AVE	Concrete	2	Very Poor	1.70	3.80	4	4	No		Yes	Yes	No	
	WALNUT	ST		ALBANY	ST	W	LEWIS	ST	Concrete	4	Fair	0.20	1.90	4	4	Yes	No	Yes	No	Yes	
	WASHINGTON	PL	W	SPRING	ST	W	MARKET	ST	Concrete	3	Poor	1.00	1.10	5	5	Yes	No	Yes	Yes	Yes	
	WASHINGTON	PL	W	SPRING	ST	W	MARKET	ST	Concrete	2	Very Poor	0.20	4.00	5	5	Yes	No	Yes	Yes	No	

Street Prefix	Street Name	Street Suffix	From Street Prefix	From Street Name	From Street Suffix	To Street Prefix	To Street Name	To Street Suffix	Surface Type	Condition	Condition Description	Max Long Slope (%)	Max Cross Slope (%)	Width Min (ft)	Width Max (ft)	Curb Ramp From St	Curb Ramp From St ADA	Curb Ramp To St	Curb Ramp To St ADA	ADA Compliant	Comments
	WATERWORKS	PL		HIGHLAND	AVE		SPRINGHILL	DR	Concrete	4	Fair	3.80	0.75	5	5	Yes	No	No		Yes	
	WATERWORKS	PL		HIGHLAND	AVE		SPRINGHILL	DR	Concrete	4	Fair	0.60	0.95	4	4	Yes	No	Yes	No	Yes	
	WATKINS PRAIRIE	LN		GREEN VALLEY	RD		SADDLEWOOD	CT	Concrete	3	Poor	0.30	0.90	4	4	Yes	No	Yes	No	Yes	
	WEBERPAL	CIR		SADDLEWOOD	CT		SADDLEWOOD	CT	Concrete	3	Poor	0.10	6.30	4	4	Yes	No	Yes	No	No	
	WELLINGTON	DR		GREENVIEW	DR		GREEN VALLEY	RD	Concrete	3	Poor	0.80	0.60	4	4	Yes	No	Yes	No	Yes	
	WELLINGTON	DR	GREENVIEW	DR		GREEN VALLEY	RD		Concrete	3	Poor	2.70	4.40	4	4	Yes	Yes	Yes	No	No	From the Jackson/Locust intersection to the blocked off entrance to
	WEST	ST		VALLEY VIEW	CT		LINCOLN	ST	Concrete	4	Fair	0.40	3.00	4	4	Yes	No	Yes	No	No	
	WEST	ST		STATE	ST		ADAMS	ST	Concrete	3	Poor	0.40	1.70	4	4	Yes	No	Yes	No	Yes	
	WEST	ST		KENT	ST		ALBANY	ST	Concrete	3	Poor	4.80	1.00	4	4	Yes	No	Yes	No	Yes	
	WEST	ST		VIRGINIA	CT		ALBANY	ST	Concrete	3	Poor	0.30	2.50	4	4	Yes	No	Yes	No	No	
	WEST	ST		EALY	ST		BAY	ST	Concrete	3	Poor	2.20	0.40	4	4	Yes	No	Yes	No	Yes	
	WEST	ST		ALBANY	ST		CEDAR RIDGE	DR	Concrete	3	Poor	3.60	2.50	4	4	Yes	No	Yes	No	No	
	WEST	ST		CHERRY	CT		CHERRY	ST	Concrete	3	Poor	1.80	1.60	4	4	Yes	No	Yes	No	Yes	
	WEST	ST		ADAMS	ST	W	COTTOM	AVE	Concrete	3	Poor	0.20	1.80	4	4	Yes	No	Yes	No	Yes	
	WEST	ST		LINDEN	ST	W	COTTOM	AVE	Concrete	3	Poor	0.70	2.10	4	4	Yes	No	Yes	No	No	First half is concrete and rated 5
	WEST	ST		CEDAR RIDGE	DR		IVY	CT	Concrete	3	Poor	1.10	5.70	4	4	Yes	No	Yes	No	No	
	WEST	ST	W	COTTOM	AVE		KENT	ST	Concrete	3	Poor	0.20	2.30	4	4	Yes	No	Yes	No	No	
	WEST	ST		LINCOLN	ST		LINDEN	ST	Concrete	3	Poor	0.40	1.00	4	4	Yes	No	Yes	No	Yes	
	WEST	ST	W	LEWIS	ST		SHERLEY	ST	Concrete	3	Poor	3.10	2.20	4	4	Yes	No	Yes	No	No	
	WEST	ST		STATE	ST		VALLEY VIEW	CT	Concrete	3	Poor	0.60	2.80	4	4	Yes	No	Yes	No	No	
	WEST	ST	W	COTTOM	AVE		VIRGINIA	CT	Concrete	3	Poor	0.30	2.30	4	4	Yes	No	Yes	No	No	
	WEST	ST		JACKSON	ST		CHERRY	ST	Concrete	2	Very Poor	1.90	1.80	4	4	Yes	No	Yes	No	Yes	
	WEST	ST		SHERLEY	ST		EALY	ST	Concrete	2	Very Poor	4.10	3.80	4	4	Yes	No	Yes	No	No	
	WEST	ST		BAY	ST		JACKSON	ST	Concrete	2	Very Poor	2.20	3.10	4	4	Yes	No	Yes	No	No	
	WEST	ST		ALBANY	ST	W	LEWIS	ST	Concrete	2	Very Poor	0.80	1.80	4	4	Yes	No	Yes	No	Yes	
	WEXFORD	CT		MT TABOR	RD		MT TABOR	RD	Concrete	5	Good	0.50	1.60	4	4	Yes	No	Yes	No	Yes	
	WILLARD	AVE		INDIANA	AVE		MCDONALD	AVE	Concrete	4	Fair	0.30	2.35	4	4	Yes	Yes	No		No	
	WILLARD	AVE		SILVER	ST		INDIANA	AVE	Concrete	2	Very Poor	1.00	3.65	4	4	Yes	No	Yes	Yes	No	
	WILLARD	AVE		SILVER	ST		INDIANA	AVE	Concrete	2	Very Poor	0.60	2.25	4	4	Yes	No	Yes	Yes	No	
	WILLARD	AVE		INDIANA	AVE		MCDONALD	AVE	Concrete	2	Very Poor	0.65	1.70	4	4	Yes	Yes	No		Yes	
	WOLFE	TRCE		WOLFE	TRCE		GRAYBROOK	LN	Concrete	3	Poor	0.90	4.70	4	4	Yes	Yes	Yes	Yes	No	
	WOLFE	TRCE		WOLFE	TRCE		GRAYBROOK	LN	Concrete	3	Poor	2.50	0.80	4	4	No		Yes	No	Yes	
	WOLFE	TRCE		WOLFE	TRCE		WOLFE	TRCE	Concrete	3	Poor	5.10	1.00	4	4	Yes	Yes	Yes	Yes	Yes	
	WOLFE	TRCE		WOLFE	TRCE		WOLFE	TRCE	Concrete	2.0000	Very Poor	2.90	3.20	4	4	Yes	No	Yes	Yes	No	
	WOODBOURNE	DR		KAYWOOD	DR		NOB VIEW	AVE	Concrete	4	Fair	2.30	0.10	4	4	Yes	Yes	Yes	Yes	Yes	
	WOODBOURNE	DR		MURR	LN		HARBROOK	DR	Concrete	3	Poor	1.00	0.60	4	4	Yes	Yes	Yes	Yes	Yes	
	WOODBOURNE	DR		HARBROOK	DR		KAYWOOD	DR	Concrete	3	Poor	0.30	1.70	4	4	Yes	Yes	Yes	Yes	Yes	
	WOODBOURNE	DR		WOODSIDE	DR		KAYWOOD	DR	Concrete	3	Poor	1.70	0.50	4	4	Yes	Yes	Yes	Yes	Yes	
	WOODBOURNE	DR		KAYWOOD	DR		NOB VIEW	AVE	Concrete	3	Poor	1.20	2.20	4	4	Yes	Yes	Yes	Yes	No	
	WOODBOURNE	DR		DEAD END			DEAD END		Concrete	2	Very Poor	1.60	3.40	4	4	No		Yes	Yes	No	
	WOODFIELD	DR		FARMGATE	LN		CREEKVIEW	CIR	Concrete	4	Fair	1.50	0.70	4	4	No		Yes	No	Yes	
	WOODFIELD	DR		FARMGATE	LN		CREEKVIEW	CIR	Concrete	4	Fair	1.90	0.30	4	4	Yes	No	No		Yes	
	WOODFIELD	DR		CREEKVIEW	CIR		FARMGATE	LN	Concrete	4	Fair	1.10	3.00	4	4	No		Yes	No	No	
	WOODFIELD	DR		CREEKVIEW	CIR		FARMGATE	LN	Concrete	4	Fair	1.20	2.20	4	4	No		Yes	No	No	
	WOODLAND	DR		MORGAN	AVE		GRAYBROOK	LN	Concrete	3	Poor	1.20	3.10	4	4	No		Yes	No	No	
	WOODLAND	DR		SHORT MINTON	DR		GRAYBROOK	LN	Concrete	3	Poor	0.80	2.90	4	4	No		Yes	No	No	
	WOODLAND	DR		MORGAN	AVE		SHORT MINTON	DR	Concrete	3	Poor	0.90	3.10	4	4	No		Yes	No	No	
	WOODROW	AVE		RENO	AVE	E	MARKET	ST	Concrete	3	Poor	1.40	1.30	4	4	Yes	No	Yes	No	Yes	
	WOODROW	AVE	E	SPRING	ST	E	MARKET	ST	Concrete	3	Poor	0.40	1.90	4	4	Yes	No	Yes	No	Yes	
	WOODROW	AVE	E	SPRING	ST		RENO	AVE	Concrete	2	Very Poor	0.60	1.80	4	4	Yes	No	Yes	No	Yes	
	WOODROW	AVE	E	ELM	ST		SPRING	AVE	Concrete	2	Very Poor	0.25	1.70	0.4	5	No		Yes	No	Yes	
	WOODROW	AVE	E	ELM	ST		SPRING	AVE	Concrete	2	Very Poor	0.28	0.50	4	4	No		Yes	No	Yes	
	WOODROW	AVE		SPRING	AVE	E	SPRING	ST	Concrete	2	Very Poor	4.80	5.90	4	5	No		Yes	No	No	
	WOODROW	AVE		SPRING	AVE	E	SPRING	ST	Concrete	2	Very Poor	5.85	1.55	4	5	No		Yes	No	Yes	
	WOODSIDE	DR		MELLWOOD	DR		MELLWOOD	DR	Concrete	3	Poor	1.20	1.20	4	4	No		No		Yes	
	WOODSIDE	DR		MELLWOOD	DR		MELLWOOD	DR	Concrete	3	Poor	1.70	0.10	4	4	No		No		Yes	
	WOODSIDE	DR		WOODBOURNE	DR		MELLWOOD	DR	Concrete	3	Poor	0.50	1.40	4	4	No		No		Yes	